




## Class Outline (continued) Type of Rated Horizontal Assemblies Floor, Roof, Floor/Ceiling or Roof/Ceiling Differences between the various assembly types Importance of ceiling membrane and affect on test temperatures Protection of structural members Marking and identification requirements (if applicable - for smoke barriers)


## Class Outline (continued) Code Requirements Difference between Sections 711 and 712 Conditions that require rated horizontal assemblies Section 711 details Section 712 details Unprotected openings allowed in roof


# Class Outline (continued) Miscellaneous topics Beam and girder substitution: modifying approved assemblies Calculated wood assemblies Eave overhangs and protection of soffits Discrepancy of Fire-Resistance Rated Floors, Ceilings and Roofs 1 Class Outline (continued) Softward Continued)














#### **Purpose of rated assemblies**

**FIRE RESISTANCE.** That property of materials or their assemblies that prevents or retards the passage of excessive heat, hot gases or flames under conditions of use.

**FIRE-RESISTANCE RATING.** The period of time a building element, component or assembly maintains the ability to confine a fire, continues to perform a given structural function, or both, as determined by the tests, or the methods based on tests, prescribed in Section 703.



012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Roofs

13

#### **Purpose of rated assemblies**

FIRE PROTECTION RATING. The period of time that an opening protective will maintain the ability to confine a fire as determined by tests prescribed in Section 715. Ratings are stated in hours or minutes.



2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Root

14

#### **Types of Horizontal Assemblies**

Horizontal assemblies may be either:

- a floor or
- roof assembly

Some may rely on the ceiling as a part of a floor/ceiling or roof/ceiling assembly. The ceiling assembly is often an integral part of a fire-resistance-rated floor/ceiling or roof/ceiling assembly; therefore:


 the integrity of the ceiling assembly must be maintained in order to reduce the potential for premature failure of the floor or roof of a building.


2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings


15


#### **Horizontal Assembly with Ceiling**


Where a ceiling membrane is a part of a rated assembly, the ability of the membrane to remain in place is important to the viability of the rating. Section 711.3.1 addresses upward force.












#### Alternative Materials, Design and **Methods of Construction** Alternates are: 104.11 Alternative materials. design and methods of Approved construction and equipment. The provisions of this code are not Complies with intent intended to prevent the installation of the code of any material or to prohibit any design or method of construction Equivalent to code not specifically prescribed by this code, provided that any such alternative has been approved. Quality, Strength, Effectiveness, Fireresistance, Durability and Safety



#### Guidelines on Fire Ratings of Archaic Materials and Assemblies – IEBC Chapter Resource A

The Guideline on Fire Ratings of Archaic Materials and Assemblies focuses upon the fire-related performance of archaic construction. "Archaic" encompasses construction typical of an earlier time, generally prior to 1950. "Fire-related performance" includes fire resistance, flame spread, smoke production and degree of combustibility.



2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Roofs

#### **Multiple Use Fire Assemblies**

**701.2 Multiple use fire assemblies.** Fire assemblies that serve multiple purposes in a building shall comply with all of the requirements that are applicable for each of the individual fire assemblies.

If it serves multiple purposes, must comply with all requirements.

**Example:** Rated floor also serving as a smoke barrier. Must meet horizontal fire assembly provisions and smoke barrier penetration and joint requirements.



2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Roofs

27

#### **Definitions**

- Annular Space
- Building Element
- Ceiling Radiation Damper
- Combination Fire/Smoke Damper
- Draftstop
- F Rating
- Fire Barrier

- Fire Damper
- Fire Door Assembly
- Fire Partition
- Fire Protection Rating
- Fire Resistance
- Fire-resistance Rating
- Fire-resistant Joint System

spection of Fire-Resistance Rated Floors, Ceilings and Roofs

#### **Definitions (continued)**

- Fire Separation Distance
- Firewall
- Fire Window Assembly
- Fireblocking
- Horizontal Assembly
- Joint
- Member Penetration
- Shaft

- Shaft Enclosure
- Smoke Barrier
- Smoke Compartment
- T Rating
- Through Penetration
- Primary Structural Frame
- Secondary members



2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Roofs

26

## **Sections 711 and 712 Different Topics**

Section 711

Primarily is the construction requirements for horizontal assemblies

Section 712

Primarily is addressing the openings and protection of them through the horizontal assembly



2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Roofs


~\B|F


#### **Section 711**


- Horizontal assemblies are required by various provisions of the code:
  - Type of construction requirements
  - Separated occupancies
  - Incidental accessory occupancy separation
  - Separation of fire areas
  - Horizontal exit alternative
  - Dwelling unit and sleeping unit separations
  - Horizontal separation allowances (Section 510)
  - Due to supporting rated walls


2012 IBC Inenaction of Eira-Paeietanca Pated Floare Callings and Page


28































## Unprotected Skylights and Other Penetrations Certain code provisions prohibit openings (protected or unprotected) in specific locations of horizontal assemblies. Examples: Adjacent to fire walls – Section 706.6 exceptions 2, 3 or 4 Lower roof of stepped building – Section 706.6.1 Plastic skylight near exterior wall requiring protected openings – Section 2610.7












## Different Types of Fire-Protection Penetrations – 711.5 (Section 714) Joint Systems – 711.6 (Section 715) Ducts and Air Transfer Openings – 711.7 (Section 717) Dampers Floor fire door assemblies – 711.8





### Section 711.9 – Smoke Barrier


If horizontal assembly is required to resist movement of smoke by other sections:


- Penetrations and joints protected as required for smoke barriers (714.5 and 715.6)
- Protect elevator shaft doors with elevator lobby (regardless of number of stories)
- Protect openings with shaft enclosures (713)
- Unprotected vertical openings not allowed




















## **Section 712.1.3.2 – Automatic shutters**

- Approved automatic shutters provided at every floor.
- Shutters to be of noncombustible construction with minimum 90-minute fire-resistance rating.
- Shutter closure to be smoke detector actuated.
- Shutter actuation to initiate escalator shutdown.
- Maximum shutter speed of 30 feet/minute.
- Shutter to have sensitive leading edge to arrest progress when in contact with obstacle, then continue upon release.






## Section 712.1.4, 712.1.5 – Penetrations and ducts

- Penetrations by pipe, tube, conduit, wire, cable and vents protected in accordance with Section 714 are permitted.
- Penetrations by ducts protected in accordance with Section 717.6 are permitted. Grease ducts shall be protected in accordance with the International Mechanical Code® (IMC®).







## Section 714.4 – Horizontal assemblies

- Penetrations of horizontal assemblies are regulated for:
  - Floors.
  - Floor/ceiling assemblies.
  - Ceiling membranes of roof/ceiling assemblies.
- Requirements are applicable to:
  - Fire-resistance-rated assemblies.
  - Nonfire-resistance-rated assemblies.







#### **Section 714 - Penetrations**

Penetrations of fire-resistive assemblies can be protected by one of three basic methods:

- Tested as a part of the original fireresistive assembly test
- Tested as a Penetration Firestop System complying with ASTM E 714 or UL 1479
- Comply with one of the exceptions listed in Sections 714.4.1.1 or 714.4.1.2



#### **Penetration Firestop Systems**

- Review and understand definitions!
- Tested and listed as a system. Must be installed and used for walls and penetrants as tested.
- Required to have an "F" and a "T" rating of not less than the fire-resistance rating of the floor. (Section 714.4.1.1.2)
- Required to have an "L" rating for penetrations in smoke barriers (Section 714.5)


2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Roofs


## Special Inspection – Section 1705.16

Special inspection of penetration firestops, joint systems and perimeter barrier systems is required in:

- High-rise buildings
- Buildings in Risk Category III or IV in accordance with Section 1604.5







## Section 714.4.1.1 – Through penetrations

- Unless protected by a shaft enclosure, through penetrations of fire-resistancerated horizontal assemblies shall:
  - Be installed as tested in an approved fireresistance-rated assembly; or
  - Protected by an approved penetration firestop system (ASTM E 814 or UL 1479).



#### **Section 714.4.1.1 – Exception 1**

- Through-penetration firestop systems are not required for through penetrations of a single fire-resistance-rated floor assembly for steel, ferrous or copper conduits, pipes, tubes or vents where:
  - Annular space protected with materials that prevent the passage of flame and hot gases in accordance with ASTM E 119 or UL 263.



#### **Section 714.4.1.1 – Exception 2**

- Through-penetration firestop systems are not required for through penetrations of a single fire-resistance-rated concrete floor assembly for steel, ferrous or copper conduits, pipes, tubes or vents where:
  - Maximum size of penetrating item is 6 inches in
  - Annular space is protected with concrete, grout or mortar for the full thickness of the floor or the thickness required to maintain the fire-resistance rating.



#### Section 714.4.1.2 - Membrane penetrations

 Penetrations of membranes that are a part of a fire-resistance-rated horizontal assembly shall comply with the requirements for through penetrations in such horizontal assemblies.



#### Section 714.4.1.2 – Exception 1

- Annular space protection of membrane penetrations permitted in lieu of listed firestop system where:
  - Penetrating items are steel, ferrous or copper pipes, tubes or conduits.
  - Annular space is protected to prevent the free passage of flame and products of combustion.
  - Aggregate area of openings through membrane is limited to 100 square inches in any 100 square feet.



#### Section 714.4.1.2 – Exception 2

- Ceiling membrane penetrations of steel electrical boxes may be made subject to the following conditions:
  - Horizontal assembly to be maximum 2 hours.
  - Boxes to be a maximum of 16 square inches.
  - Aggregate area of boxes is not to exceed 100 square inches per 100 square feet of wall area.
  - Annular space between box and ceiling membrane is not to exceed 1/8 inch.



## Section 714.4.1.2 – Exception 3 and 4

- Ceiling membrane penetrations of listed electrical boxes of any material may be made subject to the following conditions:
  - Boxes have been tested for use in a fireresistance-rated assembly.
  - Boxes are installed in accordance with their listing.
  - Annular space between the box and ceiling membrane is not to exceed 1/8 inch.


2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Roofs

73

#### Section 714.4.1.2 – Exception 5

- Ceiling membrane penetrations created by the penetration of a fire sprinkler need not be protected by an approved firestop system provided the annular space is covered by a metal escutcheon plate.
  - Applicable only where a sprinkler is installed at the point of the ceiling membrane penetration.






#### Section 714.4.1.2 – Exception 6

 Penetrations of noncombustible items are permitted where cast into concrete building elements provided the items do not penetrate both the top and bottom surfaces of the element.





#### Section 714.4.2 – Nonfireresistance-rated assemblies

- Penetrations of nonfire-resistance-rated horizontal assemblies by shall comply with:
  - Section 713, for shaft enclosures.
  - Section 714.4.2.1, for noncombustible penetrating items.
  - Section 714.4.2.2, for penetrations that connect a maximum of two stories.



## Section 714.4.2.1 – Noncombustible penetrating items

- Noncombustible penetrations of nonfireresistance-rated horizontal assemblies need not meet the shaft enclosure provisions of Section 713 provided the:
  - Penetrating items do not connect more than five stories; and
  - Annular space is filled with an approved noncombustible material to resist the free passage of flame and the products of combustion.



## Section 714.4.2.2 – Penetrating items

- Combustible penetrations of nonfire-resistancerated horizontal assemblies need not meet the shaft enclosure provisions of Section 713 provided the:
  - Penetrating items do not connect more than two stories; and
  - Annular space is filled with an approved noncombustible material to resist the free passage of flame and the products of combustion.



## Section 714.5 – Penetrations in smoke barriers

- Penetrations in smoke barriers to be protected by a through-penetration firestop system installed and tested in accordance with UL 1479 for air leakage L rating of the system, measured at 0.30 inch (7.47 Pa) of water in both the ambient and elevated temperature tests, not to exceed:
  - 5.0 cubic feet per minute (cfm) per square foot per penetration; or
  - Cumulative leakage of 50 cfm for any 100 square feet of wall or floor area.



2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Roofs

81

#### Section 712.1.5 Ducts

#### Reference to Section 717.6.

- Fire dampers, smoke dampers and combination fire/smoke dampers protect openings created by duct penetrations and air transfer openings in those fire-resistancerated assemblies required to be protected.
- Ceiling radiation dampers protect duct penetrations, which only penetrate the ceiling membrane of a fire-resistance-rated assembly.



2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Roof

92

## Section 717.1.1 – Ducts that penetrate fire-resistance-rated assemblies without dampers

- Ducts that penetrate horizontal assemblies and not required to be within a shaft and not required to have dampers shall comply with the provisions of Section 714.4 through 714.4.2.2 and are regulated as penetrations.
- The annular space around ducts penetrating nonrated floor assemblies shall comply with 717.6.3.



2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Roofs

83


## Section 717.3 – Damper testing, ratings and actuation


- Dampers shall be listed, labeled and in compliance with the following standards:
  - Fire dampers: UL 555.
  - Smoke dampers: UL 555S.
  - Combination fire/smoke dampers to comply with both UL 555 and 555S.
    - A "Corridor damper" is a specific type of combination damper used in a tunnel type corridor.
  - Ceiling radiation dampers: UL 555C.




2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Roofs

84





# Section 717.6 – Horizontal assemblies • Penetrations by ducts and air transfer openings of a floor, floor/ceiling assembly or the ceiling membrane of a roof/ceiling assembly shall be protected by a shaft enclosure that complies with Section 713 or shall comply with Sections 717.6.1 through 717.6.3.



#### Section 717.6.1 – Exception

- A duct is permitted to penetrate three floors or less without a fire damper at each floor provided:
  - Duct within wall cavity:
  - Minimum 26 gage in thickness;
  - Duct opens to only one dwelling or sleeping unit, and duct is continuous from the unit to exterior:



#### Section 717.6.1 - Exception (continued)

- A duct is permitted to penetrate three floors or less without a fire damper at each floor provided:
  - Maximum 4-inch diameter duct with maximum total area of 100 square inches per 100 square feet of floor area;
  - Annular space protected to prevent the passage of flame and hot gases; and
  - Grille openings located in floor/ceiling or roof/ceiling assembly shall be protected with ceiling damper.



#### Section 717.6.2 - Membrane penetrations

- Ducts and air transfer openings constructed of approved materials that penetrate the ceiling of a fire-resistance-rated floor/ceiling assembly shall be protected with one of the following:
  - Shaft enclosure in accordance with Section 713.
  - Listed ceiling radiation damper installed at the ceiling line where a:
    - Duct penetrates the ceiling.
    - Diffuser with no duct attached penetrates the ceiling.



#### Section 717.6.2.1 – Ceiling radiation dampers

Ceiling radiation dampers are not required where:

- Tests (see ASTM E 119 or UL 263) have shown that the dampers are not necessary to maintain the fire-resistance rating of the assembly; or
- Exhaust duct penetrations are:
  - Protected in accordance with Section 714.4.1.2 (penetrations).
  - Located within the cavity of the wall; and
  - Do not pass through another dwelling unit or tenant space.



### Section 717.6.3 – Nonfire-resistance-rated floor assemblies

- Duct systems of approved materials that penetrate nonfire-resistance-rated floor assemblies shall be protected by any of the following methods:
  - Shaft enclosure in accordance with Section 7138.
  - Where duct only connects two stories, protection of annular space around penetrating duct with approved noncombustible material that resists the free passage of flame and products of combustion.
  - Where duct connects a maximum of three stories, protection of annular space around penetrating duct with approved noncombustible material that resists the free passage of flame and products of combustion; and a fire damper is installed at each floor line.



2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Roofs

93

#### **Damper Inspection Issues**

- Dampers must be installed in accordance with their listing. Get and review manufacturer's installation instructions.
- Verify access is provided per Section 717.4.
- Verify proper type of damper being used and is installed in the correct direction.
- Breakaway connections provided on ductwork.
- Proper gap and support brackets provided around damper. (See manufacturer's instructions)

SIBC Sim

2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Roofs

94

#### Section 712.1.6 - Atriums

 For other than Group H occupancies, the atrium provisions of Section 404 are permitted as a method of addressing vertical openings.






2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Roofs


## Section 712.1.7 – Masonry chimney


Approved masonry chimneys may penetrate floors and floor/ceiling assemblies where annular space protection is provided at each floor level in accordance with Section 718.2.5



SIBC E

#### Section 712.1.8 – Two-story openings In other than Group I-2 and I-3 occupancies, a floor opening is permitted where all of the following conditions are met: Does not connect more than two stories. Is not concealed within construction of a wall or floor/ceiling assembly. Is not open to a corridor in Group I and R occupancies. Is not open to a corridor on nonsprinklered floors. Is separated from other floor openings and air transfer openings by construction equal to shaft construction.





#### Section 712.1.9 through 712.1.11 -Parking garages, mezzanine and joints

- Automobile ramps in open and enclosed parking garages constructed in accordance with Sections 406.5 and 406.6, respectively are permitted.
- Floor openings between a mezzanine and the floor below, are permitted.
- Joints protected by a fire-resistant joint system in accordance with Section 715 are permitted.



#### **Section 715.1 – Exceptions**

Fire-resistant joint systems are not required in the following locations:

#### Floors:

- Where the joint is protected by a shaft enclosure
- Within atriums
- Within malls
- Within open parking garages

#### Mezzanines

#### Other locations:


- Within a single dwelling unit
   Walls permitted to have unprotected openings
  - Roofs where openings are permitted
  - Maximum 5/8-inch (15.9) mm) wide control joints (tested in accordance with ASTM E 119 or UL 263)

## Section 712.1.12 – Unenclosed stairs and ramps


- Floor openings are permitted where they contain unenclosed stairs and ramps and are permitted where in compliance with the applicable provisions of Sections 1009.2 and 1009.3.
- In other than Group I-2 and I-3 occupancies, exit access stairways that serve, or atmospherically communicate between, only two stories are not required to be enclosed.











# Sections 712.1.15 and 712.1.16 Where contained within and serving only the parking garage, vertical openings are allowed for: Elevators Mechanical supply or exhaust ducts Conceptually similar to 712.1.9 for the vehicle ramps. If they are allowed to be open, then why get excited about these other floor openings?














#### How do you handle?

The protection of soffits or eave overhangs?

- Does it affect attic vents
- Is there a difference depending on if a truss is used versus rafters?



#### **Closing Comment**

It is only through the proper construction and protection of openings or penetrations that a fire-resistance rated assembly can do what it is intended to do.

If one aspect is done incorrectly it can compromise the integrity of the assembly and lead to it not doing its intended job.

So verify construction, continuity and protection of openings of all fire-resistance-rated walls.



International Code Council is a Registered Provider with The American Institute of Architects Continuing Education Systems. Credit earned on completion of this program will be reported to CES Records for AIA members. Certificates of Completion for non-AIA members are available on request.

This program is registered with the AIA/CES for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product. Questions related to specific materials, methods, and services will be addressed at the conclusion of this presentation.



2012 IBC Inspection of Fire-Resistance Rated

#### **Copyright Materials**

This presentation is protected by US and International Copyright laws. Reproduction, distribution, display and use of the presentation without written permission of the speaker is prohibited.

© International Code Council 2013



2012 IBC Inspection of Fire-Resistance Rated

11/

#### Thank you for participating

To schedule a seminar, contact:

**The ICC Training & Education Department** 

1-888-ICC-SAFE (422-7233) Ext. 33818

or

E-mail: icctraining@iccsafe.org



2012 IBC Inspection of Fire-Resistance Rated Floors, Ceilings and Roofs

115