

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION


| | | | |
|-----------------------|---------------|-------|--------------|
| STATE OF SOUTH DAKOTA | PROJECT | SHEET | TOTAL SHEETS |
| | IM-P 0022(85) | 1 | 64 |

Plotting Date: 03/25/2022

INDEX OF SHEETS

| | |
|--------------|------------------------------------|
| Sheets 1 & 2 | Title Sheet & Layout Maps |
| Sheet 3 | Estimate of Quantities |
| Sheet 4 | Environmental Commitments |
| Sheets 5-8 | Plan Notes |
| Sheets 9-35 | Tables for NRC Pavement Repair |
| Sheets 36-48 | NRC Pavement Repair Details |
| Sheets 49-55 | Pavement Marking & Traffic Control |
| Sheets 56-63 | Standard Plates |
| Sheet 64 | Miscellaneous Special Detail |

PLANS FOR PROPOSED
PROJECT IM-P 0022(85)
INTERSTATES 29, 90 & 229,
SD HIGHWAYS 34 & 38
MINNEHAHA & MINER COUNTIES
PAVEMENT RESTORATION -
NRC PAVEMENT REPAIR,
SPALL REPAIR, TIE BAR RETROFIT STITCHING,
SEALING RANDOM CRACKS, JOINT SEALING,
PAVEMENT MARKING & ASPHALT REPAIR MASTIC
PCN 089K



190 WBL **LENGTH: 6.866 MILES**
MRM 390.00 +0.402 to MRM 397.00 +0.271
MILEAGE 390.602 to MILEAGE 397.468
From Begin Concrete 830' E of Exit 390
over SD38, E to 1,515' E of Kiwanis Ave

190 EBL **LENGTH: 7.212 MILES**
MRM 390.00 +0.046 to MRM 397.00 +0.263
MILEAGE 390.260 to MILEAGE 397.472
From Begin Concrete 1,140' W of Exit 390
over SD38, E to 1,470' E of Kiwanis Ave


SD38 WBL AT SDDOT **LENGTH: 0.363 MILE**
SD38 EBL AT SDDOT **LENGTH: 0.363 MILE**
MRM 364.26 +0.119 to MRM 364.74 +0.015
MILEAGE 0.119 to MILEAGE 0.482
From Begin Concrete Divided, E to Jct Marion Rd

SD38 IN HARTFORD
LENGTH: 0.602 MILE
MRM 356.00 +0.121 to
MRM 356.00 +0.723
MILEAGE 55.758 to
MILEAGE 56.360
From Begin Concrete
134' W of Jct Western Ave,
ESE to End Concrete 130'
SE of Vandemark Ave

STORM WATER PERMIT
(None required)

190 WBL ADT(2021) 8,782
190 EBL ADT(2021) 8,792
SD38 AT HARTFORD ADT(2021) 3,337
SD38 BUFFALO RIDGE ADT(2021) 4,148
SD38W AT SDDOT ADT(2021) 3,076
SD38E AT SDDOT ADT(2021) 3,076

SD38 AT BUFFALO RIDGE LENGTH: 0.208 MILE
MRM 360.00 +0.133 to MRM 360.22 +0.114
MILEAGE 59.808 to MILEAGE 60.016
From Begin Concrete 304' W of Begin Bridge,
E to End Concrete 604' E of End Bridge



PLOT SCALE - 1" = 7000'


PLOTTED FROM - TRSF12114

FILE - ... \089K - MINNEHAHA\TTL089K.DGN

PLOT SCALE - 1"=7000'

PLOT NAME - 2

FILE - ... \089K - MINNEHAHA\TTL089K.DGN





I29 NBL **LENGTH: 1.689 MILES**
 MRM 83.38 +0.400 to MRM 85.00 +0.503
 MILEAGE 83.737 to MILEAGE 85.426
 From CRC Terminal 2, 110' N of 60th St N,
 N to End Concrete 480' N of 259th St

I229 SBL **LENGTH: 2.007 MILES**
 MRM 8.28 +0.565 to MRM 10.82 +0.041
 MILEAGE 10.092 to MILEAGE 12.099
 From Begin NRC Pavement 3,195' S of
 Benson Rd, N to End Concrete 216' N of I90W

I90 WBL **LENGTH: 0.264 MILE**
 MRM 401.00 +0.468 to MRM 401.61 +0.142
 MILEAGE 401.668 to MILEAGE 401.932
 From Concrete Change 625' W of Slip Up Creek,
 E to Concrete Change 770' E of Slip Up Creek

I90 EBL **LENGTH: 0.267 MILE**
 MRM 401.00 +0.464 to MRM 401.61 +0.143
 MILEAGE 401.675 to MILEAGE 401.942
 From Concrete Change 630' W of Slip Up Creek,
 E to Concrete Change 780' E of Slip Up Creek



SD34 ADT(2021) 1,785
I29 NBL ADT(2021) 11,970
I90 WBL ADT(2021) 16,005
I90 EBL ADT(2021) 16,005
I229 SBL ADT(2021) 12,892

SD34 IN HOWARD **LENGTH: 1.384 MILES**
 85' W of MRM 365.00 to MRM 366.00 +0.392
 MILEAGE 304.403 to MILEAGE 305.787
 From Begin Concrete 135' W of Jct SD25, E
 through Howard to End Concrete 60' E of Miner St

ESTIMATE OF QUANTITIES

| BID ITEM NUMBER | ITEM | QUANTITY | UNIT |
|-----------------|---|----------|------|
| 009E0010 | Mobilization | Lump Sum | LS |
| 110E7700 | Remove Drop Inlet Frame and Grate Assembly for Reset | 9 | Each |
| 320E0402 | Asphalt Repair Mastic Type 2 | 137,794 | Lb |
| 320E1200 | Asphalt Concrete Composite | 300.0 | Ton |
| 380E5030 | Nonreinforced PCC Pavement Repair | 8,496.7 | SqYd |
| 380E6000 | Dowel Bar | 9,556 | Each |
| 380E6110 | Insert Steel Bar in PCC Pavement | 18,623 | Each |
| 380E6200 | Tie Bar Retrofit, Stitching | 335 | Each |
| 380E6302 | Reseal PCC Pavement Joint - Hot Pour | 123,887 | Ft |
| 380E6310 | Seal Random Cracks in PCC Pavement | 1,239 | Ft |
| 380E6510 | Grinding PCC Pavement | 744.4 | SqYd |
| 390E0200 | Repair Type A Spall | 22.0 | SqFt |
| 410E2600 | Membrane Sealant Expansion Joint | 52.0 | Ft |
| 460E0700 | Joint Nosing Material | 10 | SqFt |
| 633E0225 | Preformed Thermoplastic Pavement Marking, 24" | 816 | Ft |
| 633E0235 | Preformed Thermoplastic Pavement Marking, Arrow | 29 | Each |
| 633E0240 | Preformed Thermoplastic Pavement Marking, Combination Arrow | 1 | Each |
| 633E1200 | High Build Waterborne Pavement Marking Paint, White | 155 | Gal |
| 633E1205 | High Build Waterborne Pavement Marking Paint, Yellow | 93 | Gal |
| 633E5015 | Grooving for Cold Applied Plastic Pavement Marking, 24" | 816 | Ft |
| 633E5025 | Grooving for Cold Applied Plastic Pavement Marking, Arrow | 29 | Each |
| 633E5030 | Grooving for Cold Applied Plastic Pavement Marking, Combination Arrow | 1 | Each |
| 634E0010 | Flagging | 500.0 | Hour |
| 634E0020 | Pilot Car | 250.0 | Hour |
| 634E0110 | Traffic Control Signs | 3,221.8 | SqFt |
| 634E0120 | Traffic Control, Miscellaneous | Lump Sum | LS |
| 634E0275 | Type 3 Barricade | 32 | Each |
| 634E0330 | Temporary Raised Pavement Markers | 21,500 | Ft |
| 634E0420 | Type C Advance Warning Arrow Board | 12 | Each |
| 634E0600 | 4" Temporary Pavement Marking Tape Type I | 2,544 | Ft |
| 634E0900 | Portable Temporary Traffic Control Signal | 2 | Unit |
| 634E1215 | Contractor Furnished Portable Changeable Message Sign | 6 | Each |
| 650E9000 | Repair Concrete Curb and/or Gutter | 255 | Ft |
| 670E7000 | Reset Drop Inlet Frame and Grate Assembly | 9 | Each |

SPECIFICATIONS

Standard Specifications for Roads and Bridges, 2015 Edition and Required Provisions, Supplemental Specifications and Special Provisions as included in the Proposal.

ENVIRONMENTAL COMMITMENTS

The SDDOT is committed to protecting the environment and uses Environmental Commitments as a communication tool for the Engineer and Contractor to ensure that attention is given to avoid, minimize, and/or mitigate an environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency with permitting authority can delay a project if identified environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. During construction, the Project Engineer will verify that the Contractor has met Environmental Commitment requirements. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office.

Additional guidance on SDDOT's Environmental Commitments can be accessed through the Environmental Procedures Manual found at: <https://dot.sd.gov/media/documents/EnvironmentalProceduresManual.pdf> >

For questions regarding change orders in the field that may have an effect on an Environmental Commitment, the Project Engineer will contact the Environmental Engineer at 605-773-3180 or 605-773-4336 to determine whether an environmental analysis and/or resource agency coordination is necessary.

Once construction is complete, the Project Engineer will review all environmental commitments for the project and document their completion.

COMMITMENT E: STORM WATER

Construction activities constitute less than 1 acre of disturbance.

Action Taken/Required:

At a minimum and regardless of project size, appropriate erosion and sediment control measures must be installed to control the discharge of pollutants from the construction site.

COMMITMENT H: WASTE DISPOSAL SITE

The Contractor will furnish a site(s) for the disposal of construction and/or demolition debris generated by this project.

Action Taken/Required:

Construction and/or demolition debris may be disposed of within the Public ROW.

The waste disposal site(s) will be managed and reclaimed in accordance with the following from the General Permit for Construction/Demolition Debris Disposal Under the South Dakota Waste Management Program issued by the Department of Agriculture and Natural Resources.

The waste disposal site(s) will not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation, aesthetic value of an area, or any threatened or endangered species, as approved by the Environmental Office and the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements will apply:

1. Construction and/or demolition debris consisting of concrete, asphalt concrete, or other similar material will be buried in a trench separate from wood debris. The final cover over the construction and/or demolition debris will consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the Public ROW will be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor will control the access to waste disposal sites not within the Public ROW with fences, gates, and placement of a sign or signs at the entrance to the site stating, No Dumping Allowed.
2. Concrete and asphalt concrete debris may be stockpiled within view of the ROW for a period not to exceed the duration of the project. Prior to project completion, the waste will be removed from view of the ROW or buried, and the waste disposal site reclaimed as noted above.

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58, SDCL 34A-6-1.13, and ARSD 74:27:10:06.

Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law, SDCL 34A-6-1.31.

Cost associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates and signs), and reclamation of the waste disposal site(s) will be incidental to the various contract items.

COMMITMENT I: HISTORIC PRESERVATION OFFICE CLEARANCES

The SDDOT has obtained concurrence with the State Historic Preservation Office (SHPO or THPO) for all work included within the project limits and all department designated sources and designated option material sources, stockpile sites, storage areas, and waste sites provided within the plans.

Action Taken/Required:

All earth disturbing activities not designated within the plans require a cultural resource review prior to scheduling the pre-construction meeting. This work includes but is not limited to: Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas.

The Contractor will arrange and pay for a record search and when necessary, a cultural resource survey. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another qualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review if the site was previously surveyed; however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor will provide ARC with the following: a topographical map or aerial view in which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor will submit the cultural resources survey report to SDDOT Environmental Office, 700 East Broadway Avenue, Pierre, SD 57501-2586. SDDOT will submit the information to the appropriate SHPO/THPO. Allow **30 Days** from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

In the event of an inadvertent discovery of human remains, funerary objects, or if evidence of cultural resources is identified during project construction activities, then such activities within 100 feet of the inadvertent discovery will immediately cease and the Project Engineer will be immediately notified. The Project Engineer will contact the SDDOT Environmental Office, who will contact the appropriate SHPO/THPO within 48 hours of the discovery to determine an appropriate course of action.

SHPO/THPO review does not relieve the Contractor of the responsibility for obtaining any additional permits and clearances for Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas that affect wetlands, threatened and endangered species, or waterways. The Contractor will not utilize a site known or suspected of having contaminated soil or water. The Contractor will provide the required permits and clearances to the Project Engineer at the preconstruction meeting.

| | | | |
|-----------------------------|---------------|-------|-----------------|
| STATE OF SOUTH DAKOTA | PROJECT | SHEET | TOTAL SHEETS |
| | IM-P 0022(85) | 5 | 64 |

Rev 4/12/22 MR

SCOPE OF WORK

This project consists of full depth replacement of Nonreinforced Concrete Pavement (NRCP) in areas where concrete pavement blowups or major failures have occurred. Joints will be sawed and sealed where sealant has failed.

COORDINATION BETWEEN CONTRACTORS

A separate contract for Project IM 0909(91)394 - PCN 065D has been awarded to another Contractor for bridge repair over I90 located 2.1 miles west of I29.

In addition, another separate contract for Project IM-B 2291(01)10 - PCN 01QA has been awarded to another Contractor for bridge replacement on 60th St. N. over I229.

The Contractor will schedule work so as not to interfere with or hinder the progress of the work performed by other Contractors on the projects listed above.

UTILITIES

The Contractor will contact the involved utility companies through South Dakota One Call (1-800-781-7474) prior to starting work. It will be the responsibility of the Contractor to coordinate work with the utility owners to avoid damage to existing facilities.

Utilities are not planned to be affected on this project. If utilities are identified near the improvement area through the SD One Call process as required by South Dakota Codified Law 49-7A and Administrative Rule Article 20:25; the Contractor will contact the Project Engineer to determine if project changes are necessary to avoid utility impacts.

The Contractor will be aware that the existing utilities shown in the plans were surveyed prior to the design of this project and might have been relocated or replaced by a new utility facility prior to construction of this project, might be relocated or replaced by a new utility facility during the construction of this project, or might not require adjustment and may remain in its current location. The Contractor will contact each utility owner and confirm the status of all existing and new utility facilities. The utility contact information is provided elsewhere in the plans or bidding documents.

EXISTING NON-REINFORCED CONCRETE (NRC) PAVEMENT

SD38 in Hartford, SD

The existing pavement is 8" NRC PCC Pavement. Existing contraction joints are spaced at approximately 20'. Longitudinal joints are reinforced with No. 5 x 30" deformed tie bars spaced 48" center to center. Transverse joints are reinforced with 1¼" x 18" plain round dowel bars spaced 12" center to center. The aggregate in the existing NRC Pavement is quartzite.

SD38 over Skunk Creek

The existing pavement is 8" NRC PCC Pavement. Existing contraction joints are spaced at approximately 15'. Longitudinal joints are reinforced with No. 5 x 30" deformed tie bars spaced 48" center to center. Transverse joints are reinforced with 1¼" x 18" plain round dowel bars spaced 12" center to center. The aggregate in the existing NRC Pavement is quartzite.

EXISTING NON-REINFORCED CONCRETE (NRC) PAVEMENT (CONTINUED)

SD38E/W at West 60th St N in Sioux Falls, SD

The existing pavement is 9" NRC PCC Pavement. Existing contraction joints are spaced at approximately 20'. Longitudinal joints are reinforced with No. 5 x 30" deformed tie bars spaced 48" center to center. Transverse joints are reinforced with 1¼" x 18" plain round dowel bars spaced 12" center to center. The aggregate in the existing NRC Pavement is quartzite.

I90E/W near Buffalo Ridge

The existing pavement is 11.5" x 20' NRC PCC Pavement. Existing contraction joints are spaced at approximately 20'. Longitudinal joints are reinforced with No. 5 x 30" deformed tie bars spaced 48" center to center. Transverse joints are reinforced with 1¼" x 18" plain round dowel bars spaced 12" center to center. The aggregate in the existing NRC Pavement is quartzite.

I29N near I90 interchange in Sioux Falls, SD

The existing pavement is 11" NRC PCC Pavement. Existing contraction joints are spaced at approximately 20'. Longitudinal joints are reinforced with No. 5 x 30" deformed tie bars spaced 48" center to center. Transverse joints are reinforced with 1¼" x 18" plain round dowel bars spaced 12" center to center. The aggregate in the existing NRC Pavement is quartzite.

SD34 in Howard, SD

The existing pavement is 8" NRC PCC Pavement. Existing contraction joints are spaced at approximately 20'. Longitudinal joints are reinforced with No. 5 x 30" deformed tie bars spaced 48" center to center. Transverse joints are reinforced with 1¼" x 18" plain round dowel bars spaced 12" center to center. The aggregate in the existing NRC Pavement is quartzite.

I229S near I90 interchange in Sioux Falls, SD

The existing pavement is 12" NRC PCC Pavement. Existing contraction joints are spaced at approximately 20'. Longitudinal joints are reinforced with No. 5 x 30" deformed tie bars spaced 48" center to center. Transverse joints are reinforced with 1¼" x 18" plain round dowel bars spaced 12" center to center. The aggregate in the existing NRC Pavement is quartzite.

I90E/W near I229 interchange in Sioux Falls, SD

The existing pavement is 11.5" NRC PCC Pavement. Existing contraction joints are spaced at approximately 15'. Longitudinal joints are reinforced with No. 5 x 30" deformed tie bars spaced 48" center to center. Transverse joints are reinforced with 1¼" x 18" plain round dowel bars spaced 12" center to center. The aggregate in the existing NRC Pavement is quartzite.

NONREINFORCED PCC PAVEMENT REPAIR – GENERAL

NRC Pavement Repair will be done prior to Grinding PCC Pavement.

New pavement thickness will equal existing pavement thickness ($T_N = T$).

Locations and size (length or width) of concrete repair areas are subject to change in the field, at the discretion of the Engineer, at no additional cost to the state. Payment will be based on actual area replaced.

Existing concrete pavement will be sawed full depth at the beginning and end of the NRCP repair areas. When either the beginning or end of a NRCP repair area falls close to an existing joint or crack, the NRCP repair area will be extended to eliminate the existing joint or crack. Where possible, new working joints will be adjacent to existing working joints.

Saw cuts that extend beyond the repair area will be minimized and filled with a non-shrinkage mortar mix at the Contractor's expense.

Existing concrete pavement in the replacement areas will be removed by the lift out method or by means that minimize damage to the base and sides of remaining in place concrete. Removed material will be removed from within the right-of-way by the end of the workday. Damage to adjacent concrete caused by the Contractor's operations will be removed and replaced at the Contractor's expense.

If the pavement replacement area is entirely on either side of the existing contraction joint, the location of one of the working joints will be at the original location. Any existing dowel bar assemblies/steel bars will be sawed off and removed.

At full roadway width repairs and when specified, a working joint will be reconstructed at both ends of each pavement replacement area as shown in these plans.

Concrete placed adjacent to gravel and asphalt concrete shoulders will be formed full depth to match the width of existing concrete pavement. Asphalt concrete shoulders adjacent to concrete pavement replacements will be repaired with new hot-mix asphalt concrete.

At repair locations where the new working joint is not opposite the existing working joint, the Contractor will place a ¼" preformed asphalt expansion joint material along the longitudinal joint from the existing working joint to the new working joint. The expansion joint material will meet the requirements of AASHTO M33. Cost for this material will be incidental to the contract unit price per square yard for Nonreinforced PCC Pavement Repair.

The initial contraction joint sawing will be performed as soon as practical after placement to avoid random cracking.

Joints (longitudinal and transverse) through and around the repair areas will be sawed and sealed in accordance with the details shown in these plans. Refer to Saw and Seal Joints notes.

SAW AND SEAL JOINTS (NRCP)

Longitudinal and transverse joints at concrete repair areas will be sawed and sealed.

Joint sealing will conform to Section 380.3 P.

Longitudinal and transverse joints in urban and rural sections will be sealed with Hot Poured Elastic Joint Sealer.

Hot Poured Elastic Joint Sealer will be based on visual inspection by the Engineer.

Cost for sawing and sealing for both longitudinal construction and transverse joints will be incidental to the contract unit prices per square yard for Nonreinforced PCC Pavement Repair.

NONREINFORCED PCC PAVEMENT REPAIR

Concrete will meet the requirements stated in Section 380 of the specifications, except as modified by the following notes:

The fine aggregate will be screened over a one-inch square-opening screen just prior to introduction into the concrete paving mix if required by the Engineer.

The slump requirement will be limited to 3" maximum after water reducer is added and the concrete will contain 4.5% to 7.0% entrained air. The concrete will contain a minimum of 50% coarse aggregate by weight. Coarse aggregate will be crushed ledge rock, Size No. 1 unless an alternative gradation is approved by the Concrete Engineer as part of the mix design submittal. The mix design will contain between 650 and 800 lbs total cementitious material with a fly ash content of 20%. The minimum 28-day compressive strength will be 4,000 psi. The Contractor is responsible for the mix design used.

The Contractor will submit a mix design and supporting documentation for approval at least 2 weeks prior to use.

The use of a water reducer at manufacturer's recommended dosage will be required.

Concrete will be cured with white pigmented curing compound (AASHTO M148, Type 2) applied as soon as practical at a rate of 125 square feet per gallon. Concrete will be cured for a minimum of 48 hours before opening to traffic. The 48 hours is based upon a concrete surface temperature of 60°F or higher throughout the cure period. If the concrete temperature falls below 60°F, the cure time will be extended, or other measures taken, at no additional cost to the State. A strength of 3,000 psi must be attained prior to opening to traffic.

Upon placement of the concrete, repair areas will be straight edged to ensure a smooth riding surface and will be textured longitudinally with the pavement by finishing with a stiff broom. Repair areas will then be checked with a 10' foot straight edge. The permissible longitudinal and transverse surface deviation will be 1/8" in 10'.

NONREINFORCED PCC PAVEMENT REPAIR (CONTINUED)

Concrete will be covered with suitable insulation blanket consisting of a layer of closed cell polystyrene foam protected by at least one layer of plastic. Insulation blanket will have an R-value of at least 0.5, as rated by the manufacturer. Insulation blanket will be left in place, except for joint sawing operations, until the 3,000 psi is attained. Insulation blanket will be overlapped on to the existing concrete by 4'. This requirement for covering repair areas with insulation blankets may be waived during periods of hot weather upon approval of the Engineer.

Cost for performing the aforementioned work including sawing and removing concrete, furnishing and placing concrete, sawing and sealing joints, repairing gravel and asphalt concrete shoulders, labor, tools and equipment will be included in the contract unit price per square yard for Nonreinforced PCC Pavement Repair.

STEEL BAR INSERTION (NRCP)

Steel bars will conform to Section 1010.

Locations and quantities of concrete repair are subject to change in the field at the discretion of the Engineer. The Contractor will be responsible for ordering the actual quantity of steel bars necessary to complete the work.

For existing pavement thickness greater than or equal to 10.5" (T >= 10.5"):

The Contractor will insert the steel bars (1½" x 18" epoxy coated plain round dowel bars and No. 11 x 18" epoxy coated deformed tie bars for transverse joints and No. 5 x 24" epoxy coated deformed tie bars for longitudinal joints) into drilled holes in the existing concrete pavement. An epoxy resin adhesive must be used to anchor the steel bar in the drilled hole as per Section 380.3 C.1.

For existing pavement thickness greater than or equal to 8.5" and less than 10.5" (T >= 8.5" and T < 10.5"):

The Contractor will insert the steel bars (1¼" x 18" epoxy coated plain round dowel bars and No. 9 x 18" epoxy coated deformed tie bars for transverse joints and No. 5 x 24" epoxy coated deformed tie bars for longitudinal joints) into drilled holes in the existing concrete pavement. An epoxy resin adhesive must be used to anchor the steel bar in the drilled hole as per Section 380.3 C.1.

For existing pavement thickness less than 8.5" (T < 8.5"):

The Contractor will insert the steel bars (1" x 18" epoxy coated plain round dowel bars and No. 8 x 18" epoxy coated deformed tie bars for transverse

joints and No. 5 x 24" epoxy coated deformed tie bars for longitudinal joints) into drilled holes in the existing concrete pavement. An epoxy resin adhesive must be used to anchor the steel bar in the drilled hole as per Section 380.3 C.1.

Steel bars will be inserted in the transverse joint on 18" centers. The first steel bar in the transverse joint will be placed 9" from the edge of the slab closest to centerline. Steel bars will be inserted in the longitudinal joint on 30" centers and will be a minimum of 15" from either transverse joint. A typical one-lane patch 12' wide and 6' long will require 18 steel bars (8 in each transverse joint and 2 in the longitudinal joint). It will be necessary to laterally adjust the location of some of the inserted steel bars when the dimensions above interfere with existing steel bar locations.

A rigid frame or mechanical device will be required to guide the drill to ensure proper horizontal and vertical alignment of the steel bars in the drilled holes

TIE BAR RETROFIT, STITCHING

Drilling of holes and epoxy resin adhesive will conform to Section 380. Steel bars will conform to Section 1010.

Tie Bar Retrofit, Stitching will be done prior to Grinding PCC Pavement. If this sentence is applicable.

Tie Bar Retrofit, Stitching will be done on longitudinal joints and random cracks as marked out by the Engineer.

The Contractor will insert No. 5 epoxy coated deformed tie bars into drilled holes in the existing concrete pavement. An epoxy resin adhesive must be used to anchor the steel bar in the drilled hole. A rotary drill or other approved drill will be used that will not damage the concrete surface. The diameter of the disturbed surface from drilling will be less than 2 inches. A rigid frame or mechanical device will be required to guide the drill to ensure the proper angle of the steel bars in the drilled holes.

The diameter of the drilled holes in the existing concrete pavement for the steel bars will not be less than 1/8 inch nor more than 3/8 inch greater than the overall diameter of the steel bar. The holes will be drilled at an angle alternating from opposite sides of the joint to produce a cross-stitching pattern.

Fill the drilled holes sufficiently with epoxy prior to the insertion of the tie bar such that the epoxy will be level with the top of the concrete pavement after insertion of the tie bar. Rotate the steel bar during insertion to eliminate voids and ensure complete bonding of the bar. Insertion of the bars by the dipping method will not be allowed. The top of the drilled hole will be filled with epoxy or excess epoxy removed such that the epoxy is level with the existing pavement.

No bars will be inserted within 15" of an existing transverse contraction joint. Any bars not functioning or damaged will be repaired or replaced at the Contractor's expense.

Cost for the epoxy resin adhesive, tie bars, drilling of holes, debris or loose material removal, applying the adhesive, inserting the tie bars into the drilled holes and incidentals necessary for the insertion of the tie bars will be included in the contract unit price per each for Tie Bar Retrofit, Stitching.

GRINDING PCC PAVEMENT

PCC Pavement Repair will be done prior to Grinding PCC Pavement. Grinding PCC Pavement will be done prior to sawing and sealing joints. Approximately 4' of grinding is expected on either side of the joint line in the tie bar retrofit stitching areas of SD38 over Skunk Creek, I90 near Buffalo Ridge and I229 near I90 interchange in Sioux Falls.

RESEAL PCC PAVEMENT JOINT

Existing transverse and longitudinal joints will be cleaned and resealed for the full width of the joints with Hot Poured Elastic Joint Sealer; except on SD34, where the joints will be cleaned and resealed with Asphalt Repair Mastic Type 2.

Joints will not be sealed unless they are thoroughly clean and dry. Cleaning will be accomplished by sandblasting and other tools as necessary. Sand blasting of both sides of the vessel will be accomplished simultaneously with a mechanical device approved by the Engineer. Just prior to sealing, each joint will be blown out using a jet of compressed air to remove all traces of dust. Final joint width is to be kept as narrow as possible and may only be widened to provide a clean surface. Each joint will not be widened more than 1/8 inch if sawing is utilized to prepare the joint for sealant.

If sawing is used this may require 2 passes with the saw, one pass for each side of the joint.

In certain areas the joint may be wider than the original construction. It may be necessary to provide backer rod in the wide areas. Any additional cost to perform this work will be at no additional cost to the State. The Contractor will be responsible to verify joint widths prior to establishing the contract unit price.

It is not essential that all of the sealant be removed. Remaining sealant adhering to the sides may remain in place if the Engineer determines that it is not detrimental to the joint.

Cost for cleaning and resealing transverse and longitudinal joints will be included in the contract unit price per foot for Reseal PCC Pavement Joint – Hot Pour.

SEAL RANDOM CRACKS IN PCC PAVEMENT

Random cracks will be repaired in accordance with the detail for Sealing Random Cracks. Reservoir dimensions may vary slightly from the details, due to the nature of this operation. However, any variance due to Contractor negligence will be repaired at the Contractor's expense.

Only those random cracks in the existing concrete pavement that are open and accept water and incompressible material as selected by the Engineer will be prepared and sealed with Hot Poured Elastic Joint Sealer.

Prior to sealing, each random crack will be routed and thoroughly cleaned with compressed air or by other methods satisfactory to the Engineer. Routing will be performed with a saw designed for that purpose.


Random cracks narrower than 1/2 inch will be routed and sealed 1/2 inch wide by 1/2 inch deep.

Random cracks wider than 1/2 inch may require the placement of a backer rod prior to sealing. Use of backer rod should be limited to locations where, once placed, the top of the backer rod will be a minimum of 2 1/4 inches below the top surface of the pavement. The hot pour in cracks wider than 1/2" should be placed 2 inch thick with the final surface of the hot pour remaining recessed 1/4 inch below the top surface of the pavement.

Sealant will be placed in the routed reservoir with equipment and by methods that insure complete and uniform filling. Hot Poured Elastic Joint Sealer will be placed level with the driving surface of the concrete for cracks 1/2" or narrower. Any excess or overrun of sealant will be removed by the Contractor at no additional cost to the State.

SEAL RANDOM CRACKS IN PCC PAVEMENT (CONTINUED)

Seal Random Cracks in PCC Pavement will be measured by the foot to the nearest 0.1 foot of random cracks sealed and accepted and will be paid for at the contract unit price per foot measured for payment. Payment will be full compensation for labor, equipment, material and incidentals required for crack routing, cleaning, furnishing and installing backer rod when necessary, furnishing and placing sealant and removing routed and foreign material from the roadway.



SD34 JOINT SEALING WITH ASPHALT REPAIR MASTIC TYPE 2

Pavement joints on SD34 specified for joint sealing will be cleaned and resealed with Asphalt Repair Mastic Type 2.

Pavement joints will be cleaned in accordance with the notes for RESEAL PCC PAVEMENT JOINT.

The Special Provision for Asphalt Concrete Crack Leveling will apply except that use of a compressed air heated lance will not be required for surface preparation, and references to placing mastic material on pavement surfaces (other than in the joint itself) do not apply.

5" SAW CUT OF NRC AT TERMINAL ANCHOR LOCATIONS

A 5" opening saw cut is required in the NRC at these terminal anchor locations and may require a multi-step process if the existing sealant joint is fully compressed. If the existing joint is fully compressed, the Contractor will be required to cut the joint to a 3" opening across the right lane. As soon as possible and on the same day, the Contractor will be required to adjust traffic control to install a lane closure to provide a 3" opening saw cut across the left lane. Traffic will not be permitted across any expansion joint wider than 3". Installation of the 5" joint membrane will not be permitted for 1-week.

Upon completion of the 1-week waiting period, the contractor will be required to set up traffic control in the right lane, resaw the joint to the required 5" and install the new 5" membrane joint sealant in the right lane. As soon as possible and on the same day, the Contractor will be required to adjust traffic control to install a lane closure to resaw the joint in the left lane to the required 5" and install the new 5" membrane joint sealant in the left lane.

See the traffic control details in the plans for lane closure details for this work.

REPAIR TYPE A SPALLS

Spall repair work will be done prior to Grinding PCC Pavement.

Concrete Patch Material will be Type III conforming to Section 390.2 B.3. SF.

As an alternative, the Contractor may remove concrete by milling, provided it produces results similar to the sawing and chipping process described in the Specifications.

It is anticipated that a number of locations scheduled for Type A Spall Repair will have deteriorated to the point of needing full depth repair. Additional Quantities are included in the Table(s) for NRC Pavement Repair for this work. The Engineer will determine these locations on construction.

Spalls which are repaired according to plans and specifications and exhibit partial respalling or cracking, will be repaired to the satisfaction of the Engineer at no additional cost to the State.

NOSING MATERIAL FOR CONCRETE REPAIR

A quantity of Nosing Material has been set up for use if spalling occurs, an existing crack is too close to the new saw cut, or a crack intersects the new saw cut for the Membrane Sealant Expansion Joint. The following quantity of 35 square feet is included in the Estimate of Quantities. This is based on a width of 26 feet length and 0.3 feet wide at full 11.5" depth. Actual depth may vary from full 11.5" depth to 2" partial depth spalls. The Engineer will determine if and where this nosing material is to be used.

The nosing material used must be one of types from the approved product list for Nosing Material. The nosing material will be furnished from one source and must be installed in accordance with the manufacturer's recommendations as approved by the Engineer.

The nosing material will be measured to the nearest 0.1 square foot. The Engineer will make measurements on the driving surface to the nearest 0.1 foot. Joint nosing material repairs will be paid for at the contract unit price per nearest square foot installed. Cost for material, removal of concrete, cleaning substrate, labor, equipment, tools and any incidentals necessary to prep, furnish and install the nosing material will be incidental to the contract unit price per square foot for Joint Nosing Material.

REPAIR CONCRETE CURB AND/OR GUTTER

The existing concrete curb and gutter is Type B68 in Hartford, SD. The existing curb and gutter will match in place.

Refer to the repair tables and details for locations of removal and replacement. These locations will be designated by the Engineer during construction.

If the end of any section to be removed does not fall on an existing joint, a sawed joint (4" deep) must be made to provide a vertical face for the new joint.

Existing foundation material will be shaped and compacted to a firm, uniform bearing surface, conforming to the existing section or established grades as set by the Engineer.

Unsuitable foundation material will be removed and replaced as directed. Gravel cushion material will be furnished by the Contractor.

Cost for labor, equipment, material, and incidentals required for excavation and providing cushion material will be incidental to the contract unit prices for the various items.

Curb and Gutter will be tied to existing PCC pavement with drilled in No. 5 x 24" epoxy coated deformed tie bars spaced 30" center to center or by salvaged in place tie bars. Also, two No. 5 x 24" epoxy coated deformed tie bar will be drilled into the existing curb and gutter at each end of the replacement area. Refer to the notes for STEEL BAR INSERTION.

Cost for this work will be included in the contract unit price per each for Insert Steel Bar in PCC Pavement.

The Contractor will satisfactorily restore disturbed areas adjacent to the new concrete placement to the satisfaction of the Engineer. Cost for this restoration work will be incidental to the contract unit prices for the various items.

Standard specifications for sawing, removing and replacing concrete curb and/or gutter, and material composition will apply except that the cost for such will be included in the contract unit price per foot for Repair Concrete Curb and/or Gutter.

REMOVE DROP INLET FRAME AND GRATE ASSEMBLY FOR RESET

The Contractor will reset drop inlet frame and grates on drop inlets that are in place on the 60th St N location along SD38. The elevations of the frame and grate will be flush with the adjacent concrete at each location.

| Hwy | DMI | L/R | Class M6 Concrete (CuYd) | Quantity |
|--------------|--------|-----|--------------------------|----------|
| SD38E | 364.68 | R | 0.05 | 1 |
| SD38E | 364.64 | R | 0.05 | 1 |
| SD38E | 364.55 | R | 0.05 | 1 |
| SD38W | 364.72 | R | 0.05 | 1 |
| SD38W | 364.68 | R | 0.05 | 1 |
| SD38W | 364.64 | R | 0.05 | 1 |
| SD38W | 364.52 | R | 0.05 | 1 |
| SD38W | 364.50 | R | 0.05 | 1 |
| SD38W | 364.48 | R | 0.05 | 1 |
| Grand Totals | | | 0.45 | 9 |

*The quantity of Class M6 Concrete will be incidental to the contract unit price per each for Reset Drop Inlet Frame and Grate Assembly

ASPHALT CONCRETE COMPOSITE

If damage to the shoulder occurs from driver behavior, not to the fault of the Contractor as determined by the Engineer, the damaged shoulder areas will be repaired with Asphalt Concrete Composite. Removal of damaged asphalt on the shoulders prior to placement will be incidental to the contract unit price for Asphalt Concrete Composite. The Asphalt Concrete Composite item is not intended for repairs/fill adjacent to repair areas due to forms or Contractor operations.

Asphalt concrete composite will be placed at a thickness of 3" and will not require asphalt for flush seal or sand for flush seal.




TABLE FOR SUMMARY OF PCC REPAIRS

| HWY | BEGIN | | END | | EXCEPTION LENGTH | Beg DMI | End DMI | NRCP REPAIR (SqYd) | REPAIR CONCRETE CURB/GUTTER (Ft) | INSERT STEEL BAR IN NRCP (Each) | INSERT DOWEL (Each) | REPAIR TYPE A SPALL IN NRCP (SqFt) | TIE BAR RETROFIT STITCHING (Each) |
|---------------------|--------|-------|--------|-------|------------------|---------|---------|--------------------|----------------------------------|---------------------------------|---------------------|------------------------------------|-----------------------------------|
| | MRM | DISP | MRM | DISP | | | | | | | | | |
| SD38 | 356.00 | 0.135 | 356.69 | 0.018 | 0 | 356.135 | 356.708 | 2017.6 | 255 | 4325 | 2336 | 22 | |
| SD38 | 360.00 | 0.138 | 360.22 | 0.114 | 0 | 360.138 | 360.334 | 170.4 | | 358 | 190 | | 70 |
| SD38E | 364.26 | 0.116 | 364.75 | 0.000 | 0 | 364.376 | 364.750 | 512.6 | | 1068 | 614 | | |
| SD38W | 364.26 | 0.116 | 364.75 | 0.000 | 0 | 364.376 | 364.750 | 1160.5 | | 2419 | 1390 | | |
| I90E | 390.37 | 0.041 | 397.00 | 0.252 | 0 | 390.411 | 397.252 | 60.4 | | 186 | 109 | | 77 |
| I90W | 390.29 | 0.136 | 397.00 | 0.252 | 0 | 390.426 | 397.252 | 397.3 | | 1220 | 717 | | |
| I29N | 83.70 | 0.096 | 85.35 | 0.116 | 0 | 83.796 | 85.466 | 129.9 | | 401 | 194 | | |
| SD34 | 364.00 | 0.987 | 366.37 | 0.012 | 0 | 364.987 | 366.382 | 2589.8 | | 5191 | 2846 | | |
| I229S | 8.28 | 0.584 | 10.84 | 0.000 | 0 | 8.864 | 10.840 | 732.5 | | 1297 | 540 | | 188 |
| I90E | 401.00 | 0.464 | 401.61 | 0.143 | 0 | 401.464 | 401.753 | 139.9 | | 170 | 100 | | |
| I90W | 401.00 | 0.468 | 401.61 | 0.142 | 0 | 401.468 | 401.752 | 585.8 | | 1988 | 520 | | |
| GRAND TOTALS | | | | | | | | 8,496.7 | 255 | 18,623 | 9,556 | 22 | 335 |

TABLE FOR SUMMARY OF GRINDING PCC PAVEMENT

| HWY | BEGIN | | END | | EXCEPTION LENGTH (Ft) | Beg DMI | End DMI | WIDTH OF GRINDING (Ft) | LENGTH OF GRINDING (Ft) | GENERAL AREAS | GRINDING PCC PAVEMENT (SqYd) |
|---------------------|--------|-------|--------|-------|-----------------------|---------|---------|------------------------|-------------------------|----------------------------|------------------------------|
| | MRM | DISP | MRM | DISP | | | | | | | |
| SD38 | 360.00 | 0.138 | 360.22 | 0.114 | 859.9 | 360.138 | 360.334 | 8 | 175.0 | Tie Bar Retrofit Stitching | 155.6 |
| I90E | 390.37 | 0.041 | 397.00 | 0.252 | 36,024.2 | 390.411 | 397.252 | 8 | 96.3 | Tie Bar Retrofit Stitching | 85.6 |
| I90W | 390.29 | 0.136 | 397.00 | 0.252 | 35,945.0 | 390.426 | 397.252 | 8 | 96.3 | Tie Bar Retrofit Stitching | 85.6 |
| I229S | 8.28 | 0.584 | 10.84 | 0.000 | 9,963.3 | 8.864 | 10.840 | 8 | 470.0 | Tie Bar Retrofit Stitching | 417.8 |
| GRAND TOTALS | | | | | | | | | | | 744.4 |

TABLE FOR JOINT RESEALING

| | | | | | | | | RESEAL LONGITUDINAL JOINTS (Ft) | RESEAL LONGITUDINAL JOINTS TYPE | RESEAL TRANSVERSE JOINTS (Ft) | RESEAL TRANSVERSE JOINTS TYPE |
|---------------------|--------|-------|--------|-------|-----------|---------|---------|--|--|--|--|
| | BEGIN | | END | | EXCEPTION | | | | | | |
| HWY | MRM | DISP | MRM | DISP | LENGTH | Beg DMI | End DMI | | | | |
| SD38 | 356.00 | 0.135 | 356.69 | 0.018 | 0 | 356.135 | 356.708 | 5,446 | Hot Pour | 14,704 | Hot Pour |
| SD38 | 360.00 | 0.138 | 360.22 | 0.114 | 0 | 360.138 | 360.334 | 310 | Hot Pour | 621 | Hot Pour |
| SD38E | 364.26 | 0.116 | 364.75 | 0.000 | 0 | 364.376 | 364.750 | 1,580 | Hot Pour | 3,318 | Hot Pour |
| SD38W | 364.26 | 0.116 | 364.75 | 0.000 | 0 | 364.376 | 364.750 | 1,975 | Hot Pour | 4,147 | Hot Pour |
| I90E | 390.37 | 0.041 | 397.00 | 0.252 | 0 | 390.411 | 397.252 | 3,612 | Hot Pour | 4,696 | Hot Pour |
| I90W | 390.29 | 0.136 | 397.00 | 0.252 | 0 | 390.426 | 397.252 | 3,604 | Hot Pour | 4,685 | Hot Pour |
| I29N | 83.70 | 0.096 | 85.35 | 0.116 | 0 | 83.796 | 85.466 | 882 | Hot Pour | 1,146 | Hot Pour |
| SD34 | 364.00 | 0.987 | 366.37 | 0.012 | 0 | 364.987 | 366.382 | 22,097 | Hot Pour | 40,879 | Hot Pour |
| I229S | 8.28 | 0.584 | 10.84 | 0.000 | 0 | 8.864 | 10.840 | 3,130 | Hot Pour | 5,947 | Hot Pour |
| I90E | 401.00 | 0.464 | 401.61 | 0.143 | 0 | 401.464 | 401.753 | 153 | Hot Pour | 407 | Hot Pour |
| I90W | 401.00 | 0.468 | 401.61 | 0.142 | 0 | 401.468 | 401.752 | 150 | Hot Pour | 400 | Hot Pour |
| GRAND TOTALS | | | | | | | | 42,938 | | 80,949 | |
| | BEGIN | | END | | EXCEPTION | | | RESEAL LONGITUDINAL JOINTS (lb) | RESEAL LONGITUDINAL JOINTS TYPE | | DESCRIPTION |
| HWY | MRM | DISP | MRM | DISP | LENGTH | Beg DMI | End DMI | | | | |
| SD34 | 364.00 | 0.987 | 366.37 | 0.012 | 0 | 364.987 | 366.382 | 137,794 | Type II Mastic | | Centerline Joint |
| GRAND TOTAL | | | | | | | | 137,794 | | | |

SD38 IN HARTFORD

| DMI | WB DRIVING LANE | | CENTER TURN LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | * REMOVE CONCRETE CURB &/OR GUTTER | * TYPE CONCRETE C&G BY WB DRIVING LANE | * TYPE CONCRETE C&G BY EB DRIVING LANE | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | | REPAIR TYPE A SPALL SqFt | |
|---------|-----------------|------|------------------|------|-----------------|------|-------------------|---------------------------|------------------------------------|--|--|---|------------------------------------|------------------------------------|--------------------------|-------------------------------------|
| | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | | | Ft | Ft | Ft | 1" x 18" PLAIN ROUND DOWEL BARS Each | No. 8 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | INSERT STEEL BAR IN NRCP TOTAL Each |
| 356.124 | 10 | 12 | 6 | 12 | 6 | 14 | 30.7 | W | | | | 48 | | 4 | 52 | |
| 356.127 | 6 | 4 | 6 | 12 | 6 | 20 | 24.0 | R | | | | | 36 | 6 | 42 | 28 |
| 356.133 | 8 | 12 | 4 | 4 | 4 | 4 | 14.2 | R | | | | | 24 | 8 | 32 | 20 |
| 356.134 | | | | | 6 | 14 | 9.3 | R | | | | | 16 | 4 | 20 | 12 |
| 356.139 | | | | | 60 | 4 | 26.7 | R | | | | | 4 | 48 | 52 | 12 |
| 356.140 | 20 | 12 | | | 6 | 14 | 36.0 | R | | | | | 32 | 12 | 44 | 24 |
| 356.144 | | | | | 4 | 4 | 1.8 | R | | | | | 4 | 4 | 8 | 4 |
| 356.146 | | | 8 | 12 | | | 10.7 | R | 101 | 58 | 43 | | 16 | 6 | 22 | 12 |
| 356.155 | 6 | 12 | 8 | 12 | 8 | 14 | 31.1 | W | | | | 48 | | 3 | 51 | |
| 356.156 | | | | | 6 | 12 | 8.0 | R | | | | | 16 | 2 | 18 | 12 |
| 356.157 | | | | | 4 | 4 | 1.8 | R | | | | | 4 | 4 | 8 | 4 |
| 356.158 | | | | | 6 | 12 | 8.0 | R | | | | | 16 | 2 | 18 | 12 |
| 356.159 | 8 | 8 | | | 6 | 12 | 15.1 | R | 21 | 21 | | | 26 | 5 | 31 | 20 |
| 356.162 | 6 | 12 | | | 6 | 14 | 17.3 | R | | | | | 32 | 6 | 38 | 24 |
| 356.164 | | | | | 6 | 12 | 8.0 | R | | | | | 16 | 2 | 18 | 12 |
| 356.165 | 6 | 14 | 6 | 12 | 4 | 4 | 19.1 | R | | | | | 36 | 6 | 42 | 28 |
| 356.166 | | | | | 4 | 4 | 1.8 | R | | | | | 4 | 4 | 8 | 4 |
| 356.169 | 4 | 4 | 4 | 4 | 4 | 4 | 5.3 | R | | | | | 12 | 10 | 22 | 12 |
| 356.173 | 6 | 14 | 6 | 12 | 6 | 12 | 25.3 | W | | | | 48 | | 4 | 52 | |
| 356.176 | 6 | 14 | 6 | 12 | 6 | 12 | 25.3 | W | | | | 48 | | 4 | 52 | |
| 356.177 | 6 | 14 | 6 | 12 | 6 | 8 | 22.7 | R | | | | | 42 | 6 | 48 | 32 |
| 356.179 | 6 | 14 | 6 | 12 | | | 17.3 | R | | | | | 32 | 6 | 38 | 24 |
| 356.183 | 6 | 14 | | | | | 9.3 | R | | | | | 16 | 2 | 18 | 12 |
| 356.187 | 6 | 14 | 6 | 12 | | | 17.3 | R | | | | | 32 | 6 | 38 | 24 |
| 356.190 | 6 | 14 | | | | | 9.3 | R | | | | | 16 | 2 | 18 | 12 |
| 356.194 | 4 | 4 | 4 | 4 | 6 | 8 | 8.9 | R | | | | | 18 | 10 | 28 | 16 |
| 356.198 | 4 | 4 | 4 | 4 | | | 3.6 | R | | | | | 8 | 6 | 14 | 8 |
| 356.201 | 4 | 4 | 4 | 4 | 6 | 8 | 8.9 | R | | | | | 18 | 10 | 28 | 16 |
| 356.205 | 4 | 4 | 4 | 4 | 4 | 6 | 6.2 | R | | | | | 16 | 10 | 26 | 14 |
| 356.208 | 4 | 4 | 4 | 4 | | | 3.6 | R | | | | | 8 | 6 | 14 | 8 |
| 356.212 | 4 | 4 | 4 | 4 | 6 | 12 | 11.6 | R | | | | | 24 | 8 | 32 | 20 |
| 356.215 | 6 | 14 | | | | | 9.3 | R | | | | | 16 | 2 | 18 | 12 |
| 356.219 | 4 | 4 | 4 | 4 | | | 3.6 | R | | | | | 8 | 6 | 14 | 8 |
| 356.223 | 4 | 4 | 4 | 4 | | | 3.6 | R | 4 | 4 | | | 8 | 6 | 14 | 8 |
| 356.227 | 4 | 4 | | | 6 | 8 | 7.1 | R | | | | | 14 | 6 | 20 | 12 |
| 356.230 | 6 | 20 | | | 6 | 12 | 21.3 | R | | | | | 32 | 4 | 36 | 24 |
| 356.233 | 6 | 20 | | | | | 13.3 | R | | | | | 16 | 2 | 18 | 12 |
| 356.237 | | | 6 | 14 | | | 9.3 | R | 4 | | 4 | | 16 | 4 | 20 | 12 |
| 356.241 | | | 6 | 14 | | | 9.3 | R | | | | | 16 | 4 | 20 | 12 |
| 356.244 | | | 4 | 6 | 4 | 4 | 4.4 | R | | | | | 12 | 8 | 20 | 10 |
| 356.248 | | | 4 | 4 | 4 | 4 | 3.6 | R | | | | | 8 | 8 | 16 | 8 |
| 356.252 | | | 6 | 12 | | | 8.0 | R | | | | | 16 | 4 | 20 | 12 |
| 356.256 | | | 6 | 12 | | | 8.0 | R | | | | | 16 | 4 | 20 | 12 |
| 356.259 | | | 6 | 12 | | | 8.0 | R | | | | | 16 | 4 | 20 | 12 |
| 356.262 | 6 | 12 | | | 4 | 20 | 16.9 | R | | | | | 32 | 6 | 38 | 24 |
| 356.266 | 6 | 20 | | | | | 13.3 | R | 6 | 6 | | | 16 | 2 | 18 | 12 |
| 356.273 | 6 | 12 | | | | | 8.0 | R | | | | | 16 | 2 | 18 | 12 |
| 356.277 | 4 | 4 | | | | | 1.8 | R | | | | | 4 | 2 | 6 | 4 |
| 356.281 | 4 | 4 | 4 | 4 | 6 | 12 | 11.6 | R | | | | | 24 | 8 | 32 | 20 |
| 356.286 | 4 | 4 | | | | | 1.8 | R | | | | | 4 | 2 | 6 | 4 |
| 356.295 | 4 | 4 | 4 | 4 | 4 | 4 | 5.3 | R | | | | | 12 | 10 | 22 | 12 |
| 356.298 | 4 | 4 | | | 4 | 4 | 3.6 | R | | | | | 8 | 6 | 14 | 8 |
| 356.302 | | | | | | | | R | | | | | | | | 1.00 |
| 356.306 | | | | | 6 | 10 | 6.7 | R | | | | | 12 | 4 | 16 | 10 |
| 356.310 | 4 | 4 | 4 | 4 | 6 | 8 | 8.9 | R | | | | | 18 | 10 | 28 | 16 |
| 356.313 | 6 | 12 | 6 | 10 | | | 14.7 | R | | | | | 28 | 2 | 30 | 22 |
| 356.317 | 4 | 4 | 4 | 4 | | | 3.6 | R | | | | | 8 | 6 | 14 | 8 |
| 356.321 | 6 | 18 | | | | | 12.0 | R | | | | | 16 | 2 | 18 | 12 |
| 356.324 | 6 | 18 | | | | | 12.0 | R | | | | | 16 | 2 | 18 | 12 |
| 356.328 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 |
| 356.332 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 |
| 356.335 | 4 | 4 | 4 | 4 | | | 3.6 | R | | | | | 8 | 6 | 14 | 8 |

* Cost for this work will be included in the contract unit price per foot for Repair Concrete Curb and/or Gutter

SD38 IN HARTFORD

| DMI | WB DRIVING LANE | | CENTER TURN LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | * REMOVE CONCRETE CURB &/OR GUTTER Ft | * TYPE CONCRETE C&G BY WB DRIVING LANE Ft | * TYPE CONCRETE C&G BY EB DRIVING LANE Ft | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | | REPAIR TYPE A SPALL SqFt | | |
|---------|-----------------|---------|------------------|---------|-----------------|---------|----------------------|------------------------------|--|--|--|---|-------------------|----|-----------------------------|----|------|
| | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | | | 1" x 18" PLAIN ROUND DOWEL BARS Each | No. 8 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | INSERT STEEL BAR IN NRCP TOTAL Each | DOWEL BAR Each | | | | |
| 356.339 | 4 | 4 | 4 | 4 | | | 3.6 | R | | | | | 8 | 6 | 14 | 8 | |
| 356.342 | 4 | 4 | 4 | 4 | | | 3.6 | R | | | | | 8 | 6 | 14 | 8 | |
| 356.346 | 80 | 4 | 4 | 4 | | | 37.3 | R | 4 | 4 | | | 8 | 36 | 44 | 20 | |
| 356.349 | 6 | 16 | | | | | 10.7 | R | | | | | 16 | 2 | 18 | 12 | |
| 356.353 | 6 | 16 | | | | | 10.7 | R | | | | | 16 | 2 | 18 | 12 | |
| 356.357 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.360 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | 1.00 |
| 356.375 | 4 | 4 | | | | | 1.8 | R | | | | | 4 | 2 | 6 | 4 | |
| 356.379 | 4 | 4 | 4 | 4 | 4 | 4 | 5.3 | R | | | | | 12 | 10 | 22 | 12 | |
| 356.383 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.386 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.389 | | | | | 6 | 8 | 5.3 | R | | | | | 10 | 4 | 14 | 8 | |
| 356.393 | | | 4 | 4 | 4 | 4 | 3.6 | R | | | | | 8 | 8 | 16 | 8 | |
| 356.401 | | | | | 6 | 14 | 9.3 | R | | | | | 16 | 4 | 20 | 12 | 1.00 |
| 356.404 | | | | | 6 | 8 | 5.3 | R | | | | | 10 | 4 | 14 | 8 | |
| 356.407 | | | | | 6 | 12 | 8.0 | R | | | | | 16 | 2 | 18 | 12 | |
| 356.411 | | | | | 6 | 12 | 8.0 | R | | | | | 16 | 2 | 18 | 12 | |
| 356.414 | | | 4 | 4 | 4 | 4 | 3.6 | R | | | | | 8 | 8 | 16 | 8 | |
| 356.418 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.421 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.425 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.433 | 4 | 6 | 6 | 6 | 6 | 18 | 18.7 | R | 4 | | 4 | | 32 | 10 | 42 | 24 | |
| 356.438 | 4 | 4 | | | 6 | 16 | 12.4 | R | | | | | 20 | 6 | 26 | 16 | |
| 356.440 | | | 4 | 4 | 6 | 8 | 7.1 | R | | | | | 14 | 8 | 22 | 12 | 1.00 |
| 356.446 | | | 6 | 12 | 6 | 16 | 18.7 | R | | | | | 32 | 4 | 36 | 24 | |
| 356.448 | | | 4 | 4 | | | 1.8 | R | 12 | 12 | | | 4 | 4 | 8 | 4 | |
| 356.451 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | 1.00 |
| 356.454 | | | | | 4 | 4 | 1.8 | R | | | | | 4 | 4 | 8 | 4 | 1.00 |
| 356.458 | | | | | 4 | 4 | 1.8 | R | 4 | | 4 | | 4 | 4 | 8 | 4 | 1.00 |
| 356.461 | | | | | 6 | 10 | 6.7 | R | | | | | 12 | 4 | 16 | 10 | |
| 356.465 | 6 | 6 | 4 | 4 | 4 | 4 | 7.6 | R | | | | | 16 | 10 | 26 | 14 | |
| 356.473 | 4 | 4 | 4 | 4 | 4 | 4 | 5.3 | R | | | | | 12 | 10 | 22 | 12 | |
| 356.476 | | | 4 | 4 | 4 | 4 | 3.6 | R | 4 | 4 | | | 8 | 8 | 16 | 8 | |
| 356.479 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.483 | | | 4 | 4 | 4 | 4 | 3.6 | R | | | | | 8 | 8 | 16 | 8 | 1.00 |
| 356.490 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.494 | | | 4 | 4 | 4 | 4 | 3.6 | R | | | | | 8 | 8 | 16 | 8 | |
| 356.498 | | | | | 4 | 4 | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.501 | | | | | 4 | 4 | 1.8 | R | | | | | 4 | 4 | 8 | 4 | 1.00 |
| 356.505 | | | 4 | 4 | 4 | 4 | 3.6 | R | | | | | 8 | 8 | 16 | 8 | |
| 356.508 | | | 4 | 4 | 4 | 4 | 3.6 | R | | | | | 8 | 8 | 16 | 8 | |
| 356.512 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.516 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.519 | | | | | 4 | 4 | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.523 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.526 | | | | | 4 | 6 | 2.7 | R | | | | | 8 | 4 | 12 | 6 | |
| 356.530 | | | 4 | 4 | 4 | 4 | 3.6 | R | | | | | 8 | 8 | 16 | 8 | 1.00 |
| 356.533 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.540 | | | 4 | 4 | 4 | 4 | 3.6 | R | 15 | | 15 | | 8 | 8 | 16 | 8 | 1.00 |
| 356.544 | 6 | 10 | 6 | 8 | 4 | 4 | 13.8 | R | | | | | 26 | 10 | 36 | 22 | 1.00 |

* Cost for this work will be included in the contract unit price per foot for Repair Concrete Curb and/or Gutter

SD38 IN HARTFORD

| DMI | WB DRIVING LANE | | CENTER TURN LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | * REMOVE CONCRETE CURB &/OR GUTTER Ft | * TYPE CONCRETE C&G BY WB DRIVING LANE Ft | * TYPE CONCRETE C&G BY EB DRIVING LANE Ft | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | | REPAIR TYPE A SPALL SqFt | | |
|-------------------------------|-----------------|------|------------------|------|-----------------|------|-------------------|---------------------------|---------------------------------------|---|---|---|------------------------------------|------------------------------------|--------------------------|-------------------------------------|----------------|
| | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | | | | | | 1" x 18" PLAIN ROUND DOWEL BARS Each | No. 8 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | INSERT STEEL BAR IN NRCP TOTAL Each | DOWEL BAR Each |
| 356.551 | | | 4 | 4 | 4 | 4 | 3.6 | R | | | | | 8 | 8 | 16 | 8 | |
| 356.555 | | | | | 6 | 16 | 10.7 | R | | | | | 16 | 4 | 20 | 12 | 1.00 |
| 356.558 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.562 | | | 4 | 4 | 4 | 4 | 3.6 | R | | | | | 8 | 8 | 16 | 8 | |
| 356.566 | 4 | 4 | 4 | 4 | 4 | 4 | 5.3 | R | | | | | 12 | 10 | 22 | 12 | |
| 356.569 | | | 4 | 4 | 4 | 4 | 3.6 | R | | | | | 8 | 8 | 16 | 8 | |
| 356.573 | | | | | 4 | 4 | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.576 | | | 4 | 4 | 4 | 4 | 3.6 | R | | | | | 8 | 8 | 16 | 8 | |
| 356.579 | | | | | 6 | 18 | 12.0 | R | | | | | 16 | 4 | 20 | 12 | |
| 356.583 | | | | | 6 | 8 | 5.3 | R | | | | | 10 | 4 | 14 | 8 | |
| 356.587 | 4 | 4 | 4 | 4 | 4 | 4 | 5.3 | R | | | | | 12 | 10 | 22 | 12 | |
| 356.591 | | | | | 4 | 4 | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.594 | | | | | 6 | 18 | 12.0 | R | | | | | 16 | 4 | 20 | 12 | 1.00 |
| 356.601 | | | | | 6 | 16 | 10.7 | R | 4 | 4 | | | 16 | 4 | 20 | 12 | |
| 356.605 | | | 6 | 12 | | | 8.0 | R | | | | | 16 | 4 | 20 | 12 | 1.00 |
| 356.608 | | | 6 | 12 | | | 8.0 | R | | | | | 16 | 4 | 20 | 12 | |
| 356.612 | | | 4 | 4 | 4 | 4 | 3.6 | R | | | | | 8 | 8 | 16 | 8 | |
| 356.616 | | | 4 | 4 | 4 | 4 | 3.6 | R | | | | | 8 | 8 | 16 | 8 | |
| 356.620 | 6 | 12 | | | 6 | 18 | 20.0 | R | | | | | 32 | 6 | 38 | 24 | |
| 356.627 | | | | | 6 | 16 | 10.7 | R | | | | | 16 | 4 | 20 | 12 | |
| 356.630 | | | 6 | 8 | 6 | 12 | 13.3 | R | | | | | 26 | 6 | 32 | 20 | |
| 356.634 | | | | | 6 | 14 | 9.3 | R | | | | | 16 | 4 | 20 | 12 | |
| 356.638 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.641 | 6 | 12 | | | 6 | 18 | 20.0 | R | | | | | 32 | 6 | 38 | 24 | |
| 356.645 | | | | | 4 | 6 | 2.7 | R | | | | | 8 | 4 | 12 | 6 | 1.00 |
| 356.648 | | | | | 6 | 12 | 8.0 | R | | | | | 16 | 2 | 18 | 12 | 1.00 |
| 356.652 | 6 | 6 | | | 6 | 12 | 12.0 | R | | | | | 24 | 4 | 28 | 18 | |
| 356.656 | 20 | 12 | 8 | 8 | | | 33.8 | R | | | | | 26 | 7 | 33 | 20 | |
| 356.657 | 6 | 12 | | | 6 | 18 | 20.0 | R | | | | | 32 | 6 | 38 | 24 | |
| 356.659 | | | 4 | 4 | 4 | 4 | 3.6 | R | | | | | 8 | 8 | 16 | 8 | |
| 356.663 | | | | | 6 | 12 | 8.0 | R | | | | | 16 | 2 | 18 | 12 | |
| 356.665 | | | 6 | 8 | | | 5.3 | R | | | | | 10 | 4 | 14 | 8 | |
| 356.667 | | | | | 8 | 12 | 10.7 | R | | | | | 16 | 3 | 19 | 12 | |
| 356.668 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.670 | | | | | 6 | 12 | 8.0 | R | | | | | 16 | 2 | 18 | 12 | |
| 356.673 | | | | | 6 | 14 | 9.3 | R | | | | | 16 | 4 | 20 | 12 | 1.00 |
| 356.674 | | | | | 6 | 20 | 13.3 | R | 20 | 20 | | | 16 | 4 | 20 | 12 | 1.00 |
| 356.676 | | | | | 6 | 20 | 13.3 | R | | | | | 16 | 4 | 20 | 12 | |
| 356.679 | | | | | 6 | 16 | 10.7 | R | 6 | | 6 | | 16 | 4 | 20 | 12 | |
| 356.682 | 38 | 6 | 4 | 4 | | | 27.1 | R | | | | | 12 | 19 | 31 | 10 | |
| 356.684 | 10 | 12 | | | 30 | 4 | 26.7 | R | | | | | 20 | 28 | 48 | 16 | |
| 356.686 | | | 4 | 4 | | | 1.8 | R | | | | | 4 | 4 | 8 | 4 | |
| 356.688 | | | | | 6 | 16 | 10.7 | R | | | | | 16 | 4 | 20 | 12 | |
| 356.688 | | | | | 14 | 4 | 6.2 | R | | | | | 4 | 10 | 14 | 4 | |
| 356.690 | 9 | 12 | | | | | 12.0 | R | 6 | 6 | | | 16 | 3 | 19 | 12 | |
| TOTALS: | | | | | | | 1369.1 | | 215 | 139 | 76 | 192 | 2040 | 922 | 3154 | 1694 | 22.0 |
| ADDITIONAL QUANTITIES: | | | | | | | 270.0 | | 40 | 30 | 20 | 40 | 410 | 180 | 630 | 340 | - |
| GRAND TOTALS: | | | | | | | 1639.1 | | 255 | 169 | 96 | 232 | 2450 | 1102 | 3784 | 2034 | 22.0 |

NRC PAVEMENT REPAIR AREA TYPES

W = Two Working Joints (Use only if repair is full roadway width and uniform length (across all lanes))
T = Two Tied Joints
B = One Working & One Tied Joint
R = Two Tied Joints with Original Joint Restored with Dowel Bar Assembly

* Cost for this work will be included in the contract unit price per foot for Repair Concrete Curb and/or Gutter

SD38 IN HARTFORD

| DMI | WB DRIVING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | INSERT STEEL BAR IN NRCP TOTAL Each | DOWEL BAR Each |
|-------------------------------|-----------------|----|-----------------|----|-------------------|---------------------------|---|------------------------------------|-------------------------------------|----------------|
| | L | W | L | W | | | No. 8 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | |
| | Ft | Ft | Ft | Ft | | | | | | |
| 356.000 | 4 | 4 | | | 1.8 | R | 4 | 2 | 6 | 4 |
| 356.004 | 6 | 12 | | | 8.0 | R | 16 | 2 | 18 | 12 |
| 356.008 | 4 | 4 | | | 1.8 | R | 4 | 2 | 6 | 4 |
| 356.019 | 6 | 6 | | | 4.0 | R | 8 | 2 | 10 | 6 |
| 356.023 | 4 | 4 | | | 1.8 | R | 4 | 2 | 6 | 4 |
| 356.027 | 4 | 4 | | | 1.8 | R | 4 | 2 | 6 | 4 |
| 356.030 | 4 | 6 | | | 2.7 | R | 8 | 2 | 10 | 6 |
| 356.034 | 10 | 12 | | | 13.3 | R | 16 | 4 | 20 | 12 |
| 356.057 | 4 | 4 | | | 1.8 | R | 4 | 2 | 6 | 4 |
| 356.061 | 4 | 4 | | | 1.8 | R | 4 | 2 | 6 | 4 |
| 356.064 | 20 | 20 | | | 44.4 | R | 16 | 8 | 24 | 12 |
| 356.068 | 4 | 4 | | | 1.8 | R | 4 | 2 | 6 | 4 |
| 356.072 | 10 | 4 | | | 4.4 | R | 4 | 4 | 8 | 4 |
| 356.083 | | | 15 | 30 | 50.0 | R | 16 | 12 | 28 | 12 |
| 356.087 | | | 4 | 6 | 2.7 | R | 8 | 4 | 12 | 6 |
| 356.091 | | | 10 | 10 | 11.1 | R | 12 | 8 | 20 | 10 |
| 356.102 | 10 | 12 | | | 13.3 | R | 16 | 4 | 20 | 12 |
| 356.106 | 6 | 10 | | | 6.7 | R | 12 | 2 | 14 | 10 |
| 356.110 | 6 | 8 | | | 5.3 | R | 10 | 2 | 12 | 8 |
| 356.121 | | | 6 | 10 | 6.7 | R | 12 | 4 | 16 | 10 |
| 356.125 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 356.129 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 356.133 | | | 6 | 12 | 8.0 | R | 16 | 2 | 18 | 12 |
| 356.144 | 8 | 20 | | | 17.8 | R | 16 | 3 | 19 | 12 |
| 356.148 | 4 | 4 | | | 1.8 | R | 4 | 2 | 6 | 4 |
| 356.152 | 8 | 20 | | | 17.8 | R | 16 | 3 | 19 | 12 |
| 356.155 | 6 | 8 | | | 5.3 | R | 10 | 2 | 12 | 8 |
| 356.167 | | | 12 | 6 | 8.0 | R | 8 | 8 | 16 | 6 |
| 356.170 | | | 12 | 4 | 5.3 | R | 4 | 8 | 12 | 4 |
| 356.174 | | | 8 | 6 | 5.3 | R | 8 | 6 | 14 | 6 |
| 356.178 | | | 20 | 20 | 44.4 | R | 16 | 16 | 32 | 12 |
| 356.182 | | | 8 | 12 | 10.7 | R | 16 | 3 | 19 | 12 |
| 356.186 | | | 6 | 8 | 5.3 | R | 10 | 4 | 14 | 8 |
| TOTALS: | | | | | 318.5 | | 314 | 137 | 451 | 252 |
| ADDITIONAL QUANTITIES: | | | | | 60.0 | | 60 | 30 | 90 | 50 |
| GRAND TOTALS: | | | | | 378.5 | | 374 | 167 | 541 | 302 |

NRC PAVEMENT REPAIR AREA TYPES

W = Two Working Joints (Use only if repair is full roadway width and uniform length (across all lanes))

T = Two Tied Joints

B = One Working & One Tied Joint

R = Two Tied Joints with Original Joint Restored with Dowel Bar Assembly

SD38 OVER SKUNK CREEK

| MRM | DISP | DMI | WB DRIVING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | | DOWEL BAR Each | TIE BAR RETROFIT STITCHING Each | | |
|-------------------------------|-------|---------|-----------------|------|-----------------|------|-------------------|---------------------------|---|------------------------------------|------------------------------------|----------------|---------------------------------|-------------------------------------|-------------------|
| | | | L Ft | W Ft | L Ft | W Ft | | | 1" x 18" PLAIN ROUND DOWEL BARS Each | No. 8 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | | INSERT STEEL BAR IN NRCP TOTAL Each | |
| | | | | | | | | | | | | | | | NRCP REPAIR SqYds |
| 360.00 | 0.140 | 360.140 | 6 | 12 | 4 | 4 | 9.8 | R | | 20 | 2 | 22 | 16 | | |
| 360.00 | 0.143 | 360.143 | 6 | 12 | | | 8.0 | R | | 16 | 2 | 18 | 12 | | |
| 360.00 | 0.146 | 360.146 | 6 | 12 | | | 8.0 | R | | 16 | 2 | 18 | 12 | | |
| 360.00 | 0.149 | 360.149 | 6 | 12 | 4 | 4 | 9.8 | R | | 20 | 2 | 22 | 16 | | |
| 360.00 | 0.152 | 360.152 | 6 | 12 | 6 | 12 | 16.0 | R | | 32 | | 32 | 24 | | |
| 360.00 | 0.160 | 360.160 | 6 | 6 | | | 4.0 | R | | 8 | 2 | 10 | 6 | | |
| 360.00 | 0.163 | 360.163 | 6 | 12 | | | 8.0 | R | | 16 | 2 | 18 | 12 | | |
| 360.00 | 0.166 | 360.166 | | | | | | | | | | | | 40 | |
| 360.00 | 0.129 | 360.129 | | | | | | | | | | | | 20 | |
| 360.00 | 0.310 | 360.310 | 8 | 12 | 4 | 4 | 12.4 | R | | 20 | 4 | 24 | 16 | | |
| 360.00 | 0.320 | 360.320 | 8 | 12 | 4 | 4 | 12.4 | R | | 20 | 4 | 24 | 16 | | |
| 360.00 | 0.323 | 360.323 | 6 | 6 | | | 4.0 | R | | 8 | 2 | 10 | 6 | | |
| 360.00 | 0.330 | 360.330 | | | 6 | 12 | 8.0 | R | | 16 | 2 | 18 | 12 | | |
| 360.00 | 0.333 | 360.333 | 6 | 12 | 6 | 12 | 16.0 | W | 32 | | | 32 | | | |
| 360.00 | 0.336 | 360.336 | 6 | 12 | 6 | 12 | 16.0 | W | 32 | | | 32 | | | |
| 360.00 | 0.339 | 360.339 | 6 | 12 | | | 8.0 | R | | 16 | 2 | 18 | 12 | | |
| TOTALS: | | | | | | | 140.4 | | | 64 | 208 | 26 | 298 | 160 | 60 |
| ADDITIONAL QUANTITIES: | | | | | | | 30.0 | | | 10 | 40 | 10 | 60 | 30 | 10 |
| GRAND TOTALS | | | | | | | 170.4 | | | 74 | 248 | 36 | 358 | 190 | 70 |

NRC PAVEMENT REPAIR AREA TYPES

W = Two Working Joints (Use only if repair is full roadway width and uniform length (across all lanes))

T = Two Tied Joints

B = One Working & One Tied Joint

R = Two Tied Joints with Original Joint Restored with Dowel Bar Assembly

SD38 AT W 60TH ST N IN SIOUX FALLS

| JOINT NO. | WB DRIVING LANE | | WB PASSING LANE | | LEFT TURN LANE | | EB PASSING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | INSERT STEEL BAR IN NRCP TOTAL Each | DOWEL BAR Each |
|-----------|-----------------|------|-----------------|------|----------------|------|-----------------|------|-----------------|------|-------------------|---------------------------|---|------------------------------------|-------------------------------------|----------------|
| | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | | | No. 9 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | |
| | 1 | 6 | 14 | | | 4 | 4 | 4 | 4 | 4 | | | 4 | 14.7 | | |
| 2 | 6 | 24 | | | 4 | 4 | 4 | 4 | 4 | 4 | 21.3 | R | 28 | 14 | 42 | 24 |
| 3 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 8.9 | R | 20 | 18 | 38 | 20 |
| 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 8.9 | R | 20 | 18 | 38 | 20 |
| 5 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 8.9 | R | 20 | 18 | 38 | 20 |
| 6 | 4 | 4 | 4 | 4 | | | | | 6 | 12 | 11.6 | R | 24 | 10 | 34 | 20 |
| 7 | 4 | 4 | 4 | 4 | | | | | 6 | 12 | 11.6 | R | 24 | 10 | 34 | 20 |
| 8 | | | | | | | | | 6 | 28 | 18.7 | R | 16 | 4 | 20 | 12 |
| 9 | 4 | 4 | 4 | 4 | | | | | 6 | 28 | 22.2 | R | 24 | 10 | 34 | 20 |
| 10 | 4 | 4 | 4 | 4 | | | | | 6 | 28 | 22.2 | R | 24 | 10 | 34 | 20 |
| 11 | 4 | 4 | 4 | 4 | | | | | 6 | 28 | 22.2 | R | 24 | 10 | 34 | 20 |
| 12 | 4 | 4 | 4 | 4 | | | | | 6 | 14 | 12.9 | R | 24 | 8 | 32 | 20 |
| 13 | 4 | 4 | 4 | 4 | | | 4 | 4 | 4 | 4 | 7.1 | R | 16 | 14 | 30 | 16 |
| 14 | 4 | 4 | 4 | 4 | | | | | | | 3.6 | R | 8 | 6 | 14 | 8 |
| 15 | 4 | 4 | 4 | 4 | | | 4 | 4 | 4 | 4 | 7.1 | R | 16 | 14 | 30 | 16 |
| 16 | 4 | 4 | 4 | 4 | | | | | 4 | 4 | 5.3 | R | 12 | 10 | 22 | 12 |
| 17 | 4 | 4 | 6 | 8 | | | | | 4 | 4 | 8.9 | R | 18 | 10 | 28 | 16 |
| 18 | 6 | 28 | | | 4 | 4 | 4 | 4 | 4 | 4 | 24.0 | R | 28 | 14 | 42 | 24 |
| 19 | 6 | 14 | 4 | 4 | | | | | 4 | 4 | 12.9 | R | 24 | 6 | 30 | 20 |
| 20 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 8.9 | R | 20 | 18 | 38 | 20 |
| 21 | 6 | 16 | | | | | 4 | 4 | | | 12.4 | R | 20 | 6 | 26 | 16 |
| 22 | 4 | 4 | 4 | 4 | | | 4 | 4 | | | 5.3 | R | 12 | 10 | 22 | 12 |
| 23 | 4 | 4 | 4 | 4 | | | 4 | 4 | | | 5.3 | R | 12 | 10 | 22 | 12 |
| 24 | 4 | 6 | 4 | 4 | 4 | 4 | | | 6 | 16 | 16.9 | R | 32 | 14 | 46 | 26 |
| 25 | 6 | 18 | | | | | 4 | 4 | 4 | 4 | 15.6 | R | 24 | 10 | 34 | 20 |
| 26 | 4 | 4 | 4 | 4 | | | | | 4 | 4 | 5.3 | R | 12 | 10 | 22 | 12 |
| 27 | 4 | 4 | 6 | 12 | | | | | | | 9.8 | R | 20 | 6 | 26 | 16 |
| 28 | 4 | 4 | 4 | 4 | | | | | | | 3.6 | R | 8 | 6 | 14 | 8 |
| 29 | 6 | 28 | | | | | | | | | 18.7 | R | 16 | 2 | 18 | 12 |
| 30 | 6 | 28 | | | 6 | 28 | 6 | 28 | | | 56.0 | R | 48 | 10 | 58 | 36 |
| 31 | 6 | 14 | | | | | | | | | 9.3 | R | 16 | 2 | 18 | 12 |
| 32 | 4 | 4 | 6 | 8 | | | | | 4 | 4 | 8.9 | R | 18 | 10 | 28 | 16 |
| 33 | 4 | 4 | 4 | 4 | | | | | | | 3.6 | R | 8 | 6 | 14 | 8 |
| 34 | 6 | 28 | | | | | | | | | 18.7 | R | 16 | 2 | 18 | 12 |
| 35 | 6 | 28 | | | | | 6 | 14 | | | 28.0 | R | 32 | 6 | 38 | 24 |
| 36 | 6 | 28 | | | 4 | 4 | 4 | 4 | 4 | 4 | 24.0 | R | 28 | 14 | 42 | 24 |
| 37 | 6 | 28 | | | | | 4 | 4 | | | 20.4 | R | 20 | 6 | 26 | 16 |
| 38 | 4 | 4 | 6 | 12 | | | | | 4 | 4 | 11.6 | R | 24 | 10 | 34 | 20 |
| 39 | 6 | 28 | | | | | 4 | 4 | 4 | 4 | 22.2 | R | 24 | 10 | 34 | 20 |
| 40 | 6 | 28 | | | 4 | 4 | 4 | 4 | 4 | 4 | 24.0 | R | 28 | 14 | 42 | 24 |
| 41 | 6 | 28 | | | 4 | 4 | 4 | 4 | 4 | 4 | 24.0 | R | 28 | 14 | 42 | 24 |
| 42 | 6 | 16 | | | 4 | 4 | 4 | 4 | | | 14.2 | R | 24 | 10 | 34 | 20 |
| 43 | 6 | 28 | | | | | 4 | 4 | | | 20.4 | R | 20 | 6 | 26 | 16 |
| 43 | 40 | 4 | | | | | 4 | 4 | | | 19.6 | R | 8 | 20 | 28 | 12 |
| 44 | 4 | 4 | | | | | 4 | 4 | 4 | 4 | 5.3 | R | 12 | 10 | 22 | 12 |
| 45 | 4 | 4 | | | | | 4 | 4 | 4 | 4 | 5.3 | R | 12 | 10 | 22 | 12 |
| 46 | 4 | 6 | 6 | 12 | | | 4 | 4 | | | 12.4 | R | 28 | 10 | 38 | 22 |
| 47 | 6 | 18 | | | | | 4 | 4 | | | 13.8 | R | 20 | 6 | 26 | 16 |
| 48 | 4 | 4 | 6 | 14 | | | 4 | 4 | | | 12.9 | R | 24 | 10 | 34 | 20 |
| 49 | 4 | 4 | 4 | 4 | | | 4 | 4 | | | 5.3 | R | 12 | 10 | 22 | 12 |
| 50 | 6 | 28 | | | | | 4 | 4 | 4 | 4 | 22.2 | R | 24 | 10 | 34 | 20 |
| 51 | 6 | 28 | | | | | 4 | 4 | | | 20.4 | R | 20 | 6 | 26 | 16 |
| 52 | 6 | 18 | | | | | | | | | 12.0 | R | 16 | 2 | 18 | 12 |
| 53 | 6 | 28 | | | | | | | | | 18.7 | R | 16 | 2 | 18 | 12 |
| 54 | 6 | 28 | | | | | | | | | 18.7 | R | 16 | 2 | 18 | 12 |
| 55 | 4 | 4 | 4 | 4 | | | | | | | 3.6 | R | 8 | 6 | 14 | 8 |

SD38 AT W 60TH ST N IN SIOUX FALLS

| | | | |
|----------|---------------|-----------|--------------|
| STATE OF | PROJECT | SHEET NO. | TOTAL SHEETS |
| S.D. | IM-P 0022(85) | 17 | 64 |

| JOINT NO. | WB DRIVING LANE | | WB PASSING LANE | | LEFT TURN LANE | | EB PASSING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | INSERT STEEL BAR IN NRCP TOTAL Each | DOWEL BAR Each |
|-----------|-----------------|----|-----------------|----|----------------|----|-----------------|----|-----------------|----|-------------------|---------------------------|---|------------------------------------|-------------------------------------|----------------|
| | L | W | L | W | L | W | L | W | L | W | | | No. 9 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | |
| | Ft | Ft | Ft | Ft | Ft | Ft | Ft | Ft | Ft | Ft | | | | | | |
| 56 | 6 | 28 | | | | | 4 | 4 | 4 | 4 | 22.2 | R | 24 | 10 | 34 | 20 |
| 57 | 6 | 18 | | | | | | | | | 12.0 | R | 16 | 2 | 18 | 12 |
| 58 | | | 4 | 4 | | | | | | | 1.8 | R | 4 | 4 | 8 | 4 |
| 59 | | | | | | | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 60 | 6 | 40 | | | | | | | 4 | 4 | 28.4 | R | 20 | 6 | 26 | 16 |
| 61 | | | | | | | | | 6 | 28 | 18.7 | R | 16 | 4 | 20 | 12 |
| 62 | | | 4 | 4 | | | | | | | 1.8 | R | 4 | 4 | 8 | 4 |
| 63 | 4 | 4 | | | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 |
| 64 | 4 | 4 | 4 | 4 | | | 4 | 4 | | | 5.3 | R | 12 | 10 | 22 | 12 |
| 65 | 4 | 4 | 4 | 4 | | | | | | | 3.6 | R | 8 | 6 | 14 | 8 |
| 66 | | | 4 | 4 | | | | | | | 1.8 | R | 4 | 4 | 8 | 4 |
| 68 | | | | | | | 4 | 4 | | | 1.8 | R | 4 | 4 | 8 | 4 |
| 69 | | | 4 | 4 | | | | | | | 1.8 | R | 4 | 4 | 8 | 4 |
| 70 | 4 | 4 | 4 | 4 | | | | | | | 3.6 | R | 8 | 6 | 14 | 8 |
| 71 | 4 | 4 | 4 | 4 | | | | | | | 3.6 | R | 8 | 6 | 14 | 8 |
| 72 | 4 | 4 | 4 | 4 | | | 4 | 4 | 4 | 4 | 7.1 | R | 16 | 14 | 30 | 16 |
| 73 | 6 | 16 | | | | | | | 4 | 4 | 12.4 | R | 20 | 6 | 26 | 16 |
| 74 | 6 | 18 | | | | | | | 12 | 14 | 30.7 | R | 32 | 6 | 38 | 24 |
| 75 | 6 | 18 | | | | | 4 | 4 | 4 | 4 | 15.6 | R | 24 | 10 | 34 | 20 |
| 76 | 6 | 18 | | | | | 4 | 4 | 4 | 4 | 15.6 | R | 24 | 10 | 34 | 20 |
| 76 | 140 | 4 | | | | | | | | | 62.2 | R | 4 | 56 | 60 | 28 |
| 77 | 4 | 4 | 4 | 4 | | | 4 | 4 | 4 | 4 | 7.1 | R | 16 | 14 | 30 | 16 |
| 78 | 4 | 4 | 4 | 6 | | | 4 | 4 | 4 | 4 | 8.0 | R | 20 | 14 | 34 | 18 |
| 79 | 6 | 16 | | | | | 4 | 4 | 4 | 4 | 14.2 | R | 24 | 10 | 34 | 20 |
| 80 | 6 | 16 | | | | | 4 | 4 | 4 | 4 | 14.2 | R | 24 | 10 | 34 | 20 |
| 81 | 4 | 4 | 4 | 4 | | | 4 | 4 | 4 | 4 | 7.1 | R | 16 | 14 | 30 | 16 |
| 82 | 6 | 16 | | | | | 4 | 4 | 4 | 4 | 14.2 | R | 24 | 10 | 34 | 20 |
| 83 | 6 | 14 | 4 | 4 | | | 4 | 4 | 4 | 4 | 14.7 | R | 28 | 10 | 38 | 24 |
| 84 | 4 | 4 | 4 | 4 | | | 4 | 4 | 4 | 4 | 7.1 | R | 16 | 14 | 30 | 16 |
| 85 | 4 | 4 | 4 | 4 | | | 4 | 4 | 4 | 4 | 7.1 | R | 16 | 14 | 30 | 16 |
| 86 | 4 | 4 | 4 | 4 | | | 4 | 4 | 4 | 4 | 5.3 | R | 12 | 10 | 22 | 12 |
| 87 | 4 | 4 | 4 | 4 | | | 4 | 4 | 4 | 4 | 7.1 | R | 16 | 14 | 30 | 16 |
| 88 | 4 | 4 | 4 | 4 | | | 4 | 4 | 4 | 4 | 7.1 | R | 16 | 14 | 30 | 16 |
| 89 | 4 | 4 | 4 | 4 | | | | | 4 | 4 | 5.3 | R | 12 | 10 | 22 | 12 |
| 90 | 4 | 4 | 4 | 4 | | | 4 | 4 | 4 | 4 | 7.1 | R | 16 | 14 | 30 | 16 |
| 91 | 4 | 4 | 4 | 4 | | | | | 4 | 4 | 5.3 | R | 12 | 10 | 22 | 12 |
| 92 | 4 | 4 | 4 | 4 | | | 4 | 4 | 4 | 4 | 7.1 | R | 16 | 14 | 30 | 16 |
| 93 | 4 | 4 | 4 | 4 | | | | | 4 | 4 | 5.3 | R | 12 | 10 | 22 | 12 |
| 94 | 4 | 4 | 4 | 4 | | | | | | | 3.6 | R | 8 | 6 | 14 | 8 |
| 95 | 4 | 4 | 4 | 4 | | | | | | | 3.6 | R | 8 | 6 | 14 | 8 |
| 96 | 4 | 4 | 6 | 8 | | | | | | | 7.1 | R | 14 | 6 | 20 | 12 |
| 97 | 4 | 4 | 4 | 4 | | | 4 | 4 | | | 5.3 | R | 12 | 10 | 22 | 12 |
| 98 | 6 | 28 | | | | | | | | | 18.7 | R | 16 | 2 | 18 | 12 |
| 99 | 4 | 4 | | | | | | | 6 | 28 | 20.4 | R | 20 | 6 | 26 | 16 |
| 100 | 4 | 4 | | | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 |
| 103 | | | | | | | 4 | 4 | | | 1.8 | R | 4 | 4 | 8 | 4 |
| 105 | | | 4 | 4 | | | | | | | 1.8 | R | 4 | 4 | 8 | 4 |
| 106 | 4 | 4 | 4 | 4 | | | | | | | 3.6 | R | 8 | 6 | 14 | 8 |
| 107 | 4 | 4 | | | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 |
| 108 | 4 | 4 | 4 | 4 | | | | | | | 3.6 | R | 8 | 6 | 14 | 8 |
| 109 | 6 | 28 | | | | | | | 6 | 28 | 37.3 | R | 32 | 6 | 38 | 24 |
| 109 | 6 | 28 | | | | | 4 | 4 | 4 | 4 | 22.2 | R | 24 | 10 | 34 | 20 |
| 110 | 6 | 28 | | | | | | | 6 | 28 | 37.3 | R | 32 | 6 | 38 | 24 |
| 110 | 18 | 4 | | | | | | | | | 8.0 | R | 4 | 7 | 11 | 4 |
| 110 | 6 | 12 | | | | | | | | | 8.0 | R | 16 | 2 | 18 | 12 |

SD38 AT W 60TH ST N IN SIOUX FALLS

| | | | |
|----------|---------------|-----------|--------------|
| STATE OF | PROJECT | SHEET NO. | TOTAL SHEETS |
| S.D. | IM-P 0022(85) | 18 | 64 |

| JOINT NO. | WB DRIVING LANE | | WB PASSING LANE | | LEFT TURN LANE | | EB PASSING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | INSERT STEEL BAR IN NRCP TOTAL | DOWEL BAR |
|-------------------------------|-----------------|------|-----------------|------|----------------|------|-----------------|------|-----------------|------|-------------------|---------------------------|---|------------------------------------|--------------------------------|-----------|
| | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | | | No. 9 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | |
| TOTALS: | | | | | | | | | | | 1393.1 | | 1898 | 1009 | 2907 | 1674 |
| ADDITIONAL QUANTITIES: | | | | | | | | | | | 280.0 | | 380 | 200 | 580 | 330 |
| GRAND TOTALS | | | | | | | | | | | 1673.1 | | 2278 | 1209 | 3487 | 2004 |

NRC PAVEMENT REPAIR AREA TYPES

W = Two Working Joints (Use only if repair is full roadway width and uniform length (across all lanes))

T = Two Tied Joints

B = One Working & One Tied Joint

R = Two Tied Joints with Original Joint Restored with Dowel Bar Assembly

I90 NEAR BUFFALO RIDGE

| DMI | WB DRIVING LANE | | WB PASSING LANE | | EB PASSING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | INSERT STEEL BAR IN NRCP TOTAL Each | DOWEL BAR Each | TIE BAR RETROFIT STITCHING Each |
|---------|-----------------|------|-----------------|------|-----------------|------|-----------------|------|-------------------|---------------------------|---|------------------------------------|-------------------------------------|----------------|---------------------------------|
| | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | | | No. 11 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | | |
| | 390.225 | | | | | | | 4 | | | 4 | 1.8 | | | |
| 390.227 | | | | | 4 | 4 | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 390.324 | | | | | 4 | 4 | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 390.471 | | | | | 4 | 4 | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 390.630 | | | | | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 | |
| 390.717 | | | | | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 | |
| 390.721 | | | | | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 | |
| 391.012 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 391.064 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 391.102 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 391.135 | | | | | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 | |
| 391.273 | | | | | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 | |
| 391.405 | | | | | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 | |
| 391.503 | | | | | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 | |
| 391.536 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 391.571 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 391.936 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 392.087 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 392.099 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 392.129 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 392.140 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 392.166 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 392.181 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 392.282 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 392.436 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 392.752 | | | | | 6 | 12 | 6 | 14 | 17.3 | R | 32 | | 32 | 24 | |
| 392.800 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 392.901 | 4 | 6 | 4 | 4 | | | | | 4.4 | R | 12 | 6 | 18 | 10 | |
| 392.994 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 393.153 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 393.160 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 393.198 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 393.266 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 393.273 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 393.288 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 393.434 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 393.479 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 393.495 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 393.518 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 393.603 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 393.618 | 12 | 8 | | | | | | | 10.7 | R | 10 | 4 | 14 | 8 | |
| 393.650 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 393.653 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 393.664 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 393.724 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 393.799 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 393.924 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 393.977 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 394.087 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 394.249 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 394.272 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 394.282 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 394.294 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 394.443 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 394.568 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 394.584 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |

I90 NEAR BUFFALO RIDGE

| DMI | WB DRIVING LANE | | WB PASSING LANE | | EB PASSING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | INSERT STEEL BAR IN NRCP TOTAL | DOWEL BAR | TIE BAR RETROFIT STITCHING |
|---------|-----------------|----|-----------------|----|-----------------|----|-----------------|----|-------------------|---------------------------|---|-------------------------------|--------------------------------|-----------|----------------------------|
| | L | W | L | W | L | W | L | W | | | No. 11 x 18" DEFORMED TIE BARS | No. 5 x 24" DEFORMED TIE BARS | | | |
| | Ft | Ft | Ft | Ft | Ft | Ft | Ft | Ft | | | Each | Each | | | |
| 394.659 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 394.711 | 20 | 8 | 20 | 4 | | | | | 26.7 | R | 14 | 24 | 38 | 12 | |
| 394.740 | 20 | 8 | | | | | | | 17.8 | R | 10 | 8 | 18 | 8 | |
| 394.747 | | | 10 | 12 | | | | | 13.3 | R | 16 | 4 | 20 | 12 | |
| 394.770 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 394.819 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 394.827 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 394.860 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 394.915 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 394.917 | | | | | | | | | | | | | | | 12 |
| 394.930 | 6 | 8 | | | | | | | 5.3 | R | 10 | 2 | 12 | 8 | |
| 394.952 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 394.960 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 394.967 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 394.986 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 394.994 | | | | | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 | |
| 395.000 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 395.002 | | | | | 4 | 4 | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.049 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.063 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.078 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.086 | | | | | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 | |
| 395.116 | | | | | 4 | 4 | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.131 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 395.172 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.198 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 395.309 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.336 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.348 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.407 | 4 | 4 | 4 | 4 | | | | | 3.6 | R | 8 | 6 | 14 | 8 | |
| 395.410 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 395.419 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.517 | 4 | 4 | 4 | 4 | | | | | 3.6 | R | 8 | 6 | 14 | 8 | |
| 395.532 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.539 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.565 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.573 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.588 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.602 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.621 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.632 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.643 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.655 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.674 | 4 | 4 | 4 | 4 | | | | | 3.6 | R | 8 | 6 | 14 | 8 | |
| 395.681 | 4 | 4 | 4 | 4 | | | | | 3.6 | R | 8 | 6 | 14 | 8 | |
| 395.704 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.708 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 395.722 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.745 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.764 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.782 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.786 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.801 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.802 | | | | | | | 4 | 6 | 2.7 | R | 8 | 4 | 12 | 6 | |
| 395.808 | 4 | 4 | 4 | 4 | | | | | 3.6 | R | 8 | 6 | 14 | 8 | |
| 395.816 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |

I90 NEAR BUFFALO RIDGE

| DMI | WB DRIVING LANE | | WB PASSING LANE | | EB PASSING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | INSERT STEEL BAR IN NRCP TOTAL | DOWEL BAR | TIE BAR RETROFIT STITCHING |
|-------------------------------|-----------------|----|-----------------|----|-----------------|----|-----------------|----|-------------------|---------------------------|---|-------------------------------|--------------------------------|------------|----------------------------|
| | L | W | L | W | L | W | L | W | | | No. 11 x 18" DEFORMED TIE BARS | No. 5 x 24" DEFORMED TIE BARS | | | |
| | Ft | Ft | Ft | Ft | Ft | Ft | Ft | Ft | | | Each | Each | | | |
| 395.822 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.849 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.860 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.876 | 6 | 8 | | | | | | | 5.3 | R | 10 | 2 | 12 | 8 | |
| 395.879 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.901 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 395.940 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 395.943 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 395.985 | 6 | 4 | | | | | | | 2.7 | R | 4 | 2 | 6 | 4 | |
| 396.034 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.040 | 6 | 14 | 6 | 12 | | | | | 17.3 | R | 32 | | 32 | 24 | |
| 396.049 | 4 | 4 | 6 | 6 | | | | | 5.8 | R | 12 | 6 | 18 | 10 | |
| 396.064 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.075 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 396.113 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.158 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.173 | | | 4 | 4 | | | | | 1.8 | R | 4 | 4 | 8 | 4 | |
| 396.183 | | | | | | | | | | | | | | | 15 |
| 396.191 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.218 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.251 | | | | | | | | | | | | | | | 20 |
| 396.294 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.309 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.320 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.327 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.335 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.346 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.368 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.387 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.398 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.436 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.510 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.630 | | | | | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 | |
| 396.641 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| 396.667 | | | | | | | | | | | | | | | 20 |
| 396.850 | | | | | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 | |
| 396.899 | 4 | 4 | | | | | | | 1.8 | R | 4 | 2 | 6 | 4 | |
| TOTALS: | | | | | | | | | 377.7 | | 722 | 454 | 1176 | 686 | 67 |
| ADDITIONAL QUANTITIES: | | | | | | | | | 80.0 | | 140 | 90 | 230 | 140 | 10 |
| GRAND TOTALS: | | | | | | | | | 457.7 | | 862 | 544 | 1406 | 826 | 77 |

NRC PAVEMENT REPAIR AREA TYPES

W = Two Working Joints (Use only if repair is full roadway width and uniform length (across all lanes))

T = Two Tied Joints

B = One Working & One Tied Joint

R = Two Tied Joints with Original Joint Restored with Dowel Bar Assembly

I29N NEAR I90 INTERCHANGE IN SIOUX FALLS

| DMI | NB PASSING LANE | | NB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | INSERT STEEL BAR IN NRCP TOTAL Each | DOWEL BAR Each |
|-------------------------------|-----------------|----|-----------------|----|-------------------|---------------------------|---|------------------------------------|-------------------------------------|----------------|
| | L | W | L | W | | | No. 11 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | |
| | Ft | Ft | Ft | Ft | | | | | | |
| 83.780 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 83.784 | 4 | 4 | 4 | 4 | 3.6 | R | 8 | 6 | 14 | 8 |
| 83.801 | 4 | 4 | | | 1.8 | R | 4 | 2 | 6 | 4 |
| 83.890 | | | 60 | 4 | 26.7 | R | 4 | 48 | 52 | 12 |
| 83.925 | | | 6 | 6 | 4.0 | R | 8 | 4 | 12 | 6 |
| 83.941 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 83.944 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 83.947 | | | 6 | 6 | 4.0 | R | 8 | 4 | 12 | 6 |
| 83.951 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 83.954 | 4 | 4 | 8 | 14 | 14.2 | R | 20 | 5 | 25 | 16 |
| 83.959 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 83.969 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 83.974 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 83.996 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 84.061 | 4 | 4 | 4 | 4 | 3.6 | R | 8 | 6 | 14 | 8 |
| 84.067 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 84.092 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 84.270 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 84.280 | 4 | 4 | 6 | 6 | 5.8 | R | 12 | 6 | 18 | 10 |
| 84.325 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 84.336 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 84.390 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 84.399 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 84.406 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 84.416 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 84.477 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 84.504 | | | 4 | 4 | 1.8 | R | 4 | 4 | 8 | 4 |
| 84.542 | | | 6 | 6 | 4.0 | R | 8 | 4 | 12 | 6 |
| 84.553 | | | 6 | 6 | 4.0 | R | 8 | 4 | 12 | 6 |
| 84.582 | | | 6 | 6 | 4.0 | R | 8 | 4 | 12 | 6 |
| TOTALS: | | | | | 109.9 | | 172 | 169 | 341 | 164 |
| ADDITIONAL QUANTITIES: | | | | | 20.0 | | 30 | 30 | 60 | 30 |
| GRAND TOTALS: | | | | | 129.9 | | 202 | 199 | 401 | 194 |

NRC PAVEMENT REPAIR AREA TYPES

W = Two Working Joints (Use only if repair is full roadway width and uniform length (across all lanes))

T = Two Tied Joints

B = One Working & One Tied Joint

R = Two Tied Joints with Original Joint Restored with Dowel Bar Assembly

SD34 IN HOWARD

| MRM | DISP | DMI | WB DRIVING LANE | | WB PASSING LANE | | EB PASSING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | | DOWEL BAR Each | |
|--------|-------|---------|-----------------|------|-----------------|------|-----------------|------|--------------------------------------|------------------------------------|-------------------|---------------------------|---|-------------------------------------|----|----------------|----|
| | | | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | 1" x 18" PLAIN ROUND DOWEL BARS Each | No. 8 x 18" DEFORMED TIE BARS Each | | | No. 5 x 24" DEFORMED TIE BARS Each | INSERT STEEL BAR IN NRCP TOTAL Each | | | |
| 366.00 | 0.370 | 366.370 | 6 | 12 | 6 | 12 | | | 4 | 4 | 17.8 | R | | 36 | 6 | 42 | 28 |
| 366.00 | 0.367 | 366.367 | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.353 | 366.353 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.351 | 366.351 | 6 | 12 | 6 | 12 | | | | | 16.0 | R | | 32 | 2 | 34 | 24 |
| 366.00 | 0.348 | 366.348 | 6 | 12 | | | | | | | 8.0 | R | | 16 | 2 | 18 | 12 |
| 366.00 | 0.342 | 366.342 | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.338 | 366.338 | | | | | 40 | 4 | 4 | 4 | 19.6 | R | | 8 | 36 | 44 | 12 |
| 366.00 | 0.334 | 366.334 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.331 | 366.331 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.327 | 366.327 | | | | | 4 | 4 | 4 | 4 | 3.6 | R | | 8 | 8 | 16 | 8 |
| 366.00 | 0.324 | 366.324 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.323 | 366.323 | 6 | 6 | | | | | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 366.00 | 0.319 | 366.319 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.316 | 366.316 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.313 | 366.313 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.310 | 366.310 | 6 | 12 | | | | | | | 8.0 | R | | 16 | 2 | 18 | 12 |
| 366.00 | 0.294 | 366.294 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.287 | 366.287 | 42 | 4 | | | | | | | 18.7 | R | | 4 | 16 | 20 | 8 |
| 366.00 | 0.285 | 366.285 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.278 | 366.278 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.267 | 366.267 | | | 4 | 4 | | | 4 | 4 | 3.6 | R | | 8 | 8 | 16 | 8 |
| 366.00 | 0.263 | 366.263 | | | 6 | 6 | | | | | 4.0 | R | | 8 | 4 | 12 | 6 |
| 366.00 | 0.260 | 366.260 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.259 | 366.259 | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.255 | 366.255 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.253 | 366.253 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.249 | 366.249 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.244 | 366.244 | 6 | 14 | | | | | | | 9.3 | R | | 16 | 2 | 18 | 12 |
| 366.00 | 0.240 | 366.240 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.237 | 366.237 | 4 | 4 | 4 | 4 | | | | | 3.6 | R | | 8 | 6 | 14 | 8 |
| 366.00 | 0.233 | 366.233 | | | | | 4 | 4 | 4 | 4 | 3.6 | R | | 8 | 8 | 16 | 8 |
| 366.00 | 0.228 | 366.228 | 6 | 12 | 6 | 12 | | | | | 16.0 | R | | 32 | 2 | 34 | 24 |
| 366.00 | 0.226 | 366.226 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.222 | 366.222 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 7.1 | R | | 16 | 14 | 30 | 16 |
| 366.00 | 0.215 | 366.215 | | | | | | | 6 | 12 | 8.0 | R | | 16 | 2 | 18 | 12 |
| 366.00 | 0.207 | 366.207 | | | 6 | 12 | 4 | 4 | 4 | 4 | 11.6 | R | | 24 | 8 | 32 | 20 |
| 366.00 | 0.203 | 366.203 | 4 | 4 | | | 12 | 4 | 4 | 4 | 8.9 | R | | 12 | 14 | 26 | 12 |
| 366.00 | 0.200 | 366.200 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.197 | 366.197 | | | | | 20 | 4 | 4 | 4 | 10.7 | R | | 8 | 20 | 28 | 8 |
| 366.00 | 0.196 | 366.196 | | | 6 | 6 | 14 | 6 | 4 | 4 | 13.3 | R | | 16 | 14 | 30 | 12 |
| 366.00 | 0.189 | 366.189 | | | | | 4 | 4 | 4 | 4 | 3.6 | R | | 8 | 8 | 16 | 8 |
| 366.00 | 0.188 | 366.188 | 6 | 14 | | | | | | | 9.3 | R | | 16 | 2 | 18 | 12 |
| 366.00 | 0.183 | 366.183 | | | | | 8 | 28 | | | 24.9 | W | 16 | | 6 | 22 | |
| 366.00 | 0.181 | 366.181 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.177 | 366.177 | 6 | 14 | 6 | 14 | | | | | 18.7 | R | | 32 | 6 | 38 | 24 |
| 366.00 | 0.176 | 366.176 | | | | | 8 | 8 | | | 7.1 | R | | 10 | 6 | 16 | 8 |
| 366.00 | 0.174 | 366.174 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.172 | 366.172 | | | | | 20 | 4 | 8 | 8 | 16.0 | R | | 14 | 22 | 36 | 12 |
| 366.00 | 0.169 | 366.169 | | | | | 6 | 28 | | | 18.7 | W | 16 | | 4 | 20 | |
| 366.00 | 0.165 | 366.165 | | | | | 4 | 4 | 4 | 4 | 3.6 | R | | 8 | 8 | 16 | 8 |
| 366.00 | 0.162 | 366.162 | 4 | 4 | | | 4 | 4 | 4 | 4 | 5.3 | R | | 12 | 10 | 22 | 12 |
| 366.00 | 0.158 | 366.158 | | | | | 4 | 4 | 4 | 4 | 3.6 | R | | 8 | 8 | 16 | 8 |
| 366.00 | 0.155 | 366.155 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.151 | 366.151 | | | | | 6 | 14 | 4 | 4 | 11.1 | R | | 20 | 8 | 28 | 16 |
| 366.00 | 0.149 | 366.149 | 14 | 12 | 14 | 12 | | | | | 37.3 | R | | 32 | 5 | 37 | 24 |
| 366.00 | 0.136 | 366.136 | | | | | 6 | 16 | 6 | 8 | 16.0 | R | | 26 | 8 | 34 | 20 |

SD34 IN HOWARD

| MRM | DISP | DMI | WB DRIVING LANE | | WB PASSING LANE | | EB PASSING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | | DOWEL BAR Each | |
|--------|-------|---------|-----------------|------|-----------------|------|-----------------|------|--------------------------------|------------------------------------|-------------------|---------------------------|---|-------------------------------------|----|----------------|----|
| | | | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | 1" x 18" ROUND DOWEL BARS Each | No. 8 x 18" DEFORMED TIE BARS Each | | | No. 5 x 24" DEFORMED TIE BARS Each | INSERT STEEL BAR IN NRCP TOTAL Each | | | |
| 366.00 | 0.132 | 366.132 | | | | | 4 | 4 | 4 | 4 | 3.6 | R | | 8 | 8 | 16 | 8 |
| 366.00 | 0.125 | 366.125 | | | 6 | 6 | 4 | 4 | | | 5.8 | R | | 12 | 8 | 20 | 10 |
| 366.00 | 0.121 | 366.121 | | | | | | | 6 | 14 | 9.3 | R | | 16 | 4 | 20 | 12 |
| 366.00 | 0.118 | 366.118 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.109 | 366.109 | 10 | 12 | 6 | 12 | | | | | 21.3 | R | | 32 | 4 | 36 | 24 |
| 366.00 | 0.104 | 366.104 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.102 | 366.102 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.098 | 366.098 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.094 | 366.094 | | | 6 | 14 | | | | | 9.3 | R | | 16 | 4 | 20 | 12 |
| 366.00 | 0.091 | 366.091 | | | | | | | 6 | 14 | 9.3 | R | | 16 | 4 | 20 | 12 |
| 366.00 | 0.090 | 366.090 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.087 | 366.087 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.083 | 366.083 | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.079 | 366.079 | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.072 | 366.072 | 6 | 6 | | | | | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 366.00 | 0.069 | 366.069 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.068 | 366.068 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.064 | 366.064 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.062 | 366.062 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.061 | 366.061 | 4 | 4 | 4 | 4 | | | | | 3.6 | R | | 8 | 6 | 14 | 8 |
| 366.00 | 0.059 | 366.059 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.057 | 366.057 | | | 6 | 12 | | | | | 8.0 | R | | 16 | 4 | 20 | 12 |
| 366.00 | 0.055 | 366.055 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.053 | 366.053 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.051 | 366.051 | | | | | 4 | 6 | | | 2.7 | R | | 8 | 4 | 12 | 6 |
| 366.00 | 0.050 | 366.050 | | | 6 | 14 | | | | | 9.3 | R | | 16 | 4 | 20 | 12 |
| 366.00 | 0.047 | 366.047 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.043 | 366.043 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.041 | 366.041 | | | | | 4 | 4 | 4 | 4 | 3.6 | R | | 8 | 8 | 16 | 8 |
| 366.00 | 0.039 | 366.039 | | | 12 | 12 | | | | | 16.0 | R | | 16 | 8 | 24 | 12 |
| 366.00 | 0.035 | 366.035 | | | 6 | 14 | | | | | 9.3 | R | | 16 | 4 | 20 | 12 |
| 366.00 | 0.031 | 366.031 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.028 | 366.028 | 4 | 4 | | | 80 | 4 | 28 | 4 | 49.8 | R | | 12 | 88 | 100 | 24 |
| 366.00 | 0.021 | 366.021 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.020 | 366.020 | 6 | 14 | | | | | | | 9.3 | R | | 16 | 2 | 18 | 12 |
| 366.00 | 0.016 | 366.016 | 6 | 14 | | | | | | | 9.3 | R | | 16 | 2 | 18 | 12 |
| 366.00 | 0.014 | 366.014 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 366.00 | 0.013 | 366.013 | 6 | 14 | 6 | 14 | | | | | 18.7 | R | | 32 | 6 | 38 | 24 |
| 366.00 | 0.011 | 366.011 | | | | | | | 6 | 14 | 9.3 | R | | 16 | 4 | 20 | 12 |
| 366.00 | 0.007 | 366.007 | | | | | 60 | 4 | 6 | 16 | 37.3 | R | | 20 | 52 | 72 | 24 |
| 366.00 | 0.001 | 366.001 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 366.00 | 0.000 | 366.000 | | | | | | | 6 | 14 | 9.3 | R | | 16 | 4 | 20 | 12 |
| 366.00 | 0.000 | 366.000 | | | | | 4 | 4 | 4 | 4 | 3.6 | R | | 8 | 8 | 16 | 8 |
| 365.00 | 0.999 | 365.999 | 6 | 6 | | | | | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 365.00 | 0.998 | 365.998 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.994 | 365.994 | 4 | 4 | | | 4 | 4 | 4 | 4 | 5.3 | R | | 12 | 10 | 22 | 12 |
| 364.00 | 1.991 | 366.991 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 364.00 | 1.987 | 366.987 | 6 | 4 | | | | | | | 2.7 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.983 | 365.983 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.980 | 365.980 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.976 | 365.976 | 6 | 12 | | | | | | | 8.0 | R | | 16 | 2 | 18 | 12 |
| 365.00 | 0.972 | 365.972 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.968 | 365.968 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.964 | 365.964 | | | 6 | 12 | | | | | 8.0 | R | | 16 | 4 | 20 | 12 |
| 365.00 | 0.961 | 365.961 | | | 6 | 12 | | | | | 8.0 | R | | 16 | 4 | 20 | 12 |
| 365.00 | 0.957 | 365.957 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |

SD34 IN HOWARD

| MRM | DISP | DMI | WB DRIVING LANE | | WB PASSING LANE | | EB PASSING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | | DOWEL BAR Each | |
|--------|-------|---------|-----------------|------|-----------------|------|-----------------|------|--------------------------------|------------------------------------|-------------------|---------------------------|---|-------------------------------------|----|----------------|----|
| | | | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | 1" x 18" ROUND DOWEL BARS Each | No. 8 x 18" DEFORMED TIE BARS Each | | | No. 5 x 24" DEFORMED TIE BARS Each | INSERT STEEL BAR IN NRCP TOTAL Each | | | |
| 365.00 | 0.954 | 365.954 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.950 | 365.950 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.947 | 365.947 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.943 | 365.943 | 4 | 4 | 4 | 4 | | | | | 3.6 | R | | 8 | 6 | 14 | 8 |
| 365.00 | 0.940 | 365.940 | 12 | 12 | 12 | 12 | 4 | 4 | 4 | 4 | 35.6 | R | | 40 | 9 | 49 | 32 |
| 365.00 | 0.937 | 365.937 | | | | | 4 | 4 | 4 | 4 | 3.6 | R | | 8 | 8 | 16 | 8 |
| 365.00 | 0.936 | 365.936 | 6 | 14 | 6 | 14 | | | | | 18.7 | R | | 32 | 6 | 38 | 24 |
| 365.00 | 0.933 | 365.933 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.932 | 365.932 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.928 | 365.928 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.927 | 365.927 | 12 | 6 | | | | | | | 8.0 | R | | 8 | 4 | 12 | 6 |
| 365.00 | 0.925 | 365.925 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.920 | 365.920 | 14 | 12 | | | | | | | 18.7 | R | | 16 | 5 | 21 | 12 |
| 365.00 | 0.918 | 365.918 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.916 | 365.916 | 12 | 12 | 12 | 12 | 6 | 14 | | | 41.3 | R | | 48 | 4 | 52 | 36 |
| 365.00 | 0.911 | 365.911 | | | | | 4 | 4 | 4 | 4 | 3.6 | R | | 8 | 8 | 16 | 8 |
| 365.00 | 0.907 | 365.907 | | | | | 4 | 4 | 4 | 4 | 3.6 | R | | 8 | 8 | 16 | 8 |
| 365.00 | 0.904 | 365.904 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.903 | 365.903 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.901 | 365.901 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.899 | 365.899 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.898 | 365.898 | | | | | 6 | 28 | | | 18.7 | R | | 16 | 4 | 20 | 12 |
| 365.00 | 0.897 | 365.897 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.896 | 365.896 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.893 | 365.893 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.892 | 365.892 | 6 | 12 | 6 | 12 | | | | | 16.0 | R | | 32 | 2 | 34 | 24 |
| 365.00 | 0.890 | 365.890 | | | | | 4 | 4 | 4 | 4 | 3.6 | R | | 8 | 8 | 16 | 8 |
| 365.00 | 0.886 | 365.886 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.882 | 365.882 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.882 | 365.882 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.879 | 365.879 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.877 | 365.877 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.875 | 365.875 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.873 | 365.873 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.871 | 365.871 | | | | | 84 | 4 | | | 37.3 | R | | 4 | 66 | 70 | 16 |
| 365.00 | 0.860 | 365.860 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.850 | 365.850 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.842 | 365.842 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.839 | 365.839 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.835 | 365.835 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.833 | 365.833 | 12 | 14 | | | | | | | 18.7 | R | | 16 | 4 | 20 | 12 |
| 365.00 | 0.831 | 365.831 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.824 | 365.824 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.813 | 365.813 | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.811 | 365.811 | 6 | 6 | | | | | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 365.00 | 0.808 | 365.808 | 38 | 4 | 4 | 4 | | | | | 18.7 | R | | 8 | 19 | 27 | 8 |
| 365.00 | 0.793 | 365.793 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.791 | 365.791 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.780 | 365.780 | | | | | 6 | 14 | | | 9.3 | R | | 16 | 4 | 20 | 12 |
| 365.00 | 0.779 | 365.779 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.772 | 365.772 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.768 | 365.768 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.765 | 365.765 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.750 | 365.750 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.746 | 365.746 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.742 | 365.742 | | | | | | | 6 | 12 | 8.0 | R | | 16 | 2 | 18 | 12 |

SD34 IN HOWARD

| MRM | DISP | DMI | WB DRIVING LANE | | WB PASSING LANE | | EB PASSING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | | DOWEL BAR Each | |
|--------|-------|---------|-----------------|------|-----------------|------|-----------------|------|--------------------------------------|------------------------------------|-------------------|---------------------------|---|-------------------------------------|---|----------------|----|
| | | | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | 1" x 18" PLAIN ROUND DOWEL BARS Each | No. 8 x 18" DEFORMED TIE BARS Each | | | No. 5 x 24" DEFORMED TIE BARS Each | INSERT STEEL BAR IN NRCP TOTAL Each | | | |
| 365.00 | 0.735 | 365.735 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.734 | 365.734 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.732 | 365.732 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.728 | 365.728 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.727 | 365.727 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.721 | 365.721 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.716 | 365.716 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.704 | 365.704 | 6 | 6 | | | | | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 365.00 | 0.685 | 365.685 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.670 | 365.670 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.658 | 365.658 | 6 | 6 | | | | | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 365.00 | 0.655 | 365.655 | 6 | 8 | | | | | | | 5.3 | R | | 10 | 2 | 12 | 8 |
| 365.00 | 0.653 | 365.653 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.652 | 365.652 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.648 | 365.648 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.644 | 365.644 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.642 | 365.642 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.640 | 365.640 | 6 | 8 | | | | | | | 5.3 | R | | 10 | 2 | 12 | 8 |
| 365.00 | 0.633 | 365.633 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.630 | 365.630 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.626 | 365.626 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.619 | 365.619 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.613 | 365.613 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.612 | 365.612 | 6 | 28 | | | | | | | 18.7 | W | 16 | | 2 | 18 | |
| 365.00 | 0.600 | 365.600 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.598 | 365.598 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.594 | 365.594 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.593 | 365.593 | 6 | 6 | | | | | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 365.00 | 0.578 | 365.578 | 6 | 6 | | | | | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 365.00 | 0.576 | 365.576 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.572 | 365.572 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.563 | 365.563 | 6 | 28 | | | | | | | 18.7 | w | 16 | | 2 | 18 | |
| 365.00 | 0.555 | 365.555 | 6 | 10 | | | | | | | 6.7 | R | | 12 | 2 | 14 | 10 |
| 365.00 | 0.548 | 365.548 | 6 | 6 | | | | | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 365.00 | 0.541 | 365.541 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.539 | 365.539 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.527 | 365.527 | | | | | | | 6 | 8 | 5.3 | R | | 10 | 4 | 14 | 8 |
| 365.00 | 0.525 | 365.525 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.518 | 365.518 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.506 | 365.506 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.495 | 365.495 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.494 | 365.494 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.487 | 365.487 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.479 | 365.479 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.476 | 365.476 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.473 | 365.473 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.469 | 365.469 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.465 | 365.465 | 6 | 14 | | | | | 4 | 4 | 11.1 | R | | 20 | 6 | 26 | 16 |
| 365.00 | 0.462 | 365.462 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.454 | 365.454 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.447 | 365.447 | 6 | 6 | | | | | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 365.00 | 0.443 | 365.443 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.439 | 365.439 | 6 | 16 | | | | | | | 10.7 | R | | 16 | 2 | 18 | 12 |
| 365.00 | 0.432 | 365.432 | | | | | | | 6 | 14 | 9.3 | R | | 16 | 4 | 20 | 12 |
| 365.00 | 0.421 | 365.421 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.417 | 365.417 | 6 | 10 | | | | | | | 6.7 | R | | 12 | 2 | 14 | 10 |

SD34 IN HOWARD

| MRM | DISP | DMI | WB DRIVING LANE | | WB PASSING LANE | | EB PASSING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | | DOWEL BAR Each | |
|--------|-------|---------|-----------------|------|-----------------|------|-----------------|------|-----------------|------|-------------------|---------------------------|---|------------------------------------|------------------------------------|----------------|------------------------|
| | | | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | | | 1" x 18" PLAIN ROUND DOWEL BARS Each | INSERT STEEL BAR IN | | | |
| | | | | | | | | | | | | | | No. 8 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | BAR IN NRCP TOTAL Each |
| 365.00 | 0.398 | 365.398 | 6 | 14 | | | | | | 9.3 | R | | 16 | 2 | 18 | 12 | |
| 365.00 | 0.383 | 365.383 | 6 | 6 | | | | | 4 | 6 | 6.7 | R | | 16 | 6 | 22 | 12 |
| 365.00 | 0.380 | 365.380 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.369 | 365.369 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.364 | 365.364 | 6 | 14 | | | | | | | 9.3 | R | | 16 | 2 | 18 | 12 |
| 365.00 | 0.352 | 365.352 | 6 | 14 | | | | | | | 9.3 | R | | 16 | 2 | 18 | 12 |
| 365.00 | 0.341 | 365.341 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.332 | 365.332 | | | | | | | 6 | 14 | 9.3 | R | | 16 | 4 | 20 | 12 |
| 365.00 | 0.326 | 365.326 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.320 | 365.320 | | | | | | | 6 | 8 | 5.3 | R | | 10 | 4 | 14 | 8 |
| 365.00 | 0.307 | 365.307 | 6 | 14 | | | | | | | 9.3 | R | | 16 | 2 | 18 | 12 |
| 365.00 | 0.294 | 365.294 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.291 | 365.291 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.285 | 365.285 | 6 | 14 | | | | | | | 9.3 | R | | 16 | 2 | 18 | 12 |
| 365.00 | 0.276 | 365.276 | | | | | | | 4 | 6 | 2.7 | R | | 8 | 4 | 12 | 6 |
| 365.00 | 0.274 | 365.274 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.268 | 365.268 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.261 | 365.261 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.253 | 365.253 | | | | | | | 4 | 6 | 2.7 | R | | 8 | 4 | 12 | 6 |
| 365.00 | 0.247 | 365.247 | 6 | 14 | | | | | | | 9.3 | R | | 16 | 2 | 18 | 12 |
| 365.00 | 0.231 | 365.231 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.228 | 365.228 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.227 | 365.227 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.225 | 365.225 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.217 | 365.217 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.216 | 365.216 | | | | | | | 6 | 8 | 5.3 | R | | 10 | 4 | 14 | 8 |
| 365.00 | 0.202 | 365.202 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.198 | 365.198 | 6 | 4 | | | | | | | 2.7 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.187 | 365.187 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.177 | 365.177 | 48 | 24 | | | | | | | 128.0 | W | 16 | | 19 | 35 | 24 |
| 365.00 | 0.172 | 365.172 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.157 | 365.157 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.142 | 365.142 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.115 | 365.115 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.111 | 365.111 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.108 | 365.108 | 4 | 4 | | | | | 4 | 4 | 3.6 | R | | 8 | 6 | 14 | 8 |
| 365.00 | 0.104 | 365.104 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.097 | 365.097 | | | | | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 365.00 | 0.089 | 365.089 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.078 | 365.078 | 6 | 6 | | | | | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 365.00 | 0.074 | 365.074 | 6 | 6 | | | | | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 365.00 | 0.070 | 365.070 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.059 | 365.059 | 6 | 6 | | | | | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 365.00 | 0.052 | 365.052 | 6 | 10 | | | | | | | 6.7 | R | | 12 | 2 | 14 | 10 |
| 365.00 | 0.044 | 365.044 | 6 | 6 | | | | | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 365.00 | 0.041 | 365.041 | 6 | 14 | | | | | | | 9.3 | R | | 16 | 2 | 18 | 12 |
| 365.00 | 0.037 | 365.037 | 6 | 14 | | | | | | | 9.3 | R | | 16 | 2 | 18 | 12 |
| 365.00 | 0.033 | 365.033 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.029 | 365.029 | 6 | 18 | | | | | | | 12.0 | R | | 16 | 2 | 18 | 12 |
| 365.00 | 0.027 | 365.027 | 6 | 18 | | | | | 4 | 4 | 13.8 | R | | 20 | 6 | 26 | 16 |
| 365.00 | 0.022 | 365.022 | 4 | 4 | | | | | 6 | 8 | 7.1 | R | | 14 | 6 | 20 | 12 |
| 365.00 | 0.019 | 365.019 | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 365.00 | 0.018 | 365.018 | | | | | | | 6 | 14 | 9.3 | R | | 16 | 4 | 20 | 12 |
| 365.00 | 0.011 | 365.011 | | | | | | | 6 | 6 | 4.0 | R | | 8 | 4 | 12 | 6 |
| 365.00 | 0.000 | 365.000 | | | | | 4 | 4 | | | 1.8 | R | | 4 | 4 | 8 | 4 |

SD34 IN HOWARD

| MRM | DISP | DMI | WB DRIVING LANE | | WB PASSING LANE | | EB PASSING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | | DOWEL BAR | |
|-------------------------------|------|-----|-----------------|------|-----------------|------|-----------------|------|--------------------------------|------------------------------------|-------------------|---------------------------|---|-------------------------------------|------|-----------|------|
| | | | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | 1" x 18" ROUND DOWEL BARS Each | No. 8 x 18" DEFORMED TIE BARS Each | | | No. 5 x 24" DEFORMED TIE BARS Each | INSERT STEEL BAR IN NRCP TOTAL Each | | | |
| TOTALS: | | | | | | | | | | | | 1653.3 | 80 | 2298 | 1319 | 3697 | 2024 |
| ADDITIONAL QUANTITIES: | | | | | | | | | | | | 330.0 | 20 | 460 | 260 | 740 | 400 |
| GRAND TOTALS | | | | | | | | | | | | 1983.3 | 100 | 2758 | 1579 | 4437 | 2424 |

NRC PAVEMENT REPAIR AREA TYPES

W = Two Working Joints (Use only if repair is full roadway width and uniform length (across all lanes))

T = Two Tied Joints

B = One Working & One Tied Joint

R = Two Tied Joints with Original Joint Restored with Dowel Bar Assembly

SD34 IN HOWARD

| WB DRIVING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | | DOWEL BAR Each | |
|-----------------|------|-----------------|------|-------------------|---------------------------|---|------------------------------------|------------------------------------|----------------|-------------------------------------|
| L Ft | W Ft | L Ft | W Ft | | | 1" x 18" ROUND DOWEL BARS Each | No. 8 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | INSERT STEEL BAR IN NRCP TOTAL Each |
| 6 | 20 | | | 13.3 | R | | 16 | 2 | 18 | 12 |
| 6 | 20 | | | 13.3 | R | | 16 | 2 | 18 | 12 |
| 6 | 20 | | | 13.3 | R | | 16 | 2 | 18 | 12 |
| 6 | 6 | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 6 | 40 | | | 26.7 | R | | 16 | 2 | 18 | 12 |
| 6 | 50 | | | 33.3 | R | | 16 | 2 | 18 | 12 |
| 6 | 20 | | | 13.3 | R | | 16 | 2 | 18 | 12 |
| 6 | 40 | | | 26.7 | R | | 16 | 2 | 18 | 12 |
| 6 | 40 | | | 26.7 | R | | 16 | 2 | 18 | 12 |
| 6 | 20 | | | 13.3 | R | | 16 | 2 | 18 | 12 |
| 6 | 20 | | | 13.3 | R | | 16 | 2 | 18 | 12 |
| 6 | 6 | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 6 | 40 | | | 26.7 | | 16 | 16 | 2 | 34 | |
| 6 | 10 | | | 6.7 | | 12 | 12 | 2 | 26 | |
| 4 | 6 | | | 2.7 | R | | 8 | 2 | 10 | 6 |
| 6 | 20 | | | 13.3 | R | | 16 | 2 | 18 | 12 |
| 8 | 14 | | | 12.4 | R | | 16 | 3 | 19 | 12 |
| 6 | 6 | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 20 | 12 | | | 26.7 | R | | 16 | 8 | 24 | 12 |
| | | 6 | 18 | 12.0 | R | | 16 | 4 | 20 | 12 |
| | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| | | 8 | 8 | 7.1 | R | | 10 | 6 | 16 | 8 |
| 4 | 4 | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 6 | 10 | | | 6.7 | R | | 12 | 2 | 14 | 10 |
| 6 | 12 | | | 8.0 | R | | 16 | 2 | 18 | 12 |
| 6 | 50 | | | 33.3 | R | | 16 | 2 | 18 | 12 |
| 6 | 6 | | | 4.0 | R | | 8 | 2 | 10 | 6 |
| 6 | 20 | | | 13.3 | R | | 16 | 2 | 18 | 12 |
| 6 | 20 | | | 13.3 | R | | 16 | 2 | 18 | 12 |
| 6 | 12 | | | 8.0 | R | | 16 | 2 | 18 | 12 |
| | | 6 | 14 | 9.3 | R | | 16 | 4 | 20 | 12 |
| | | 6 | 20 | 13.3 | R | | 16 | 4 | 20 | 12 |
| | | 6 | 40 | 26.7 | R | | 16 | 4 | 20 | 12 |
| | | 6 | 40 | 26.7 | R | | 16 | 4 | 20 | 12 |
| 4 | 4 | | | 1.8 | R | | 4 | 2 | 6 | 4 |
| 28 | 4 | | | 12.4 | R | | 4 | 11 | 15 | 4 |
| | | | | 506.5 | | 28 | 490 | 106 | 624 | 352 |
| | | | | 100.0 | | 10 | 100 | 20 | 130 | 70 |
| | | | | 606.5 | | 38 | 590 | 126 | 754 | 422 |

NRC PAVEMENT REPAIR AREA TYPES

W = Two Working Joints (Use only if repair is full roadway width and uniform length (across all lanes))

T = Two Tied Joints

B = One Working & One Tied Joint

R = Two Tied Joints with Original Joint Restored with Dowel Bar Assembly

I229S NEAR I90 INTERCHANGE IN SIOUX FALLS

| MRM | DISP | SB MEDIAN SHOULDER | | SB PASSING LANE 2 | | SB PASSING LANE 1 | | SB DRIVING LANE | | SB OUTSIDE SHOULDER | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | | INSERT STEEL BAR IN NRCP TOTAL Each | DOWEL BAR Each | TIE BAR RETROFIT STITCHING Each |
|-------|-------|--------------------|------|-------------------|------|-------------------|------|-----------------|------|---------------------|------|-------------------|---------------------------|--|-------------------------------------|------------------------------------|-------------------------------------|----------------|---------------------------------|
| | | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | | | 1 1/2" x 18" PLAIN ROUND DOWEL BARS Each | No. 11 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | | |
| 10.00 | 0.530 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 10.00 | 0.010 | | | | | 10 | 4 | | | | | 4.4 | R | | 4 | 8 | 12 | 4 | |
| 9.00 | 0.988 | 40 | 6 | | | 4 | 4 | | | | | 28.4 | R | | 4 | 20 | 24 | 4 | |
| 9.00 | 0.985 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.981 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.978 | | | 6 | 4 | | | | | | | 2.7 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.976 | 25 | 6 | | | | | | | | | 16.7 | R | | | 10 | 10 | | |
| 9.00 | 0.972 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.970 | | | 4 | 4 | 4 | 4 | | | | | 3.6 | R | | 8 | 6 | 14 | 8 | |
| 9.00 | 0.967 | 80 | 6 | | | 6 | 12 | | | | | 61.3 | R | | 16 | 36 | 52 | 12 | |
| 9.00 | 0.963 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.959 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.955 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.948 | | | | | 6 | 12 | | | | | 8.0 | R | | 16 | 4 | 20 | 12 | |
| 9.00 | 0.945 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.942 | | | | | 6 | 12 | | | | | 8.0 | R | | 16 | 4 | 20 | 12 | |
| 9.00 | 0.934 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.931 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.927 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.923 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.909 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.906 | | | | | 6 | 12 | | | | | 8.0 | R | | 16 | 4 | 20 | 12 | |
| 9.00 | 0.902 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.898 | | | 4 | 4 | 4 | 4 | | | | | 3.6 | R | | 8 | 6 | 14 | 8 | |
| 9.00 | 0.891 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.888 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.884 | 20 | 6 | 4 | 4 | 4 | 4 | | | | | 16.9 | R | | 8 | 14 | 22 | 8 | |
| 9.00 | 0.865 | | | 4 | 4 | 4 | 4 | | | | | 3.6 | R | | 8 | 6 | 14 | 8 | |
| 9.00 | 0.862 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.858 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.857 | 15 | 6 | | | | | | | | | 10.0 | R | | | 6 | 6 | | |
| 9.00 | 0.836 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.830 | | | | | 6 | 12 | | | | | 8.0 | R | | 16 | 4 | 20 | 12 | |
| 9.00 | 0.825 | | | | | 8 | 4 | | | | | 3.6 | R | | 4 | 6 | 10 | 4 | |
| 9.00 | 0.809 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.790 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.752 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.739 | | | 8 | 4 | 4 | 4 | | | | | 5.3 | R | | 8 | 7 | 15 | 8 | |
| 9.00 | 0.737 | | | 20 | 4 | | | | | | | 8.9 | R | | 4 | 8 | 12 | 4 | |
| 9.00 | 0.735 | | | 4 | 4 | 4 | 4 | | | | | 3.6 | R | | 8 | 6 | 14 | 8 | |
| 9.00 | 0.731 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.727 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.690 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.675 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.671 | | | 6 | 12 | | | | | | | 8.0 | R | | 16 | 2 | 18 | 12 | |
| 9.00 | 0.664 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.660 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.658 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.573 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.570 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.562 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.418 | | | | | | | | | | | | | | | | | | 8 |
| 9.00 | 0.390 | | | 6 | 12 | 4 | 4 | | | | | 9.8 | R | | 20 | 2 | 22 | 16 | |
| 9.00 | 0.375 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.371 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.356 | | | 6 | 12 | | | | | | | 8.0 | R | | 16 | 2 | 18 | 12 | |

I229S NEAR I90 INTERCHANGE IN SIOUX FALLS

| MRM | DISP | SB MEDIAN SHOULDER | | SB PASSING LANE 2 | | SB PASSING LANE 1 | | SB DRIVING LANE | | SB OUTSIDE SHOULDER | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | | INSERT STEEL BAR IN NRCP TOTAL | DOWEL BAR Each | TIE BAR RETROFIT STITCHING Each |
|-------------------------------|-------|--------------------|------|-------------------|------|-------------------|------|-----------------|------|---------------------|------|-------------------|---------------------------|--|-------------------------------------|------------------------------------|--------------------------------|----------------|---------------------------------|
| | | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | L Ft | W Ft | | | 1 1/2" x 18" PLAIN ROUND DOWEL BARS Each | No. 11 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | | |
| 9.00 | 0.353 | 120 | 6 | 6 | 12 | | | | | | | 88.0 | R | | 16 | 50 | 66 | 12 | |
| 9.00 | 0.326 | | | 6 | 12 | | | | | | | 8.0 | R | | 16 | 2 | 18 | 12 | |
| 9.00 | 0.324 | | | | | 6 | 12 | | | | | 8.0 | R | | 16 | 4 | 20 | 12 | |
| 9.00 | 0.323 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.319 | | | | | 6 | 12 | | | | | 8.0 | R | | 16 | 4 | 20 | 12 | |
| 9.00 | 0.273 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.239 | | | | | | | | | 4 | 4 | 1.8 | R | | | 4 | 4 | | |
| 9.00 | 0.236 | | | | | | | | | 4 | 4 | 1.8 | R | | | 4 | 4 | | |
| 9.00 | 0.232 | | | | | | | | | 4 | 4 | 1.8 | R | | | 4 | 4 | | 20 |
| 9.00 | 0.224 | | | | | 20 | 6 | | | | | 13.3 | R | | 8 | 16 | 24 | 6 | |
| 9.00 | 0.221 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.214 | | | 20 | 6 | | | | | | | 13.3 | R | | 8 | 8 | 16 | 6 | |
| 9.00 | 0.141 | | | 4 | 4 | | | 20 | 6 | | | 15.1 | R | | 12 | 18 | 30 | 10 | |
| 9.00 | 0.132 | | | | | | | 20 | 6 | | | 13.3 | R | | 8 | 16 | 24 | 6 | |
| 9.00 | 0.119 | | | | | 20 | 12 | | | | | 26.7 | R | | 16 | 16 | 32 | 12 | 20 |
| 9.00 | 0.112 | | | | | 6 | 12 | | | | | 8.0 | R | | 16 | 4 | 20 | 12 | |
| 9.00 | 0.105 | 10 | 6 | | | | | 6 | 12 | | | 14.7 | R | | 16 | 8 | 24 | 12 | |
| 9.00 | 0.104 | | | | | 4 | 4 | | | | | 1.8 | T | | 4 | 4 | 8 | | |
| 9.00 | 0.103 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.098 | | | | | | | | | | | | | | | | | | 20 |
| 9.00 | 0.095 | | | | | 20 | 6 | | | | | 13.3 | R | | 8 | 16 | 24 | 6 | |
| 9.00 | 0.088 | | | | | 4 | 4 | | | | | 1.8 | R | | 4 | 4 | 8 | 4 | |
| 9.00 | 0.080 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 9.00 | 0.076 | | | | | | | | | | | | | | | | | | 20 |
| 9.00 | 0.064 | | | | | | | | | | | | | | | | | | 20 |
| 9.00 | 0.050 | | | | | | | | | | | | | | | | | | 40 |
| 8.00 | 0.999 | | | 4 | 4 | | | | | | | 1.8 | R | | 4 | 2 | 6 | 4 | |
| 8.00 | 0.993 | | | | | 4 | 4 | | | | | 1.8 | T | | 4 | 4 | 8 | | |
| 8.00 | 0.950 | 65 | 6 | | | | | 4 | 4 | | | 45.1 | | 4 | 4 | 30 | 38 | | 10 |
| 8.00 | 0.940 | 20 | 6 | | | | | | | | | 13.3 | | | | 8 | 8 | | |
| 8.00 | 0.938 | | | 4 | 4 | | | | | | | 1.8 | | 4 | 4 | 2 | 10 | | |
| 8.00 | 0.937 | 4 | 4 | | | | | | | | | 1.8 | | | | 2 | 2 | | |
| 8.00 | 0.924 | | | 6 | 6 | | | | | | | 4.0 | | 8 | 8 | 2 | 18 | | |
| 8.00 | 0.891 | | | | | 4 | 4 | | | | | 1.8 | | 4 | 4 | 4 | 12 | | |
| 8.00 | 0.883 | | | 4 | 4 | | | | | | | 1.8 | | 4 | 4 | 2 | 10 | | |
| TOTALS: | | | | | | | | | | | | 612.5 | | 24 | 552 | 511 | 1087 | 450 | 158 |
| ADDITIONAL QUANTITIES: | | | | | | | | | | | | 120.0 | | - | 110 | 100 | 210 | 90 | 30 |
| GRAND TOTALS | | | | | | | | | | | | 732.5 | | 24 | 662 | 611 | 1297 | 540 | 188 |

NRC PAVEMENT REPAIR AREA TYPES

W = Two Working Joints (Use only if repair is full roadway width and uniform length (across all lanes))

T = Two Tied Joints

B = One Working & One Tied Joint

R = Two Tied Joints with Original Joint Restored with Dowel Bar Assembly

I90E NEAR I229 INTERCHANGE

| DMI | EB PASSING LANE | | EB DRIVING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | COMMENTS | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | INSERT STEEL BAR IN NRCP TOTAL Each | DOWEL BAR Each |
|-------------------------------|-----------------|------|-----------------|------|-------------------|---------------------------|-------------------------|---|------------------------------------|-------------------------------------|----------------|
| | L Ft | W Ft | L Ft | W Ft | | | | No. 11 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | |
| 401.465 | | | | | | | Begin Concrete | | | | |
| 401.675 | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 401.683 | | | 6 | 6 | 4.0 | R | | 8 | 4 | 12 | 6 |
| 401.702 | | | 6 | 14 | 9.3 | R | | 16 | 2 | 18 | 12 |
| 401.732 | | | 6 | 14 | 9.3 | R | | 16 | 2 | 18 | 12 |
| 401.755 | | | 6 | 14 | 9.3 | R | | 16 | 2 | 18 | 12 |
| 401.773 | | | 10 | 6 | 6.7 | T | | 8 | 8 | 16 | |
| 401.789 | 26 | 12 | 26 | 14 | 75.1 | R | | 32 | | 32 | 24 |
| 401.796 | 4 | 4 | 4 | 6 | 4.4 | R | | 12 | 6 | 18 | 10 |
| 401.800 | | | | | | | Replace Expansion Joint | | | | |
| 401.811 | | | | | | | End Concrete | | | | |
| TOTALS: | | | | | 119.9 | | | 112 | 28 | 140 | 80 |
| ADDITIONAL QUANTITIES: | | | | | 20.0 | | | 20 | 10 | 30 | 20 |
| GRAND TOTALS: | | | | | 139.9 | | | 132 | 38 | 170 | 100 |

NRC PAVEMENT REPAIR AREA TYPES

W = Two Working Joints (Use only if repair is full roadway width and uniform length (across all lanes))

T = Two Tied Joints

B = One Working & One Tied Joint

R = Two Tied Joints with Original Joint Restored with Dowel Bar Assembly

I90W NEAR I229 INTERCHANGE

| DMI | WB DRIVING LANE | | WB PASSING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | COMMENTS | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | INSERT STEEL BAR IN NRCP TOTAL Each | DOWEL BAR Each |
|---------|-----------------|------|-----------------|------|-------------------|---------------------------|-----------------------|---|------------------------------------|-------------------------------------|----------------|
| | L Ft | W Ft | L Ft | W Ft | | | | No. 11 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | |
| 401.803 | | | | | | | Expansion Joint | | | | |
| 401.799 | 8 | 14 | 6 | 12 | 20.4 | R | | 32 | | 32 | 24 |
| 401.773 | 12 | 14 | | | 18.7 | R | | 16 | 4 | 20 | 12 |
| 401.769 | | | 6 | 12 | 8.0 | R | | 16 | 2 | 18 | 12 |
| 401.758 | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 401.739 | 6 | 14 | 6 | 12 | 17.3 | R | | 32 | | 32 | 24 |
| 401.731 | | | 18 | 2 | 4.0 | R | | 2 | 14 | 16 | 2 |
| 401.727 | | | 6 | 2 | 1.3 | R | | 2 | 4 | 6 | 2 |
| 401.723 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.720 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.719 | | | 6 | 2 | 1.3 | R | | 2 | 4 | 6 | 2 |
| 401.717 | | | 6 | 2 | 1.3 | R | | 2 | 4 | 6 | 2 |
| 401.715 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.713 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.710 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.708 | | | 18 | 2 | 4.0 | R | | 2 | 14 | 16 | 2 |
| 401.707 | | | 2 | 3 | 0.7 | R | | 4 | 4 | 8 | 3 |
| 401.705 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.702 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.700 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.696 | | | 6 | 2 | 1.3 | R | | 2 | 4 | 6 | 2 |
| 401.694 | | | 12 | 2 | 2.7 | R | | 2 | 8 | 10 | 2 |
| 401.692 | | | 8 | 2 | 1.8 | R | | 2 | 6 | 8 | 2 |
| 401.690 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.687 | | | 6 | 2 | 1.3 | R | | 2 | 4 | 6 | 2 |
| 401.684 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.681 | | | 10 | 2 | 2.2 | R | | 2 | 8 | 10 | 2 |
| 401.679 | | | 8 | 2 | 1.8 | R | | 2 | 6 | 8 | 2 |
| 401.677 | | | 10 | 2 | 2.2 | R | | 2 | 8 | 10 | 2 |
| 401.673 | | | 6 | 2 | 1.3 | R | | 2 | 4 | 6 | 2 |
| 401.669 | | | 14 | 2 | 3.1 | R | | 2 | 10 | 12 | 2 |
| 401.667 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.665 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.662 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.659 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.657 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.654 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.651 | | | 20 | 6 | 13.3 | R | Remove Shoulder Panel | 8 | 16 | 24 | 6 |
| 401.649 | | | 12 | 2 | 2.7 | R | | 2 | 8 | 10 | 2 |
| 401.646 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.644 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.642 | | | 6 | 2 | 1.3 | R | | 2 | 4 | 6 | 2 |
| 401.642 | | | 6 | 2 | 1.3 | R | | 2 | 4 | 6 | 2 |
| 401.640 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.637 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.634 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.632 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.629 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.629 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.623 | | | 20 | 3 | 6.7 | R | | 4 | 16 | 20 | 3 |
| 401.621 | | | 12 | 2 | 2.7 | R | | 2 | 8 | 10 | 2 |
| 401.619 | | | 12 | 2 | 2.7 | R | | 2 | 8 | 10 | 2 |
| 401.617 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.617 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.614 | | | 6 | 2 | 1.3 | R | | 2 | 4 | 6 | 2 |
| 401.611 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |

I90W NEAR I229 INTERCHANGE

| DMI | WB DRIVING LANE | | WB PASSING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | COMMENTS | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | INSERT STEEL BAR IN NRCP TOTAL Each | DOWEL BAR Each |
|---------|-----------------|----|-----------------|----|-------------------|---------------------------|-----------------------|---|------------------------------------|-------------------------------------|----------------|
| | L | W | L | W | | | | No. 11 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | |
| | Ft | Ft | Ft | Ft | | | | | | | |
| 401.611 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.608 | | | 20 | 6 | 13.3 | R | Remove Shoulder Panel | 8 | 16 | 24 | 6 |
| 401.608 | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 401.606 | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 401.606 | | | 20 | 6 | 13.3 | R | Remove Shoulder Panel | 8 | 16 | 24 | 6 |
| 401.603 | | | 18 | 2 | 4.0 | R | | 2 | 14 | 16 | 2 |
| 401.603 | | | 2 | 4 | 0.9 | R | | 4 | 4 | 8 | 4 |
| 401.599 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.597 | | | 20 | 6 | 13.3 | R | Remove Shoulder Panel | 8 | 16 | 24 | 6 |
| 401.595 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.593 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.591 | | | 7 | 12 | 9.3 | R | | 16 | 2 | 18 | 12 |
| 401.590 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.588 | 7 | 4 | 7 | 12 | 12.4 | R | | 20 | 4 | 24 | 16 |
| 401.587 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.587 | | | 10 | 2 | 2.2 | R | | 2 | 8 | 10 | 2 |
| 401.584 | | | 10 | 2 | 2.2 | R | | 2 | 8 | 10 | 2 |
| 401.582 | | | 10 | 2 | 2.2 | R | | 2 | 8 | 10 | 2 |
| 401.579 | | | 6 | 2 | 1.3 | R | | 2 | 4 | 6 | 2 |
| 401.579 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.579 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.576 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.574 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.574 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.572 | | | 14 | 2 | 3.1 | R | | 2 | 10 | 12 | 2 |
| 401.572 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.569 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.567 | | | 10 | 2 | 2.2 | R | | 2 | 8 | 10 | 2 |
| 401.566 | | | 4 | 6 | 2.7 | R | | 8 | 4 | 12 | 6 |
| 401.564 | | | 20 | 6 | 13.3 | R | Remove Shoulder panel | 8 | 16 | 24 | 6 |
| 401.562 | | | 12 | 2 | 2.7 | R | | 2 | 8 | 10 | 2 |
| 401.562 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.560 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.557 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.554 | | | 14 | 2 | 3.1 | R | | 2 | 10 | 12 | 2 |
| 401.554 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.552 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.552 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.549 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.549 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.547 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.547 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.547 | | | 6 | 2 | 1.3 | R | | 2 | 4 | 6 | 2 |
| 401.544 | | | 8 | 2 | 1.8 | R | | 2 | 6 | 8 | 2 |
| 401.544 | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 401.542 | | | 18 | 2 | 4.0 | R | | 2 | 14 | 16 | 2 |
| 401.542 | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 401.539 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.539 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.536 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.536 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.534 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.534 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.532 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.532 | | | 4 | 2 | 0.9 | R | | 2 | 4 | 6 | 2 |
| 401.529 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |

I90W NEAR I229 INTERCHANGE

| DMI | WB DRIVING LANE | | WB PASSING LANE | | NRCP REPAIR SqYds | NEW JOINT CON-FIG. (NRCP) | COMMENTS | INSERT STEEL BAR IN PCC PAVEMENT (NRCP) | | INSERT STEEL BAR IN NRCP TOTAL | DOWEL BAR |
|-------------------------------|-----------------|------|-----------------|------|-------------------|---------------------------|-----------------------|---|------------------------------------|--------------------------------|------------|
| | L Ft | W Ft | L Ft | W Ft | | | | No. 11 x 18" DEFORMED TIE BARS Each | No. 5 x 24" DEFORMED TIE BARS Each | | |
| 401.529 | | | 7 | 12 | 9.3 | R | | 16 | 2 | 18 | 12 |
| 401.527 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.527 | | | 6 | 2 | 1.3 | R | | 2 | 4 | 6 | 2 |
| 401.524 | | | 6 | 2 | 1.3 | R | | 2 | 4 | 6 | 2 |
| 401.524 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.521 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.521 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.519 | | | 8 | 2 | 1.8 | R | | 2 | 6 | 8 | 2 |
| 401.519 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.514 | | | 8 | 2 | 1.8 | R | | 2 | 6 | 8 | 2 |
| 401.514 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.511 | | | 20 | 6 | 13.3 | R | Remove Shoulder Panel | 8 | 16 | 24 | 6 |
| 401.507 | | | 20 | 6 | 13.3 | R | Remove Shoulder Panel | 8 | 16 | 24 | 6 |
| 401.505 | | | 14 | 2 | 3.1 | R | | 2 | 10 | 12 | 2 |
| 401.505 | | | 2 | 2 | 0.4 | R | | 2 | 4 | 6 | 2 |
| 401.504 | | | 4 | 4 | 1.8 | R | | 4 | 4 | 8 | 4 |
| 401.503 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.501 | | | 20 | 6 | 13.3 | R | Remove Shoulder Panel | 8 | 16 | 24 | 6 |
| 401.501 | | | 2 | 4 | 0.9 | R | | 4 | 4 | 8 | 4 |
| 401.497 | | | 18 | 2 | 4.0 | R | | 2 | 14 | 16 | 2 |
| 401.497 | | | 2 | 4 | 0.9 | R | | 4 | 4 | 8 | 4 |
| 401.495 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.493 | | | 16 | 2 | 3.6 | R | | 2 | 12 | 14 | 2 |
| 401.490 | | | 20 | 2 | 4.4 | R | | 2 | 16 | 18 | 2 |
| 401.481 | | | 4 | 6 | 2.7 | R | End Project | 8 | 4 | 12 | 6 |
| TOTALS: | | | | | 485.8 | | | 488 | 1170 | 1658 | 430 |
| ADDITIONAL QUANTITIES: | | | | | 100.0 | | | 100 | 230 | 330 | 90 |
| GRAND TOTALS: | | | | | 585.8 | | | 588 | 1400 | 1988 | 520 |

NRC PAVEMENT REPAIR AREA TYPES

W = Two Working Joints (Use only if repair is full roadway width and uniform length (across all lanes))

T = Two Tied Joints

B = One Working & One Tied Joint


R = Two Tied Joints with Original Joint Restored with Dowel Bar Assembly

NONREINFORCED PCC PAVEMENT REPAIR

ANY SINGLE LANE ROADWAY (RAMPS, ETC.) TYPICAL REPAIR AREAS

| | | | |
|-----------------------|---------------|-------|--------------|
| STATE OF SOUTH DAKOTA | PROJECT | SHEET | TOTAL SHEETS |
| | IM-P 0022(85) | 36 | 64 |

Plotting Date: 02/28/2022



KEY:

PCC Pavement Repair Area

PCC PAVEMENT REPAIR AREA TYPES:

- (W) Two Working Joints (Use only if repair is full roadway width and uniform length (across entire driving surface))
- (T) Two Tied Joints
- (B) One Working & One Tied Joint
- (R) Two Tied Joints with Original Joint Restored with Dowel Bar Assembly

Steel Bars for Transverse Joints

Pavement Thickness $\geq 10.5"$

— Drilled in $1\frac{1}{2}" \times 18"$ epoxy coated plain round dowel bars spaced 18" center to center.

..... Drilled in No. 11 x 18" epoxy coated deformed tie bars spaced 18" center to center.

Pavement Thickness $\geq 8.5"$ and $< 10.5"$

— Drilled in $1\frac{1}{4}" \times 18"$ epoxy coated plain round dowel bars spaced 18" center to center.

..... Drilled in No. 9 x 18" epoxy coated deformed tie bars spaced 18" center to center.

Pavement Thickness $< 8.5"$

— Drilled in $1" \times 18"$ epoxy coated plain round dowel bars spaced 18" center to center.

..... Drilled in No. 8 x 18" epoxy coated deformed tie bars spaced 18" center to center.

DBA Dowel Bar Assembly

Steel Bars for Longitudinal Joints

..... No. 5 x 30" epoxy coated deformed tie bars. Sawn Joint - spaced 48" center to center. Construction Joint - spaced 48" center to center.

..... No. 5 x 24" epoxy coated deformed tie bars. Drilled In - spaced 30" center to center.


NOTES: Saw around repair areas full depth for removal.

- (1) Where possible, transverse joints will be constructed/maintained full roadway width.
- (2) Edges of repair areas will be formed to match the width of the existing concrete pavement.
- (3) Need for bars in small repair areas on/near the shoulder to be determined on a case-by-case basis, on construction by the Engineer.

NONREINFORCED PCC PAVEMENT REPAIR

Plotting Date: 02/28/2022

UP TO TWO LANE ROADWAY WITH CENTER LANE OR UP TO SIX LANE DIVIDED ROADWAY TYPICAL REPAIR AREAS



KEY:

PCC Pavement Repair Area

PCC PAVEMENT REPAIR AREA TYPES:

Two Working Joints (Use only if repair is full roadway width and uniform length (across all lanes))

Two Tied Joints

One Working & One Tied Joint

Two Tied Joints with Original Joint Restored with Dowel Bar Assembly

Longitudinal Keyway Joints Without Bars

Where a repair area intersects an existing longitudinal keyway joint without tie bars, the newly constructed joint should also be a keyway without tie bars.

Steel Bars for Transverse Joints

Pavement Thickness ≥ 10.5 "

— Drilled in $1\frac{1}{2}$ " x 18" epoxy coated plain round dowel bars spaced 18" center to center.

..... Drilled in No. 11 x 18" epoxy coated deformed tie bars spaced 18" center to center.

Pavement Thickness ≥ 8.5 " and < 10.5 "

— Drilled in $1\frac{1}{4}$ " x 18" epoxy coated plain round dowel bars spaced 18" center to center.

..... Drilled in No. 9 x 18" epoxy coated deformed tie bars spaced 18" center to center.

Pavement Thickness < 8.5 "

— Drilled in 1" x 18" epoxy coated plain round dowel bars spaced 18" center to center.

..... Drilled in No. 8 x 18" epoxy coated deformed tie bars spaced 18" center to center.

Dowel Bar Assembly

Steel Bars for Longitudinal Joints

..... No. 5 x 30" epoxy coated deformed tie bars. Sawn Joint - spaced 48" center to center. Construction Joint - spaced 48" center to center.

..... No. 5 x 24" epoxy coated deformed tie bars. Drilled In - spaced 30" center to center.

NOTES: Saw around repair areas full depth for removal.

① Where possible, transverse joints will be constructed/maintained full roadway width.

② Edges of repair areas will be formed to match the width of the existing concrete pavement.


③ Need for bars in small repair areas on/near the shoulder to be determined on a case-by-case basis, on construction by the Engineer.

NONREINFORCED PCC PAVEMENT REPAIR

UP TO FOUR LANE ROADWAY OR UP TO EIGHT LANE DIVIDED ROADWAY

TYPICAL REPAIR AREAS

Plotting Date: 02/28/2022



KEY:

PCC Pavement Repair Area

PCC PAVEMENT REPAIR AREA TYPES:

- Two Working Joints (Use only if repair is full roadway width and uniform length (across all lanes))
- Two Tied Joints
- One Working & One Tied Joint
- Two Tied Joints with Original Joint Restored with Dowel Bar Assembly

Longitudinal Keyway Joints Without Bars

Where a repair area intersects an existing longitudinal keyway joint without tie bars, the newly constructed joint should also be a keyway without tie bars.

Steel Bars for Transverse Joints

- Pavement Thickness ≥ 10.5 "**
 - Drilled in $1\frac{1}{2}$ " x 18" epoxy coated plain round dowel bars spaced 18" center to center.
 - Drilled in No. 11 x 18" epoxy coated deformed tie bars spaced 18" center to center.
- Pavement Thickness ≥ 8.5 " and < 10.5 "**
 - Drilled in $1\frac{1}{4}$ " x 18" epoxy coated plain round dowel bars spaced 18" center to center.
 - Drilled in No. 9 x 18" epoxy coated deformed tie bars spaced 18" center to center.
- Pavement Thickness < 8.5 "**
 - Drilled in 1" x 18" epoxy coated plain round dowel bars spaced 18" center to center.
 - Drilled in No. 8 x 18" epoxy coated deformed tie bars spaced 18" center to center.

Dowel Bar Assembly

Steel Bars for Longitudinal Joints

- No. 5 x 30" epoxy coated deformed tie bars. Sawn Joint - spaced 48" center to center. Construction Joint - spaced 48" center to center.
- No. 5 x 24" epoxy coated deformed tie bars. Drilled In - spaced 30" center to center.

NOTES: Saw around repair areas full depth for removal.

- Where possible, transverse joints will be constructed/maintained full roadway width.
- Edges of repair areas will be formed to match the width of the existing concrete pavement.
- Need for bars in small repair areas on/near the shoulder to be determined on a case-by-case basis, on construction by the Engineer.

PLOT SCALE - 1:10

PLOTTED FROM - TRSF12114


PLOT NAME - 1

FILE - ... \PCC REPAIR\PATCH 5.DGN


NONREINFORCED PCC PAVEMENT REPAIR

Plotting Date: 02/28/2022


**PLAIN ROUND DOWEL BAR INSERTION
TYPE W - (TWO WORKING JOINTS)**




**DEFORMED TIE BAR AND PLAIN ROUND DOWEL BAR INSERTION
TYPE B - (ONE TIED JOINT AND ONE WORKING JOINT)**



**DEFORMED TIE BAR INSERTION
TYPE T - (TWO TIED JOINTS)**



**DEFORMED TIE BAR INSERTION WITH DOWEL BAR ASSEMBLY
TYPE R - (TWO TIED JOINTS AND ONE WORKING JOINT - ORIGINAL JOINT RESTORED)**



| Existing Pavement Thickness | Epoxy Coated Deformed Tie Bar Size | Epoxy Coated Plain Round Dowel Bar Size |
|-----------------------------|------------------------------------|---|
| $T \geq 10.5"$ | No. 11 x 18" | 1½" x 18" |
| $T \geq 8.5"$ & $T < 10.5"$ | No. 9 x 18" | 1¼" x 18" |
| $T < 8.5"$ | No. 8 x 18" | 1" x 18" |

T = Existing pavement thickness.
T_N = New pavement thickness.

Bar embedded to a minimum depth of 9 inches into the existing pavement by utilizing an epoxy resin adhesive.

Cost for furnishing and inserting steel bars (deformed tie and plain round dowel) will be included in the contract unit price per each for Insert Steel Bar in PCC Pavement.

Cost for furnishing and installing dowel bar assembly will be included in the contract unit price per each for Dowel Bar.

T_N = T
(top of new pavement will be flush with top of existing pavement)

PLOT SCALE - 1/4"=1'-0"

PLOTTED FROM - TRSF12114

PLOT NAME - 16


FILE - ... \PCC REPAIR\BARS.DGN

NONREINFORCED PCC PAVEMENT REPAIR

| | | | |
|-----------------------------|---------------|-------|-----------------|
| STATE OF SOUTH DAKOTA | PROJECT | SHEET | TOTAL SHEETS |
| | IM-P 0022(85) | 40 | 64 |

Plotting Date: 02/28/2022


LONGITUDINAL CONSTRUCTION JOINT WITH TIE BARS & KEYWAY



T_N = New pavement thickness.

Cost for furnishing and inserting tie bars will be incidental to the contract unit price per square yard for Nonreinforced PCC Pavement Repair.

SAWED LONGITUDINAL JOINT




T_N = New pavement thickness.

The first saw cut to control cracking will be a minimum of 1/3 the depth of the pavement. Additional sawing for widening the saw cut will be necessary.

Cost for furnishing and inserting tie bars will be incidental to the contract unit price per square yard for Nonreinforced PCC Pavement Repair.

LONGITUDINAL CONSTRUCTION JOINT WITH DRILLED IN TIE BARS




T = Existing pavement thickness.
 T_N = New pavement thickness.

Bar embedded a minimum depth of 9 inches into the existing pavement by utilizing an epoxy resin adhesive.

Bars will be placed a minimum of 15 inches from existing transverse contraction joints.

Cost for furnishing and inserting drilled in tie bars will be included in the contract unit price per each for Insert Steel Bar in PCC Pavement.

LONGITUDINAL CONSTRUCTION JOINT WITH DRILLED IN TIE BARS



T = Existing pavement thickness.

Bar embedded a minimum depth of 9 inches into the existing pavement by utilizing an epoxy resin adhesive.

Bars will be placed a minimum of 15 inches from existing transverse contraction joints.

Cost for furnishing and inserting drilled in tie bars will be included in the contract unit price per each for Insert Steel Bar in PCC Pavement.

PLOT SCALE - 1:11.25

PLOTTED FROM - TRSF12114

PLOT NAME - 15


FILE - ... \PCC REPAIR\BARS.DGN

NONREINFORCED PCC PAVEMENT REPAIR

| | | | |
|-----------------------------|---------------|-------|-----------------|
| STATE OF SOUTH DAKOTA | PROJECT | SHEET | TOTAL SHEETS |
| | IM-P 0022(85) | 41 | 64 |

Plotting Date: 02/28/2022


LONGITUDINAL SHOULDER CONSTRUCTION JOINT WITH TIE BARS & KEYWAY



T_s = New shoulder pavement thickness.

Cost for furnishing and inserting tie bars will be incidental to the contract unit price per square yard for Nonreinforced PCC Pavement Repair.

SAWED LONGITUDINAL SHOULDER JOINT




T_s = New shoulder pavement thickness.

The first saw cut to control cracking will be a minimum of 1/3 the depth of the pavement. Additional sawing for widening the saw cut will be necessary.

Cost for furnishing and inserting tie bars will be incidental to the contract unit price per square yard for Nonreinforced PCC Pavement Repair.

LONGITUDINAL SHOULDER JOINT WITH DRILLED IN TIE BARS




T = Existing shoulder pavement thickness.

Bar embedded a minimum depth of 9 inches into the existing pavement by utilizing an epoxy resin adhesive.

Bars will be placed a minimum of 15 inches from existing transverse contraction joints.

Cost for furnishing and inserting drilled in tie bars will be included in the contract unit price per each for Insert Steel Bar in PCC Pavement.

LONGITUDINAL SHOULDER JOINT WITH DRILLED IN TIE BARS



T_s = New shoulder pavement thickness.

Bar embedded a minimum depth of 9 inches into the existing pavement by utilizing an epoxy resin adhesive.

Bars will be placed a minimum of 15 inches from existing transverse contraction joints.

Cost for furnishing and inserting drilled in tie bars will be included in the contract unit price per each for Insert Steel Bar in PCC Pavement.


NONREINFORCED PCC PAVEMENT REPAIR

SAW & SEAL TRANSVERSE JOINTS


| | | | |
|-----------------------------|--------------------------|-------------|-----------------------|
| STATE OF SOUTH DAKOTA | PROJECT IM-P 0022(85) | SHEET 42 | TOTAL SHEETS 64 |
|-----------------------------|--------------------------|-------------|-----------------------|

Plotting Date: 02/28/2022


WITH HOT POURED ELASTIC JOINT SEALER AT WORKING JOINTS ENTIRELY WITHIN REPAIR AREAS




WITH HOT POURED ELASTIC JOINT SEALER AT WORKING JOINTS (TYPICALLY URBAN)



WITH HOT POURED ELASTIC JOINT SEALER AT TIED JOINTS



WITH LOW MODULUS SILICONE SEALANT AT WORKING JOINTS (TYPICALLY RURAL)



* Refer to Standard Plate 380.13 for installation details using Joint Width J=3/8".

** The saw cut to control cracking will be a minimum of 1/4 the thickness of the pavement.

PLOT SCALE - 1:0.12


PLOTTED FROM - TRSF12114

PLOT NAME - 1

FILE - ...REPAIR_TRANSVERSE_JOINT.DGN

REPAIR OF TYPE A SPALLS


REMOVAL (NRC)




If Dowel Bar is exposed coat the bar with duct tape as a bond breaker

* Existing Sealant to be removed is low modulus silicone sealant with backer rod or hot poured elastic joint sealer.

REMOVAL (CRC)




PATCHING




** Form Material will be removed by sawing or other means approved by the Engineer. Spall repaired joints will then be sealed with Backer Rod and Low Modulus Silicone Sealant.

REPAIR OF TYPE A SPALLS

NRC SPALL PATCHES (PLAN VIEW)



CRC SPALL PATCHES (PLAN VIEW)




PLOT SCALE - 1:10

PLOTTED FROM - TRSF12114

PLOT NAME - 3


FILE - ... \DGN\PCPREP\TR\SPALL.DGN

TIE BAR RETROFIT (STITCHING)



PLAN VIEW

TIE BAR RETROFIT (STITCHING)



T = Pavement Thickness

ELEVATION VIEW

TABLE OF STITCHING DIMENSIONS

| T | A | B | Length of Tie Bar |
|---------|--------|---------|-------------------|
| 8" | 5" | 1 1/2"± | 10" |
| 8 1/2" | 5 1/4" | 1 3/8"± | 11" |
| 9" | 5 5/8" | 1 1/4"± | 12" |
| 9 1/2" | 6" | 1 5/8"± | 12 1/2" |
| 10" | 6 3/8" | 1 1/2"± | 13 1/2" |
| 10 1/2" | 6 3/4" | 1 3/8"± | 14 1/2" |
| 11" | 7" | 1 1/4"± | 15 1/2" |
| 11 1/2" | 7 3/8" | 1 3/8"± | 16" |
| 12" | 7 3/4" | 1 3/8"± | 16 1/2" |
| 12 1/2" | 8 1/8" | 1 1/4"± | 17 1/2" |

Stitch Bar Spacing 24" Max.


| Joint Spacing | Number of Bars |
|---------------|----------------|
| 3' to 4.5' | 2 |
| 5' to 6.5' | 3 |
| 7' to 8.5' | 4 |
| 9' to 10.5' | 5 |
| 11' to 12.5' | 6 |
| 13' to 14.5' | 7 |
| 15' to 16.5' | 8 |
| 17' to 18.5' | 9 |
| 19' to 20.5' | 10 |
| 21 to 22.5' | 11 |
| 23' to 24.5' | 12 |
| 25' to 26.5' | 13 |
| 27' to 28.5' | 14 |
| 29' to 30.5' | 15 |

TYPICAL PCC PAVEMENT REPAIR AROUND MANHOLES


| | | | |
|-----------------------------|---------------|-------|-----------------|
| STATE OF SOUTH DAKOTA | PROJECT | SHEET | TOTAL SHEETS |
| | IM-P 0022(85) | 45 | 64 |

Plotting Date: 02/28/2022


BOX-OUT DETAIL IN PCC PAVEMENT



Where the utility access is offset from the longitudinal and transverse joints




Where the utility access is intersected by the longitudinal and transverse joints




Where no Longitudinal or Transverse joints are present or at Longitudinal or Transverse joint.


REBAR LAYOUTS IN PCC PAVEMENT WITH BOX-OUT



Where the utility access is offset from the longitudinal and transverse joints




Where the utility access is intersected by the longitudinal and transverse joints




Where no Longitudinal or Transverse joints are present or at Longitudinal or Transverse joint.

REBAR LAYOUT IN PCC PAVEMENT WITHOUT BOX-OUT



The rebar will not cross any joint in the concrete pavement. If manhole is next to a joint in the concrete pavement the Engineer will approve a revised layout of the rebar.

MANHOLE EXPANSION JOINT DETAIL



* Rebar will be placed at the midpoint depth of the PCC Pavement. Cost for furnishing & installing rebar and constructing box-outs will be incidental to the contract unit price per square yard for Nonreinforced PCC Pavement Repair and/or Fast Track Concrete for PCC Pavement Repair.

PLOT SCALE - 1/4" = 1'-0"

PLOTTED FROM - TRSF12114


FILE - ... \PCC REPAIR\MANHOLES.DGN

REPAIR CONCRETE CURB AND/OR GUTTER

| | | | |
|-----------------------|---------------|-------|--------------|
| STATE OF SOUTH DAKOTA | PROJECT | SHEET | TOTAL SHEETS |
| | IM-P 0022(85) | 46 | 64 |

Plotting Date: 03/22/2022


REMOVAL



Remove Concrete Curb and/or Gutter

* If sawing is required, the cost will be incidental to the contract unit price per foot for Repair Concrete Curb and/or Gutter.




INSTALLATION



Class M6 Concrete

- ▲ 9" Minimum
23" Maximum
- ▲▲ No. 5 x 24" Epoxy Coated Deformed Tie Bar Drilled 9" into in place pavement **
- ▲▲▲ No. 5 x 24" Epoxy Coated Deformed Tie Bar Drilled 9" into in place curb & gutter **

See standard plate(s) for Type B, D and F Concrete Curb and Gutter and Type P Concrete Gutter for construction and forming details.



** Cost for this work will be included in the contract unit price per each for Insert Steel Bar in PCC Pavement.

Maintain 2" clear cover on all rebar.

PLOT SCALE - 1:2


PLOTTED FROM - TRSF12114

PLOT NAME - 1

FILE - ... \DESKTOP\CURB & GUTTER.DGN

LAYOUT FOR REPAIR CONCRETE CURB AND/OR GUTTER ADJACENT TO DROP INLET


REMOVAL



 Remove Concrete Curb and/or Gutter


* If sawing is required, the cost will be incidental to the contract unit price per foot for Repair Concrete Curb and/or Gutter.

INSTALLATION




- ▲ 9" Minimum
23" Maximum
- ▲▲ No. 5 x 24" Epoxy Coated Deformed Tie Bar Drilled 9" into in place pavement **
- ▲▲▲ No. 5 x 24" Epoxy Coated Deformed Tie Bar Drilled 9" into in place curb & gutter **

Sec. A-A



Sec. B-B



Maintain 2" clear cover on all rebar.

See standard plate for Type B Concrete Curb and Gutter for forming details.


** Cost for this work will be included in the contract unit price per each for Insert Steel Bar in PCC Pavement.

RESEAL PCC PAVEMENT JOINTS

| | | | |
|-----------------------|---------------|-------|--------------|
| STATE OF SOUTH DAKOTA | PROJECT | SHEET | TOTAL SHEETS |
| | IM-P 0022(85) | 48 | 64 |


Plotting Date: 02/28/2022

RESEAL TRANSVERSE JOINT WITH HOT POURED ELASTIC JOINT SEALER



The first saw cut to control cracking will be a minimum of 1/4 the depth of the pavement. Additional sawing for widening the saw cut to provide the width for the installation of the Hot Poured Elastic Joint Sealer will be necessary.

RESEAL LONGITUDINAL JOINT WITH HOT POURED ELASTIC JOINT SEALER



Additional sawing for widening the saw cut to provide the width for the installation of the Hot Poured Elastic Joint Sealer will be necessary.

SEQUENCE OF OPERATIONS

1. Install Traffic Control devices per the details in these plans
2. Complete all concrete repair work
3. Grind areas listed in the plans
4. Reseal joints
5. Install permanent pavement marking

If the Contractor requests to deviate from the sequence of operations will be submitted in writing to the Engineer for review. Approval of an alternate sequence of operations will only be allowed when the proposed changes meet with the Department's intent for traffic control and sequencing of the work. An alternate sequence will be submitted for review a minimum of one week prior to potential implementation.

GENERAL TRAFFIC CONTROL

Existing guide, route, informational logo, regulatory, and warning signs will be temporarily reset and maintained during construction. Removing, relocating, covering, salvaging, and resetting of existing traffic control devices, including delineation, will be the responsibility of the Contractor. Cost for this work will be incidental to the contract unit prices for the various items unless otherwise specified in the plans. Any delineators and signs damaged or lost will be replaced by the Contractor at no cost to the State.

All temporary traffic control sign locations will be set in the field by the Contractor and verified by the Engineer prior to installation.

All temporary speed limit signs will have a minimum mounting height of 5 feet in rural locations, even when mounted on portable supports.

Portable sign supports will not be located on sidewalks, bicycle facilities, or other areas designated for pedestrian or bicycle traffic.

All construction operations will be conducted in the general direction of traffic movement.

If there is a discrepancy between the traffic control plans, standard plates, and the MUTCD, whichever is more stringent will be used, as determined by the Engineer.

Unless otherwise stated in these plans, work will not be allowed during hours of darkness.

Fixed location signing placed more than 4 calendar days prior to the start of construction will be covered or laid down until the time of construction. The covers must be approved by the Engineer prior to installation. The cost of material, labor, and equipment necessary to complete this work will be incidental to other contract items. No separate payment will be made.

All fixed location signs, sign posts, and breakaway bases will be removed within 7 calendar days following pavement marking.

All haul trucks will be equipped with an additional flashing amber light that is visible from the backside of the haul truck. Cost for flashing amber lights will be incidental to the contract unit prices for the various related items.

GENERAL TRAFFIC CONTROL (CONTINUED)

Traffic will be maintained on the driving lanes only. Use of the shoulder as a driving lane will not be permitted. Any damage to the shoulder due to rerouted traffic or Contractor's equipment will be repaired at no expense to the Department.

A Type 3 Barricade will be installed at the end of a lane closure taper as detailed in these plans. Additional Type 3 Barricades will be installed facing traffic within the closed lane at a spacing of ¼ mile.

Lane closures will be limited to 5 miles in length. The distance between the closest points of any two-lane closures will be at least 3 miles, excluding tapers.

Construction vehicles will exit or enter the construction work zone at locations identified by the Engineer. At no time will construction vehicles utilize the maintenance crossovers or the Interstate median to exit or enter Interstate traffic.

On Interstate projects with more than one construction site, slow moving equipment that operates at a speed less than 40 MPH may mobilize between sites if the equipment travels on the shoulder. The slow-moving equipment will also display a flashing amber light and a slow-moving sign.

LANE CLOSURES

Interstate lane closures shorter than 5 miles will be used if 5 miles is greater than the length of work that can be accomplished in one day's production. More than one lane closure may be permitted; however, there will be a minimum of a three-mile section between lane closures, excluding the tapers.

Interstate lane closures will be removed when work will not be occurring for a period of 3 or more calendar days. Activities that do not involve workers being present, such as curing time for concrete, constitute work. Lane closures will not be set up on a Friday if no work will be occurring on Saturday or Sunday. In these cases, the lane closure will be installed on Monday.

FLAGGING

Operations will be conducted so that the traveling public will not have to wait longer than 15 minutes at the flagger station.

Additional flagger warning signs and flagger hours have been included in the Estimate of Quantities for use on intersecting roads. These flaggers will be used as directed by the Engineer and will be used primarily during daytime hours. Also included in the Estimate of Quantities are WAIT FOLLOW PILOT CAR signs for use on low volume intersecting roads as determined by the Engineer. WAIT FOLLOW PILOT CAR signs will not block the view of the stop sign.



FLAGGING (CONTINUED)

It is required that the flaggers and pilot car operators be able to communicate with one another. If an emergency vehicle needs to pass through the project, the Contractor will be required to expedite traffic movement. Cost associated with this will be incidental to the contract unit price per hour for Flagging.

WORK ZONE SPEED REDUCTION

The Department is required to obtain a speed reduction resolution prior to the installation of any SPEED LIMIT (R2-1) signs shown on standard plate 634.63 or as shown in the plans. To provide adequate time for the resolution to be enacted, the Contractor will inform the Engineer a minimum of 3 weeks prior to the scheduled installation of any work zone speed reduction signs on the project. The information provided by the Contractor will include the anticipated date of sign installation, the newly reduced speed limit, the location of the work zone, and the anticipated completion date of work requiring the speed reduction.

TEMPORARY PAVEMENT MARKING

Temporary flexible vertical markers (tabs) will be used to mark dashed centerline, No Passing Zones, and applicable lane lines. Paint will not be allowed for temporary pavement marking on the asphalt concrete wear course.

Temporary flexible vertical markers (tabs) may be used as detailed in the specifications.

Covers on the tabs will be sufficiently secured to prevent traffic from dislodging the cover and when removed, the covers will be properly disposed of. The Contractor will remove and properly dispose of the tabs after permanent pavement marking is applied. Method of removal will be nondestructive to the road surface and will be accomplished within one week of completion of the permanent pavement marking.

Full reflectivity of all temporary flexible vertical markers (tabs) is required at all times. The Contractor will be required to replace any missing or non-reflective tabs at no additional cost to the State.

Prior to nightfall, tabs will be required to mark centerline on segments of roadway where existing centerline marking has been removed and new marking has not been installed.

PERMANENT PAVEMENT MARKING

The Contractor will be required to repaint all existing pavement marking including centerline, edge line, lane lines, turn arrows, stop bars, and pedestrian crossings. This list is approximate. The Contractor will be required to document and be able to relocate for replacement of the existing, turn arrows, stop bars, pedestrian crossings, etc. before such marking is obliterated. Additional quantities are included in the estimate of quantities to paint the additional pavement marking. Cost to duplicate the existing marking locations will be incidental to the contract unit prices for the various contract items.

TRAFFIC CONTROL FOR PCCP REPAIR

Each mainline concrete repair location, from which the in-place concrete has been removed, will be marked with a minimum of two reflectorized drums. In areas containing numerous concrete repair locations, two reflectorized drums should be installed at a spacing of 660 feet alternating with the Type 3 Barricades.

Construction workspaces on undivided roadways will be limited to 1000 feet in length. The distance between the closest points of any two construction workspaces, including channeling devices, will not be less than 3 miles. Drivers in two-way traffic workspaces must be able to see approaching traffic through and beyond the work zone. Flagger controlled workspaces will be limited to 1 mile in length.

Construction workspaces in urban areas will be limited to 3 blocks in length. The minimum distance between workspaces will be 3 blocks.

When work is in progress within an intersection, Flaggers will be required to direct traffic.

The Contractor will use Flaggers during peak traffic hours and at times specified by the Engineer to supplement the stop conditions. Peak traffic hours are assumed to be 6:30 am to 8:30 am, 11:30 am to 1:00 pm and 4:30 pm to 6:00 pm. It is possible that Flagging will be required during all daytime hours. Advance warning Flagger signs will be required when Flaggers are present and removed when no Flaggers are present.

Holes adjacent to centerline in the lane open to traffic created during removal and replacement of PCC pavement repair areas will be filled with gravel cushion material and cold-mix asphalt concrete prior to opening the lane to traffic. Gravel cushion material and cold-mix asphalt concrete will be furnished by the Contractor.

Holes in the gravel and asphalt concrete shoulders created during removal and replacement of PCC pavement repair areas will be filled with gravel cushion material and hot-mix asphalt concrete (to match the shoulder surfacing) prior to opening the lane to traffic. Gravel cushion material and hot-mix asphalt concrete will be furnished and installed by the Contractor at no additional cost to the State.

Cost for furnishing, hauling, and placing gravel cushion material and asphalt concrete will be incidental to the contract unit price per square yard for Nonreinforced PCC Pavement Repair.

Routing traffic onto the mainline shoulders during any phase of the construction will not be allowed.

Extra care will be taken to protect the in place asphalt concrete shoulders on I90 and I29 locations. In all workspaces in these areas, flexible delineators will be required on the shoulders and will also be placed in locations to adequately keep traffic completely off the shoulders. Continuous maintenance will be required to keep them in place.

Type B warning lights will be placed on top of FLAGGER (W20-7) symbol signs.

Joints in approaches to signalized intersections containing vehicle detector loops will not be sawed, sealed, or otherwise disturbed.

The Contractor will be required to contact the Engineer two weeks in advance so that the Region Traffic Engineer can arrange for signal timings to be adjusted to accommodate traffic when a lane is closed near a signalized intersection.

TRAFFIC CONTROL FOR PCCP REPAIR (CONTINUED)

The Contractor will maintain pedestrian access at crosswalk locations. Additional traffic control devices will be used as necessary to accommodate the pedestrian traffic if work activities block an existing crosswalk.

Reflectorized drums or Type 2 Barricades will be used to maintain a minimum of two-way traffic at intersecting roads or streets. The Contractor will mark and maintain alternating one-way access to businesses and residences along the project with cones, drums, or Type 1 Barricades. The Contractor will advise affected businesses before a restriction to the business is installed, as well as the anticipated duration of the restriction.

PORTABLE TEMPORARY TRAFFIC CONTROL SIGNAL

Bridge over Skunk Creek on SD38

| PHASING AND SEQUENCING | | | | | | | |
|---|-----|---|-----|---|---------------------------|---|---------------|
| INTERVAL | 1 | 2 | 3 | 4 | 5 | 6 | FLASH DISPLAY |
| SIGNAL HEADS | | | | | | | |
| SD38 EB | φ A | G | Y | R | R | R | R |
| SD38 WB | φ B | R | R | R | G | Y | R |
| TIMINGS BASED ON MAXIMUM 1400 FT* DISTANCE BETWEEN OPPOSING STOP LINES AND TRAFFIC SPEED OF 35 MPH. | | | | | | | FLASH TIME |
| CYCLE LENGTH = 112 Seconds | | | | | | | |
| PHASES | φ A | | φ B | | | | |
| MOVEMENTS | → | | ← | | FAILURE OR EMERGENCY ONLY | | |
| MIN. GREEN (SEC) | 10 | | 10 | | | | |
| EXTENSION GREEN (SEC) | 5 | | 5 | | | | |
| MAX GREEN(SEC) | 25 | | 25 | | | | |
| YELLOW (SEC) | 4 | | 4 | | | | |
| ALL RED (SEC) | 27 | | 27 | | | | |

* - The timings may be adjusted if the length between the stop lines varies from the 1400 ft value used in calculations. The all red times may be recalculated as follows:

$$\text{All Red} = t + \frac{V}{2a} + \frac{W + L}{V} - Y$$

Where W = The distance between stop lines (ft).

Green times may be adjusted accordingly, however the total cycle length shall not exceed 120 seconds.

The portable temporary traffic control signal will be set up to dwell in red.

All vehicle signal heads will have backplates with retroreflective border. The vehicle signal head backplates will have a factory applied 3-inch wide yellow retroreflective border. Sheeting for the border will be Type IX or Type XI in conformance with ASTM D4956.

PORTABLE TEMPORARY TRAFFIC CONTROL SIGNAL (CONTINUED)

Signal backplates will be polycarbonate, aluminum, or aluminum-composite. Minimum material thicknesses are:

- Polycarbonate, 0.10-inch
- Aluminum, 0.06-inch
- Aluminum-Composite, 0.08-inch

Signal backplates will extend not less than 5 inches from the edge of the signal head at the top, bottom, and sides.

All traffic signal equipment and material will meet the requirements of Sections 635 and 985 of the Specifications except the controller requirements.

Cost involved with constructing the portable temporary traffic control signal as specified above and on the plans, will be included in the contract unit price per unit for Portable Temporary Traffic Control Signal.

CONTACTOR FURNISHED PORTABLE CHANGEABLE MESSAGE SIGN

One week prior to starting work affecting the traveling public, portable changeable message signs (PCMS) will be installed at locations detailed in the plans to notify drivers of the upcoming construction. The Contractor will program the portable changeable message signs with the following message:

ROAD WORK
STARTS
DATE

When work begins that will affect traffic patterns, the Contractor will re-program the PCMS with the messages below:

ROAD
WORK
AHEAD

BE PREPARED
TO STOP

INCIDENTS

An incident is an emergency road user occurrence, a natural disaster, or other unplanned event that affects or impedes the normal flow of traffic such as a crash, hazardous material spill, or other event.

The Contractor will set up a meeting prior to start of work to plan and coordinate responses to an incident. The Contractor will invite the Department of Transportation, the South Dakota Highway Patrol, the County Sheriffs, and local emergency response entities to the meeting.

The Contractor will assist to maintain traffic as required by these plan notes and as agreed to at that meeting.

Emergency vehicle access through the project will be considered and discussed at the meeting.

The Contractor may be required to modify messages on portable changeable message signs or relocate portable changeable message signs, and to provide flaggers to direct or detour traffic. The Contractor should be prepared to relocate advance warning signs if determined to be necessary for a major traffic incident lasting more than two hours. Fixed location ground mounted signs may be covered and additional portable signs provided.

No additional payment will be made for the modification of portable changeable message sign messages or the relocation of portable changeable message signs.

Cost for the relocation of an advance warning sign due to an incident will be 50% of the designated sign rate. Flaggers will be paid for at the contract unit price per hour for Flagging.

TEMPORARY PAVEMENT MARKING TAPE, TYPE I

Temporary pavement marking for stop lines will consist of 4" Temporary Pavement Marking Tape Type I. Placement of each 24" white stop line will be accomplished by placing six pieces of 4" x 12' tape adjacent to one another. Each workspace requires two stop lines which is an equivalent of approximately 144' of 4" tape (2,544 ft total per workspace). Temporary Pavement Marking Tape Type I will be required for centerline marking shown on standard plate 634.25. Temporary tape will be removed upon completion of the project.

TEMPORARY RAISED PAVEMENT MARKERS

Temporary raised pavement markers will be used for marking edge lines, lane lines, and tapers and centerlines. Temporary raised pavement markers will be used on all new permanent surfacing sections of roadway and on existing surfacing where temporary marking locations are different than existing marking locations, unless noted or as directed by the Engineer.

Temporary raised pavement markers will be attached to the roadway surface with a flexible non-permanent bituminous adhesive capable of being removed from the roadway surface or with an adhesive approved by the Engineer.

Cost to furnish, install, replace if necessary, and remove the markers will be incidental to the contract unit price per foot for Temporary Raised Pavement Markers.

GROOVING FOR COLD APPLIED PLASTIC PAVEMENT MARKING

The Contractor will establish a positive means for the removal of the grinding and/or grooving residue. Residue from dry grooving will be vacuumed. Solid residue will be removed from the pavement surfaces before being blown by traffic action or wind. The Contractor will conduct this work to control and minimize airborne dust and similar debris that may become a hazard to motor vehicle operation or nuisance to property owners. Residue from wet grooving will not be permitted to flow across lanes being used by public traffic or into gutter or drainage facilities. Residue, whether in solid or slurry form, will be disposed of in a manner that will prevent it from reaching any waterway in a concentrated state. The cleaning of the residue for grooving will be to the satisfaction of the Engineer and may require more than one pass to adequately remove material. Cost for removal of grinding and/or grooving residue will be included in the contract unit price per square foot, for Grooving for Cold Applied Plastic Pavement Marking contract items.

PREFORMED THERMOPLASTIC PAVEMENT MARKING

General

- Made of prefabricated retroreflective, resilient thermoplastic material;
- Contains glass beads uniformly distributed through the entire cross-sectional area;
- Capable of being affixed to bituminous or concrete pavement by heating;
- Resistant to deterioration due to exposure to sunlight, water, salt, and adverse weather conditions;
- Under traffic wear, shows no appreciable fading in accordance with the color requirements, lifting, or shrinkage throughout the life of the marking;
- Capable of conforming to pavement contours, breaks, and faults through the action of traffic at normal pavement temperatures;
- Possesses resealing characteristics, such that it is capable of fusing with itself and previous thermoplastic marking when heated; and
- Protected during shipment and in storage.

Apply the preformed thermoplastic pavement marking as recommended by the manufacturer to provide a neat, durable marking that will not flow, distort, or crack due to temperature if the pavement surface remains stable. Use equipment and application methods specified by the manufacturer. Primer as required by the manufacturer will be provided with the material.

Application of the marking will include the use of any manufacturer recommended sealers. Sealers may be required on concrete pavements, inside grooves, or on older asphalt pavements. Prior to placing any marking on new concrete, the Contractor will remove any curing compounds. Removal will be by sandblasting or other standard industry methods.

Any required primers or sealers will be included in the contract unit price for the various preformed thermoplastic pavement marking items.

Provide precut messages and symbols meeting the requirements of the MUTCD and the Standard Signs Manual in custom kits. Use separate pieces or segments to form individual letters or symbols only to the extent supplied by the manufacturer. Provide shapes, sizes, and colors as required by the contract.

Color

- Will meet the color specification limits and luminance factors for Cold Applied Plastic Pavement Marking and Legends (Section 983.2 D, Tables 1 and 2).

PREFORMED THERMOPLASTIC PAVEMENT MARKING (CONTINUED)

Glass Beads

- Ensure the preformed thermoplastic pavement marking contains a minimum 30% intermixed glass beads by weight and a minimum 80% true spheres.
- Ensure preformed thermoplastic pavement marking contains only clear beads.

Skid Resistance

- Ensure the surface of the preformed thermoplastic pavement marking provides a skid resistance value of at least 45 British Pendulum Number (BPN) when tested in accordance with ASTM E303.

Retroreflectivity

- Provide preformed thermoplastic pavement marking meeting the minimum initial pavement marking retroreflectivity values using 30 m geometry and meeting the testing procedures of ASTM E1710:

| Minimum Initial Pavement Marking Retroreflectivity | | |
|--|---------------------|---------------------|
| | White | Yellow |
| Thermoplastic | 400 mcd/sq. ft./ft. | 250 mcd/sq. ft./ft. |
| Thermoplastic, enhanced skid resistance (ESR) | 250 d/sq. ft./ft. | 150 d/sq. ft./ft. |

Thickness

- A longitudinal marking is a minimum 90 mils thick at the edges, and a maximum 125 mils thick at the center of the stripe.
- Transverse marking and symbols are a minimum 125 mils thick at the edges, and a maximum 160 mils thick at the center.

Sample

- Prior to application, the Contractor will provide a sample of the preformed thermoplastic pavement marking to be used on the project to the Region Traffic Engineer for inspection and approval.
- Do not begin application of the preformed thermoplastic pavement marking prior to obtaining the Region Traffic Engineer's approval of the preformed thermoplastic pavement marking material. The Region Traffic Engineer's approval of the preformed thermoplastic pavement marking does not void other preformed thermoplastic pavement marking requirements specified.

HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT

Material will be applied as per manufacturer's recommendations. Reflective media consisting of glass beads as well as bonded core reflective elements will be adhered to the paint.

No further testing of this material will be required. Reflective media consisting of glass beads as well as bonded core reflective elements will be adhered to the paint.

The bonded core reflective elements will contain either clear or yellow tinted microcrystalline ceramic beads bonded to the outer surface. The bonded core reflective elements will provide a 50/50 blend of dry to wet ratio of reflective element. All microcrystalline ceramic beads bonded to reflective elements will have a minimum index of refraction of 1.8 for dry retroreflectivity and 2.4 for wet retroreflectivity when tested using the liquid oil immersion method.

Pavement marking not conforming to the retroreflectivity requirements will be removed and replaced. If replacement of marking cannot be applied within the same year, the Contractor will schedule subject work to be completed no later than June 15th in the following year.

Upon replacement, the retroreflectivity testing process will be done again requiring new readings.

The Department will randomly select one test location per mile of each edge line including ramps and one test location per mile of centerline (solid and/or skip line will be considered as one centerline). Three retroreflectivity readings will be taken at each test location. The three readings will be averaged and become the reading for that test location.

Initial readings:

| Pavement Marking Color | Minimum Value |
|------------------------|----------------------------|
| White | 350 mc/m ² /lux |
| Yellow | 275 mc/m ² /lux |

All pavement marking not conforming to the requirements provided in these plans will be considered deficient and will be removed and replaced. Additional retroreflectivity readings will be taken by the Department to determine the limits of removal. The removal will be accomplished using suitable sand blasting or grinding equipment unless the Engineer authorizes other means. The removal process will remove at least 90% of the deficient line, with no excessive scarring of the existing pavement. The removal width will be one inch wider all around the nominal width of the pavement marking to be removed. Removal and replacement of the pavement marking will be at the Contractor's expense, with no cost incurred by the State.

High Build Waterborne Pavement Marking Paint applied after October 15 must be formulated as cold-weather waterborne paint. Cold weather waterborne paint will meet the requirements of Section 980.1 B.

RATES OF MATERIALS FOR HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT

Solid 4" line = 27.8 Gals/Mile
Dashed 4" line = 7.6 Gal/Mile
Glass Beads = 5.3 Lbs/Gal.
Composite Reflective Elements = 2.1 Lbs/Gal.

Cost for material, labor and equipment necessary to furnish and install the pavement marking will be incidental to the contract unit price for the respective High Build Waterborne Pavement Marking Paint items.

PAINTING FOR PCC REPAIRS

PAVEMENT MARKING

Typical pavement marking as shown on this sheet will be applied throughout the entire length of the roadway.

Traffic Control will be incidental to the cost of application. The striper and advance or trailing warning vehicle will be equipped with flashing amber lights and advance warning arrow board.

Left Arrows, in sets of two, spaced 8' or 16' arrow tip to arrow tip, (when two are required) will be positioned in the center turn lane at 300' spacing, at a frequency of one set of arrows per block or at existing arrow locations.

Application rates will be as follows:

| Two Lane Roadway with Center Turn Lane (Rates for one line) | |
|--|--|
| Solid Yellow Centerline | Rate = 22.5 Gals./Pass-Mile |
| Dashed Yellow Centerline | Rate = 6.2 Gals./Pass-Mile |
| Solid White Edgeline | Rate = 22.5 Gals./Pass-Mile (Not applicable in curb and gutter) |

| ESTIMATED QUANTITIES (BASED ON ONE APPLICATION) | |
|---|-------------|
| HIGH BUILD | QUANTITY |
| WHITE | 155 GALLONS |
| YELLOW | 93 GALLONS |

| Included in the above quantities are: | | | |
|---------------------------------------|----------|---|---------|
| Additional White (1 Application) | | Additional Yellow (1 Application) | |
| Description | Gallons | Description | Gallons |
| 4" Lines | 2060' 12 | Transitions 2 Ea | 1220' 7 |
| 8" Lines | - | 4" Skip Lines | - |
| 12" Gore Lines | - | 8" Lines | - |
| Crosswalks | - | 12" Lines | - |
| 24" Stop Lines | - | 24" Hatches | 60' 3 |
| 24" Hatches | 342' 17 | Solid Areas 150sf | 6 |
| Solid Areas | - | Additional Yellow: | 16 |
| <u>Arrows</u> | | | |
| Left Arrows | - | Additional Quantities | |
| Right Arrows | - | <u>Rates of Coverage:</u> SqFt/Gal | |
| Straight Arrows | - | 4", 8" & 12" Lines | 60 |
| Combo Arrows | - | 24" Lines & Hatches | 40 |
| Lane Drop Arrows | - | Arrows, Messages and Solid Areas | 25 |
| <u>Messages</u> | | | |
| STOP | - | All pavement marking dimensions are based on 12' driving lanes. | |
| STOP AHEAD | - | | |
| R X R w/ Stop Lines | - | | |
| SCHOOL X-ING | - | | |
| Additional White: | | 29 | |

| ESTIMATED QUANTITIES | | | | | |
|----------------------|----|----|-----|------|-------------|
| THERMO | 4" | 8" | 12" | 24" | SOLID AREAS |
| WHITE | - | - | - | 816' | - |
| YELLOW | - | - | - | - | - |

| Included in the above quantities are: | | | |
|---------------------------------------|------|-------------------|---|
| Additional White | | Additional Yellow | |
| Description | | Description | |
| 4" Lines | - | Transitions | - |
| 8" Lines | - | 4" Skip Lines | - |
| 12" Gore Lines | - | 8" Lines | - |
| Crosswalks 9 Ea, 24" W | 504' | 12" Lines | - |
| 24" Stop Lines | 312' | 24" Hatches | - |
| 24" Hatches | - | Solid Areas | - |
| Solid Areas | - | | |

| Additional White Items | | Additional Yellow Item | |
|-------------------------------|-------|---|--|
| <u>Arrows</u> | | <u>Symbols</u> | |
| Left Arrows | 28 Ea | All pavement marking dimensions are based on 12' driving lanes. | |
| Right Arrows | 1 Ea | | |
| Straight Arrows | - | | |
| Combo Arrows | 1 Ea | | |
| Lane Drop Arrows | - | | |
| <u>Messages</u> | | | |
| STOP | - | | |
| STOP AHEAD | - | | |
| R X R w/ Stop Lines | - | | |
| SCHOOL X-ING | - | | |
| <u>Symbols</u> | | | |
| Symbols | - | | |
| Int'l Symbol of Accessibility | - | | |

SD38 IN HARTFORD

| SIGN CODE | SIGN DESCRIPTION | CONVENTIONAL ROAD | | | |
|---|---------------------------------|-------------------|-----------|---------------|--------------|
| | | NUMBER | SIGN SIZE | SQFT PER SIGN | SQFT |
| R1-1 | STOP | 8 | 48" | 13.3 | 106.4 |
| R3-1 | RIGHT TURN PROHIBITION (symbol) | 8 | 24" x 24" | 4.0 | 32.0 |
| R3-2 | LEFT TURN PROHIBITION (symbol) | 8 | 24" x 24" | 4.0 | 32.0 |
| R4-7 | KEEP RIGHT (symbol) | 8 | 24" x 30" | 5.0 | 40.0 |
| W1-4 | REVERSE CURVE (L or R) | 2 | 48" x 48" | 16.0 | 32.0 |
| W9-3 | CENTER LANE CLOSED AHEAD | 1 | 48" x 48" | 16.0 | 16.0 |
| W13-1P | ADVISORY SPEED (plaque) | 2 | 30" x 30" | 6.3 | 12.6 |
| W20-1 | ROAD WORK AHEAD | 12 | 48" x 48" | 16.0 | 192.0 |
| G20-2 | END ROAD WORK | 6 | 36" x 18" | 4.5 | 27.0 |
| CONVENTIONAL ROAD TRAFFIC CONTROL SIGNS SQFT | | | | | 490.0 |

SD38 OVER SKUNK CREEK

| SIGN CODE | SIGN DESCRIPTION | CONVENTIONAL ROAD | | | |
|---|-------------------------|-------------------|-----------|---------------|--------------|
| | | NUMBER | SIGN SIZE | SQFT PER SIGN | SQFT |
| R10-6 | STOP HERE ON RED | 2 | 24" x 36" | 6.0 | 12.0 |
| W1-4 | REVERSE CURVE (L or R) | 2 | 48" x 48" | 16.0 | 32.0 |
| W3-3 | SIGNAL AHEAD (symbol) | 2 | 48" x 48" | 16.0 | 32.0 |
| W13-1P | ADVISORY SPEED (plaque) | 2 | 30" x 30" | 6.3 | 12.6 |
| W20-1 | ROAD WORK AHEAD | 2 | 48" x 48" | 16.0 | 32.0 |
| W20-4 | ONE LANE ROAD AHEAD | 2 | 48" x 48" | 16.0 | 32.0 |
| G20-2 | END ROAD WORK | 2 | 36" x 18" | 4.5 | 9.0 |
| CONVENTIONAL ROAD TRAFFIC CONTROL SIGNS SQFT | | | | | 161.6 |

SD38E AT W 60 ST N IN SIOUX FALLS

| SIGN CODE | SIGN DESCRIPTION | CONVENTIONAL ROAD | | | |
|---|----------------------------------|-------------------|-----------|---------------|--------------|
| | | NUMBER | SIGN SIZE | SQFT PER SIGN | SQFT |
| R3-1 | RIGHT TURN PROHIBITION (symbol) | 4 | 24" x 24" | 4.0 | 16.0 |
| R3-2 | LEFT TURN PROHIBITION (symbol) | 4 | 24" x 24" | 4.0 | 16.0 |
| R3-7R | RIGHT LANE MUST TURN RIGHT | 2 | 30" x 30" | 6.3 | 12.6 |
| R3-7L | LEFT LANE MUST TURN LEFT | 2 | 30" x 30" | 6.3 | 12.6 |
| R4-7 | KEEP RIGHT (symbol) | 4 | 24" x 30" | 5.0 | 20.0 |
| W4-2 | LEFT or RIGHT LANE ENDS (symbol) | 1 | 48" x 48" | 16.0 | 16.0 |
| W20-1 | ROAD WORK AHEAD | 3 | 48" x 48" | 16.0 | 48.0 |
| W20-5 | LEFT or RIGHT LANE CLOSED AHEAD | 1 | 48" x 48" | 16.0 | 16.0 |
| G20-2 | END ROAD WORK | 1 | 36" x 18" | 4.5 | 4.5 |
| CONVENTIONAL ROAD TRAFFIC CONTROL SIGNS SQFT | | | | | 161.7 |

SD38W AT W 60 ST N IN SIOUX FALLS

| SIGN CODE | SIGN DESCRIPTION | CONVENTIONAL ROAD | | | |
|---|----------------------------------|-------------------|-----------|---------------|-------------|
| | | NUMBER | SIGN SIZE | SQFT PER SIGN | SQFT |
| W4-2 | LEFT or RIGHT LANE ENDS (symbol) | 1 | 48" x 48" | 16.0 | 16.0 |
| W20-1 | ROAD WORK AHEAD | 1 | 48" x 48" | 16.0 | 16.0 |
| W20-5 | LEFT or RIGHT LANE CLOSED AHEAD | 1 | 48" x 48" | 16.0 | 16.0 |
| G20-2 | END ROAD WORK | 1 | 36" x 18" | 4.5 | 4.5 |
| CONVENTIONAL ROAD TRAFFIC CONTROL SIGNS SQFT | | | | | 52.5 |

190E NEAR BUFFALO RIDGE

| SIGN CODE | SIGN DESCRIPTION | EXPRESSWAY / INTERSTATE | | | |
|---|----------------------------------|-------------------------|-----------|---------------|--------------|
| | | NUMBER | SIGN SIZE | SQFT PER SIGN | SQFT |
| R2-1 | SPEED LIMIT 65 | 4 | 36" x 48" | 12.0 | 48.0 |
| R2-1 | SPEED LIMIT 45 | 2 | 36" x 48" | 12.0 | 24.0 |
| R2-1 | SPEED LIMIT 80 | 2 | 36" x 48" | 12.0 | 24.0 |
| R2-6aP | FINES DOUBLE (plaque) | 2 | 36" x 24" | 6.0 | 12.0 |
| W3-5 | SPEED REDUCTION AHEAD (65 MPH) | 2 | 48" x 48" | 16.0 | 32.0 |
| W4-2 | LEFT or RIGHT LANE ENDS (symbol) | 2 | 48" x 48" | 16.0 | 32.0 |
| W20-1 | ROAD WORK AHEAD | 2 | 48" x 48" | 16.0 | 32.0 |
| W3-5 | SPEED REDUCTION AHEAD (45 MPH) | 2 | 48" x 48" | 16.0 | 32.0 |
| W20-5 | LEFT or RIGHT LANE CLOSED AHEAD | 2 | 48" x 48" | 16.0 | 32.0 |
| G20-2 | END ROAD WORK | 2 | 48" x 24" | 8.0 | 16.0 |
| EXPRESSWAY / INTERSTATE TRAFFIC CONTROL SIGNS SQFT | | | | | 284.0 |

190W NEAR BUFFALO RIDGE

| SIGN CODE | SIGN DESCRIPTION | EXPRESSWAY / INTERSTATE | | | |
|---|----------------------------------|-------------------------|-----------|---------------|--------------|
| | | NUMBER | SIGN SIZE | SQFT PER SIGN | SQFT |
| R2-1 | SPEED LIMIT 65 | 4 | 36" x 48" | 12.0 | 48.0 |
| R2-1 | SPEED LIMIT 45 | 2 | 36" x 48" | 12.0 | 24.0 |
| R2-1 | SPEED LIMIT 80 | 2 | 36" x 48" | 12.0 | 24.0 |
| R2-6aP | FINES DOUBLE (plaque) | 2 | 36" x 24" | 6.0 | 12.0 |
| W3-5 | SPEED REDUCTION AHEAD (65 MPH) | 2 | 48" x 48" | 16.0 | 32.0 |
| W4-2 | LEFT or RIGHT LANE ENDS (symbol) | 2 | 48" x 48" | 16.0 | 32.0 |
| W20-1 | ROAD WORK AHEAD | 2 | 48" x 48" | 16.0 | 32.0 |
| W3-5 | SPEED REDUCTION AHEAD (45 MPH) | 2 | 48" x 48" | 16.0 | 32.0 |
| W20-5 | LEFT or RIGHT LANE CLOSED AHEAD | 2 | 48" x 48" | 16.0 | 32.0 |
| G20-2 | END ROAD WORK | 2 | 48" x 24" | 8.0 | 16.0 |
| EXPRESSWAY / INTERSTATE TRAFFIC CONTROL SIGNS SQFT | | | | | 284.0 |

I29N NEAR I90 INTERCHANGE

| SIGN CODE | SIGN DESCRIPTION | EXPRESSWAY / INTERSTATE | | | |
|---|----------------------------------|-------------------------|-----------|---------------|--------------|
| | | NUMBER | SIGN SIZE | SQFT PER SIGN | SQFT |
| R2-1 | SPEED LIMIT 65 | 4 | 36" x 48" | 12.0 | 48.0 |
| R2-1 | SPEED LIMIT 45 | 2 | 36" x 48" | 12.0 | 24.0 |
| R2-1 | SPEED LIMIT 80 | 2 | 36" x 48" | 12.0 | 24.0 |
| R2-6aP | FINES DOUBLE (plaque) | 2 | 36" x 24" | 6.0 | 12.0 |
| W3-5 | SPEED REDUCTION AHEAD (65 MPH) | 2 | 48" x 48" | 16.0 | 32.0 |
| W4-2 | LEFT or RIGHT LANE ENDS (symbol) | 2 | 48" x 48" | 16.0 | 32.0 |
| W20-1 | ROAD WORK AHEAD | 2 | 48" x 48" | 16.0 | 32.0 |
| W3-5 | SPEED REDUCTION AHEAD (45 MPH) | 2 | 48" x 48" | 16.0 | 32.0 |
| W20-5 | LEFT or RIGHT LANE CLOSED AHEAD | 2 | 48" x 48" | 16.0 | 32.0 |
| G20-2 | END ROAD WORK | 2 | 48" x 24" | 8.0 | 16.0 |
| EXPRESSWAY / INTERSTATE TRAFFIC CONTROL SIGNS SQFT | | | | | 284.0 |

I90E NEAR I229 INTERCHANGE

| SIGN CODE | SIGN DESCRIPTION | EXPRESSWAY / INTERSTATE | | | |
|---|----------------------------------|-------------------------|-----------|---------------|--------------|
| | | NUMBER | SIGN SIZE | SQFT PER SIGN | SQFT |
| R2-1 | SPEED LIMIT 65 | 4 | 36" x 48" | 12.0 | 48.0 |
| R2-1 | SPEED LIMIT 45 | 2 | 36" x 48" | 12.0 | 24.0 |
| R2-1 | SPEED LIMIT 80 | 2 | 36" x 48" | 12.0 | 24.0 |
| R2-6aP | FINES DOUBLE (plaque) | 2 | 36" x 24" | 6.0 | 12.0 |
| W1-4 | REVERSE CURVE (L or R) | 2 | 48" x 48" | 16.0 | 32.0 |
| W3-5 | SPEED REDUCTION AHEAD (65 MPH) | 2 | 48" x 48" | 16.0 | 32.0 |
| W4-2 | LEFT or RIGHT LANE ENDS (symbol) | 2 | 48" x 48" | 16.0 | 32.0 |
| W20-1 | ROAD WORK AHEAD | 2 | 48" x 48" | 16.0 | 32.0 |
| W3-5 | SPEED REDUCTION AHEAD (45 MPH) | 2 | 48" x 48" | 16.0 | 32.0 |
| W20-5 | LEFT or RIGHT LANE CLOSED AHEAD | 2 | 48" x 48" | 16.0 | 32.0 |
| G20-2 | END ROAD WORK | 2 | 48" x 24" | 8.0 | 16.0 |
| EXPRESSWAY / INTERSTATE TRAFFIC CONTROL SIGNS SQFT | | | | | 316.0 |

SD34 IN HOWARD


| SIGN CODE | SIGN DESCRIPTION | CONVENTIONAL ROAD | | | |
|---|----------------------------------|-------------------|-----------|---------------|--------------|
| | | NUMBER | SIGN SIZE | SQFT PER SIGN | SQFT |
| R1-1 | STOP | 4 | 48" | 13.3 | 53.2 |
| R3-1 | RIGHT TURN PROHIBITION (symbol) | 6 | 24" x 24" | 4.0 | 24.0 |
| R3-2 | LEFT TURN PROHIBITION (symbol) | 6 | 24" x 24" | 4.0 | 24.0 |
| R3-7R | RIGHT LANE MUST TURN RIGHT | 2 | 30" x 30" | 6.3 | 12.6 |
| R3-7L | LEFT LANE MUST TURN LEFT | 2 | 30" x 30" | 6.3 | 12.6 |
| W1-4 | REVERSE CURVE (L or R) | 2 | 48" x 48" | 16.0 | 32.0 |
| W4-1 | MERGE (symbol) | 2 | 48" x 48" | 16.0 | 32.0 |
| W4-2 | LEFT or RIGHT LANE ENDS (symbol) | 2 | 48" x 48" | 16.0 | 32.0 |
| W9-2 | LANE ENDS MERGE LEFT | 2 | 48" x 48" | 16.0 | 32.0 |
| W13-1P | ADVISORY SPEED (plaque) | 2 | 30" x 30" | 6.3 | 12.6 |
| W20-1 | ROAD WORK AHEAD | 14 | 48" x 48" | 16.0 | 224.0 |
| W20-5 | LEFT or RIGHT LANE CLOSED AHEAD | 2 | 48" x 48" | 16.0 | 32.0 |
| G20-2 | END ROAD WORK | 2 | 36" x 18" | 4.5 | 9.0 |
| CONVENTIONAL ROAD TRAFFIC CONTROL SIGNS SQFT | | | | | 532.0 |

I90W NEAR I229 INTERCHANGE

| SIGN CODE | SIGN DESCRIPTION | EXPRESSWAY / INTERSTATE | | | |
|---|----------------------------------|-------------------------|-----------|---------------|--------------|
| | | NUMBER | SIGN SIZE | SQFT PER SIGN | SQFT |
| R2-1 | SPEED LIMIT 65 | 4 | 36" x 48" | 12.0 | 48.0 |
| R2-1 | SPEED LIMIT 45 | 2 | 36" x 48" | 12.0 | 24.0 |
| R2-1 | SPEED LIMIT 80 | 2 | 36" x 48" | 12.0 | 24.0 |
| R2-6aP | FINES DOUBLE (plaque) | 2 | 36" x 24" | 6.0 | 12.0 |
| W1-4 | REVERSE CURVE (L or R) | 2 | 48" x 48" | 16.0 | 32.0 |
| W3-5 | SPEED REDUCTION AHEAD (65 MPH) | 2 | 48" x 48" | 16.0 | 32.0 |
| W4-2 | LEFT or RIGHT LANE ENDS (symbol) | 2 | 48" x 48" | 16.0 | 32.0 |
| W20-1 | ROAD WORK AHEAD | 2 | 48" x 48" | 16.0 | 32.0 |
| W3-5 | SPEED REDUCTION AHEAD (45 MPH) | 2 | 48" x 48" | 16.0 | 32.0 |
| W20-5 | LEFT or RIGHT LANE CLOSED AHEAD | 2 | 48" x 48" | 16.0 | 32.0 |
| G20-2 | END ROAD WORK | 2 | 48" x 24" | 8.0 | 16.0 |
| EXPRESSWAY / INTERSTATE TRAFFIC CONTROL SIGNS SQFT | | | | | 316.0 |

I229S NEAR I90 INTERCHANGE

| SIGN CODE | SIGN DESCRIPTION | EXPRESSWAY / INTERSTATE | | | |
|---|----------------------------------|-------------------------|-----------|---------------|--------------|
| | | NUMBER | SIGN SIZE | SQFT PER SIGN | SQFT |
| R2-1 | SPEED LIMIT 65 | 4 | 36" x 48" | 12.0 | 48.0 |
| R2-1 | SPEED LIMIT 45 | 2 | 36" x 48" | 12.0 | 24.0 |
| R2-6aP | FINES DOUBLE (plaque) | 2 | 36" x 24" | 6.0 | 12.0 |
| W3-5 | SPEED REDUCTION AHEAD (65 MPH) | 2 | 48" x 48" | 16.0 | 32.0 |
| W4-2 | LEFT or RIGHT LANE ENDS (symbol) | 3 | 48" x 48" | 16.0 | 48.0 |
| W4-3 | ADDED LANE (symbol) | 1 | 48" x 48" | 16.0 | 16.0 |
| W20-1 | ROAD WORK AHEAD | 4 | 48" x 48" | 16.0 | 64.0 |
| W3-5 | SPEED REDUCTION AHEAD (45 MPH) | 2 | 48" x 48" | 16.0 | 32.0 |
| W20-5 | LEFT or RIGHT LANE CLOSED AHEAD | 3 | 48" x 48" | 16.0 | 48.0 |
| G20-2 | END ROAD WORK | 2 | 48" x 24" | 8.0 | 16.0 |
| EXPRESSWAY / INTERSTATE TRAFFIC CONTROL SIGNS SQFT | | | | | 340.0 |



Signals will be installed and operated in accordance with the requirements of Part 4 of the MUTCD. Temporary traffic control signals will meet the physical display and operational requirements of conventional traffic signals.

Temporary traffic control signal timing will be established by the Region Traffic Engineer.


When the temporary traffic control signal is changed to a flashing mode, either manually or automatically, red signal indications will be flashed to both approaches.

Adjustments in the height of the signal heads will be made as necessary to conform to the vertical alignment of the roadway.

The channelizing devices will be drums or 42" cones.

The length of A may be adjusted to fit field conditions.

January 22, 2021



Prohibit left turns as required by traffic conditions. Unless the streets are wide, it may be physically impossible to turn left, especially for large vehicles.

A minimum of six channelizing devices will be used for each taper.

The channelizing devices will be drums or type 2 barricades if traffic control must remain overnight.

For short duration operations (1 hour or less) all channelizing devices may be eliminated if a vehicle with an activated flashing or revolving yellow light is used.

Flashing warning lights and/or flags may be used to call attention to the advance warning signs.

January 22, 2021

| Posted Speed Prior to Work (M.P.H.) | Spacing of Advance Warning Signs (Feet) (A) | Taper Length (Feet) (L) | Spacing of Channelizing Devices (Feet) (G) |
|-------------------------------------|---|-------------------------|--|
| 0 - 30 | 200 | 180 | 25 |
| 35 - 40 | 350 | 320 | 25 |
| 45 | 500 | 600 | 25 |
| 50 | 500 | 600 | 50 * |
| 55 | 750 | 660 | 50 * |
| 60 - 65 | 1000 | 780 | 50 * |

* Spacing is 40' for 42" cones.


- ⊙ Reflectorized Drum
- Channelizing Device
- ④ 4" White Temporary Pavement Marking

The channelizing devices will be 42" cones or drums.

42" cones may be used in place of the drums shown in the taper if setup will not be used during night time hours.

Temporary pavement markings will be used if traffic control must remain overnight.


The length of A and L may be adjusted to fit field conditions.



September 22, 2021

| | | |
|----------------------------------|--|-------------------------------|
| S D D O T | 4-LANE UNDIVIDED, RIGHT LANE CLOSED | PLATE NUMBER 634.47 |
| | | Sheet 1 of 1 |

Published Date: 1st Qtr. 2022



| Posted Speed Prior to Work (M.P.H.) | Spacing of Advance Warning Signs (Feet) (A) | Taper Length (Feet) (L) | Spacing of Channelizing Devices (Feet) (G) |
|-------------------------------------|---|-------------------------|--|
| 0 - 30 | 200 | 180 | 25 |
| 35 - 40 | 350 | 320 | 25 |
| 45 | 500 | 600 | 25 |
| 50 | 500 | 600 | 50 * |
| 55 | 750 | 660 | 50 * |
| 60 - 65 | 1000 | 780 | 50 * |

- * Spacing is 40' for 42" cones.
- ⊙ Reflectorized Drum
- Channelizing Device
- ④ 4" Yellow Temporary Pavement Marking

Pavement markings no longer applicable will be removed or obliterated as soon as practical.

Temporary pavement markings will be used if traffic control must remain overnight.

The channelizing devices will be 42" cones or drums.

42" cones may be used in place of the drums shown in the taper if setup will not be used during night time hours.



Use opposing left lane closure only when work may encroach in that lane. If closure is not required use only the ROAD WORK AHEAD sign for opposing traffic and center line channelizing markers.

The length of A and L may be adjusted to fit field conditions.

September 22, 2021

| | | |
|----------------------------------|---|-------------------------------|
| S D D O T | 4-LANE UNDIVIDED, LEFT LANE CLOSED | PLATE NUMBER 634.48 |
| | | Sheet 1 of 1 |

Published Date: 1st Qtr. 2022



| Posted Speed Prior to Work (M.P.H.) | Spacing of Advance Warning Signs (Feet) | | |
|-------------------------------------|---|------|------|
| | (A) | (B) | (C) |
| 0 - 30 | 200 | | |
| 35 - 40 | 350 | | |
| 45 - 50 | 500 | | |
| 55 | 750 | | |
| 60 - 65 | 1000 | | |
| 70 - 80 | 1000 | 1500 | 2640 |


** Speed appropriate for location.

⊙ ReflectORIZED Drum

■ Channelizing Device

ROAD WORK AHEAD sign is only required in advance of the first lane closure.

High speed is defined as having a posted speed limit greater than 45 mph.



September 22, 2021

| Posted Speed Prior to Work (M.P.H.) | Spacing of Channelizing Devices (Feet) (G) | Taper Length (Feet) (L) |
|-------------------------------------|--|-------------------------|
| 0 - 30 | 25 | 180 |
| 35 - 40 | 25 | 320 |
| 45 | 25 | 600 |
| 50 | 50 * | 600 |
| 55 | 50 * | 660 |
| 60 - 65 | 50 * | 780 |
| 70 - 80 | 50 * | 960 |

* Spacing is 40' for 42" cones.

** Speed appropriate for location.

*** Use speed limit designated for the condition when workers are present in the work space. Signs will be covered or removed when workers are not present.

■ Flagger (As Necessary)

⊙ ReflectORIZED Drum

■ Channelizing Device


The Work Space will be a minimum of 500' from the end of the taper.

The FLAGGER sign will be used whenever there is a Flagger present.

The channelizing devices will be 42" cones or drums.



42" cones may be used in place of the drums shown in the taper if setup will not be used during night time hours.

4" white temporary pavement marking tape for right lane closures, 4" yellow temporary pavement marking tape for left lane closures, or temporary raised pavement markers at 5' spacing will be installed in the taper when the lane is closed overnight, and along the tangent section where the skip lines do not exist and the lane is closed for more than 3 days.



DETAIL A

September 22, 2021



Published Date: 1st Qtr. 2022

S
D
D
O
T

LANE CLOSURE WITHOUT BARRIER

PLATE NUMBER
634.64

Sheet 1 of 1

Published Date: 1st Qtr. 2022

S
D
D
O
T

PARTIAL EXIT RAMP CLOSURE

PLATE NUMBER
634.69

Sheet 1 of 1

| Posted Speed Prior to Work (M.P.H.) | Spacing of Advance Warning Signs (Feet) | | | Taper Length (Feet) (L) |
|-------------------------------------|---|------|------|-------------------------|
| | (A) | (B) | (C) | |
| 0 - 30 | 200 | | | 180 |
| 35 - 40 | 350 | | | 320 |
| 45 - 50 | 500 | | | 600 |
| 55 | 750 | | | 660 |
| 60 - 65 | 1000 | | | 780 |
| | (A) | (B) | (C) | |
| 70 - 80 | 1000 | 1500 | 2640 | 1125 |

| Posted Speed Prior to Work (M.P.H.) | Spacing of Channelizing Devices (Feet) | |
|-------------------------------------|--|-----|
| | (G) | (H) |
| 0 - 30 | 25 | |
| 35 - 45 | 25 | |
| 50 | 50 | * |
| 55 | 50 | * |
| 60 - 80 | 50 | * |

* Spacing is 40' for 42" cones.

⊙ Reflectorized Drum


■ Channelizing Device

④ 4" White Temporary Pavement Marking

Temporary pavement markings will be used if traffic control must remain overnight.


The channelizing devices will be drums or 42" cones if traffic control must remain overnight.

42" cones may be used in place of the drums shown in the taper if setup will not be used during night time hours.




September 22, 2021

| | | | |
|-------------------------------|-----------------------|-----------------------------------|------------------------|
| Published Date: 1st Qtr. 2022 | S D D O T | WORK IN VICINITY OF ENTRANCE RAMP | PLATE NUMBER 634.70 |
| | | | Sheet 1 of 1 |




RURAL DISTRICT

RURAL DISTRICT WITH SUPPLEMENTAL PLATE



URBAN DISTRICT





RURAL DISTRICT 3 DAY MAXIMUM

(Not applicable to regulatory signs)

* If the bottom of supplemental plate is mounted lower than 7 feet above a pedestrian walkway, the supplemental plate should not project more than 4" into the pedestrian facility.

January 22, 2021

| | | | |
|-------------------------------|-----------------------|---|------------------------|
| Published Date: 1st Qtr. 2022 | S D D O T | CRASHWORTHY SIGN SUPPORTS (Typical Construction Signing) | PLATE NUMBER 634.85 |
| | | | Sheet 1 of 1 |



GENERAL NOTES:

The top of anchor posts and slip bases WILL NOT extend above a 60" chord line within a 120" diameter circle around the post with ends 4" above the ground.

At locations where there is curb and gutter adjacent to the breakaway sign support, the stub height will be a maximum of 4" above the ground line at the localized area adjacent to the breakaway support stub.

The 4" stub height clearance is not necessary for U-channel lap splices where the support is designed to yield (bend) at the base.

January 22, 2021


| | | |
|----------------------------------|---|-------------------------------|
| S D D O T | BREAKAWAY SUPPORT STUB CLEARANCE | PLATE NUMBER 634.99 |
| | | Sheet 1 of 1 |

Published Date: 1st Qtr. 2022

LANE SHIFT DETAIL FOR 5" JOINT AT TERMINAL ANCHORS

| Posted Speed Prior to Work (M.P.H.) | Spacing of Channelizing Devices (Feet) (G) | Taper Length (Feet) (L) | Spacing of Advanced Warning Signs (Feet) (A) (B) (C) |
|-------------------------------------|--|-------------------------|--|
| 0 - 30 | 25 | 180 | 200 |
| 35 - 40 | 25 | 320 | 350 |
| 45 - 50 | 50 * | 600 | 500 |
| 55 | 50 * | 660 | 750 |
| 60 - 65 | 50 * | 780 | 1000 |
| 70 - 80 | 50 * | 960 | 1000 1500 2640 |


* Spacing to be every 40' for 42" cones.



See Detail "A"


ROAD WORK AHEAD sign is only required in advance of the first lane closure.

The FLAGGER sign shall be used whenever there is a Flagger present.



⊙ Reflectorized Drum

■ Channelizing Device shall be 42" cones or drums



⊙ Reflectorized Drum

■ Channelizing Device shall be 42" cones or drums