

Dickinson Township
Cumberland County, Pennsylvania
ORDINANCE NO. 2020-02

AN ORDINANCE OF DICKINSON TOWNSHIP, CUMBERLAND COUNTY, PENNSYLVANIA AMENDING AND RESTATING CHAPTER 205 [ZONING] OF THE CODE OF ORDINANCES OF DICKINSON TOWNSHIP AND ADOPTING A NEW ZONING MAP

WHEREAS, Dickinson Township is a municipality (the “Township”), being a second class township in the Commonwealth of Pennsylvania; and

WHEREAS, the Township has created a Code of the Township (“Code”) codifying the Ordinances of the Township; and

WHEREAS, the Township now desires to approve and adopt an amendment and restatement to the Code by enacting an Ordinance adopting the amendment and restatement to the Code, which Ordinance will be codified in the Code as follows; and

WHEREAS, the Township now desires to approve and adopt a new zoning map based on the amendments made to Chapter 205.

NOW, THEREFORE, be it ordained and enacted as follows:

SECTION 1: Chapter 205. [Zoning] of the Code is hereby amended by deleting the contents of such Chapter 205 in its entirety, and by restating such Chapter 205 by adopting the attached “Exhibit A” in its entirety.

SECTION 2: The current zoning map of the Township is hereby replaced with the zoning map attached hereto as “Exhibit B”.

SECTION 3: This Ordinance shall be effective five (5) days after its enactment.

ORDAINED AND ENACTED this 3 day of August 2020.

ATTEST:

DICKINSON TOWNSHIP
BOARD OF SUPERVISORS

Marjorie E. Bear

Marjorie E. Bear, Secretary

By: *Lorelei Coplen*
Lorelei Coplen, Chairperson



(SEAL)

By: ABSENT
Thomas Imholte, Supervisor

By: *RL*
Robert Line, Supervisor

I, Marjorie E. Bear, Secretary for Dickinson Township, do hereby attest that the foregoing Ordinance No. 2020-02 was voted upon and approved by majority vote of the Board of Supervisors on the 3rd day of August 2020.

EXHIBIT A

EXHIBIT B



Zoning Ordinance
for

**Dickinson Township,
Cumberland County, PA**

Adopted August 3, 2020

Table of Contents

	<u>Page</u>
Article 1 - Background Provisions	
Section 101	Short Title 1
Section 102	Purpose 1
Section 103	Scope 1
Section 104	Interpretation 2
Section 105	Conflict 3
Section 106	Validity and Severability 3
Section 107	Principal Uses; Uses Not Provided For 3
Section 108	Establishment of Zones 4
Section 109	Zoning & Natural and Cultural Features Maps 4
Section 110	Zone Boundary Lines 5
Section 111	Word Usage 5
Section 112	Specific Words and Phrases 6
Article 2 – Zones	
Section 200	Conservation Zone (C) 45
Section 201	Agricultural Zone (A) 50
Section 202	Low Density Residential Zone (LDR) 56
Section 203	Mixed Use Zone (MU) 60
Section 204	Mining Industrial Zone (MI) 67
Section 205	Business Industrial Zone (BI) 72
Section 206	Billboard Sign Overlay Zone (BS) 78

Article 3 - General Provisions

Note - The following sections include requirements that apply to all uses throughout the Township.

Section 301	Access Drive Requirements (Non-Single-Family)	79
Section 302	Access to Properties and Structures	79
Section 303	Clear Sight Triangle	79
Section 304	Common Open Space Requirements	80
Section 305	Driveway Requirements (Single family dwellings)	81
Section 306	Establishment of More Than One Principal Use on a Lot	87
Section 307	Front Yard Exceptions	87
Section 308	Access Drives	87
Section 309	Height Limit Exceptions	88
Section 310	Outdoor Lighting	88
Section 311	Reserved for Future Use	88
Section 312	Minimum Habitable Floor Area	88
Section 313	Materials and Waste Storage, Handling and Disposal	88
Section 314	Off-Street Loading	90
Section 315	Off-Street Parking	90
Section 316	Operations and Performance Standards	98
Section 317	Outdoor Storage and Display Requirements	98
Section 318	Reserved for Future Use	99
Section 319	Required Traffic Study Standards	100
Section 320	Roadway Classifications	100
Section 321	Screening and Landscaping Requirements	100
Section 322	Signs	100
Section 323	On-Lot Sewage Disposal System Requirements	111

Article 4 – Specific Criteria

Note - The following sections include requirements imposed upon permitted uses, special exceptions and conditional uses as permitted within the respective Zones of the Township.

Section 401	Specific Standards for Permitted Uses, Special Exception & Conditional Uses	112
Section 402	Adult Entertainment Uses	113
Section 403	Airports / Heliports	114
Section 404	Alternate Energy Systems	114
Section 405	Public Utility Structures	120

	<u>Page</u>
Section 406	Domestic Pets..... 120
Section 407	Animal Hospitals and Veterinary Offices..... 121
Section 408	Auction House, Excluding Automobile Auctions 121
Section 409	Automobile/Animal Racing Facility with or without Related Wagering 121
Section 410	Automobile Auctions and Storage Yards 125
Section 411	Gas Stations (Including Minor Incidental Repair) 128
Section 412	Bed and Breakfasts 128
Section 413	Beekeeping 129
Section 414	Billboards 129
Section 415	Boarding Houses 130
Section 416	Campgrounds 131
Section 417	Car Washes 132
Section 418	Cemeteries 133
Section 419	Churches and Related Uses 133
Section 420	Communication Antennas that are Co-Located upon Existing Structures 134
Section 421	Child Day-Care Facilities 135
Section 422	Commercial Produce Operations 137
Section 423	Commercial Recreation Facilities 139
Section 424	Concentrated Animal Feeding Operations (CAFOs & CAOs)..... 140
Section 425	Conservation Design Developments..... 141
Section 426	Convenience Stores..... 148
Section 427	Convention and/or Conference Centers 148
Section 428	Composting 150
Section 429	Restaurants..... 150
Section 430	Dry Cleaners, Laundries and Laundromats 151
Section 431	Temporary Family Housing 151
Section 432	Group Homes..... 152
Section 433	Farm Occupations..... 153
Section 434	Farmers and/or Flea Markets..... 154
Section 435	Fences and Walls 154
Section 436	Fish Hatcheries and/or Fish Farms 155
Section 437	Medical Marijuana Facilities 156
Section 438	Freestanding Communications Antennas, Towers and Equipment..... 156
Section 439	Funeral Homes 160
Section 440	Garage / Yard / Moving Sales 160

	<u>Page</u>
Section 441	Golf Courses and Driving Ranges 160
Section 442	Health, Fitness, Social, Fraternal and Other Private Clubs 163
Section 443	Heavy Equipment and/or Commercial Truck Sales, Service and/or Repair..... 163
Section 444	Heavy Industrial Uses 164
Section 445	Helicopter Pads, Private 164
Section 446	Historic Structure Conversions 165
Section 447	Home Improvement and Building Supply Stores 166
Section 448	Home Occupations 166
Section 449	Hospitals with Related Uses..... 167
Section 450	Junkyards..... 169
Section 451	Drop Lot or Drop and Hook Lot..... 170
Section 452	Kennels 170
Section 453	Man-Made Lakes, Dams, Ponds and Impoundments..... 171
Section 454	Mobile Home Parks 172
Section 455	Manure Storage Facilities 173
Section 456	Mass Transit and/or Taxicab Terminals 174
Section 457	Medical Residential Campuses 175
Section 458	Methadone Treatment Facility 176
Section 459	Mining, Quarrying & Related Processing Operations 177
Section 460	Storage Unit Centers 181
Section 461	Entertainment Facilities 182
Section 462	Noncommercial Keeping of Livestock 182
Section 463	Nursing, Rest or Retirement Homes..... 183
Section 464	Ornamental Ponds and Wading Pools 184
Section 465	Short Term Rentals 184
Section 466	Outdoor Residential Athletic Courts 185
Section 467	Outdoor Shooting Ranges (Public and Private)..... 185
Section 468	Parking and/or Storage of Recreational Vehicles, Personal Cargo Trailers and POD Storage Containers 186
Section 469	Passenger Motor Vehicle and Recreational Vehicle Sales, Service and Repair Facilities Including, But Not Limited To, Auto Mechanics, Drive-Thru Lubrication Services and Tires, Auto Paint, Brake, Muffler, Transmission, Windshield, Auto Body, Car Radio, and Upholstery Shop 188
Section 470	Power Generation Facilities..... 188
Section 471	Principal Waste Handling, Recycling, Processing, Transfer & Disposal Facilities .. 192

Section 472	Public, Private and Commercial Schools	194
Section 473	Reserved for Future Use	195
Section 474	Recycling Facilities for Paper, Glass, Plastic, and Metal Products	195
Section 475	Residential Swimming Pools	195
Section 476	Riding Stables	196
Section 477	Roadside Stands	197
Section 478	Reserved for Future Use	197
Section 479	Rural Occupations	198
Section 480	Sales of Compost, Mulch, Woodchips and Coal	199
Section 481	Satellite Dish Antennas	200
Section 482	Sawmills	201
Section 483	Septage and Compost Processing	202
Section 484	Shopping Centers	203
Section 485	Slaughtering, Processing, Rendering, and Packaging of Food Products and their By-products	205
Section 486	Truck or Motor Freight Terminal	207
Section 487	Truck Stops	208
Section 488	Two-Family Conversions	209
Section 489	Warehousing and Wholesale Trade Establishments	210
Section 490	Wind and/or Solar Farms	212

Article 5 – Environmental Protection

Note - The following sections include requirements that apply to all uses throughout the Township.

Section 500	Purpose	217
Section 501	Relationship to Other Sections of this Ordinance	217
Section 502	Floodplains	217
Section 503	Riparian Buffers	217
Section 504	Wetlands and Wetland Buffers	220
Section 505	Steep Slopes	220
Section 506	Appalachian Trail Overlay Zone	221
Section 507	Historic Site Protection	222

Article 6 – Nonconformities

Section 600	Non-Conforming Uses and Structures	224
Section 601	Continuation of Non-Conforming Uses and Structures	224

Section 602	Repairs and Maintenance	225
Section 603	Registration of Non-Conforming Uses and Structures	225
Section 604	Expansion and Change of Non-Conforming Uses and Structures	225
Section 605	Non-Conforming Lots.....	226

Article 7 - Zoning Hearing Board

Section 700	Establishment and Membership	227
Section 701	Organization of Zoning Hearing Board	227
Section 702	Expenditures for Services.....	228
Section 703	Public Hearings	228
Section 704	Zoning Hearing Board's Jurisdiction	231
Section 705	Appeals to the Zoning Hearing Board.....	235
Section 706	Time Limitations.....	236
Section 707	Stay of Proceeding.....	236
Section 708	Appeal.....	237
Section 709	Mediation Option.....	237

Article 8 – Administration

Section 800	Zoning Officer.....	238
Section 801	Zoning Permits	241
Section 802	Certificate of Zoning Compliance	246
Section 803	Fees.....	246
Section 804	Amendments.....	248
Section 805	Conditional Uses	252
Section 806	Mediation Option.....	259
Section 807	Information Submission Requirements	259

USE CHARTS following page 260

ZONING MAP

Article I

Background Provisions

Section 101 **SHORT TITLE**

This Ordinance shall be known and may be cited as the “Dickinson Township Zoning Ordinance of 2020.”

Section 102 **PURPOSE**

102.A. This Ordinance is enacted for the following purposes:

1. To promote, protect, and facilitate any or all of the following: the public health, safety, morals, and the general welfare; coordinated and practical community development and proper density of population; emergency management preparedness and operations, airports, and national defense facilities; the provision of adequate light and air; access to incident solar energy, police protection, vehicle parking and loading space, transportation, water, sewerage, schools, recreational facilities, and public grounds; the provision of a safe, reliable, and adequate water supply for domestic, commercial, agricultural, and industrial use; as well as the preservation of the natural, scenic, and historic values in the environment and the preservation of forests, wetlands, aquifers, and floodplains.
2. To prevent any or all of the following: overcrowding of land; blight; danger, and congestion in travel and transportation; and loss of health, life, and property from fire, panic or other dangers.
3. To preserve prime agriculture and farmland considering topography, soil type and classification, and present use.
4. To provide for the use of land within the Township for residential housing of various dwelling types encompassing all basic forms of housing, including single-family and two-family dwellings, and a reasonable range of multi-family dwellings in various arrangements, as well as mobile homes and mobile home parks.
5. To accommodate reasonable overall community growth, including population and employment growth, and opportunities for development of a variety of residential dwelling types and non-residential uses.

102.B. This Ordinance was prepared with careful consideration being given to, among other things, the character of various areas within the Township, and their suitability for particular uses, and with a view toward conserving the value of property and encouraging the most appropriate use of land throughout the Township.

SECTION 103 **SCOPE**

103.A. Except as noted below, from and after the effective date of this Ordinance, the use of all land and every building or structure or portion of a building or structure erected, altered with respect to height and area, added to, or relocated, and every use within a building or structure or use accessory thereto, in Dickinson Township shall be in conformity with the provisions of this Ordinance. Any

legally-existing building or use of land not in conformity with the regulations herein prescribed shall be regarded as nonconforming but may be continued, extended, or changed subject to the special regulations herein provided with respect to nonconforming buildings, structures or uses.

- 103.B.** This Ordinance shall not apply to any existing or proposed buildings, structures, or extension thereof, used or to be used by a public utility corporation if, upon petition of the corporation, the Pennsylvania Public Utility commission shall, after a public hearing, decide that the present or proposed building in question is reasonably necessary for the convenience or welfare of the public. This exemption shall not apply to telecommunications antennas, communications equipment buildings, and communications towers for wireless telecommunications services regulated under the 1996 Telecommunications Act or any use that has been de-regulated by the appropriate state and/or federal agencies.
- 103.C.** This Ordinance shall not apply to any existing or proposed uses, buildings structures, signs, or extension thereof, occupied, owned and/or operated by the Township.
- 103.D.** The application of requirements of this Ordinance shall be limited only to the extent that regulations of mineral, coal and fuel extraction have heretofore been superseded and preempted by applicable state or federal law.
- 103.E.** The application of requirements of this Ordinance shall be limited only to the extent that activities related to commercial agricultural production would exceed the requirements imposed under:
1. the act of May 20, 1993 (P.L. 12, No.6), known as the "Nutrient Management Act," regardless of whether any agricultural operation within the area to be affected by the Ordinance would be a concentrated animal operation as defined by the "Nutrient Management Act;"
 2. the act of June 30, 1981 (P.L. 128 No. 43), known as the "Agricultural Area Security Law;" or,
 3. the act of June 10, 1982 (P.L. 454, No. 133), entitled "An act protecting agricultural operations from nuisance suits and ordinances under certain circumstances," or that regulation of other activities are preempted, but only to the extent preempted, by other Federal or State laws.

SECTION 104 INTERPRETATION

- 104.A.** In interpreting and applying the provisions of this Ordinance, such shall be considered to be necessary for the promotion of the health, safety, and general welfare of the residents of the Township.
- 104.B.** In interpreting the language of this Zoning Ordinance to determine the extent of the restriction upon the use of the property, the language shall be interpreted, where doubt exists as to the intended meaning of the language written and enacted by the governing body, in favor of the property owner and against any implied extension of the restriction.
- 104.C.** In this Ordinance, when not inconsistent with the context:
1. words in the present tense imply also the future tense.
 2. the singular includes the plural.
 3. the male gender includes the female gender.
 4. the word "person" includes an individual, partnership, corporation, firm, company, association, governmental entity, trustee, receiver, successor, assignee or similar representative.

5. the term “shall” or “must” is always mandatory.

104.D. References to laws, codes, ordinances, guidelines, lists, resolutions, plans, maps, governmental bodies, commissions or agencies or officials are to laws, codes, ordinances, guidelines, lists, resolutions, plans, maps, governmental bodies, commissions or agencies or officials of the Township or the Commonwealth of Pennsylvania as in effect or office from time to time including amendments thereto or revisions or successors thereof, unless the text indicates another reference is intended.

SECTION 105 CONFLICT

It is not intended by this Ordinance to repeal, abrogate, annul, or interfere with any existing ordinances or enactment, or with any rule, regulation or permit adopted or issued thereunder, except insofar as the same may be inconsistent or in conflict with any of the provisions of this Ordinance, provided that where this Ordinance imposes greater restrictions upon the use of buildings or land, or upon the height and bulk of buildings, or prescribed larger open spaces than are required by the provisions of other such ordinance, enactment, rule, regulation or permit, then the provisions of this Ordinance shall control. Furthermore, if a discrepancy exists between any regulations contained within this Ordinance, that regulation which imposes the greater restriction shall apply.

SECTION 106 VALIDITY AND SEVERABILITY

Should any section or provision of this Ordinance be declared by a Court of competent jurisdiction to be invalid, such decision shall not affect the validity of this Ordinance as a whole or of any other part thereof.

SECTION 107 PRINCIPAL USES; USES NOT PROVIDED FOR

107.A. Unless allowed otherwise herein or approved by a variance granted by the Zoning Hearing Board, only one principal use shall be allowed on each individual lot.

107.B. Whenever a use is neither specifically permitted nor denied by this Ordinance, and an application is made by an applicant to the Zoning Officer for such use, the Zoning Officer shall refer the application to the Zoning Hearing Board to hear and decide such request as a special exception. The Zoning Hearing Board shall have the authority to permit the use or deny the use in accordance with the standards governing special exception applications. To approve the use the Board must find that the proposed use:

1. is located in a Zone in which the most similar use to the proposed use is permitted, either by right, by special exception or by conditional use, and in doing so the Zoning Hearing Board shall have discretion in determining whether the proposed use is actually most similar to the use advanced by the applicant as most similar;
2. is not permitted in any other Zone under the terms of this Ordinance;
3. is proposed in a manner that complies with all applicable requirements imposed upon other uses that in the opinion of the Zoning Hearing Board most closely reflect the likely impacts that will be generated by the proposed use;
4. complies with all other applicable sections of this Ordinance and other ordinances of the Township;
5. does not conflict with the general purposes and intent of this Ordinance; and,
6. would not be detrimental to the public health, safety and welfare of the neighborhood or Township.

The burden of proof shall be upon the applicant to demonstrate that the proposed use meets the foregoing criteria and meets all applicable regulations contained within this Ordinance including but

not limited to those general criteria contained within Section 704.C.2.

SECTION 108 ESTABLISHMENT OF ZONES

For the purpose of this Ordinance, Dickinson Township is hereby divided into Zones which shall be designated as follows:

Zones Mapped on the Zoning Map
Conservation Zone (C) – Section 200
Agricultural Zone (A) – Section 201
Low Density Residential Zone (LDR) – Section 202
Mixed Use Zone (MU) – Section 203
Mining Industrial Zone (MI) – Section 204
Business Industrial Zone (BI)– Section 205
Overlay Zones
Billboard Sign Overlay Zone (BS)- Section 206
Appalachian Trail Overlay Zone – Section 506

SECTION 109 ZONING MAP

109.A. The areas within Dickinson Township, as assigned to each Zone and the location of the Zones established by this Ordinance, are shown upon the Zoning Map, which together with all explanatory matter thereon, is attached to and is declared to be a part of this Ordinance.

109.B. If changes are made to Zone boundaries or other matters portrayed on the Zoning Map, such changes shall be made in accordance with the provisions of Section 804 of this Ordinance and the Pennsylvania Municipalities Planning Code, and the changes shall be entered on the Zoning Map promptly after the amendment has been approved by the Board of Supervisors. No changes of any nature shall be made to the Zoning Map, or matter thereon shown, except in conformity with the applicable procedures established in this Zoning Ordinance. All changes shall be noted by date with a brief description of the nature of the change.

109.C. The Zoning Map shall be located in a place designated by the Board of Supervisors, and shall be the final authority as to the current zoning status of land and water area in Dickinson Township regardless of unofficial copies, which may have been made or published from time to time.

109.D. In the event that the Zoning Map becomes damaged, destroyed, lost or difficult to interpret because of the nature or number of changes and additions, the Board of Supervisors may, by resolution, adopt a new Zoning Map. The new Zoning Map may correct drafting or other errors or omissions in the prior Zoning Map, but no such correction shall have the effect of amending the original Zoning Map or any subsequent amendment thereof. The new Zoning Map shall be identified by the signature of the Board of Supervisors, attested by the Dickinson Township Manager or Secretary, and bear the seal of Dickinson Township under the following words:

"This is to certify that in accordance with Section 109.D.of the Zoning Ordinance, this Zoning Map of Dickinson Township supersedes and replaces the Zoning Map adopted as part of Ordinance No. of Dickinson Township, Cumberland County, Pennsylvania."

109.E. Unless the prior Zoning Map has been lost or has been destroyed, the prior map or any significant parts thereof remaining shall be preserved together with all applicable records pertaining to its adoption or amendment.

SECTION 110 ZONE BOUNDARY LINES

- 110.A.** The Zone boundary lines shall be as shown on the Zoning Map. Zone boundary lines are intended to coincide with lot lines, centerlines of streets and alleys, railroad rights-of-way, and streams at time of passage of this Ordinance, the corporate boundary of the Township or as dimensioned on the map. Where uncertainty exists as to the boundaries of the base districts as indicated on the Zoning Map, the following rules and guidelines, as provided within this section shall be applicable.
1. Where Zone boundaries are indicated as approximately coinciding with the centerlines of streets, highways, lanes, alleys, railroad tracks, rivers or creeks, such centerline shall be construed to be such boundaries.
 2. Where Zone boundaries are indicated as approximately coinciding with lot lines or deed lines, such lines shall be construed to be such boundaries.
 3. Where Zone boundaries are indicated as approximately coinciding or municipal boundary lines, such lines shall be construed to be such boundaries.
 4. Where Zone boundaries are indicated as being approximately parallel to the center or right-of-way lines of streets or highways, lanes, alleys, railroad tracks, rivers or creeks, such district boundaries shall be construed as being parallel to the center or right-of-way lines at such distance as is indicated on the Zoning Map.
 5. Where Zone boundaries are indicated as being approximately perpendicular to the right-of-way lines of streets or highways, such district boundaries shall be construed as being perpendicular to the right-of-way lines.
 6. Where Zone boundaries are referenced by a distance or measurement from a specific feature, such distance shall be measured in feet and the district boundaries shall follow the specified setback.
 7. Where Zone or measurements are not specifically referenced on the Zoning Map, the scale of the Zoning Map shall determine the unspecified setback.
- 110.B.** In the event of dispute about the location of the boundary of any Zone, the Zoning Officer shall investigate and render a decision on the location of the line. Appeals from this decision shall be made to the Zoning Hearing Board in accordance with Section 704.E. of this Ordinance.
- 110.C.** When a property is contained within more than one Zone, any use is required to comply with all applicable design standards upon that portion of the property within the Zone in which the use is located.

SECTION 111 WORD USAGE

Words and phrases shall be presumed to be used in their ordinary context, unless such word or phrase is defined differently within this section.

SECTION 112 SPECIFIC WORDS AND PHRASES

The following words and phrases shall have the particular meaning assigned by this section in the appropriate sections of this Ordinance.

ACCESS DRIVE - An improved cartway designed and constructed to provide for vehicular movement between a public or private road and the off-street parking and/or loading area for any use other than one single-family dwelling unit or farm.

ACCESSORY BUILDING – A detached, subordinate building, the use of which is customarily incidental to that of the principal use and which is located on the same lot as the principal use.

ACCESSORY USE - A use customarily incidental and subordinate to the principal use or building and located on the same lot as the principal use or building.

ACT - The Pennsylvania Municipalities Planning Code.

ADJACENT / ADJOINING - The state of being side by side, next to or abutting one another.

ADULT ENTERTAINMENT USE - Any structure, building, or use which is open to the general public in which 20% or more of the occupied sales or display area offers for sale, for rent, lease, loan or for view upon the premises pictures, photographs, drawings, prints, images, sculpture, still film, motion-picture film, videotape, or similar visual representations distinguished or characterized by an emphasis on sexual content or sexually explicit nudity depicting exposed male or female genitalia, or books, pamphlets, magazines, printed matter or sound recordings, containing explicit or detailed descriptions or narrative accounts distinguished or characterized by an emphasis on sexual content, or which offers for sale sexual devices. This definition shall also include a building, structure, or a portion thereof, or a use open to the general public, used for presenting motion-picture film, videotape, live performances, or similar visual representation or materials distinguished or characterized by an emphasis on sexual conduct or sexually explicit nudity depicting exposed male or female genitalia.

AGRICULTURE - The tilling of the soil, the raising of crops, horticulture, and the keeping or raising of livestock. This definition also includes noncommercial greenhouses and mushroom houses, the processing and retail sale of goods produced on a farm, uses devoted to research into agricultural technology that would change the conduct of normal farming operations and custom work. For the purposes of this definition custom work shall mean the hiring of another person or agency who does not reside on the subject property to perform one or more activities necessary to the function of the principal farm use as a whole. This definition of agriculture does not include concentrated animal feeding operations, concentrated animal operations, commercial produce operations and gardening, each, as defined below. Agriculture shall be a principal use and shall be understood to include one (1) dwelling unit as well as all structures necessary for the housing of animals, storage of feed and equipment, and other operations customarily incidental to agricultural use. Below are definitions relevant to agriculture:

AGRICULTURAL SHORT-TERM RENTALS - see "Short Term Rental".

COMMERCIAL GREENHOUSE – A retail business devoted to the raising and/or selling of trees, ornamental shrubs, flowers, and houseplants for transplanting, along with the sale of ancillary supplies wherein the preponderance of the growing operation is indoors.

COMMERCIAL PRODUCE OPERATION - An agricultural use whereby plant materials are principally grown within enclosed buildings, and where such use exceeds a lot coverage of ten percent (10%).

CONCENTRATED ANIMAL FEEDING OPERATION (CAFO) - An agricultural use which includes an animal feeding operation that is, due to the quantities of commercial keeping and handling of livestock with certain characteristics, required to obtain NPDES permits in accordance with the Clean Water Act as set forth at 33 U.S.C. § 1251, *et seq.*, as may be amended from time to time.

CONCENTRATED ANIMAL OPERATION (CAO) - An agricultural use which includes an animal feeding operation that is, due to the quantities of commercial keeping and handling of livestock with certain characteristics, required to develop a nutrient management plan in accordance with the Pennsylvania Nutrient Management Act as set forth at 3 Pa.C.S. § 501, *et seq.*, as may be amended from time to time.

FARM - A parcel of land that is used for one (1) or more agricultural operations, including but not necessarily limited to the raising of agricultural products, livestock, poultry, or the production of dairy products. A "farm" shall be understood to include a dwelling unit as well as all structures necessary

for the housing of animals, storage of feed and equipment, and other operations customarily incidental to farm use.

FARM OCCUPATION - A business or commercial activity that is conducted as an accessory use to a principal agricultural or horticultural use.

LIVESTOCK – An animal typically bred and raised associated with some form of agriculture. This term shall expressly include alpacas, birds, bees, burrows, cattle, cows, donkeys, fish, fowl, goats, hogs, horses, mules, sheep, goats, llamas, peacocks, pot-belly pigs, poultry, rabbits, shellfish, swine, and other similar animals for commercial distribution.

PRIME AGRICULTURAL LAND - Land used for agricultural purposes that contains soil of the first or second class as defined by the latest edition of the United States Department of Agriculture Natural Resource and Conservation Services Web Soil Survey.

AIRCRAFT - Any contrivance, except an unpowered hang glider or parachute, used for manned ascent into flight through the air.

AIRPORT - Any area of land or water which is used, or intended to be used, for the landing and takeoff of aircraft and any appurtenant areas which are used, or intended to be used, for airport buildings or navigation facilities or rights of way, together with all airport buildings and facilities thereon.

PRIVATE AIRPORT - An airport that is privately owned and which is not open or intended to be open to the public, as defined in 74 Pa.Const.Stat. Section 5102.

PUBLIC AIRPORT - An airport that is either publicly or privately owned and that is open to the public as defined in 74 Pa.Const.Stat. Section 5102.

ALLEY - A minor right-of-way, privately or publicly owned, primarily for service access to the rear or sides of properties.

ALTERATIONS - Any exterior structural addition to a building; any renovation to a building which would change its use; any change or rearrangement in the structural parts of a building such as bearing walls, columns, beams or girders, joists or rafters, or enclosing walls; the moving of a building from one location or position to another.

ALTERNATIVE ENERGY SYSTEM – Any device installed as an accessory use that supplies energy principally for the principal use of the property that is derived from natural sources (e.g. solar panels, wind turbines, hydro turbines, geo-thermal exchangers and similar and emerging technologies.) This definition shall expressly exclude outdoor furnaces, as defined herein.

APPLICANT - A landowner or developer, as hereinafter defined, who has filed an application for development including his heirs, successors, and assigns.

APPLICATION FOR DEVELOPMENT - Every application required to be filed and approved prior to start of construction or development, including but not limited to, an application for a zoning permit, for the approval of a subdivision plat or plan or for the approval of a development plan.

AREA - The two-dimensional measurement of space between known lines or boundaries.

BUILDING AREA: The total area of all buildings (principal and accessory) taken on a horizontal plane at the main grade level.

GROSS FLOOR AREA: The sum of the floor areas of a building as measured to the outside surfaces of exterior walls and/or all areas intended for the conduct of a use.

GROSS LOT AREA: The total surface area contained within the property lines of a lot, exclusive of exterior public rights-of-way.

HABITABLE FLOOR AREA: The sum of the floor areas of a dwelling unit as measured to the outside surfaces of exterior walls and including all rooms used for habitation, such as living room, dining room, kitchen, basement, bedroom, bathroom, family room, closets, hallways, stairways, and foyers, but not including cellars or attics, service or utility rooms, nor unheated areas such as enclosed porches.

NET LOT AREA: The total surface area contained within the property lines of a lot, exclusive of public rights-of-way, public and private streets and the following features:

- A. street rights-of-way;
- B. ultimate rights-of-way;
- C. access easements serving another principal use;
- D. sanitary sewer and water easements serving another principal use;
- E. gas pipeline easements and/or rights-of-way;
- F. land within easements and/or rights-of-way for overhead electric transmission lines 66 KV and greater;
- G. storm water management facilities, pipes and/or swales intended to serve another principal use;
- H. riparian buffers as regulated in Section 511 of this Ordinance;
- I. permanent and open bodies of water;
- J. the Floodplain Zone as delineated under the terms of Section 510 of this Ordinance;
- K. wetlands as regulated as delineated under the terms of Section 512 of this Ordinance; and/or,
- L. slopes of 25% or greater.

MINIMUM LOT AREA - The least amount of lot area required to be associated with a principal use as specified within this Zoning Ordinance.

RETAIL SALES AREA: The total area of use which is devoted to the display of goods and/or services, including aisles, to prospective patrons.

SITE AREA – The lot area or portion thereof devoted to a particular use as regulated by this Ordinance.

AREA OF DISTURBANCE - The total land area proposed to be used for and/or within any, and all, of the following:

- A. Except as modified by subsection C. below, any area within the lot proposed for development that is within fifteen (15) feet of any or all of the following existing or proposed features:
 - 1. A principal building or structure (except as provided in Subsection 3. below);
 - 2. Accessory structures existing or proposed at the time of development of the principal building or structure; and
 - 3. An accessory structure of more than four hundred (400) square feet of lot coverage.
- B. Any areas within the lot proposed for development that are within ten (10) feet of any existing or proposed gravel or paved areas, including gravel or paved driveways;

- C. Any areas within the lot proposed for development that are within forty (40) feet of the rear of the principal building; and
- D. Any areas proposed to be graded, cleared or otherwise altered that are one thousand (1000) square feet or greater in size.

ATTIC - That part of a building which is immediately below and completely or partly within the roof framing. Within a dwelling unit, an attic shall not be counted as floor area unless it is constructed as or modified into a habitable room by the inclusion of dormer windows, an average ceiling height of five (5) feet or more, and a permanent stationary interior access stairway to a lower building story.

AUCTION HOUSE – A principal commercial use at which items are imported for public or private sale during a competitive bidding process. This use shall also expressly include a cafeteria or refreshment counter provided such use is contained completely within an enclosed building and patrons are limited to those participating in the auction. This term shall not include automobile auctions as defined below.

AUDITORIUM – A building containing a stage and/or screen and seating for meetings, performances, or screening of movies.

AUTOMOBILE AUCTION - A use whereby passenger vehicles are offered for wholesale and/or retail sales at prearranged sales during a competitive bidding process.

AUTOMOBILE STORAGE YARD - A use whereby passenger vehicles are stored awaiting transport to a different location.

AVOIDANCE MEASURES – Specific actions that have been identified by one of the Pennsylvania Natural Diversity Inventory (PNDI) jurisdictional agencies that must be fulfilled by an applicant in order to inflict no impact upon a special concern species or resource in the vicinity of the project area.

BASEMENT – A space with less than half of its floor-to-ceiling height above the average finished grade of the adjoining ground and with a floor-to-ceiling height of greater than six and one-half (6½) feet.

BED AND BREAKFAST - A single-family detached dwelling, where between one and five sleeping accommodations are rented to overnight guests on a daily basis for periods not exceeding two weeks. Breakfast may be offered only to registered overnight guests.

BEEKEEPING - The raising or keeping of bees within a man-made enclosure (beehive) for hobby or business purposes.

BILLBOARD – See “Sign.”

BOARD OF SUPERVISORS – The governing body of Dickinson Township, Cumberland County, Pennsylvania.

BOARDER - An individual other than a member of a family occupying a room within a dwelling unit or a lodging facility who, for compensation, is furnished sleeping accommodations within such dwelling unit or lodging facility, and who also may be furnished meals or other domestic services in return for compensation.

BOARDING HOUSE - A building or portion thereof arranged or used for sheltering or feeding, or both, as a gainful business, for one or more boarders. This term includes single-room occupancy residences (SROs), tourist homes, and rooming houses. It expressly excludes “bed and breakfast” arrangements and short-term rentals (including arrangements known as “AirBNB”).

BUFFER – Except as referenced in Sections 511 and 512 of this Ordinance, a continuous strip of land that is clear of all buildings and paved areas and is landscaped in accordance with Section 321 of this Ordinance.

BUILDING - Any structure with a roof intended for shelter or enclosure of persons, animals or property.

DETACHED: A building which has no common wall.

SEMI-DETACHED: A building which has only one common wall.

ATTACHED: A building which has two or more common walls.

BUILDING AREA: See "Area."

BUILDING ENVELOPE - The area of a lot that is available for development and free of restrictions as specified in this Ordinance, which may include building set back requirements, rights-of-way, easements, floodplains, wetlands, steep slopes, and all similar restrictions

BUILDING HEIGHT - A building's vertical measurement from the mean level of the ground abutting the corners of the building to the highest point of the building, including except as noted in Section 309, any signs, antennas or other appurtenances.

BUILDING LENGTH – The longest horizontal measurement of a building.

BUILDING SETBACK LINE - The actual distance between the closest part of a building including roof overhangs, (excluding those permitted projections listed in Section 307 of this Ordinance) and:

- A. in the case of a front yard, all adjoining street right-of-way lines;
- B. in the case of a side yard, all side lot lines; and,
- C. in the case of a rear yard, all rear lot lines.

BUILDING PERMIT – Permits issued under the Uniform Code Construction Code. Permits issued under this Zoning Ordinance are "zoning permits.")

CAMPGROUND - A lot, tract, or parcel of land upon which two or more campsites are located or established, intended and maintained for occupation by guests, travelers and/or transients in recreational vehicles or tents.

CAMPSITE - A plot of ground within a campground intended for occupation by a recreational vehicle, tent or travel trailer.

CARPORT – A roofed structure open on two (2) or more sides for the storage of motor vehicles.

CARTWAY - The paved surface of a street or access drive intended and available for use by vehicular traffic.

CAR WASH – A commercial use used to clean the exterior, and sometimes the interior, of automobiles. There are several types of car washes, ranging from self-service coin operated automatic car washes to fee-based full-service operations.

CASINOS - A gaming facility other than a racetrack and/or an off-track betting parlor wherein wagering and other lawful gambling activity, is conducted under Pennsylvania law. This use shall include any facility in which gambling devices, including but not limited to slot machines, video poker machines, punch boards, and similar devices are located. The term "lawful gambling activity" shall not include the sale of lottery tickets in compliance with State Lottery law.

CATERERS, BAKERS AND CONFECTIONERS – A retail commercial use devoted to the preparation, packaging and/or delivery of prepared foods for consumption at another location. This use shall also

expressly include the retail sales of those goods produced on the site; however, no seating for on site consumption shall be permitted.

CELLAR - A space with less than one-half of its floor-to-ceiling height above the average finished grade of the adjoining ground or with a floor-to-ceiling height of less than six and one-half (6½) feet. Within a dwelling unit, a cellar shall not be counted as floor area.

CEMETERY - Land used or intended to be used for the burial of the deceased, including columbariums, crematoria, mausoleums, and mortuaries when operated in conjunction with the cemetery and within the boundaries thereof. This definition shall also include facilities for the burial of domestic pets.

CERTIFICATE OF ZONING COMPLIANCE - A statement, signed by the Zoning Officer setting forth that a building, structure, sign, and/or use of land complies with this Zoning Ordinance and a previously issued zoning permit.

CHILD DAY CARE FACILITY - A facility in which a wide range of formal care is provided by qualified staff for remuneration to children under the age of 16 years, if such children are not related to the provider by blood, marriage or adoption or are not placed in the home as foster children pursuant to direction by an authorized licensed foster child agency or who are not placed in the home by court order. This definition does not include the offering of overnight accommodations. Any child day care use shall meet all applicable requirements of the State Department of Public Welfare. The following types of child day care uses are regulated by the Pennsylvania Department of Public Welfare:

CHILD-CARE CENTER - A child-care facility in which seven (7) or more children who are not related to the operator receive childcare. A child-care center must have a certificate of compliance ("license") from the PA Department of Public Welfare in order to legally operate. (55 Pa. Code, Chapter 3270)

GROUP CHILD-CARE HOME - A child-care facility in which seven (7) though twelve (12) children of various ages or in which seven (7) though fifteen (15) children from 4th grade through 15 years of age who are not related to the operator receive childcare. A group child-care home must have a certificate of compliance ("license") from the PA Department of Public Welfare in order to legally operate. (55 Pa. Code, Chapter 3280)

FAMILY CHILD-CARE HOME - A child-care facility located in a home in which four (4), five (5) or six (6) children who are not related to the caregiver receive childcare. A family child-care home must have a certificate of registration from PA Department of Public Welfare in order to legally operate. (55 Pa. Code, Chapter 3290) This definition shall include any childcare services provided in a home for less than four (4) children who are not related to the caregiver despite not being regulated by the PA Department of Public Welfare.

CHURCH AND RELATED USES - A building, structure, or group of buildings or structures, including accessory uses, designed or intended for public worship. This definition shall include synagogues, mosques, temples, rectories, convents, cemeteries and church-related recreation, educational and/or day-care facilities and orphanages.

CLAY LINER – Fine grained soil that is used in the construction of a liner that limits the rate of surface water intrusion into the subsurface.

CLEAR SIGHT TRIANGLE - An area of unobstructed vision at a street intersection defined by a line of sight between points at center lines.

CLUB, PRIVATE - An organization catering exclusively to members and their guests, or premises or buildings for social, recreational and administrative purposes which are not conducted for profit, provided there are not conducted any vending stands, merchandising or commercial activities except as required for the membership of such club. Clubs shall include but not be limited to, service and political organizations,

labor unions, as well as social and athletic clubs.

CODE - Code of the Township of Dickinson.

COMMERCIAL GREENHOUSE – See “Agriculture.”

COMMERCIAL MESSAGE - Words and/or images intended to influence consumer behavior.

COMMERCIAL PRODUCE OPERATION - See “Agriculture.”

COMMERCIAL RECREATION FACILITY - An activity operated as a business, open to the public, for the purpose of public recreation or entertainment, including but not limited to, bowling alleys, cinemas, drive-in motion picture facilities, swimming pools, health clubs, miniature golf courses, museums, and etc. This does ***not*** include adult entertainment uses, outdoor shooting ranges, automobile and/or animal racing with or without related wagering facilities, campgrounds, convention or conference center, gaming operations, golf courses and driving ranges, off-track betting, slot machine parlors and/or casinos.

COMMERCIAL SCHOOL – See “School, Commercial.”

COMMERCIAL VEHICLE – A motor vehicle that is associated with a business and/or exceeds the limitations of a “passenger vehicle” as defined herein.

COMMON OPEN SPACE - A parcel or parcels of land or an area of water, or a combination of land and water within a development site and designed and intended for the use or enjoyment of residents of a development, not including streets, off-street parking areas, and areas set aside for public facilities.

COMMON PARKING AREA - A parking facility serving multiple uses or properties that is not owned by one user or property, although it may be owned jointly by all or some of the users.

COMMON WALL - A wall used or adopted for joint service between two buildings or parts thereof.

COMMUNICATIONS ANTENNA - Any device or equipment used for the transmission or reception of wireless communications signals for ultimate reception by a modem, computer, similar internet use or purpose, radio, television, wireless telephone (mobile or cell phone), pager, commercial mobile radio service, or any similar device. This term includes without limitation wireless telecommunication devices, small cells, communication antenna employing stealth technology, distributed antenna systems, omni-directional (or whip) antennas and directional (or panel) antennas owned or operated by any person or entity licensed by the Federal Communications Commission (FCC) to operate such device. This definition shall not include residential satellite dishes, residential television antennas, or antennae for amateur radio equipment.

CO-LOCATED COMMUNICATION ANTENNAS - Any communication antenna that is attached to an existing structure.

COMMUNICATIONS EQUIPMENT BUILDING - An unmanned building or cabinet containing equipment required for the operation of communications antennae.

COMMUNICATIONS TOWER - A freestanding structure designed and used solely to support communications antennae, regardless of the height, size, or any other dimension of such tower. Such definition shall expressly include without limitation small cells, nodes and any other freestanding communications structure employing stealth technology.

DISTRIBUTED ANTENNA SYSTEMS – A small network of communication antennas that are connected to a common source that provides wireless communications coverage in a building or a small geographic area.

FREESTANDING COMMUNICATION FACILITIES – Any communications antenna, communications

tower and/or communications equipment that is not co-located upon an existing structure.

STEALTH TECHNOLOGY – State-of-the-art design techniques used to blend objects into the surrounding environment and to minimize the visual impact as much as possible. For purposes of communication antenna, these techniques are applied to communication antenna, communication equipment, communication equipment facilities, and communication towers, and other communication facilities which blend the proposed communication facility (as listed above) into the existing structure or visual backdrop in such a manner as to render it less visible to the casual observer. Such methods include without limitation architecturally screened roof-mounted antennas, building-mounted antennas painted to match the existing structure and facilities constructed to resemble trees, shrubs, light poles, utility poles or flag poles.

COMMUNITY CENTER - A building or portion of a building used as a gathering place or meeting area by local residents of the Township or development within which it is located.

COMPOSTING; COMPOST - The conversion of organic matter, such as yard waste, into fertilizer and similar materials useful for gardening and lawn care, conducted within a portable open structure used and properly maintained by on-site residents.

COMPREHENSIVE PLAN - The latest adopted version of the Dickinson Township Comprehensive Plan, including any freestanding supplemental documents, as may be amended.

CONCENTRATED ANIMAL FEEDING OPERATION (CAFO) - See “Agriculture.”

CONCENTRATED ANIMAL OPERATION (CAO) – See “Agriculture.”

CONDITIONAL USE - A use permitted in a particular Zone pursuant to the provisions in Article VI of the Act and in accordance with Section 805 of this Ordinance.

CONDOMINIUM - Real estate, portions of which in accordance with the provisions of the Pennsylvania Uniform Condominium Act of 1980, are designated for separate ownership and the remainder of which is designed for common ownership solely by the owners of those portions. Real estate is not a condominium unless the undivided interests in the common elements are vested in the unit owners.

CONSERVATION DESIGN DEVELOPMENT - A development that integrates required common open space and residential dwellings. Conservation design developments are further regulated by Section 425 of this Ordinance.

CONSERVATION EASEMENT – An agreement between the landowner and the Township (and possibly other designated persons or parties) that is applied to property to perpetually protect it from future development. This definition is not meant to relate to a conservation easement as defined under the Pennsylvania Conservation Easement Act.

CONSERVATION MEASURE – A specific action that has been identified by one of the Pennsylvania Natural Diversity Inventory (PNDI) jurisdictional agencies that can minimize impact upon a special concern species or resource in the vicinity of the project area.

CONSERVATION PLAN - A plan including a map(s) and narrative that, at a minimum, outlines an erosion and sedimentation control plan for an identified parcel of land.

CONSTRUCTION - The placement of materials and equipment in a defined area to be assembled, built, applied, and/or demolished in a temporary or permanent manner, as approved by the designated officials of the Township.

CONVENIENCE STORE - A business which specializes in the retail sales and/or rental of household products and foods, which may or may not be operated in conjunction with a gas station use. Although this use is permitted by right within the (BI) Zone, additional activities are permitted pursuant to section 426 of

this Ordinance.

CONVENTION /CONFERENCE CENTER - An assemblage of uses that provide a setting for indoor and outdoor exhibits and activities to serve various business activities, meetings, training sessions, entertainment, and recreation on a temporary basis. This use may include hotels and eating and drinking establishments as accessory uses.

CONVERSION - To change or adapt improved property to a use, occupancy, or purpose other than what was intended at its time of construction.

COUNTY - The County of Cumberland, Commonwealth of Pennsylvania.

COUNTY PLANNING COMMISSION - The Cumberland County Planning Commission.

CURATIVE AMENDMENT - A proposed zoning amendment:

- A. requested of the Board of Supervisors by any landowner or applicant who desires to challenge the substantive validity of an ordinance that prohibits or restricts the use or the development of land in which the landowner or applicant has an interest; or,
- B. initiated by the Board of Supervisors to cure some known substantial defect.

DANCE, MUSIC, ART, FASHION AND PHOTOGRAPHIC STUDIO AND GALLERY – A principal use devoted to the:

- A. training and performance of dance and music;
- B. development, display, and sales of individual works of art and/or photography; and,
- C. design, development, display and sales of custom articles of clothing.

DENSITY - A term used to express the allowable number of dwelling units per acre of land exclusive of unimproved public rights-of-way, and rights-of-way of public and private streets.

DEVELOPER - Any landowner, agent of such landowner, or tenant with the permission of such landowner, who makes or causes to be made a subdivision of land, a land development or a use requiring zoning approval.

DEVELOPMENT - Any manmade change to improved or unimproved real estate, including but not limited to buildings or other structures, mining, dredging, filling, grading, paving, excavation or drilling operations.

DOMESTIC PETS - The noncommercial keeping of adult non-farm animals that are locally available for purchase as pets, as an accessory use to a primary residential use. Domestic pets shall not include any species identified as “exotic animals” and “livestock,” both as defined herein nor any animal species that, in the opinion of the Zoning Officer, poses a threat to the health, safety and/or welfare of the community.

DRIVE-THROUGH FACILITY - Any portion of a building or structure from which business may be transacted with a customer in a motor vehicle.

DRIVEWAY – Improved cart way designed and constructed solely to accommodate vehicular movement between a public and/or private road and a tract of land serving one single-family dwelling unit or a farm.

DROP LOT or DROP AND HOOK LOT - A tract of land, or portion thereof, used by trucks and other large motor freight vehicles for the purpose of dropping or picking up loaded and/or unloaded trailers, including the incidental short-term or daily storage of loaded and/or unloaded trailers, for transfer to other points or jurisdictions. The use may include an accessory guardhouse or similar type structure to allow for trailers to

be checked in and out. The use does not include the break-down or aggregation into smaller or larger loads, truck repair and service facilities, fueling, dispensing or storage of petroleum products.

DRY CLEANERS – A use at which articles of clothing, uniforms, linens, sheets, blankets, table cloths, draperies, towels, diapers and other fabric items are delivered to be cleaned with the use of chemical agents that are generally not water soluble.

DWELLING - Any building or portion thereof designed and used exclusively for residential occupancy, including those listed below, but not including hospitals and nursing homes; hotels and motels, boarding, rooming and lodging houses, institutional houses, tourists courts, and the like, which offer overnight accommodations for guests or patients. All dwellings are permanently affixed to a completely enclosed foundation constructed of currently accepted materials that are an entire perimeter wall and extend from below the frost line to the first floor of the building. Such foundation is constructed to provide sufficient structural integrity to prevent the building from heaving, shifting, or settling unevenly, due to frost action. In addition, all dwellings are properly connected to approved and permanently designed sewer, water, electrical, and other utility systems.




Figure 1

1. **SINGLE-FAMILY DETACHED:** A freestanding building containing one dwelling unit for one family. Mobile and modular homes can be considered single-family detached dwellings if, in addition to the requirements listed for all dwellings, the mobile and/or modular home is securely anchored to the permanent foundation, and all of the apparatuses used to transport the unit shall be removed, including the towing hitch. Recreational vehicles shall not be construed as dwellings. Mobile and modular homes shall be considered single-family detached dwellings so long as they are designed and constructed in accordance with the Uniform Construction Code. (Figure 1)




Figure 2

2. **DUPLEX:** A freestanding building containing two dwelling units for two families, arranged in a side-by-side configuration. (Figure 2)




Figure 3

3. **TWO-FAMILY:** A freestanding building containing two dwelling units, arranged in an over-and-under configuration. (Figure 3)




Figure 4

4. **MULTIPLE FAMILY:** A building containing three or more dwelling units, at least one of which must be located above or below the remaining units. (Figure 4)



Figure 5

5. **TOWNHOUSE:** A building containing between three and eight dwelling units arranged in a side-by-side configuration with two or more common walls. (Figure 5)

DWELLING UNIT - A building or portion thereof arranged or designed for occupancy by not more than one family and having separate cooking and sanitary facilities.

DYNAMIC MESSAGE DISPLAY - A sign incorporating LCD, LED, plasma, CRT, pixelized lights, other video-like displays or other means of changing messages

EARTHMOVING ACTIVITY - Any construction or other activity which disturbs the surface of the land including, but not limited to, excavations, embankments, land development, subdivision development, mineral extraction and the moving, depositing or storing of soil, rock or earth. For the purposes of this Ordinance, this definition shall not include the tilling of the soils and cultivation associated with the growing of crops.

EASEMENT – An interest in land owned by another person, consisting in the right to use or control the use of land, or areas above or below it, for a specific limited purpose. The grant of an easement reserves to the owner of the land all other incidents of ownership.

ELEVATION – The level of the ground adjacent to a structure, storage area, sign or other improvement.

EMISSIONS RELEASE POINT – That location where an exhaust chimney of an outdoor furnace permits the unrestricted flow of exhaust into the environment.

ENGINEER - A professional engineer registered as such in the Commonwealth of Pennsylvania.

ENTERTAINMENT FACILITIES – A use conducted indoors that offers personal amusement and/or enjoyment through mental engagement. This does not include adult entertainment uses, amusement arcades, amusement/theme/zoo parks, automobile and/or animal racing with or without related wagering facilities, off-track betting, slot machine parlors and/or casinos.

EXOTIC ANIMALS - All bears, coyotes, lions, tigers, leopards, jaguars, cheetahs, cougars, wolves and any crossbreed of these animals which have similar characteristics in appearance or features. The definition is applicable whether or not the animals were bred or reared in captivity or imported from another state or nation.

FAÇADE – The face(s) of a principal structure that directly adjoins and whose longest axis runs generally perpendicular to the adjoining yard.

FRONT FAÇADE – That façade that faces the front yard as defined herein. Front facades must also feature the prominent pedestrian entrance of a building. In the case of lots with multiple front yards, the location of the prominent pedestrian entrance of the building shall be determined according to the descending order of requirement:

- A. That façade that faces an adjoining street sidewalk;
- B. That façade that faces the adjoining street of address; and,
- C. That façade selected at the discretion of the applicant with approval by the Township.

REAR FAÇADE - That façade that faces the rear yard as defined herein.

SIDE FAÇADE – That façade(s) that faces the side yard(s), as defined herein.

FAMILY - Any one of the following:

- A. A single individual occupying a dwelling unit.
- B. Two (2) or more persons related by blood, marriage, or adoption occupying a dwelling unit.
- C. Not more than three (3) unrelated persons occupying a dwelling unit.
- D. Not more than eight (8) related or unrelated persons who are the functional equivalent of a family in that they live together, participate in such activities as meal planning, shopping, meal preparation, and the cleaning of their dwelling unit together and who are part of a community-based residential home that qualifies as a community living arrangement licensed by the Pennsylvania Department of Public Welfare or other appropriate federal or state agency having jurisdiction, where the persons occupying the home are handicapped persons under the terms of the Fair Housing Amendments Act of 1988, and where the operator of the home provides room and board, personal care, rehabilitative services, and supervision in a family environment. The presence of staff persons in a home meeting this definition shall not disqualify the group of persons occupying the dwelling unit as a “family.”

FARM OCCUPATION – See “Agriculture.”

FARMERS AND/OR FLEA MARKET - A retail sales use where more than one vendor displays and sells general merchandise that is new or used on a regularly occurring basis. Farmers and/or flea markets can include indoor and outdoor display of merchandise.

FCC – The Federal Communications Commission of the United States of America.

FINANCIAL INSTITUTION - Bank, credit union, savings and loan association, savings bank, investment company, or philanthropic foundation. For the purpose of this Ordinance, this term shall exclude pawn shops and non-bank operations that provide check-cashing services and advances on pay checks.

FISH HATCHERIES OR FISH FARMS – A principal use devoted to the raising of fish for wholesale distribution and/or wholesale public release.

FIXTURE - A complete lighting unit consisting of one or more lamps (light sources) together with the parts designed to control the light distribution, and other mechanical and electrical components.

FLOOD - A general and temporary condition of partial or complete inundation of normally dry land areas from the overland flow of watercourses, or from the unusual and rapid accumulation or runoff of surface waters from any source.

FLOODPLAIN - An area of land adjacent to the channel of a watercourse below the flood elevation which has been or is likely to be flooded, or any area subject to the unusual and rapid accumulation or runoff of surface waters from any source as regulated by Article 3, Chapter 92 of the Code of Dickinson Township.

FLOODPROOF - Any combination of structural and non-structural additions, changes or adjustments to structures which reduce or eliminate flood damage to property, structures and their contents.

FORESTRY - The management of forests and timberlands when practiced in accordance with accepted silviculture principles, through developing, cultivating, harvesting, transporting and selling trees for commercial purposes, which does not involve any land development.

FRONTAGE - The line of a lot coincident with an abutting right-of-way line of a street.

FULL TIME – A minimum of forty (40) hours per week.

FUNERAL HOME - A building or part thereof used for human and/or domestic pet funeral services. Such building may contain space and facilities for:

- A. a funeral chapel or similar gathering place;
- B. embalming and the performance of other services used in preparation of the dead for burial;
- C. cremation of human remains;
- D. the performance of autopsies and other surgical procedures;
- E. the storage of caskets, urns, and other related supplies; and
- F. the storage of funeral vehicles.

GAMING FACILITY - Any facility or location at which any lawful gambling activity other than or in addition to pari-mutuel wagering may be conducted under Pennsylvania law, including any facility in which gambling devices, including but not limited to slot machines, video poker machines, punch boards, and similar devices are located. The term “lawful gambling activity” shall not include the sale of lottery tickets in compliance with State Lottery law. The incidental use of less than eight (8) amusement devices and/or games of skill or chance (e.g., pinball machines, video games, skeet-ball, electronic or water firing ranges and other similar

devices) is not considered to be a gaming facility and can be offered at suitable uses and locations (e.g. restaurants, taverns, nightclubs, commercial recreation establishments, and similar uses).

GARAGE, PRIVATE - An accessory building for the storage of one (1) or more personal motor vehicles and/or other vehicles all of which must be accessory and incidental to the primary use of the residential premises, except as noted in Section 315.E. of this Ordinance.

GARAGE, YARD AND MOVING SALE – An occasional and temporary use of a residential lot, wherein the occupants of the said lot display and offer personal possessions for sale to the general public.

GARDENING – The growing of plants for personal use as an accessory use upon a residential site, or the growing of plants for personal use upon assigned plots located away from the residential site.

GAS STATION - Any area of land, including structures thereon, that is used for the retail sale of gasoline, fuel, diesel or similar products used to fuel any passenger or commercial motor vehicle, which may or may not be operated in conjunction with a convenience store use.

GEOTHERMAL SYSTEM - Any device installed as an accessory use that supplies energy principally for the principal use of the property that is derived from the exchange of underground temperature.

GLARE - The sensation produced by lighting that causes annoyance, discomfort, or loss in visual performance and visibility to the eye.

GOLF COURSE – Property developed for and devoted for the recreational participation in the sport commonly known as golf, having a minimum of 675 yards of play in nine (9) holes.

GOLF COURSE DRIVING RANGE - A use devoted to the practice of driving golf balls.

GOLF COURSE, MINIATURE – A commercial recreational use based upon golf that requires only a putter and is typically, but not necessarily, lit for night play.

GOVERNING BODY - The Board of Supervisors of Dickinson Township, Cumberland County, Pennsylvania.

GOVERNMENTAL USE – A use that is operated by a duly recognized level of government (local, State and Federal) provided however, that such use shall not include solid waste and/or hazardous waste disposal and/or handling facilities, prisons, and/or hospitals.

GRADE – A measurement of slope expressed in terms of percentage of vertical versus horizontal distance.

GREENHOUSE, COMMERCIAL - A retail business devoted to the raising and/or selling of trees, ornamental shrubs, flowers, and houseplants for transplanting, along with the sale of ancillary supplies wherein the preponderance of the growing operation is indoors.

GREENHOUSE, NON-COMMERCIAL – A structure designed or used for the indoor growing of plants, typically found as an accessory structure to a residence. No sales may be conducted from the structure, nor may the plants grown in the greenhouse be sold from the residence as a business operation.

GREEN ROOFTOP – An assemblage of man-made and natural materials that support vegetation as the principal exposed surface atop a building and are designed and maintained to offer thermal protection and hydrological benefit over conventional roofing surfaces.

GROUP HOME – A single-family dwelling operated by a reasonably responsible individual, family or organization with a program to provide a supportive living arrangement for individuals where special care is needed by the individual served due to age, emotional, mental or physical disability. This definition shall expressly include facilities for the supervised care of developmentally disabled persons and those under treatment for alcohol and/or drug abuse. Group homes must be licensed by appropriate government

agencies, and a copy of any such licenses must be delivered to the Township prior to beginning the use. Group homes shall be considered as single-family dwellings and subject to the same requirements as single-family dwellings, plus the requirements found in Section 432 of this Ordinance.

HEALTH, FITNESS, FRATERNAL, SOCIAL AND OTHER PRIVATE CLUBS – A principal use that offers service, support, entertainment, recreation, leisure and other activities only to club members and their guests. Such use does not include adult entertainment uses, casinos, golf courses, off-track betting parlors or outdoor shooting ranges, all as defined herein.

HEAVY EQUIPMENT - Vehicles and machinery that are not normally associated with domestic use (e.g., excavation equipment, commercial trucks in excess of 11,000 pounds gross vehicle weight, cargo and storage containers, cargo trailers, buses, yachts, farm equipment, mechanized amusement rides, industrial machinery, and other similar items).

HEAVY INDUSTRIAL USE – A principal use that involves:

- A. the production and processing of asphalt and asphalt products, bricks, cement and cement blocks, tar and other synthetic paving and masonry-like materials;
- B. the production and processing of chemicals, dyes, solvents, fertilizers, ammonia, carbide, caustic soda, cellulose, chlorine, carbon black, bone black, creosote, hydrogen, oxygen, pharmaceutical and industrial alcohol, nitrates, potash, plastic and synthetic resins, pyroxylin, rayon, and hydrochloric, nitric, picric and sulfuric acids;
- C. the production, processing and/or refining of matches, fuels and explosives, including but not limited to, gasoline, kerosene, ethanol, coal, coke, naphtha, natural gas, oil (natural and synthetic), lubricating oil, charcoal and other fuel briquettes, and other similar materials;
- D. the above-ground bulk storage of oil, gasoline or other similar flammable liquids;
- E. the production, processing and/or distillation of gelatin, glue, soap, starch and other plant and animal by-products not associated with food processing;
- F. the production and processing of linoleum, oil cloth, paint, varnish, turpentine, vinyl, rubber (natural and synthetic) and other similar materials;
- G. the production and processing of glass and glass products;
- H. a metal foundry, reduction, refinishing, smelting, alloying and/or refining operation;
- I. the milling or processing of flour or grain;
- J. principal waste handling, processing, transfer and disposal facilities;
- K. truck or motor freight terminals and truck stops;
- L. the production and/or assembly of passenger vehicles and heavy equipment and mobile homes; and,
- M. any operation of assembly, conversion, distribution, manufacture, production, processing, storage, warehousing and/or wholesaling of goods, materials and products not listed in Section 230.B., Section 230.C., and Sections 230.D.5 through 230.D.7. of this Ordinance.

HEIGHT, STRUCTURE - A structure's vertical measurement from the mean level of the ground abutting the corners of the structure to the highest point of the structure, including except as noted in Section 309, any signs, antennas or other appurtenances.

HELICOPTER PAD (PRIVATE) - An accessory use where no more than one helicopter may land/take-off and be stored.

HELIPORT - Any area of land or water which is used, or intended to be used, for the landing and takeoff of helicopter aircraft and any appurtenant areas which are used, or intended to be used, for heliport buildings or

navigation facilities or rights of way, together with all heliport buildings and facilities thereon.

HIGHWALL – The face of exposed overburden and mineral in an open cut of a surface mining operation or for entry to underground mining activities.

HISTORIC STRUCTURE – Any structure that is:

- A. Listed individually in the National Register of Historic Places (a listing maintained by the Department of Interior) or preliminarily determined by the Secretary of the Interior as meeting the requirements for individual listing on the National Register;
- B. Certified or preliminarily determined by the Secretary of the Interior as contributing to the historical significance of a registered Historic Zone or a Zone preliminarily determined by the Secretary to qualify as a registered Historic Zone;
- C. Individually listed on a state inventory of historic places in states with historic preservation programs which have been approved by the Secretary of Interior; or
- D. Individually listed on a local inventory of historic places in communities with historic preservation programs that have been certified either:
 - 1. By an approved state program as determined by the Secretary of the Interior; or,
 - 2. Directly by the Secretary of the Interior in states without approved programs.

HISTORIC STRUCTURE CONVERSION – The change or adaptation of a historic structure for use and occupancy for a use other than that generally permitted within the site’s zone. Historic structure conversions are governed by Section 446 of this Ordinance.

HOME IMPROVEMENT, EQUIPMENT RENTAL AND BUILDING SUPPLY STORES - A facility for the retail sale and/or rental of a combination of products used in the construction, repair and improvement of homes, including, but not limited to, lumber, masonry products, exterior siding, roofing, plumbing fixtures, pipes, electrical supplies, floor coverings, paints and wall coverings, windows and glass, landscaping materials, hardware, tools, and other accessories. Home improvement stores shall always involve outdoor storage of materials; any facilities that sell the above-described products that do not have outdoor storage can be considered to offer the general retail sale of goods.

HOME OCCUPATION - An occupation customarily conducted within a dwelling unit that is clearly incidental and secondary to the residential use of the dwelling. The following uses are expressly prohibited as home occupations, without limitation, animal hospitals; commercial stables and kennels; commercial day care facilities, funeral homes; tourist homes; restaurants; wholesale sales; storage or mail order activities in which goods are distributed from the dwelling or property; the repair, servicing, storage, or rental of motor vehicles; offices of medical practitioners; clinics; hospitals; and machine and welding shops.

HORTICULTURE – The cultivation of fruits, vegetables, flowers, and ornamental plants for commercial distribution.

HOSPITAL AND RELATED USES - An institution, licensed in the Commonwealth of Pennsylvania, which renders inpatient and outpatient medical care on a twenty-four (24) hours per day basis; and provides primary health services and medical/surgical care to persons suffering from illness, disease, injury, deformity and other abnormal physical or mental conditions. A hospital use can also include attached and detached accessory uses, provided that all accessory uses are contained upon the hospital property.

HOTEL, MOTEL OR SIMILAR LODGING FACILITIES - A building or group of buildings containing rooms for rental on a transient basis of not more than thirty (30) continuous days nor more than sixty (60) days within any calendar year. This term excludes “boarding house,” “bed and breakfast” and “campground” all as

defined herein. Accommodations provided as an accessory by institutional and educational uses for their patrons shall not be considered a "hotel;" similarly, buildings where human beings are housed under legal constraint are excluded from this term. Hotels are a building or group of buildings containing rooms for rental on a transient basis whose primary access is limited through a lobby. Motels are a building or group of buildings containing rooms for rental on a transient basis whose primary exterior access occurs at each respective unit. Hotels and motels may also include related accessory uses primarily directed towards serving its patrons including but not limited to dining, recreation, meetings, gifts, laundry, maid service and other personal services. Mail service shall be limited to counter service within the facility's lobby and no individual unit mail boxes, individual unit mail slots or exterior gang mail boxes shall be permitted. All hotels, motels and similar lodging facilities shall require a full-time on-site staff that operates 24 hours per day and seven days per week and shall not require guests to sign a lease agreement.

HOUSEHOLD HAZARDOUS WASTES - Those wastes in households that are hazardous in nature, but are not regulated as hazardous waste, under Federal and State laws. Included are such items as old paints and paint related products, pesticides, pool chemicals, drain cleaners, and degreasers, car care products and etc.

HUB HEIGHT - The distance measured from the surface of the tower foundation to the highest height of the wind turbine hub, to which the blade is attached.

IMPERMEABLE LINERS – a liner system that prohibits the infiltration or surface water into the subsurface.

IMPERVIOUS SURFACE (IMPERVIOUS AREA) - A surface not readily penetrated by water under normal pressure associated with rainfall or other typical conditions associated with the proposed use. Impervious surfaces (or areas) shall include, but not be limited to, buildings, roofs (except for green roofs, as defined herein), patios, garages, storage shed and similar structures, access drives, interior drives, driveways, sidewalks, off-street parking spaces, off-street loading spaces and paved recreation courts. Any areas designed to be covered by loose surfacing materials such as gravel, stone and/or crushed stone, and intended for storage of and/or travel by motorized or non-motorized vehicles, or travel by pedestrians shall be considered impervious.

IMPORANT NATURAL AND/OR CULTURAL FEATURE - Any area characterized by any of the following:

- A. Floodplains as regulated by Section 502 of this Ordinance;
- B. Steep slopes regulated by Section 521 of the SALDO;
- C. Wetlands and wetland buffers as regulated by Section 504 of this Ordinance and Section 518 of the SALDO;
- D. Riparian buffer as regulated by Section 503 of this Ordinance and Section 519 of the SALDO;
- E. Sensitive carbonate geologic features as listed in Section 525 of the SALDO;
- F. Pennsylvania Natural Diversity Inventory (PNDI) sites as regulated in Section 526 of the SALDO;
- G. Areas within the Scenic River;
- H. The Appalachian Trail;
- I. Known and/or suspected areas of archaeological significance as identified by the Pennsylvania Historical and Museum Commission;

- J. Historic sites as defined herein;
- K. Stands of mature trees that exceed five thousand (5,000) square feet of contiguous land area; and
- L. Class I, II, or III agricultural soils as identified in the latest version of the soil survey and/or area that is otherwise agriculturally productive.

IMPROVEMENT - Any structure or paving placed upon land, including the provision of underground or above-ground utilities, as well as any physical change to the surface of the land, including but not necessarily limited to grading, paving, the placement of stormwater management facilities, sidewalks, street signs, traffic control devices, and monuments. This definition shall expressly exclude the tilling of soil.

INTERIOR DRIVE - Any on-site vehicular movement lane(s) that are associated with a use other than a single-family dwelling and/or farm.

INVASIVE PLANT SPECIES OF PENNSYLVANIA – Those plants and vegetation identified by the PA DCNR as invasive plant species, with such list being published at (as amended and updated): <http://www.dcnr.pa.gov/Conservation/WildPlants/InvasivePlants/Pages/default.aspx>

JOINT PARKING LOT – A parking lot that is designed, constructed and operated on a shared basis by two or more adjoining uses with one or more shared access drives.

JUNK - Used materials, discarded materials, or both, including, but not limited to, waste paper, rags, metal, building materials, house furnishings and appliances, machinery, vehicles or parts thereof, all of which are being stored awaiting potential reuse or ultimate disposal.

JUNKYARD – An area of land, with or without buildings, used for the storage, outside a completely enclosed building, of used and discarded materials, including but not limited to, waste paper, rags, metal, building materials, house furnishings, appliances, machinery, vehicles, or parts thereof, with or without the dismantling, processing, salvage, sale, or other use or disposition of the same. The term, “salvage yard” includes “junkyard,” but does not include scrap metal processing operations and automobile shredding establishments. The deposit or storage on a lot of one or more unlicensed, wrecked, or disabled vehicles, or the major part thereof, shall be deemed to constitute a “salvage yard.” For the purposes of this definition, a disabled vehicle is a vehicle intended to be self-propelled that shall not be operable under its own power for any reason, or a vehicle that does not have a valid current registration plate or that has a certificate of inspection which has expired.

KENNEL - Any lot on which three (3) or more non-farm animals are kept, boarded, raised, bred, treated, or trained for commercial purposes or a fee, including but not limited to dog or cat kennels. This definition shall also expressly include animal rescue and similar emergency treatment facilities whether or not they are operated on a commercial basis.

LABORATORY – A use devoted to the conduct of experiments, research and observation associated with scientific study.

LAMP - A generic term for a man-made source of light.

LAND DEVELOPMENT - Any of the following activities:

- A. The improvement of one lot or two or more contiguous lots, tracts or parcels of land for any purpose involving:
 - 1. a group of two or more residential or nonresidential buildings, whether proposed initially or cumulatively, or a single nonresidential building on a lot or lots regardless of the number of occupants or tenure; or

2. the division or allocation of land or space, whether initially or cumulatively, between or among two or more existing or prospective occupants by means of, or for the purpose of streets, common areas, leaseholds, condominiums, building groups or other features.
- B. A subdivision of land.
- C. In accordance with Section 503(1.1) of the Act, the following activities are excluded from the definition of land development:
1. the conversion of an existing single-family detached dwelling, two-family dwelling or single-family semi-detached dwelling into not more than three residential units, unless such units are intended to be a condominium;
 2. the addition of an accessory building, including farm buildings, on a lot or lots subordinate to an existing principal building; provided, however, that the addition of a non-residential or non-farm accessory building or buildings does not:
 - a. exceed a total square footage of 2,000 square feet or 10% of the principal nonresidential or nonfarm building's square footage (as existed as of any addition of an accessory building or buildings made following the effective date of this Ordinance).
 - b. create negative storm water impacts on existing storm water facilities or on neighboring properties.
 - c. require the construction of additional access drive(s).
 - d. relieve the need for DEP Sewer Planning Module or exemption.
 3. the addition or conversion of buildings, structures or rides within an amusement, theme and/or zoo park.

LANDOWNER - The legal or beneficial owner or owners of land including the holder of an option or contract to purchase (whether or not such option or contract is subject to any condition), a lessee if he is authorized under the lease to exercise the rights of the landowner, or other person who has a proprietary interest in land.

LANDSCAPE SCREEN - A planting of noninvasive species arranged to form both a low-level and a high-level barrier between grade and a predetermined height established by the applicable regulation. This definition can also include the use of an earthen berm provided such berm is covered with noninvasive vegetative materials that stabilize its slopes and form both a low-level and a high-level screen between grade and a predetermined height established by the applicable regulation.

LANDSCAPE STRIP – An area of designated width at the periphery of a property planted with required noninvasive vegetative species that generally visually and functionally separate adjoining properties and uses.

LAUNDRY - A use at which articles of clothing, uniforms, linens, sheets, blankets, table cloths, draperies, towels, diapers and other fabric items are delivered to be cleaned with the use of agents that are generally water soluble.

LAUNDROMAT – A self-service business in which patrons clean, dry clean and/or dry articles of clothing, uniforms, linens, sheets, blankets, table cloths, draperies, towels, diapers and other fabric items.

LIVESTOCK – See “Agriculture.”


LOADING SPACE - An off-street space or area having direct usable access to a street or alley suitable for the loading or unloading of goods for shipment.

LOT - A designated parcel, tract or area of land established by a plat or otherwise as permitted by law and to be used, developed, or built upon as a unit.

LOT, CORNER: A property having street frontage along two (2) or more contiguous sides or along a single curved street with an interior angle of less than 135 degrees as measured along the interior edge of the street right-of-way, or in the event of no right-of-way, along the interior edge of the cart way.

LOT, INTERIOR: A lot with only one (1) street frontage.


LOT, THROUGH / REVERSE FRONTAGE: An interior lot having frontage on two parallel or approximately parallel streets with vehicular access solely from the street of lesser functional classification.



LOT COVERAGE - A percentage of the lot area which may be covered with an impervious surface (e.g., buildings, driveways, parking area, sidewalks). To the extent a building or structure incorporates a green rooftop (as defined herein) such area shall not be considered to be impervious.

LOT DEPTH - The horizontal distance measured between the street right-of-way line and the closest rear property line measured perpendicular along straight streets rights-of-way and measured radially along curved street rights-of-way. On corner and reverse frontage lots, the depth shall be measured from the street right-of-way line of the street of address to the directly opposite property line.

LOT LINE - A recorded boundary line of a lot; however, any edge of an adjoining street or other public or quasi-public right-of-way shall be interpreted as the lot line for the purposes of determining the location of the setbacks required by this Ordinance.



LOT LINE, FRONT: The lot line coincident with the right-of-way line of a street.

LOT LINE, REAR: Lot lines that are formed at the outermost edge of any rear yard as defined herein.

LOT LINE, SIDE: Lot lines that are formed at the outermost edge of any side yard as defined herein

LOT WIDTH – The horizontal distance measured between side property lines along the minimum front yard setback line and at the street right-of-way line. On corner lots, lot width shall be measured between the right-of-way line for the non-address street and the directly opposite property line along the minimum front yard setback line and at the street right-of-way line along the street of address.

MACHINE, TOOL AND DIE AND METAL FABRICATION SHOPS – A principal use devoted to the shaping, forming and finishing of metals into finished products or parts used in other industrial production and/or assembly.

MAN-MADE LAKES, DAMS AND IMPOUNDMENTS – A body of surface water that has been constructed with a bottom and sides generally comprised of natural materials with the possible exception of an artificial dam or spillway or bottom liner.

MANUFACTURING - Production of goods from raw materials, by the assembly of constituent parts produced elsewhere, or by a combination of these means, including the final packaging of such goods for sale or shipment. Includes all activities included in the NAICS (q.v.) list of “manufacturing” activities except those excluded by the definition of heavy industry as contained herein.

MANURE - The fecal and urinary excrement of livestock and poultry, often containing some spilled feed, bedding or litter.

MANURE STORAGE FACILITY - A detached structure or other improvement built to store manure for future use or awaiting disposal.

MASS TRANSIT STOPS – An area of land with or without structures where passengers are routinely collected by and dispatched from buses, trains, subways, taxicabs or other passenger vehicles (other than aircraft) owned and operated by a provider of public transportation.

MATURE TREE - A deciduous tree with a diameter at breast height (DBH) greater than or equal to ten (10) inches or a coniferous tree at least ten (10) feet tall.

MEDIATION - A voluntary negotiating process in which parties in a dispute mutually select a neutral mediator to assist them in jointly exploring and settling their differences, culminating in a written agreement which the parties themselves create and consider acceptable.

MEDICAL MARIJUANA – Marijuana for certified medical use as set forth under the Medical Marijuana Act, Pennsylvania Act 16, adopted April 17, 2016, as may be amended. The following definitions shall apply to medical marijuana uses:

MEDICAL MARIJUANA ACT: The Pennsylvania Medical Marijuana Act, known as Pennsylvania Act 16, adopted April 17, 2016.

MEDICAL MARIJUANA DISPENSARY: A person which holds a permit issued by the Pennsylvania Dept. of Health under the Medical Marijuana Act, to dispense medical marijuana. The terms do not include a health care medical marijuana organization under the Medical Marijuana Act which has been separately approved by the Pennsylvania Dept. of Health to dispense or grow and process in accordance with a research study pursuant to Chapter 19 of the Medical Marijuana Act.

MEDICAL MARIJUANA GROWER/PROCESSOR: A person which holds a permit issued by the Pennsylvania Dept. of Health under the Medical Marijuana Act, to grow and process medical marijuana. A grower/processor under this definition shall be considered a manufacturing use, and

not an agricultural use or business. The terms does not include a health care medical marijuana organization under the Medical Marijuana Act which has been separately approved by the Pennsylvania Dept. of Health to dispense or grow and process in accordance with a research study pursuant to Chapter 19 of the Medical Marijuana Act.

MEDICAL OFFICES - A building or group of buildings occupied by medical and/or other licensed practitioners and related services for the purpose of providing health, dental, vision, emergency medical, wellness, dietary, social, behavioral, therapeutic, occupational and psychological services to outpatients. This definition does not include methadone treatment facilities, as defined herein.

MEDICAL RESIDENTIAL CAMPUS – A use that provides a harmonious and balanced mix of medical, residential, limited commercial and recreational uses, primarily serving campus residents, and public, quasi-public and medical services for the off-campus retirement-aged community.

MESSAGE DISPLAY CYCLE – That unit of time in which one complete message is displayed upon a sign incorporating a dynamic message display.

METHADONE TREATMENT FACILITY – Any use licensed by the Pennsylvania Department of Health that administers the drug methadone in the treatment, maintenance or detoxification of persons.

MINIMUM LOT AREA - The least amount of lot area required to be to be associated with a principal use as required by this Zoning Ordinance.

MINIMUM SEPARATION DISTANCE - The minimum horizontal distance measured between two identifiable points.

MINING, QUARRYING AND RELATED PROCESSING OPERATIONS - The extraction of overburden and minerals from the earth; the preparation and processing of minerals, including any activities or processes or parts thereof for the extraction or removal of minerals from their original location and the preparation, washing, cleaning, crushing, stockpiling or other processing of minerals at the mine location so as to make them suitable for commercial, industrial or construction use; the removal of such materials through sale or exchange, or for commercial, industrial or municipal use; and the disposition of overburden, tailings and waste at the mine location. Mining shall expressly exclude the following:

- A. The extraction of minerals by a landowner for the landowner’s noncommercial use from land owned or leased by the landowner.
- B. The extraction of sand, gravel, rock, stone, earth or fill from borrow pits for highway construction purposes of the Department of Transportation or the extraction of minerals under construction contracts with the Department if the work is performed under a bond, contract and specifications that substantially provide for and require reclamation of the area affected in the manner provided by the act;
- C. The handling, processing or storage of slag on the premises of a manufacturer as a part of the manufacturing process;
- D. Dredging operations that are carried out in the rivers and streams of this Commonwealth;
- E. The sale and accompanying removal of non-coal materials from retail outlets;
- F. The extraction of minerals or other deposits carried out beneath the surface by means of shafts, tunnels and similar openings; and,
- G. The extraction, handling, processing or storing of minerals from a building construction excavation on the site of the construction if the minerals removed are incidental to the building construction excavation, regardless of the commercial value of the minerals. For purposes of this definition, the minerals removed are incidental if the excavator demonstrates that:
 - 1. Extraction, handling, processing, or storing are conducted concurrently with con-

struction;

2. The area mined is limited to the area necessary to construction; and,
3. The construction is reasonably related to the use proposed for the site.

MOBILEHOME - A transportable, single family dwelling intended for permanent occupancy, contained in one unit, or in two or more units designed to be joined into one integral unit capable of again being separated for repeated towing, which arrives at a site complete and ready for occupancy except for minor and incidental unpacking and assembly operations, and constructed so that it may be used without a permanent foundation.

MOBILEHOME LOT - A parcel of land in a mobile home park, improved with the necessary utility connections and other appurtenances necessary for the erections thereon of a single mobile home.

MOBILEHOME PARK – A parcel or contiguous parcels of land which has been so designated and improved that it contains two or more mobile home lots for the placement thereon of mobile homes.

MOTEL – See definition of Hotel, motel and similar lodging facilities, as defined herein.

MUNICIPALITY – The Township of Dickinson, Cumberland County, PA.

MUNICIPAL USES – Those uses and facilities designed to furnish necessary support for the general public health, safety and welfare that are typically the responsibility of local governments and other locally operated service agencies. Such uses shall include, but are not limited to:

- A. Municipal offices, meeting halls, garages, and storage yards;
- B. Public utility services and uses, including the structures and buildings where such uses are operated, to specifically include without limitation water plants and systems for providing potable water, sewer treatment plants and systems for the collection and conveyance of sewage, any similar public utility owned and operated by a municipal body, whether or not it is provided to the municipality's residents for a fee.
- C. Emergency services comprised of voluntary and/or paid personnel whose principal function is the dispatch of trained responders to the general public, under local emergency conditions. Such uses may include facilities for the housing of personnel while on duty, vehicle and equipment storage areas, training facilities and accessory meeting, cafeteria, banquet, stage, recreation, shooting range and/or other fund-raising amenities, all of which must be conducted within a totally enclosed building. Accessory parks, athletic facilities and fairgrounds are also permitted. Suitable examples include, but are not limited to, police departments, sheriff stations, fire companies, forest fire agencies, ambulance companies, emergency medical services, advanced life support, search and rescue, national guard and civil defense. This definition does not include prisons or outdoor shooting ranges;
- D. Indoor community service uses and activities, including meeting rooms, classrooms, theaters, auditoriums, banquet and social halls, scout cabins, libraries, museums and galleries of materials that are not for sale, clubhouses, accessory cafeterias and kitchens, and other similar uses;
- E. Outdoor community service facilities and activities, including fair grounds, community bulletin boards and other similar uses; and,
- F. Uses accessory to the above permitted uses, including parking and loading spaces, signs, offices, rest rooms, maintenance equipment storage areas and buildings, lights, waste receptacles and dumpsters, bleachers, and other similar uses.

NET ACRE – An area of land with 43,560 square feet, exclusive of public rights-of-way, and public and private streets. In the case where a proposed development with more than one (1) principal use is to rely upon one or more private access drives rather than streets, the area devoted to the access drives that serve more than one principal use and any adjoining curbs and sidewalks shall also be deducted from the calculation of acreage.

NEW CONSTRUCTION – Structures, including substantial improvements thereto, for which the start of construction commenced on or after the effective date of this Ordinance.

NO-IMPACT HOME BASED BUSINESS – A business or commercial activity administered or conducted as an accessory use which is clearly secondary to the use as a residential dwelling and which involves no customer, client or patient traffic, whether vehicular or pedestrian, pickup, delivery or removal functions to or from the premises, in excess of those normally associated with residential use. The business or commercial activity must satisfy all of the following requirements:

- A. The business activity shall be compatible with the residential use of the property and surrounding residential uses.
- B. The business shall employ no employees other than family members residing in the dwelling.
- C. There shall be no display or sale of retail goods and no stockpiling or inventorying of a substantial nature.
- D. There shall be no outside appearance of a business use, including, but not limited to, parking, signs or lights.
- E. The business activity may not use any equipment or process which creates noise, vibration, glare, fumes, odors or electrical or electronic interference, including interference with radio or television reception, which is detectable in the neighborhood.
- F. The business activity may not generate any solid waste or sewage discharge, in volume or type, which is not normally associated with residential use in the neighborhood.
- G. The business activity shall be conducted only within the dwelling and may not occupy more than 25 percent of the habitable floor area.
- H. The business may not involve any illegal activity.

NONCOMMERCIAL KEEPING OF LIVESTOCK - An accessory use to a principal detached single-family dwelling that is not contained upon a farm, whereupon livestock are kept exclusively by the residents of the site.

NONCONFORMING LOT - A lot the area or dimension of which was lawful prior to the adoption or amendment of this Zoning Ordinance, but which fails to conform to the requirements of the Zone in which it is located by reasons of such adoption or amendment.

NONCONFORMING STRUCTURE - A structure or part of a structure manifestly not designed to comply with the applicable use or extent of use provisions in a zoning ordinance or amendment heretofore or hereafter enacted, where such structure lawfully existed prior to the enactment of such ordinance or amendment or prior to the application of such ordinance or amendment to its location by reason of annexation. Such nonconforming structures include, but are not limited to, nonconforming signs.

NONCONFORMING USE - A use, whether of land or of structure, which does not comply with the applicable use provisions in this Zoning Ordinance or amendment heretofore or hereafter enacted where

such use was lawfully in existence prior to the enactment of such ordinance, or amendment or prior to the application of such ordinance or amendment to its location by reason of annexation.

NONCONFORMITY, DIMENSIONAL - Any aspect of a land use that does not comply with any size, height, bulk, setback, distance, landscaping, coverage, screening, or any other design or performance standard specified by this Zoning Ordinance, where such dimensional nonconformity lawfully existed prior to the adoption of this Ordinance or amendment thereto, or when such nonconformity is the result of the acquisition of land and/or rights-of-way by a governmental agency.

NOXIOUS SPECIES – Plants identified by the Pennsylvania Department of Agriculture’s on its Noxious Weed Control list, with such list being published at (as amended and updated):
http://www.agriculture.pa.gov/Plants_Land_Water/PlantIndustry/NIPPP/Pages/default.aspx

NURSING, REST OR RETIREMENT HOMES - Facilities designed for the housing, boarding, and dining associated with some level of nursing care.

OFF-STREET LOADING - An off-street area provided for the loading or unloading of goods and/or materials that has direct usable access to a use’s loading docks and/or doors and is connected to a street or alley by an access drive subject to the requirements listed in Section 314 of this Ordinance. This definition shall also expressly include any area that directly adjoins the loading docks and/or doors that is necessary for the vehicles to maneuver into place with the use’s loading docks and/or doors. This definition shall not include the access drives on the site that do not directly adjoin the loading docks and/or doors unless they require vehicles to move in a reverse direction to negotiate access to and from the loading docks and/or doors.

OFF-STREET PARKING - An accessory use in which required and, potentially, additional parking spaces are provided subject to the requirements listed in Section 315 of this Ordinance.

OFF-TRACK BETTING FACILITY - A facility other than a racetrack wherein pari-mutuel wagering, but no other lawful gambling activity, is conducted.

OFFICE - A building or a space in a building the primary use of which is the conduct of the affairs of a business, profession, service, or government, including administration, record keeping, clerical work, and similar business functions. An office shall not involve manufacturing, fabrication, production, processing, assembling, cleaning, testing, repair, or storage of materials, goods, or products, except that office supplies necessary for the operation may be stored as an incidental use. An office shall only involve the incidental sales or delivery of any materials, goods, or products physically located on the premises.

ON-LOT SEWAGE DISPOSAL SYSTEMS, (ON-LOT SEWER SERVICE) - A system of conveyance, treatment, and discharge that provides for the safe and healthful disposal of sewage generated by one principal use within the confines of the lot on which the use is located, as approved by the Pennsylvania Department of Environmental Protection. This definition shall not prohibit the use of sewage plume easements that may extend beyond the property upon which the sewage is generated.

ON-LOT WATER SERVICE – The provision of water to a single user from a private source located on the user’s lot.

OPEN SPACE - Any area of land or water, or a combination of land and water, within a development site that is free of improvement and impervious surfaces. Open spaces shall not include, among other things, areas devoted to buildings, structures, driveways, access drives, parking lots, street rights-of-way, and/or storm water detention basins, but can include required setbacks and private yards.

ORNAMENTAL PONDS AND WADING POOLS – An accessory use that:

- A. contains no more than 337.5 cubic feet of water (2,530 gallons);
- B. has a length or diameter not exceeding fifteen feet (15’); and,

C. has a maximum depth less than one and one-half (1½) feet.

ORPHANAGE - A building or group of buildings designed for and intended to provide housing facilities for minors, who are in need of direct care in lieu of that available from their parents. The facility may include accessory medical facilities intended to serve the residents of the orphanage but not the general public.

OUTDOOR FURNACE - A freestanding or attached accessory structure or appliance designed to be located outside of a principal use which is designed to provide heat and/or hot water to said principal use through the consumption of clean wood, coal, natural gas, kerosene, propane, domestic heating oil provided that such fuels comply with all applicable sulfur limits. For the purposes of this definition clean wood fuel shall include all wood intended to be used as fuel, including but not limited to trees, cordwood, logs, lumber, sawdust, and wood from manufacturing processes (butt offs, shavings, turnings, sander dust) wood pellets, slabs, bark, chips, and waste pallets. Clean wood fuel does not include materials chemically treated with any preservative, paint, or oil.

PHASE 2 OUTDOOR FURNACE – An outdoor furnace that has been certified by the United States Environmental Protection Agency as meeting a particulate matter emission limit of 0.32 pounds per million British Thermal Units (BTUs) of output.

OUTDOOR RESIDENTIAL ATHLETIC COURT – An accessory use to a principal residence which is improved for the use by residents and their guests to engage in recreational sport.

OUTDOOR SHOOTING RANGES

PRIVATE OUTDOOR SHOOTING RANGE – Any discharge of firearms and other projectile-type weapons (e.g., guns, rifles, shotguns, pistols, air guns, archery cross-bows, etc.) on an individual's private property by the owner or occupier of such property and his/her invited guests (for no fee) for the practice of marksmanship, target shooting, recreation, competition, skill development, training, or any combination thereof. Nothing within this definition shall be construed to include hunting when conducted in accordance with the rules and regulations of the Commonwealth of Pennsylvania.

PUBLIC OUTDOOR SHOOTING RANGE – A facility, open to the public or open to a select class of individuals for a fee or membership (specifically including shooting clubs), designed and constructed that is not completely enclosed within a building that allows for the safe discharge of firearms and other projectile-type weapons (e.g., guns, rifles, shotguns, pistols, air guns, archery cross-bows, etc.) by persons for the practice of marksmanship, target shooting, recreation, competition, skill development, training, or any combination thereof. Nothing within this definition shall be construed to include hunting when conducted in accordance with the rules and regulations of the Commonwealth of Pennsylvania.

OUTPARCEL – A separate lot within a planned center that relies upon the planned center's circulation system for vehicular access.

OVERBURDEN - The strata or material overlying a non-coal mineral deposit or in between non-coal mineral deposits in its natural state and material before or after its removal by surface mining.

PA – Commonwealth of Pennsylvania.

PA DCNR – Pennsylvania Department of Conservation and Natural Resources.

PA DEP – Pennsylvania Department of Environmental Protection.

PA DOT - Pennsylvania Department of Transportation.

PACKAGING – The enclosure of products into sealers, containers, wrappers, boxes or other suitable

protective coverings for shipping, distribution and/or sales.

PARENT TRACT - When used in determining the permissible number of lots which may be subdivided or dwellings or other principal nonresidential uses which may be erected within the Conservation Zone (C) or Agricultural Zone (A), all contiguous land held in single and separate ownership is considered the parent tract, regardless of whether such land is divided into one or more lots, parcels, purparts or tracts; regardless of whether such land was acquired by the landowner at different times or by different deeds, devise, partition or otherwise; regardless of whether or such land is bisected by public or private streets or rights-of-way, which was held by the landowner or his or her predecessor in title on the effective date of this Ordinance.

PARK AND RIDE LOTS – A use provided by the Township, Cumberland County and/or the Commonwealth of Pennsylvania that is devoted to the daily storage of passenger vehicles who engage in some form of mass transit and/or carpooling.

PARKING LOT - An accessory use in which required and additional parking spaces are provided subject to the requirements listed in Section 315 of this Ordinance.

PARKING SPACE - An off-street space available for the parking of one (1) motor vehicle and having usable access to a street or alley.

PARKS AND PLAYGROUNDS – Those facilities designed and used for recreation purposes by the general public that are not operated on a commercial basis. This definition is meant to include the widest range of recreational activities, excluding adult entertainment uses, amusement arcades, amusement or theme parks, gaming facilities, golf courses, off-track betting facilities, racetracks, and shooting ranges. Such uses may include:

- A. Outdoor park and recreation facilities, including athletic fields, courts, playgrounds, open play areas, stadiums, skating rinks, skateboard, stunt-bicycle or BMX-bicycle courses, and other similar uses;
- B. Outdoor passive recreation facilities, including picnic pavilions, hiking, biking and fitness trails, park benches, fountains, statues and other memorials, barbecue grills, ponds, natural and cultural exhibits, amphitheaters, navigable and intermittent waters, publicly operated scenic sites and other similar uses;
- C. Outdoor community service facilities and activities, including fair grounds, community bulletin boards, and other similar uses;
- D. Outdoor swimming pools, including related amenities like bathhouse, wading pools, spas, snack bars, and other similar uses; and,
- E. Uses accessory to the above permitted uses, including parking and loading spaces, signs, offices, rest rooms, maintenance equipment storage areas and buildings, lights, waste receptacles and dumpsters, bleachers and other similar uses.

PART-TIME SEASONAL EMPLOYEE – A person who works less than twenty (20) hours per week or less than one thousand (1000) hours per year at a farm occupation.

PASSENGER MOTOR VEHICLE – A passenger vehicle that is less than 11,001 pounds gross vehicle weight (weight of vehicle with rated passenger and/or load capacity) that is used and licensed as the principal mode of conveyance by the occupants of a residential premises upon the public road system. This definition shall expressly exclude race vehicles, stake-body trucks, dump trucks, panel trucks, tractor trailers, commercial trucks and heavy equipment.

PASSENGER MOTOR VEHICLE SALES – Any building or land devoted to the retail sales leasing and/or

rental of passenger motor vehicles, including accessory service and repair facilities if conducted within a completely-enclosed building.

PASSENGER MOTOR VEHICLE SERVICE - The retail repair, servicing, maintenance and reconstruction of passenger motor vehicles, provided that the washing of passenger vehicles as a principal use is excluded from this definition (See “car wash”).

PAVED – A condition of surface in which man-made materials are applied resulting in a durable, smooth, stable and dust free surface over which vehicles and pedestrians may pass. This definition shall expressly include asphalt, bituminous, concrete, masonry, permeable, geo-grids and other similar materials provided they are applied with sufficient depth and base to achieve the required durable, smooth, stable and dust free surface.

PERSON - An individual, partnership, corporation, limited liability corporation, limited liability partnership, firm, company, association, governmental entity, trustee, receiver, assignee, or similar representative.

PERSONAL CARGO TRAILER – A licensed vehicle that is meant to be attached to a passenger motor vehicle for the purposes of transporting personal property upon the public road system.

PERSONAL SERVICE - A principal use (excluding adult entertainment uses) including barber shops, beauty and tanning salons, dry cleaning and laundry pick-up and drop-off facilities, tailor shops, shoe repair shops, the repair of clocks and small appliances and similar activities.

PERVIOUS SURFACE – A surface readily penetrated by water under normal pressure associated with rainfall or other typical conditions associated with the proposed use. These typically include but are not limited to yards, gardens, landscape features, fields, woodlands and other similar unimproved open spaces. These can also include special paving treatments that allow the ready penetration of surface water into the ground under normal pressure.

PESTICIDE - Any substance or mixture of substances intended for use in preventing, destroying, repelling, sterilizing, or mitigating any insects, rodents, nematodes, predatory animals, fungi, weeds, or other forms of plant or animal life.

PETROLEUM PRODUCT - Oil or petroleum of any kind and in any form, including crude oil and derivatives of crude oil. It may be alone, as a sludge, as oil refuse, or mixed with other wastes.

PHMC – Pennsylvania Historical and Museum Commission

PLANNED CENTER – A coordinated development of more than one land use all sharing common vehicle access and off-street parking.

PLANNED CENTER SIGN – A freestanding sign that is associated with a coordinated development of more than one land use all sharing common vehicle access and off-street parking.

PLANNING COMMISSION - The Planning Commission of Dickinson Township.

PLAY STRUCTURE – An accessory use to a residence comprised of a structure (freestanding or otherwise) with one or more components and supportive members which in whole or part is intended for use or play by children, including but not limited to tree houses, swingsets, sliding boards, jungle gyms, climbers, seesaws, rockers, non-portable sand boxes, big toys, modular playsets, etc.

PNDI – The Pennsylvania Natural Diversity Inventory

POD STORAGE CONTAINERS – Portable containers that are used for temporary storage of personal property of occupants on the site during times of transition (e.g. remodeling, moving, construction, emergency).

POWER GENERATION FACILITIES – Except as permitted under the definition of wind and solar farm, a principal use devoted to the creation, storage, conversion, distribution and transmission of electrical energy for use at another location.

PREMISES - The property upon which the activity is conducted as determined by physical facts rather than property lines. It is the land occupied by the buildings or other physical uses that are necessary or customarily incident to the activity, including such open spaces as are arranged and designed to be used in connection with such buildings or uses. The following are not considered to be a part of the premises on which the activity is conducted, and any signs located on such land are to be considered off-premise advertising:

- A. Any land which is not used as an integral part of the principal activity, including land which is separated from the activity by a roadway, highway, or other obstruction, and not used by the activity; and extensive undeveloped highway frontage contiguous to the land actually used by a commercial facility, even though it might be under the same ownership.
- B. Any land which is used for, or devoted to, a separate purpose unrelated to the advertised activity.
- C. Any land which is in closer proximity to the highway than to the principal activity, and developed or used only in the area of the sign site or between the sign site and the principal activity and whose purpose is for advertising purposes only. In no event shall a sign site be considered part of the premises on which the advertised activity is conducted if the site is located on a narrow strip of land which is non-buildable land, or is a common or private roadway, or is held by easement or other lesser interest than the premises where the activity is located.

PRINCIPAL WASTE HANDLING, PROCESSING, TRANSFER AND DISPOSAL FACILITIES – A principal use operated by Cumberland County devoted to the collection, sorting, storage, transport and disposal of solid waste.

PRIVATE SCHOOL – See “School, Private.”

PROCESSING – Pertaining to a systematic modification through mechanical, physical, chemical, and/or energy forces.

PUBLIC HEARING - A formal meeting held pursuant to public notice by the governing body, the Planning Commission or the Zoning Hearing Board, intended to inform and obtain public comment, prior to taking action in accordance with this Ordinance.

PUBLIC MEETING - A forum held pursuant to notice under the act of July 3, 1986 (P.L. 388, No. 84), known as the Sunshine Act.

PUBLIC NOTICE - Notice published once each week for two successive weeks in a newspaper of general circulation in the municipality. Such notice shall state the time and place of the hearing and the particular nature of the matter to be considered at the hearing. The first publication shall not be more than thirty (30) days, and the second publication shall not be less than seven (7) days from the date of the hearing. Public notice for rezoning, special exception, conditional use and/or variance requests shall also include the posting of a sign at conspicuous locations along the perimeter of the subject property deemed sufficient by the Township to notify potentially interested citizens. These sign(s) shall be posted at least one (1) week prior to the hearing and will exhibit the nature, date, time, and location of the hearing. Once posted in accordance with the requirements of the Act, the Township, absent actual notice, shall not be responsible for loss or destruction of sign(s) due to vandalism or an act of God.

PUBLIC SCHOOL – See “School, Public.”

PUBLIC SEWER - A municipal or privately-owned sanitary sewer facility approved and permitted by the Pennsylvania Department of Environmental Protection. Such systems are capable of serving multiple users.

PUBLIC UTILITIES - Use or extension thereof which is privately owned and operated and requires a "Certificate of Convenience" approved by the Pennsylvania Public Utility Commission for the purpose of providing public sewage disposal and/or sewage treatment; public water supply, storage and/or treatment; or for the purpose of providing the transmission of energy or telephone service. For purposes of this definition, no use regarding or related to communication antenna, communication equipment facilities, and communication towers shall be considered, or in any way constitute, a public utility.

PUBLIC UTILITIES STRUCTURES – Any structure built for the purpose of providing a public utility which is not owned by a municipal or government entity, whether such structure, or the land upon which it is constructed, is owned or leased by the entity operating said public utility. The following are expressly excluded from the definition of public utilities structures: communication antenna, communication equipment facilities, and communication towers.

PUBLIC WATER - A municipal or privately-owned water supply system approved and permitted by the Pennsylvania Department of Environmental Protection. Such systems are capable of serving multiple users.

RECREATIONAL VEHICLE - a vehicle which is (1) built on a single chassis; (2) not more than 400 square feet, measured at the largest horizontal projections; (3) designed to be self-propelled or permanently towable by a passenger vehicle; and (4) designed for recreation and/or human occupancy solely under transient circumstances (e.g. vacations, camping, seasonal recreation, temporary visitation, but expressly excluding residency and migrant employment).

RECYCLING COLLECTION FACILITY – A use devoted solely to the collection of discarded materials that have entered a reasonably continuous process whereby their reuse is foreseeable, for processing and disposal at another location.

RECYCLING FACILITY – A use that specializes in the collection and processing of discarded materials that have entered a reasonably continuous process whereby their reuse is foreseeable.

RESIDENTIAL SWIMMING POOL – An accessory use involving any structure and inflatable device used for swimming, not located within a completely enclosed building, and containing, or normally capable of containing, water to a depth at any point greater than twenty-four (24) inches. Farm ponds, stormwater basins and/or lakes are not included, provided that swimming was not the primary purpose for their construction.

RESTAURANT - An establishment that serves prepared food primarily on non-disposable tableware, but can provide for incidental carry-out service so long as the area used for carry-out service does not exceed five percent (5%) of the total patron seating area nor eighty (80) square feet (whichever is less). Restaurants may offer incidental live entertainment.

RESTAURANT - DRIVE-THRU OR FAST-FOOD - An establishment that serves prepared food generally packaged in paper wrappers and/or disposable plates and containers. Such food can be consumed either on or off of the site.

RETAIL – Pertaining to the general public availability for purchase and personal use and/or consumption.

RETAIL SALES – A use devoted to the display and retail transfer of ownership and/or rental of goods and products. This term shall not include "adult entertainment uses" as defined herein.

RETAINING WALL – A man-made structure used to stably contain land at a location of substantial elevation change.

RIDING STABLE - A principal use at which the operator offers services and facilities to board, train, and exercise horses that are owned by non-residents of the subject property. This use also expressly includes the recreational riding of horses for a fee, riding lessons, periodic competitions and similar events related to the care, use and enjoyment of horses.

RIGHT-OF-WAY – A defined portion of land acquired by reservation, dedication, forced dedication, prescription or condemnation that may or may not be secured for public use and which may, but need not, be improved with streets, utilities, stormwater management facilities, traffic control facilities, curbs, sidewalks, bicycle lanes or paths, streetlights, and similar improvements for public benefit or enjoyment.

RIGHT-OF-WAY, ULTIMATE – The width or area of land necessary to accommodate present or future public improvements.

ROAD, ROADWAY – See the definition of “Street.”


ROADSIDE STAND – An accessory agricultural use for the sale of local agricultural or horticultural produce, livestock or merchandise.

RURAL OCCUPATION - An accessory business or commercial activity that is conducted within an accessory structure of a principal single-family detached dwelling.

SALDO - The latest version of the Township's Subdivision and Land Development Ordinance.


SALES - A use devoted to the transfer of ownership and/or rental of goods and products. This term shall not include “adult entertainment uses” as defined herein.

SATELLITE DISH ANTENNA - A device incorporating a reflective surface which is solid, open mesh or bar-configured and is in the shape of a shallow dish, cone, horn, or cornucopia. Such device shall be used to transmit and/or receive radio or electromagnetic waves between terrestrially and/or orbitally-based uses.



SATELLITE DISH ANTENNA AZIMUTH ALIGNMENTS - That range of horizontal directions the installed satellite dish antenna must be aimed to send or receive signals. These directions are usually expressed as degrees from true north. The adjacent diagram illustrates a range of azimuth alignments between 170.1 and 252.3 degrees.

SATELLITE DISH ANTENNA ELEVATION ALIGNMENTS - That range of vertical directions the installed satellite dish antenna must be aimed to send or receive signals. These directions are usually expressed as degrees above the horizon. The adjacent diagram illustrates a range of elevation alignments between 11.4 and 43.8 degrees.



SATELLITE DISH ANTENNA LOOK ANGLES -The combination of azimuth and elevation alignments needed for an installed satellite dish antenna to send or receive signals.

SATELLITE DISH ANTENNAS RECEPTION WINDOW - The area within a direct line between the satellite dish antenna and an orbiting satellite and or a fixed terrestrially based sending station. For the satellite dish to remain unimpaired, this reception window must be kept relatively free from obstructions.

SAWMILL – A principal use devoted to the processing of natural wood products into semi-finished products for wholesale distribution.

SCHOOL - A principal use in which supervised education or instruction is offered according to the following

categories:

COMMERCIAL SCHOOL: A school not operated by a public agency that can offer any of a wide range of curriculums including, but not limited to, all levels of academic, business and technical instruction and training in artistic, dance, baton-twirling, athletic, martial arts, musical, gymnastics, cosmetology and other similar activities. Commercial schools are principal uses that are neither home occupations nor day-care operations. These uses shall not include vocational and/or mechanical trade schools as defined in this Ordinance. Nursery schools shall be considered commercial school if they are operated as a business.

PRIVATE SCHOOL: A school that offers elementary, secondary, post-secondary, post-graduate, or any combination thereof, education that may, or may not, be operated as a gainful business, and is not operated by the school Zone or another governmental agency. Plain-sect schools shall be included as a private school.

PUBLIC SCHOOL: A school licensed by the Department of Education for the purpose of providing elementary, secondary, vocational, post-secondary, post-graduate, and adult education, or any combination thereof, and operated by the School District.

VOCATIONAL-MECHANICAL TRADE SCHOOL: A school that may, or may not, be operated as a gainful business that principally offers training in any of the following occupations:

1. Agriculture and/or horticulture
2. Truck driving;
3. Engineer repairs;
4. Building construction and general contracting;
5. Woodworking;
6. Masonry;
7. Plumbing;
8. Electrical contracting; and,
9. Other similar trades, as determined by the Zoning Hearing Board pursuant to Sections 107 and 804.C. of this Ordinance.

SCREENING - An assemblage of materials that are arranged so as to block the ground level views between grade and a predetermined height established by the applicable regulation. Suitable screening materials include trees, shrubs, hedges, berms, walls, sight-tight fences, other similar type materials, or any combination thereof. No wall or fence shall be constructed of plywood, corrugated metal or fiberglass, nor sheet metal.

SEASONAL RESIDENCE - A dwelling, cabin, camp, cottage, lodge or summer house which is intended for occupancy less than one hundred eighty-two (182) days of the year.

SEPTAGE – A semi-solid waste that collects at the bottom of sewage treatment devices that is not continuously released during normal treatment flows and needs to be periodically removed and processed and disposed-of elsewhere.

SEPTAGE AND SPENT MUSHROOM COMPOST PROCESSING – A principal use devoted to the collection and conversion of the septage and/or spent mushroom compost for healthful disposal.

SETBACK - The required horizontal distance between a setback line and a property or street line.

SETBACK, FRONT: The distance between the street line and the front building setback line projected the full width of the lot. Commonly, called “required front yard.”

SETBACK, REAR: The distance between the rear lot line and the rear setback line projected the full width of the lot. Commonly called “required rear yard.”

SETBACK, SIDE: The distance between the side lot line and the side setback line projected from the front yard to the rear yard. Commonly called “required side yard.”

SETBACK LINE - A line within a property and parallel to a property or street line which delineates the required minimum distance between some particular use of property and that property or street line.

SHED – A freestanding accessory building to a residence that is generally used to store personal property solely of the inhabitants on the site.

SHADOW FLICKER - means alternating changes in light intensity caused by a moving wind rotor blade casting shadows on the ground and stationary objects.

SHOPPING CENTER - A development consisting of any single retail store in excess of 20,000 square feet of gross floor area or two (2) or more establishments which are designed to function as a unit, for retail sales; personal services; restaurants, taverns and nightclubs; business, professional, or banking offices; civic uses, commercial schools, and/or similar uses together with shared stormwater management, vehicular access, off-street parking and signage.

SHORT TERM RENTALS – Any lease or rental arrangement by a property owner of the owner's property to a third party for a fee or similar compensation, the duration of which rental, including successive weeks, is less than a month. This term shall not include boarding houses, bed and breakfasts, motels, hotels, or campgrounds.


RESIDENTIAL SHORT-TERM RENTALS – Any short-term rental that includes an owner or occupier's entire dwelling space, whether the same is an apartment or an entire detached single-family dwelling, or anything similar. The term includes short term web-based rentals of residential dwellings, commonly referred to as AirBNB, Homeaway, and similar.

AGRICULTURAL SHORT-TERM RENTALS – Any short-term rental whereby an active farm is offering third parties the experience of staying at the farm and participating, in any way, including limited or intense, with the farming activities as a type of tourist experience.

SIGN – A device for visual communication that is used to bring the subject to the attention of the public that is legible from an adjoining road or adjoining property standing at grade (for the purposes of this definition the term legible shall mean understandable by someone of sufficient age and eyesight to obtain a PA driver's license.)

THIS TERM INCLUDES:

- A. lettering, logos, trademarks, and other symbols that are an integral part of the architectural design of a building which are applied to a building or which are located elsewhere on the



- premises;
- B. signs that are affixed to windows or glass doors or are otherwise internally mounted such that they are legible from an adjoining road or adjoining property;
 - C. flags and insignia of civic, charitable, religious, fraternal, patriotic, and similar organizations;
 - D. insignia of governments and government agencies;
 - E. banners, streamers, pennants, spinners, reflectors, tinsel, and similar objects; and
 - F. inflatable objects.

THIS TERM SHALL NOT INCLUDE:

- A. architectural features that may be identified with a particular business;
- B. backlit awnings that include no lettering, logos, or other symbols;
- C. signs within a building that are obviously intended to be seen primarily from within the building;
- D. outdoor signs intended for use within a property, such as menu signs for fast-food restaurant drive-through lanes provided such signs are not legible from an adjoining road or adjoining property;
- E. signs with regulations within a park provided such signs are not legible from an adjoining road or adjoining property;
- F. building identification signs within a campus provided such signs are not legible from an adjoining road or adjoining property;
- G. flags of governments or government agencies;
- H. decorative seasonal and holiday banners on residential properties; and
- I. display of merchandise either behind store windows or outdoors.

BILLBOARD - An off-premise sign which directs attention to a product, service, business, or cause.

CANOPY SIGN – A sign that is incorporated into an awning or canopy that is attached to the building.

FLAT ROOF SIGN – A sign that has its longest axis along the same direction as the roof to which it is attached and does not project beyond the outside edges of the roof line in any direction.

FLAT WALL SIGN – A sign that is attached to the wall of a building and whose face runs parallel to the wall to which it is attached and does not extend beyond the outside of the edges of the wall in any direction.

FREESTANDING SIGN – A sign that has a separate support structure and is not physically attached to a building.


PROJECTING ROOF SIGN – A sign whose support structure is attached to the roof of a building and whose face either runs generally perpendicular to the roof line or its underlying wall, or extends beyond the outside edges of the roof to which it is attached.

PROJECTING WALL SIGN – A sign whose support structure is attached to the wall of a building and whose face either runs generally perpendicular to the wall, or extends beyond the outside edges of the wall to which it is attached.

WINDOW SIGN – A sign that is either located on the inside or outside surface of a window but whose

message faces outward.

SIGN TYPES DIAGRAM



SITE – A lot or portion thereof devoted to a particular use as regulated by this Ordinance.

SLAUGHTERING, PROCESSING, RENDERING AND PACKAGING OF MEAT PRODUCTS AND THEIR BY-PRODUCTS – A principal industrial use at which live animals and/or their physical remains are imported for preparation into materials of human, plant and/or animal nourishment or some other beneficial use.

SLOT MACHINE PARLORS - A facility other than a racetrack and/or an off-track betting parlor wherein wagering and other lawful gambling activity, is conducted under Pennsylvania law. This use shall include any facility in which gambling devices, including but not limited to slot machines, video poker machines, punch boards, and similar devices are located. The term “lawful gambling activity” shall not include the sale of lottery tickets in compliance with State Lottery law.

SMALL ENGINE REPAIR SHOPS - A use devoted to the mechanical restoration of machines that power domestic tools and other household devices and appliances. This definition shall not include uses involved in the repair of personal motor vehicles, commercial trucks and heavy equipment, all as defined herein.

SOIL SURVEY - The latest published version of the United States Department of Agriculture's soil survey for Cumberland County, Pennsylvania.

SOLAR ENERGY – Radiant energy (direct, diffuse and/or reflective) derived from the sun.

SOLAR ENERGY SYSTEM - An energy conversion system or device, including any structural design features and all appurtenances and parts thereof, whose primary purpose is to provide for the collection, storage and distribution of solar energy for space heating or cooling, for water heating and/or for electricity.

SOLAR PANEL - That part or portion of a solar energy system containing one or more receptive cells or units, the purpose of which is to convert solar energy for use in space heating or cooling, for water heating and/or for electricity.

SOLID WASTE - Garbage, refuse and other discarded materials including, but not limited to, solid and liquid waste materials resulting from municipal, industrial, commercial, agricultural and residential activities. Such

wastes shall not include biological excrement nor hazardous waste materials as defined in the *Code of Federal Regulations*, Title 40, Chapter 1, Part 261, dated July 1, 1984.

SPECIAL EXCEPTION - A use permitted in a particular Zone pursuant to the provisions of Articles VI and IX of the Act and approved by the Zoning Hearing Board in accordance with Section 704.C. of this Ordinance.

SPENT MUSHROOM COMPOST – Soil or mulch-like material that is a by-product of the cultivation of mushrooms.

STEEP SLOPES - Existing natural slopes of 15 % or greater (equal to 15 feet vertical distance over 100 feet horizontal distance). The alteration of slopes that were lawfully man-made (such as walls of a detention basin or quarry or excavated banks along a street) shall be regulated by a reasonable estimate of the pre-existing natural slope.

STORAGE UNIT CENTERS - A building, series of buildings, a portion of one or more buildings and/or exterior areas divided into separate storage spaces for personal property and/or property associated with some business or other organization. These storage spaces shall be used solely for storage and no processing, manufacturing, sales, research and development testing, service and repair, or other non-storage activities shall be permitted.

STORY - That part of a building between the surface of any floor and the next floor above it or, in its absence, the finished ceiling or roof above it. A “split level” story shall be considered a second story if its floor level is six (6) feet or more above the level of the line of the finished floor next below it. Any floor under a sloping roof at the top of a building that is more than two (2) feet below the top plate shall be counted as a half-story. A basement shall be counted a story if it averages more than five (5) feet above grade.

STREET - A public or private right-of-way, excluding driveways and access drives, intended for use as a means of vehicular and pedestrian circulation that provides a means of access to abutting property. The word “street” includes “thoroughfare,” “avenue,” “boulevard,” “court,” “drive,” “expressway,” “highway,” “lane,” “road,” and similar terms. This definition shall not include alleys as defined herein.

STREET CENTERLINE – A line laterally bisecting a street right-of-way into equal widths. Where the street right-of-way cannot be determined, the cartway centerline shall be deemed the street centerline.

STREET LINE OR RIGHT-OF-WAY LINE – The line defining the limit of a street right-of-way and separating the street from abutting property or lots. The street line shall be the same as the right-of-way line currently in existence.

STRUCTURE – Any manmade object, including buildings, having an ascertainable stationary location on or in land or water, whether or not affixed to the land, excluding stormwater management retention/detention basins and related inlet and/or outlet devices, sidewalks, driveways leading directly to a public street, and public utility lines and appurtenances. Structures shall not include such things as sandboxes, decorative fountains, swingsets, birdhouses, birdfeeders, mailboxes, and any other similar nonpermanent improvements.

- A. **Structure, Accessory**: A structure associated with an accessory use (e.g., swimming pools, patios, antennas, tennis courts, garages, utility sheds, etc.).
- B. **Structure, Principal**: A structure associated with a primary use.

SUBDIVISION - The division or redivision of a lot, tract, or parcel of land by any means into two (2) or more lots, tracts, parcels, or other divisions of land including changes in existing lot lines for the purpose, whether immediate or future, of lease, partition by the court for distribution to heirs or devisees, transfer of ownership, or building or lot development. The subdivision by lease of land for agricultural purposes into parcels of more than ten (10) acres, not involving any new street or easement of access or any residential dwelling, shall be exempted.

SWIMMING POOL - Any structure and inflatable device, not located within a completely enclosed building, and containing, or normally capable of containing, water to a depth at any point greater than twenty-four (24) inches. Farm ponds, stormwater basins and/or lakes are not included, provided that swimming was not the primary purpose for their construction.

TEMPORARY FAMILY HOUSING - A temporary dwelling unit placed on a property with another single family detached dwelling for occupancy by either an elderly, handicapped, disabled person(s), or any child, parent or other relative, any of which is related by blood, marriage, or adoption, to the occupants of the principal dwelling or their care-giving family members.

TOWNHOUSE – See definition of Dwelling, Townhouse defined herein.

TOWNSHIP - Dickinson Township.

TRAINING CENTER - A principal use that involves the indoor instruction of clients/customers on any of a wide range of subjects including but not limited to occupational, cultural, business, technical, professional, trade, religious, life skills, emergency response, and similar activities.

TRANSIENT – Any person who assumes temporary occupancy for the purposes of visitation, recreation or leisure purposes. This definition shall expressly exclude permanent residents and/or migratory workers and their families.

TRAVEL TRAILER – See “Recreational vehicle.”

TRUCK OR MOTOR FREIGHT TERMINAL – A principal use contained on a single property:

- A. to which materials and products are imported for their redistribution and export by commercial vehicle or other modes of transport; or,
- B. whereby a fleet of commercial vehicles is maintained for their dispatch on an as needed or contractual basis.

TRUCK STOP – A principal use designed as one functioning site in which various services and amenities are provided for the comfort, convenience and safety of those engaged in the trucking distribution industry and other motorists. Suitable examples include vehicle filling stations, vehicle repair and services, vehicle washing, dining and lodging, laundromats, rest lounges and areas, travel-related retail shops, gift shops, locker rooms and bathing facilities and similar uses.

TURBINE HEIGHT - The distance measured from the surface of the tower foundation upon which the wind turbine is attached to the highest point of the turbine rotor blades at their highest point of rotation.

TWO-FAMILY CONVERSION - The conversion of an existing single-family detached dwelling unit to contain two separate dwelling units.

UNIFORM CONSTRUCTION CODE (UCC) – The latest version of the statewide building code adopted by the Pennsylvania General Assembly applicable to new construction in all municipalities whether administered by the municipality, a third party of the Department of Labor and Industry. Applicable to residential and commercial buildings, the Code adopted by the International Residential Code (IRC) and the International Building Code (IBC), by reference, as the construction standard applicable with the Commonwealth floodplain construction. For coordination purposes, references to the above are made specifically to various sections of the IRC and the IBC.

USE - The specific purpose(s) for which land or a structure is designed, arranged, intended, occupied or maintained.

USE, ACCESSORY: A use customarily incidental and subordinate to the principal use or building and located on the same lot with such principal use or building.

USE, PRINCIPAL: The use of land, including vacant or open land, or structure that is most dominant (either visually or economically) in the determination of the Zoning Officer.

USE AND OCCUPANCY PERMIT – See Certificate Of Use and Occupancy as defined herein.

USES DEVOTED TO THE CONSERVATION OF LOCAL NATURAL AND CULTURAL RESOURCES – Principal uses that:

- A. Are free of buildings, structures or other improvements and require little to no property maintenance;
- B. Include outdoor passive recreation facilities, including picnic pavilions, hiking trails, park benches, drinking fountains, barbecue grills, ponds, natural and cultural exhibits, amphitheatres, navigable and intermittent waters, publicly operated scenic sites and other similar uses; and/or,
- C. House organizations whose principal purpose is the permanent protection of important and sensitive features and landscapes; and,
- D. Uses accessory to the above permitted uses, including parking and loading spaces, signs, offices, rest rooms, maintenance equipment storage areas and buildings, lights, waste receptacles and dumpsters, and other similar uses.

VARIANCE – Relief granted pursuant to the provisions of Articles VI and IX of the Act upon application to the Zoning Hearing Board in accordance with Section 704.D. of this Zoning Ordinance.

VETERINARY OFFICE/ANIMAL HOSPITAL – Any establishment, building or portion thereof, offering veterinary services to any type of animals by a licensed veterinarian. Such use is permitted to include the overnight boarding of domestic pets, but only if such domestic pets are kept inside the building where the use is operated. This term excludes the outdoor boarding or keeping of animals.

VOCATIONAL-MECHANICAL TRADE SCHOOL – See definition of “School.”

WAREHOUSE – A building whose purpose is the storage of goods awaiting further processes or delivery/distribution.

WAREHOUSE AND WHOLESALE TRADE ESTABLISHMENTS – A principal use where goods, products and/or materials are stored waiting further processing, delivery and/or distribution.

WATERCOURSE - A permanent or intermittent stream, river, brook, run, creek, channel, swale, pond, lake or other body of surface water carrying or holding surface water, whether natural or artificial.

WATERSHED - All the land from which water drains into a particular watercourse.


WELDING SHOPS – A principal use devoted to the joining of metals through intense heat for repair or the preparation of parts used in other industrial production and/or assembly.

WETLANDS - Those areas that are inundated or saturated by surface or ground water at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions, including swamps, marshes, bogs, and similar areas, and which shall be identified using that method of the following that delineates the greatest area of wetlands:

- A. The United States Army Corps of Engineers Technical Report Y87-1, Corps of Engineers

Wetlands Delineation Manual;

- B. The United States Environmental Protection Agency Wetlands Identification Delineation Manual, Volume I, Rational, Wetland Parameters, and Overview of Jurisdictional Approach, Volume II, Field Methodology, as most recently updated or modified; or,
- C. The Pennsylvania Department of Environmental Protection's Resources Wetlands Identification and Delineation, Chapter 105 Dam Safety and Waterways Management Rules and Regulations, as most recently updated or modified.



WIND AND SOLAR FARM – A principal use devoted to the generation of electrical energy for consumption elsewhere by means of solar panels and/or wind energy conversion systems.


WIND AND SOLAR FARM OPERATOR – That person or entity responsible for the day-to-day operation of the wind and solar farm.

WIND AND SOLAR FARM OWNER – That person or entity having legal or equitable interest in the wind and solar farm.

WIND TURBINE - Any device which converts wind energy to mechanical or electrical energy. This shall include blades, hubs to which blades are attached, and any device, such as a tower, used to support the hub and/or rotary blades, etc.

YARD - An area between the permitted structures and the property lines.

YARD, FRONT: The area contained between the principal structure and the street right-of-way line, except that where a portion of the site has a front property line that is located away from the street



right-of-way and runs generally parallel to the street, the front yard shall also include that area that is located between the principal structure and the front property line that generally parallels the street (see adjacent diagram). On corner lots the front yard shall be those yards that are located between the principal structure and the adjoining streets.

YARD, REAR: The area contained between the principal structure and the property line directly opposite the street of address. On corner lots that are also through lots, the rear yard shall be that yard that is located directly opposite the adjoining street that intersects with the street of address.

YARD, SIDE: The area(s) between a principal structure and any side lot line(s). On corner lots, the side yard shall be considered those areas between the principal structure and the property lines directly opposite the non-address street(s). On corner lots that are also through lots, the side yard shall be that yard that is located directly opposite the adjoining street that intersects with the street of address.

CORNER LOTS. On corner lots that are also through lots, the front yard shall be those yards that are located between the principal structure and the adjoining street of address and located between the principal structure and the adjoining street that intersects with the street of address.

YARD SALE – See “Garage, Moving and Yard Sale.”

ZONE - A portion of the Township within which certain uniform regulations and requirements or combinations thereof apply under the provisions of this Ordinance.

ZONING - The designation of specified Zones within a community or township, reserving them for certain uses together with limitations on lot size, heights of structures and other stipulated requirements.

ZONING HEARING BOARD - The Zoning Hearing Board of Dickinson Township, Cumberland County, Pennsylvania.

ZONING MAP - The Zoning Map of Dickinson Township adopted as part of this Zoning Ordinance.

ZONING OFFICER - The duly constituted municipal official designated to administer and enforce this Ordinance in accordance with its literal terms.

ZONING ORDINANCE – The Official Zoning Ordinance of Dickinson Township.

ZONING PERMIT – A permit stating that the purpose for which a building, structure, sign, and/or land is to be used is in conformity with the applicable requirements of this Ordinance for the zoning Zone in which it is, or will be, located.

Article 2

Zone Provisions

SECTION 200 – CONSERVATION ZONE (C)

200.A. PURPOSE OF ZONE

This Zone intends to protect the large concentrations of sensitive environmental and passive recreational areas which are important natural areas within the Township and the larger region. Permitted uses have been selected to encourage the most appropriate conservation/recreation activities for these unique geological and topographical features and avoid defoliation, deforestation, and destruction of ground cover. In addition, limitations on the development and disturbance of this area's steep slopes will help to minimize storm water runoff, flooding and soil erosion.

The provisions of this Zone have been specifically formulated to satisfy Section 604.(3) of the Act, which requires local zoning ordinances to “promote, protect and facilitate the preservation of the natural, scenic and historic values in the environment and preservation of forests, wetlands, aquifers and floodplains.” This Zone also incorporates resource protection policies recommended by the Township Comprehensive Plan.

200.B. PRINCIPAL USES PERMITTED BY RIGHT

1. **Agriculture and horticulture**, including one single-family detached dwelling contained on the site. This use shall also expressly exclude **concentrated animal feeding operations (CAFOs)** and **concentrated animal operations (CAOs)** and **commercial produce operations**, all as defined herein.
2. **Forestry uses.**
3. **Single family detached dwellings.**
4. **Municipal and governmental uses.**
5. **Cemeteries, including pet cemeteries.**
6. **Churches and related uses**, with a maximum permitted lot area of five (5) acres and subject to the requirements of Section 419 of this Ordinance.
7. **Conservation design developments** subject to the requirements of Section 425 of this Ordinance.
8. **Parks and playgrounds.**
9. **Accessory uses customarily incidental to the principal uses in this zone**, including, but not limited to, the following:

- a. **Agricultural Short-Term Rental**, only conducted as an accessory use to a principal agricultural use of the property, and subject to the requirements of Section 465 of this Ordinance.
- b. **Alternative energy systems**, subject to the requirements of Section 404 of this Ordinance.
- c. **Beekeeping**, subject to the requirements of Section 413 of this Ordinance.
- d. **Co-located communication antennas upon existing structures**, subject to the requirements of Section 420 of this Ordinance.
- e. **Composting**, subject to the requirements of Section 428 of this Ordinance.
- f. **Domestic pets**, subject to the requirements of Section 406 of this Ordinance.
- g. **Temporary family housing**, as defined herein, subject to the requirements of Section 431 of this Ordinance.
- h. **Family child-care homes**, as defined herein subject to the requirements of Section 421 of this Ordinance.
- i. **Farm occupations**, as defined herein, if conducted as an accessory use to a principal agricultural use of the property with a minimum of ten (10) acres, and subject to the requirements of Section 433 of this Ordinance.
- j. **Fences and walls**, subject to the requirements of Section 435 of this Ordinance.
- k. **Freestanding communication antennas, towers and equipment**, subject to a Special Exception as an accessory use pursuant to the requirements of Section 438 of this Ordinance.
- l. **Garage yard and/or moving sales**, subject to the requirements of Section 440 of this Ordinance.
- m. **Garages and sheds for the storage of personal vehicles and or personal property**, attached or detached to the dwelling unit.
- n. **Gardening and raising of plants for personal use**.
- o. **Home occupations**, as defined herein, subject to the requirements of Section 448 of this Ordinance.
- p. **Man-made lakes, dams, ponds, and impoundments**, subject to the requirements of Section 453 of this Ordinance.
- q. **Manure storage facilities**, as an accessory use to an agricultural or horticultural use if contained upon a farm, subject to the requirements of Section 455 of this Ordinance.
- r. **No-impact home-based business**, as defined herein.
- s. **Noncommercial keeping of livestock**, as defined herein, subject to the requirements of Section 462 of this Ordinance.
- t. **Ornamental ponds and wading pools** subject to the requirements of Section 464 of this Ordinance.
- u. **Outdoor residential athletic courts** (e.g. basketball, boccie, handball, tennis, volleyball, etc.) subject to the requirements of Section 466 of this Ordinance.
- v. **Outdoor shooting range (private)** subject to the requirements of Section 467 of this Ordinance.
- w. **Parking and/or storage of recreation vehicles and personal cargo trailers**, subject to the requirements of Section 468 of this Ordinance.

- x. **Play structures**, as defined herein, provided such structures are confined to the side or rear yard and are located no closer than fifteen feet (15') from the closest side and or rear lot line.
- y. **Residential Short-Term Rental**, only conducted as an accessory use to a principal residential use of the property, and subject to the requirements of Section 465 of this Ordinance.
- z. **Residential swimming pools**, subject to the requirements of Section 475 of this Ordinance.
- aa. **Roadside stands** for the seasonal sale of agricultural products subject to the requirements of Section 477 of this Ordinance.
- bb. **Rural occupations**, as defined herein, subject to the requirements of Section 479 of this Ordinance.
- cc. **Satellite dish antennas**, subject to the requirements of Section 481 of this Ordinance.
- dd. **Signs** as defined herein, subject to the requirements of Section 322 of this Ordinance.

200.C. PRINCIPAL USES PERMITTED BY SPECIAL EXCEPTION (Subject to the review procedures of Section 704.C. of this Ordinance).

- 1. **Bed and breakfasts**, subject to the requirements of Section 412 of this Ordinance.
- 2. **Campgrounds**, subject to the requirements of Section 416 of this Ordinance.
- 3. **Freestanding communication antennas, towers and equipment**, subject to a Special Exception as an accessory use pursuant to the requirements of Section 438 of this Ordinance.
- 4. **Golf courses and driving ranges**, subject to the requirements of Section 441 of this Ordinance.
- 5. **Historic structure conversions**, subject to the requirements of Section 446 of this Ordinance.
- 6. **Riding stables**, subject to the requirements of Section 476 of this Ordinance.
- 7. **Two-family conversions**, subject to the requirements of Section 488 of this Ordinance.

200.D. PRINCIPAL USES PERMITTED BY CONDITIONAL USE (Subject to the review procedures of Section 805 of this Ordinance).

- 1. **Fish hatcheries and/or fish farms**, subject to the requirements of Section 436 of this Ordinance.
- 2. **Outdoor shooting range (public)**, subject to the requirements of Section 467 of this Ordinance.
- 3. **Sawmills**, subject to the requirements of Section 482 of this Ordinance.
- 4. **Schools, private and public**, subject to the requirements of Section 472 of this Ordinance.
- 5. **Wind and solar farms**, subject to the requirements of Section 490 of this Ordinance.

200.E. SITE PLANNING OBJECTIVES

To enhance compatibility between proposed residential development and adjoining natural features, applications shall furnish evidence that the following specific design objectives have been satisfied through the design of the proposed use:

1. Minimize the loss and/or disturbance of valuable natural features (including but not limited to productive farmland) as documented pursuant to the regulations contained within Article 5 of this Ordinance;
2. Group residential lots on the subject property and, if applicable, with those lots contained on adjoining properties;
3. Successfully integrate valuable natural features during and after the development process as documented pursuant to the regulations contained within Article 5 of this Ordinance with priority towards protection of the environment; and,
4. Assure adequate vehicular access to future residences not currently proposed.

200.F. DRIVEWAYS AND ACCESS DRIVES

All driveways serving single-family dwellings shall be in accordance with Section 305 of this Ordinance. All access drives serving other uses shall be in accordance with Section 301 of this Ordinance. All lanes exclusively serving agriculture, horticulture and/or forestry-related uses shall be exempt from driveway and access drive requirements in Sections 305 and 301, respectively, except those related to the clear-sight triangle listed in Section 305.C. of this Ordinance.

200.G. AGRICULTURAL NUISANCE DISCLAIMER

All lands within the Conservation Zone are located within an area used for commercial agricultural production. Owners, residents and other users of property within this Zone may be subjected to inconvenience, discomfort and the possibility of injury to property and health arising from normal and accepted agricultural practices and operations, including, but not limited to, noise, odors, dust, the operation of machinery of any kind, including aircraft, the storage and disposal of manure, the application of fertilizers, soil amendments, herbicides, and pesticides. Owners, occupants and users of this property should be prepared to accept such inconveniences, discomfort and possibility of injury from normal agricultural operations, and are hereby put on official notice that Section 4 of Pennsylvania Act 133 of 1982, "The Right to Farm Law," and the Agriculture Communities and Rural Environment (ACRE), PA Act 38 of 2005, may bar them from obtaining a legal judgment against such normal agricultural operations. From the effective date of this Ordinance, all subsequent subdivision plans submitted within the (C) Zone shall require a note which duplicates this section, and which must be transferred to the purchaser by the seller.

200.H. GENERAL PROVISIONS

All uses permitted within this Zone shall also comply with the applicable General Provisions in Article 3 of this Ordinance.

200.I. ENVIRONMENTAL PROTECTION STANDARDS

All uses permitted within this Zone shall also comply with the applicable Environmental Protection Standards contained within Article 5 of this Ordinance.

200.J. AREA & DESIGN REQUIREMENTS WITHIN THE (C) ZONE

All uses within the Conservation Zone shall comply with those standards listed in the following Figure 200.J.

FIGURE 200.J. AREA & DESIGN REQUIREMENTS WITHIN THE (C) ZONE								
Use	Minimum Required Lot Area	Minimum Required Lot Width		Required Minimum Yard Setbacks			Maximum Permitted Impervious Lot Coverage	Maximum Permitted Height
		At Building Setback	At Lot Frontage	Front	Each Side	Rear		
Agriculture, and horticulture uses ^{1,2}	None	200 ft.	200 ft.	50 ft.	50 ft.	50 ft.	10%	150 ft., provided each structure is set back a distance at least equal to its height from each property line.
Municipal and governmental uses ²	None	None	None	None	None	None	60%	Unlimited
Single-family detached dwellings ²	80,000 sq. ft.	200 ft.	200 ft.	40 ft.	25 ft.	40 ft.	20%	35 ft.
Forestry and other principal uses ²	80,000 sq. ft.	200 ft.	200 ft.	50 ft.	50 ft.	50 ft.	20%	35 ft.
Residential accessory uses	Included in above	N/A	N/A	Not permitted in front yard, unless a minimum 50 ft. setback is provided.	Structures up to 400 sq. ft.		Included in above	20 ft.
					10 ft.	10 ft.		
					Structures exceeding 400 sq. ft.			
					Same as principal setback			

¹Special setback requirements - Except as provided for as follows, no new slaughter area, area for the storage or processing of garbage, agricultural byproducts or composted materials, structures for the cultivation of mushrooms shall be permitted within three hundred feet (300') of any adjoining property. The Zoning Hearing Board may, as a special exception, however, reduce the above special setback requirements where it is shown that, because of prevailing winds, unusual obstructions, topography, or other conditions, a lesser distance would protect adjoining lands from odor, dust or other hazards. In no case, however, shall the Zoning Hearing Board reduce the special setback requirement to less than one hundred feet (100'). The burden shall be upon the applicant to prove that a lesser distance would not be detrimental to the health, safety and general welfare of the community.

²All uses relying upon on-lot sewers shall comply with Section 323 of this Ordinance.

SECTION 201 - AGRICULTURAL ZONE (A)

201.A. PURPOSE OF ZONE

The purpose of this Zone is to protect areas within the municipality possessing prime agricultural soils (Class I, II, and III soils) which have historically been highly productive soil types most capable of supporting agricultural activities, so that agriculture as an on-going economic activity in the municipality is preserved. The Township acknowledges animal husbandry as an agricultural operation as defined by the Act. Agricultural operations are enhanced by permitting only those land uses and activities which are either agricultural in nature or are in direct support of agricultural activities. This Zone also promotes the preservation of historic sites through the adaptive re-use of such resources.

The regulations for this Zone are specifically designed to and shall be construed and interpreted to:

1. protect and enhance agricultural operations in the Zone;
2. facilitate adaptation to other agricultural technologies;
3. minimize conflicting land uses detrimental to agricultural operations;
4. limit development which requires infrastructure in excess of those required by agricultural operations;
5. maintain agricultural tracts in sizes which will preserve existing agricultural operations and facilitate adaptations to other agricultural technologies;
6. encourage and protect a locally available renewable energy source, encourage and protect a locally available renewable food source; and,
7. preserve, protect, and enhance natural, man-made, and historic features and amenities of the Township that have contributed to the historic character of the community.

In addition to the creation and perpetuation of this Zone, the Township supports creation of agricultural security areas and shall promote expansion of current agricultural security areas. The regulations are not intended to restrict agricultural operations, or changes to or expansions of agricultural operations in geographical areas where agriculture has traditionally been present.

The regulations of the Agricultural Zone are not intended to violate or exceed the provisions of the Act of May 20, 1993 (P.L. 12, No.6), known as the "Nutrient Management Act," the Act of June 30, 1981 (P.L. 128, No.43), known as the "Agricultural Area Security Law," or the Act of June 10, 1982 (P.L. 454, No.133), entitled "An Act Protecting Agricultural Operations from Nuisance Suits and Ordinances Under Certain Circumstances" as mandated by the Act, as amended.

201.B. PRINCIPAL USES PERMITTED BY RIGHT

1. **Agriculture and horticulture**, including one single-family detached dwelling contained on the site. This use shall also expressly include:
 - a. **Concentrated animal feeding operations (CAFOs)** as defined herein subject to the requirements of Section 424 of this Ordinance and further provided that the applicant provides a copy of an approved permit from the Pennsylvania Department of Environmental Protection, Bureau of Water Quality and the proposed use maintains compliance with the federal regulations governing CAFOs; and/or,

- b. **Concentrated animal operations (CAOs)** as defined herein subject to the requirements of Section 424 of this Ordinance and further provided that the applicant provides written evidence of an approval of the applicant's nutrient management plan from the County Conservation District or the Pennsylvania Conservation Commission and the applicant maintains compliance with the Pennsylvania Nutrient Management Act No. 38.
- 2. **Forestry uses.**
 - 3. **Single family detached dwellings.**
 - 4. **Municipal and governmental uses.**
 - 5. **Cemeteries, including pet cemeteries.**
 - 6. **Churches and related uses**, with a maximum permitted lot area of five (5) acres and subject to the requirements of Section 419 of this Ordinance.
 - 7. **Conservation design developments** subject to the requirements of Section 425 of this Ordinance.
 - 8. **Parks and playgrounds.**
 - 9. **Accessory uses customarily incidental to the principal uses in this zone**, including, but not limited to, the following:
 - a. **Agricultural Short-Term Rental**, only conducted as an accessory use to a principal agricultural use of the property, and subject to the requirements of Section 465 of this Ordinance.
 - b. **Alternative energy system**, subject to the requirements of Section 404 of this Ordinance.
 - c. **Beekeeping**, subject to the requirements of Section 413 of this Ordinance.
 - d. **Co-located communication antennas upon existing structures**, subject to the requirements of Section 420 of this Ordinance.
 - e. **Composting**, subject to the requirements of Section 428 of this Ordinance.
 - f. **Domestic pets**, subject to the requirements of Section 406 of this Ordinance.
 - g. **Temporary family housing**, as defined herein, subject to the requirements of Section 431 of this Ordinance.
 - h. **Family child-care homes**, as defined herein subject to the requirements of Section 421 of this Ordinance.
 - i. **Farm occupations**, as defined herein, if conducted as an accessory use to a principal agricultural use of the property with a minimum of ten (10) acres, and subject to the requirements of Section 433 of this Ordinance.
 - j. **Fences and walls**, subject to the requirements of Section 435 of this Ordinance.
 - k. **Freestanding communication antennas, towers and equipment**, subject to a Special Exception as an accessory use pursuant to the requirements of Section 438 of this Ordinance.
 - l. **Garage, yard, and/or moving sales**, subject to the requirements of Section 440 of this Ordinance.

- m. **Garages and sheds for the storage of personal vehicles and or personal property**, attached or detached to the dwelling unit.
- n. **Gardening and raising of plants for personal use.**
- o. **Home occupations**, as defined herein, subject to the requirements of Section 448 of this Ordinance.
- p. **Man-made lakes, dams, ponds, and impoundments**, subject to the requirements of Section 453 of this Ordinance.
- q. **Manure storage facilities**, as an accessory use to an agricultural or horticultural use if contained upon a farm, subject to the requirements of Section 455 of this Ordinance.
- r. **No-impact home-based business**, as defined herein.
- s. **Noncommercial keeping of livestock**, as defined herein, subject to the requirements of Section 462 of this Ordinance.
- t. **Ornamental ponds and wading pools** subject to the requirements of Section 464 of this Ordinance.
- u. **Outdoor residential athletic courts** (e.g. basketball, boccie, handball, tennis, volleyball, etc.) subject to the requirements of Section 466 of this Ordinance.
- v. **Outdoor shooting range (private)** subject to the requirements of Section 467 of this Ordinance.
- w. **Parking and/or storage of recreation vehicles and personal cargo trailers**, subject to the requirements of Section 468 of this Ordinance.
- x. **Play structures**, as defined herein, provided such structures are confined to the side or rear yard and are located no closer than fifteen feet (15') from the closest side and or rear lot line.
- y. **Residential Short-Term Rental**, only conducted as an accessory use to a principal residential use of the property, and subject to the requirements of Section 465 of this Ordinance.
- z. **Residential swimming pools**, subject to the requirements of Section 475 of this Ordinance.
- aa. **Roadside stands** for the seasonal sale of agricultural products subject to the requirements of Section 477 of this Ordinance.
- bb. **Rural occupations**, as defined herein, subject to the requirements of Section 479 of this Ordinance.
- cc. **Satellite dish antennas**, subject to the requirements of Section 481 of this Ordinance.
- dd. **Signs** as defined herein, subject to the requirements of Section 322 of this Ordinance.

201.C. PRINCIPAL USES PERMITTED BY SPECIAL EXCEPTION (Subject to the review procedures of Section 704.C. of this Ordinance).

- 1. **Bed and breakfasts**, subject to the requirements of Section 412 of this Ordinance.
- 2. **Commercial produce operations**, as defined herein, subject to the requirements of Section 422 of this Ordinance.

3. **Freestanding communication antennas, towers and equipment**, subject to a Special Exception as an accessory use pursuant to the requirements of Section 438 of this Ordinance.
4. **Golf courses and driving ranges**, subject to the requirements of Section 441 of this Ordinance.
5. **Historic structure conversions**, subject to the requirements of Section 446 of this Ordinance.
6. **Kennels**, subject to the requirements of Section 452 of this Ordinance.
7. **Riding stables**, subject to the requirements of Section 476 of this Ordinance.
8. **Sale of compost, mulch, woodchips and coal**, subject to the requirements of Section 480 of this Ordinance.
9. **Two-family conversions**, subject to the requirements of Section 488 of this Ordinance.

201.D. PRINCIPAL USES PERMITTED BY CONDITIONAL USE (Subject to the review procedures of Section 805 of this Ordinance).

1. **Fish hatcheries and/or fish farms**, subject to the requirements of Section 436 of this Ordinance.
2. **Outdoor shooting ranges (public)**, subject to the requirements of Section 467 of this Ordinance.
3. **Sawmills**, subject to the requirements of Section 482 of this Ordinance.
4. **Schools, private and public**, subject to the requirements of Section 472 of this Ordinance.

201.E. SITE PLANNING OBJECTIVES

To enhance compatibility between proposed residential development and adjoining natural features, applications shall furnish evidence that the following specific design objectives have been satisfied through the design of the proposed use:

1. Minimize the loss of valuable farmland and maximize the protection of Class I, II and III soils as identified in the soil survey;
2. Cluster residential lots on the subject property and, if applicable, with those lots contained on adjoining farms;
3. Minimize the length of property lines shared by all residential lots and adjoining farms; and,
4. Assure adequate vehicular access to future residences not currently proposed.

201.F. DRIVEWAYS AND ACCESS DRIVES

All driveways serving single-family dwellings shall be in accordance with Section 305 of this Ordinance. All access drives serving other uses shall be in accordance with Section 301 of this Ordinance. All lanes exclusively serving agriculture, horticulture and/or forestry-related uses shall be exempt from driveway and access drive requirements in Sections 305 and 301, respectively, except those related to the clear-sight triangle listed in Section 305.C. of this Ordinance.

201.G. AGRICULTURAL NUISANCE DISCLAIMER

All lands within the Agricultural Zone are located within an area used for commercial agricultural production. Owners, residents and other users of property within this Zone may be subjected to inconvenience, discomfort and the possibility of injury to property and health arising from normal and accepted agricultural practices and operations, including, but not limited to, noise, odors, dust, the operation of machinery of any kind, including aircraft, the storage and disposal of manure, the application of fertilizers, soil amendments, herbicides, and pesticides. Owners, occupants and users of this property should be prepared to accept such inconveniences, discomfort and possibility of injury from normal agricultural operations, and are hereby put on official notice that Section 4 of Pennsylvania Act 133 of 1982, "The Right to Farm Law," and the Agriculture Communities and Rural Environment (ACRE), PA Act 38 of 2005, may bar them from obtaining a legal judgment against such normal agricultural operations. From the effective date of this Ordinance, all subsequent subdivision plans submitted within the (A) Zone shall require a note which duplicates this section, and which must be transferred to the purchaser by the seller.

201.H. VEGETATION SETBACK REQUIREMENT

Except in the case of required riparian buffers under Section 511 of this Ordinance, on any separate non-farm parcel, no shrub nor tree shall be planted within ten feet (10') and thirty feet (30'), respectively, of any land used for agricultural purposes.

201.I. GENERAL PROVISIONS

All uses permitted within this Zone shall also comply with the applicable General Provisions in Article 3 of this Ordinance.

201.J. ENVIRONMENTAL PROTECTION STANDARDS

All uses permitted within this Zone shall also comply with the applicable Environmental Protection Standards contained within Article 5 of this Ordinance.

201.K. AREA & DESIGN REQUIREMENTS WITHIN THE (A) ZONE

All uses within the Agricultural Zone shall comply with those standards listed in the following Figure 201.K.

FIGURE 201.K. AREA & DESIGN REQUIREMENTS WITHIN THE (A) ZONE								
Use	Minimum Required Lot Area	Minimum Required Lot Width		Required Minimum Yard Setbacks			Maximum Permitted Impervious Lot Coverage	Maximum Permitted Height
		At Building Setback	At Lot Frontage	Front	Each Side	Rear		
Agriculture, and horticulture uses ^{1,2}	None	200 ft.	200 ft.	50 ft.	50 ft.	50 ft.	10%	150 ft., provided each structure is set back a distance at least equal to its height from each property line.
Municipal and governmental uses ²	None	None	None	None	None	None	60%	Unlimited
Single-family detached dwellings ²	2 acres	150 ft.	150 ft.	35 ft.	25 ft.	35 ft.	20%	35 ft.
Forestry and other principal uses ²	2 acres	150 ft.	150 ft.	50 ft.	50 ft.	50 ft.	20%	35 ft.
Residential accessory uses	Included in above	N/A	N/A	Not permitted in front yard, unless a minimum 50 ft. setback is provided.	Structures up to 400 sq. ft.		Included in above	20 ft.
					10 ft.	10 ft.		
					Structures exceeding 400 sq. ft.			
					Same as principal setback			

¹Special setback requirements - Except as provided for as follows, no new slaughter area, area for the storage or processing of garbage, agricultural byproducts or composted materials, structures for the cultivation of mushrooms shall be permitted within three hundred feet (300') of any adjoining property. The Zoning Hearing Board may, as a special exception, however, reduce the above special setback requirements where it is shown that, because of prevailing winds, unusual obstructions, topography, or other conditions, a lesser distance would protect adjoining lands from odor, dust or other hazards. In no case, however, shall the Zoning Hearing Board reduce the special setback requirement to less than one hundred feet (100'). The burden shall be upon the applicant to prove that a lesser distance would not be detrimental to the health, safety and general welfare of the community.

²All uses relying upon on-lot sewers shall comply with Section 323 of this Ordinance.

SECTION 202 – LOW DENSITY RESIDENTIAL ZONE (LDR)

202.A. PURPOSE OF ZONE

The purpose of this Zone is to accommodate low to medium density residential uses in areas with sufficient infrastructure to support such densities. Selected locations provide for the accommodation of future developments in accordance with the Township Comprehensive Plan and acknowledge the location of existing land uses with these suburban characteristics.

This Zone coincides with planned sewer and water utility service areas; contains an internal network of streets within a development; however, the actual availability of these services is likely to occur at different times, in different areas. As a result, permitted densities have been adjusted according to the availability of these public utilities.

202.B. PRINCIPAL USES PERMITTED BY RIGHT

1. **Agriculture and horticulture**, including one single-family detached dwelling contained on the site subject to the applicable requirements contained with 200.G. of this Ordinance. This use shall also expressly exclude **concentrated animal feeding operations (CAFOs)** and **concentrated animal operations (CAOs)** and **commercial produce operations**, all as defined herein.
2. **Forestry uses** subject to the requirements of Section 200.G. of this Ordinance.
3. **Single family detached dwellings.**
4. **Conservation design developments** subject to the requirements of Section 425 of this Ordinance.
5. **Municipal and governmental uses.**
6. **Parks and playgrounds.**
7. **Accessory uses customarily incidental to the principal uses in this zone**, including, but not limited to, the following:
 - a. **Alternative energy systems**, subject to the requirements of Section 404 of this Ordinance.
 - b. **Co-located communication antennas upon existing structures**, subject to the requirements of Section 420 of this Ordinance.
 - c. **Composting**, subject to the requirements of Section 428 of this Ordinance.
 - d. **Domestic pets**, subject to the requirements of Section 406 of this Ordinance.
 - e. **Temporary family housing**, as defined herein, subject to the requirements of Section 431 of this Ordinance.
 - f. **Family child-care homes**, as defined herein subject to the requirements of Section 421 of this Ordinance.
 - g. **Fences and walls**, subject to the requirements of Section 435 of this Ordinance.
 - h. **Garage yard and/or moving sales**, subject to the requirements of Section 440 of this Ordinance.
 - i. **Garages and sheds for the storage of personal vehicles and or personal property**, attached or detached to the dwelling unit.

- j. **Gardening and raising of plants for personal use.**
- k. **Home occupations**, as defined herein, subject to the requirements of Section 448 of this Ordinance.
- l. **Man-made lakes, dams, ponds, and impoundments**, subject to the requirements of Section 453 of this Ordinance.
- m. **No-impact home-based business**, as defined herein.
- n. **Noncommercial keeping of livestock**, as defined herein, subject to the requirements of Section 462 of this Ordinance.
- o. **Ornamental ponds and wading pools** subject to the requirements of Section 464 of this Ordinance.
- p. **Outdoor residential athletic courts** (e.g. basketball, bocci, handball, tennis, volleyball, etc.) subject to the requirements of Section 466 of this Ordinance.
- q. **Parking and/or storage of recreation vehicles and personal cargo trailers**, subject to the requirements of Section 468 of this Ordinance.
- r. **Play structures**, as defined herein, provided such structures are confined to the side or rear yard and are located no closer than fifteen feet (15') from the closest side and or rear lot line.
- s. **Residential swimming pools**, subject to the requirements of Section 475 of this Ordinance.
- t. **Satellite dish antennas**, subject to the requirements of Section 481 of this Ordinance.
- u. **Signs** as defined herein, subject to the requirements of Section 322 of this Ordinance.

202.C. PRINCIPAL USES PERMITTED BY SPECIAL EXCEPTION (Subject to the review procedures of Section 704.C. of this Ordinance).

- 1. **Bed and breakfasts**, subject to the requirements of Section 412 of this Ordinance.
- 2. **Golf courses and driving ranges**, subject to the requirements of Section 441 of this Ordinance.
- 3. **Historic structure conversions**, subject to the requirements of Section 446 of this Ordinance.
- 4. **Two-family conversions**, subject to the requirements of Section 488 of this Ordinance.

202.D. PRINCIPAL USES PERMITTED BY CONDITIONAL USE (Subject to the review procedures of Section 805 of this Ordinance).

- 1. **Schools, including only private and public**, subject to the requirements of Section 472 of this Ordinance.

202.E. DRIVEWAYS AND ACCESS DRIVES

All driveways serving single-family dwellings shall be in accordance with Section 305 of this Ordinance. All access drives serving other uses shall be in accordance with Section 301 of this Ordinance. All lanes exclusively serving agriculture, horticulture and/or forestry-related uses shall be exempt from driveway and access drive requirements in Sections 305 and 301, respectively, except those related to the clear-sight triangle listed in Section 305.C. of this Ordinance.

202.F. GENERAL PROVISIONS

All uses permitted within this Zone shall also comply with the applicable General Provisions in Article 3 of this Ordinance.

202.G. ENVIRONMENTAL PROTECTION STANDARDS

All uses permitted within this Zone shall also comply with the applicable Environmental Protection Standards contained within Article 5 of this Ordinance.

202.H. SIDEWALKS AND PEDESTRIAN ACCESS

All uses permitted within this Zone shall also comply with the applicable sidewalk requirements contained within Section 509 of the SALDO.

202.I. AGRICULTURAL NUISANCE DISCLAIMER

As a rural municipality many lands within the Township are located within an area used for commercial agricultural production. Owners, residents and other users of property within this Zone may be subjected to inconvenience, discomfort and the possibility of injury to property and health arising from normal and accepted agricultural practices and operations, including, but not limited to, noise, odors, dust, the operation of machinery of any kind, including aircraft, the storage and disposal of manure, the application of fertilizers, soil amendments, herbicides, and pesticides. Owners, occupants and users of this property should be prepared to accept such inconveniences, discomfort and possibility of injury from normal agricultural operations, and are hereby put on official notice that Section 4 of Pennsylvania Act 133 of 1982, "The Right to Farm Law," and the Agriculture Communities and Rural Environment (ACRE), PA Act 38 of 2005, may bar them from obtaining a legal judgment against such normal agricultural operations. From the effective date of this Ordinance, all subsequent subdivision plans submitted within this Zone shall require a note which duplicates this section and which must be transferred to the purchaser by the seller.

202.J. AREA & DESIGN REQUIREMENTS WITHIN THE (LDR) ZONE – All uses within the Low-Density Residential Zone shall comply with those standards listed in the following Figure 210.J.

FIGURE 202.J. AREA & DESIGN REQUIREMENTS WITHIN THE (LDR) ZONE								
Use	Minimum Required Lot Area	Minimum Required Lot Width		Required Minimum Yard Setbacks			Maximum Permitted Impervious Lot Coverage	Maximum Permitted Height
		At Building Setback	At Lot Frontage	Front	Each Side	Rear		
Municipal and governmental uses	None	None	None	None	None	None	60%	Unlimited
Single-family detached dwellings with on-lot sewer and/or on-lot water. ¹	1 acre	150 ft.	150 ft.	35 ft.	25 ft.	35 ft.	25%	35 ft.
Single-family detached dwellings with public sewer and/or public water. ¹	½ acre	100 ft.	100 ft.	35 ft.	25 ft.	35 ft.	25%	35 ft.
Other principal uses ¹	1 acre	150 ft.	150 ft.	35 ft.	25 ft.	35 ft.	25%	35 ft.
Residential accessory structures	Included in above	N/A	N/A	Not permitted in front yard, unless a minimum 100 ft. setback is provided.	Structures up to 400 sq. ft.		Included in above	20 ft.
					10 ft.	10 ft.		
					Structures exceeding 400 sq. ft.			
					Same as principal setback			

¹All uses relying upon on-lot sewers shall comply with Section 323 of this Ordinance.

SECTION 203 – MIXED USE ZONE (MU)

203.A. PURPOSE OF ZONE

The purpose of this Zone is to accommodate locally-oriented businesses and offices as in-fill developments amid the Township's established neighborhoods. This Zone accommodates a wide range of housing types with the use of public utilities in accordance with the Township Comprehensive Plan and Official Sewage Plan. Limited businesses have been selected that can take advantage of the daily traffic passing upon adjoining roads, while at the same time assure compatibility with the numerous dwellings that remain.

203.B. PRINCIPAL USES PERMITTED BY RIGHT

1. **Agriculture and horticulture**, including one single-family detached dwelling contained on the site subject to the applicable requirements contained with 200.G. of this Ordinance. This use shall also expressly exclude **concentrated animal feeding operations (CAFOs)** and **concentrated animal operations (CAOs)** and **commercial produce operations**, all as defined herein.
2. **Dance, music, art, fashion and photographic studios and galleries.**
3. **Forestry uses** subject to the requirement of Sections 200.G. of this Ordinance.
4. **Financial institutions.**
5. **Conservation design developments** subject to the requirements of Section 425 of this Ordinance.
6. **Single family detached dwellings.**
7. **Duplex and two-family dwellings**, with either public sewer or public water or with both public utilities.
8. **Two-family conversions**, as defined herein and subject to the requirements of Section 488 of this Ordinance.
9. **Townhouses**, with both public sewer and public water.
10. **Medical offices.**
11. **Multi-family dwellings**, with both public sewer and public water.
12. **Municipal and governmental uses.**
13. **Offices.**
14. **Personal services**, including: barber and beauty or tanning salons; dry cleaning and laundry pick-up/drop-off facilities tailor shops, shoe repair shops; music, art or photographic studios and repair of clocks, electronics, computers and small appliances. Dry-cleaning, laundries and laundromats shall be subject to the requirements of Section 430 of this Ordinance.
15. **Parks and playgrounds.**
16. **Public utilities structures**, subject to the requirements of Section 405 of this Ordinance.
17. **Retail sale, rental and/or repair of goods.** Permitted uses include, without limitation, the below listed. This use shall expressly exclude adult entertainment uses, casinos, off-track betting, and gaming facilities.
 - a. Card, stationery, magazine, book, or newspapers, excluding adult uses as defined herein;
 - b. Prerecorded music, video, or spoken word products;

- c. Beverages (excluding any alcoholic beverages);
 - d. Sporting goods;
 - e. Musical instruments;
 - f. Tobacco and smoking accessories supplies;
 - g. Domestic hardware and 5 & 10¢ items;
 - h. Photographic, video, audio, and electronic components and accessories;
 - i. Clothing and shoes;
 - j. Flower, balloon and gifts;
 - k. Pets and supplies with proper licensure;
 - l. Jewelry, watches, clocks;
 - m. Art and drafting supplies;
 - n. Computers, software, training and other office supplies;
 - o. Craft supplies, baskets, fabrics, and other notions;
 - p. Toy and hobby supplies;
 - q. Telephone, vacuum cleaner and other domestic appliances;
 - r. Prosthetic and therapy devices and supplies;
 - s. Drugstore, perfumes, soaps, lotions, powders, and similar items;
 - t. Draperies, wallpaper and rugs;
 - u. Bed and bath supplies;
 - v. Kitchenware, cookware and dinnerware;
 - w. Caterers, bakers, and confectioners (including items made on site);
 - x. Eyeglass and hearing aid showrooms and offices;
 - y. Specialty food stores and grocerettes;
 - z. Religious articles and artifacts; and,
 - aa. Antique, thrift and pawn shops.
18. **Cemeteries, including but not limited to pet cemeteries.**
19. **Churches and related uses**, subject to the requirements of Section 419 of this Ordinance.
20. **Veterinary offices/Animal hospital**, subject to the requirements of Section 407 of this Ordinance.
21. **Accessory uses customarily incidental to the principal uses in this zone**, including, but not limited to, the following:
- a. **Alternative energy systems**, subject to the requirements of Section 404 of this Ordinance.
 - b. **Co-located communication antennas upon existing structures**, subject to the requirements of Section 420 of this Ordinance.
 - c. **Composting**, subject to the requirements of Section 428 of this Ordinance.
 - d. **Domestic pets**, subject to the requirements of Section 406 of this Ordinance.

- e. **Temporary family housing**, as defined herein, subject to the requirements of Section 431 of this Ordinance.
- f. **Family child-care homes**, as defined herein subject to the requirements of Section 421 of this Ordinance.
- g. **Farm occupations**, as defined herein, if conducted as an accessory use to a principal agricultural use of the property with a minimum of ten (10) acres, and subject to the requirements of Section 433 of this Ordinance.
- h. **Fences and walls**, subject to the requirements of Section 435 of this Ordinance.
- i. **Garage yard and/or moving sales**, subject to the requirements of Section 440 of this Ordinance.
- j. **Garages and sheds for the storage of personal vehicles and or personal property**, attached or detached to the dwelling unit.
- k. **Gardening and raising of plants for personal use.**
- l. **Home occupations**, as defined herein, subject to the requirements of Section 448 of this Ordinance.
- m. **Man-made lakes, dams, ponds, and impoundments**, subject to the requirements of Section 453 of this Ordinance.
- n. **No-impact home-based business**, as defined herein.
- o. **Noncommercial keeping of livestock**, as defined herein, subject to the requirements of Section 462 of this Ordinance.
- p. **Ornamental ponds and wading pools** subject to the requirements of Section 464 of this Ordinance.
- q. **Outdoor residential athletic courts** (e.g. basketball, boccie, handball, tennis, volleyball, etc.) subject to the requirements of Section 466 of this Ordinance.
- r. **Outdoor shooting range (private)** subject to the requirements of Section 467 of this Ordinance.
- s. **Parking and/or storage of recreation vehicles and personal cargo trailers**, subject to the requirements of Section 468 of this Ordinance.
- t. **Play structures**, as defined herein, provided such structures are confined to the side or rear yard and are located no closer than fifteen feet (15') from the closest side and or rear lot line.
- u. **Residential Short-Term Rental**, only conducted as an accessory use to a principal residential use of the property, and subject to the requirements of Section 465 of this Ordinance.
- v. **Residential swimming pools**, subject to the requirements of Section 475 of this Ordinance.
- w. **Rural occupations**, as defined herein, subject to the requirements of Section 479 of this Ordinance.
- x. **Satellite dish antennas**, subject to the requirements of Section 481 of this Ordinance.
- y. **Signs** as defined herein, subject to the requirements of Section 322 of this Ordinance.

203.C. PRINCIPAL USES PERMITTED BY SPECIAL EXCEPTION (Subject to the review procedures of Section 704.C. of this Ordinance).

1. **Bed and breakfasts**, as defined herein, subject to the requirements of Section 412 of this Ordinance.
2. **Funeral homes**, subject to the requirements of Section and 439 of this Ordinance.
3. **Golf courses and driving ranges**, subject to the requirements of Section 441 of this Ordinance.
4. **Group homes**, subject to the requirements of Section 432 of this Ordinance.
5. **Health, fitness, social, fraternal and other private clubs**, subject to the requirements of Section 442 of this Ordinance.
6. **Historic structure conversions**, subject to the requirements of Section 446 of this Ordinance.
7. **Group child-care homes and child-care centers**, subject to the requirements of Section 421 of this Ordinance.
8. **Nursing, rest or retirement homes**, subject to the requirements of Section 463 of this Ordinance.
9. **Riding stables**, subject to the requirements of Section 476 of this Ordinance.

203.D. PRINCIPAL USES PERMITTED BY CONDITIONAL USE (Subject to the review procedures of Section 805 of this Ordinance):

1. **Boarding houses**, subject to the requirements of Section 415 of this Ordinance.
2. **Entertainment facilities**, subject to the requirements of Section 461 of this Ordinance. This use shall expressly exclude off-track betting and/or slot machine parlors, casinos, shooting ranges and adult entertainment uses.
3. **Medical residential campuses**, subject to the requirements of Section 457 of this Ordinance.
4. **Mobile home parks**, subject to the requirements of Section 454 of this Ordinance.
5. **Outdoor shooting ranges (public)**, subject to the requirements of Section 467 of this Ordinance.
6. **Restaurants**, subject to the requirements of Section 429 of this Ordinance.
7. **Schools, public, private and commercial**, subject to the requirements of Section 472 of this Ordinance.
8. **Solar farms (specifically excluding wind farms)**, subject to the requirements of Section 490 of this Ordinance.

203.E. NUMBER OF USES

1. Any number of the uses allowed in this Zone are permitted within each existing building, provided the building size and floor area remain the same as it was on the effective date of this Ordinance and Section 306 of this Ordinance shall not apply in this instance.
2. For new buildings, Section 306 of this Ordinance shall apply in this instance.
3. For existing buildings that are enlarged, the number of uses permitted per building shall be the same number (at least one) that occupied the building on the effective date of this Ordinance and Section 306 of this Ordinance shall not apply in this instance.

203.F. RESIDENTIAL ACCESSORY USE SETBACKS

1. Accessory structures with up to four hundred (400) square feet shall be setback at least ten feet (10') from each side and rear lot line. No accessory buildings are permitted within the front yard unless they are at least one hundred feet (100') from the street right-of-way.
2. Accessory structures with more than four hundred (400) square feet shall comply with the applicable principal use setbacks listed in the following Section 203.G. of this Ordinance.

203.G. AREA & DESIGN REQUIREMENTS WITHIN THE (MU) ZONE

All uses within the (MU) Zone shall comply with those standards listed in the following table and footnotes:

§ 203.G. AREA & DESIGN REQUIREMENTS WITHIN THE (MU) ZONE							
Use	Minimum Lot Area	Minimum Lot Width at Building Setback Line & Frontage	Maximum Lot Coverage	Minimum Yard Setbacks			Maximum Permitted Height
				Front	Each Side	Rear	
Uses permitted with on-lot sewers¹ and on-lot water							
Single family detached unit	1 acre	150 / 150 ft.	25%	35 ft.	15 ft.	30 ft.	35 ft.
Other principal uses	1 acre	150 / 150 ft.	25%	35 ft.	15 ft.	30 ft.	35 ft.
Uses permitted with public water and on-lot sewer¹							
Single family detached unit	1 acre	100 / 100 ft.	35%	35 ft.	12 ft.	30 ft.	35 ft.
Duplex	1 acre / unit	100 / 100 ft.	35%	35 ft.	20 ft.	30 ft.	35 ft.
Two-family dwellings	60,000 sq. ft.	100 / 100 ft.	35%	35 ft.	12 ft.	30 ft.	35 ft.
Other principal uses	1 acre	100 / 100 ft.	35%	35 ft.	12 ft.	30 ft.	35 ft.
Uses permitted with on-lot water and public sewer							
Single family detached unit	20,000 sq. ft.	75 / 75 ft.	45%	35 ft.	10 ft.	30 ft.	35 ft.
Duplex	20,000 sq. ft.	75 / 75 ft.	45%	35 ft.	15 ft.	30 ft.	35 ft.
Two-family dwellings	60,000 sq. ft.	75 / 75 ft.	45%	35 ft.	10 ft.	30 ft.	35 ft.
Other principal uses	30,000 sq. ft.	75 / 75 ft.	45%	35 ft.	10 ft.	30 ft.	35 ft.
Uses permitted with public water and public sewer							
Single family detached unit	15,000 sq. ft.	60 / 60 ft.	50%	35 ft.	10 ft.	30 ft.	35 ft.
Duplex	15,000 sq. ft.	50 / 60 ft.	50%	35 ft.	10 ft.	30 ft.	35 ft.
Two-family dwellings	30,000 sq. ft.	60 / 60 ft.	50%	35 ft.	10 ft.	30 ft.	35 ft.
Townhouses ^{2,3,4}	2,500 sq. ft./unit	20 ft. / 20ft.	55%	20 ft.	10 ft.	20 ft.	35 ft.
Multi-family dwellings ^{2,3,4}	15,000 sq. ft.	60 / 60 ft.	50%	35 ft.	10 ft.	20 ft.	30 ft.
Other principal uses	30,000 sq. ft.	60 / 60 ft.	50%	35 ft.	10 ft.	30 ft.	35 ft.
Residential accessory structures	Included in above	N/A	Included in above	Not permitted in front yard, unless a minimum 100 ft. setback is provided.	Structures up to 400 sq. ft.		20 ft.
					10 ft.	10 ft.	
					Structures exceeding 400 sq. ft.		
					Same as principal setback		
<p>¹All uses relying upon on-lot sewers shall comply with Section 323 of this Ordinance.</p> <p>²Townhouses and multi-family dwellings shall not exceed a permitted density of six dwelling units per acre. Any residual common open space must comply with applicable sections of this Ordinance.</p> <p>³No townhouse building shall contain more than six (6) units. For each townhouse building containing more than four (4) units, no more than sixty-six percent (66%) of such units shall have the same front yard setback; the minimum variation of setback shall be two feet (2'). In addition, no more than two (2) contiguous units shall have identical roof lines that generally parallel the ground along the same horizontal plane. All townhouse buildings shall be set back a minimum of fifteen feet (15') from any interior access drives, or parking facilities contained on commonly-held lands. All townhouse buildings shall be set back at least thirty feet (30') from any perimeter boundary of the development site. In those instances where several townhouse buildings are located on the same lot, the following footnote 4 shall apply.</p> <p>⁴ In those instances where several multiple-family dwelling buildings and/or townhouse buildings are located on the same lot, the following separation distances will</p>							

be provided between each building:

- a. Front to front, rear to rear, or front to rear, parallel buildings shall have at least fifty feet (50') between faces of the building. If the front or rear faces are obliquely aligned, the above distances may be decreased by as much as ten feet (10') at one end if increased by similar or greater distance at the other end.
- b. A minimum yard space of thirty feet (30') is required between end walls of buildings. If the buildings are at right angles to each other, the distance between the corners of the end walls of the building may be reduced to a minimum of twenty feet (20').
- c. A minimum yard space of thirty feet (30') is required between end walls and front or rear faces of buildings.
- d. All multiple-family dwelling buildings shall be set back a minimum of fifteen feet (15') from any interior access drives or parking facilities contained on commonly-held lands.

203.H. DRIVEWAYS AND ACCESS DRIVES

All driveways serving single-family dwellings shall be in accordance with Section 305 of this Ordinance. All access drives serving other uses shall be in accordance with Section 301 of this Ordinance. All lanes exclusively serving agriculture, horticulture and/or forestry-related uses shall be exempt from driveway and access drive requirements in Sections 305 and 301, respectively, except those related to the clear-sight triangle listed in Section 305.C. of this Ordinance.

203.I. GENERAL PROVISIONS

All uses permitted within this Zone shall also comply with the applicable General Provisions in Article 3 of this Ordinance.

203.J. ENVIRONMENTAL PROTECTION STANDARDS

All uses permitted within this Zone shall also comply with the applicable Environmental Protection Standards contained within Article 5 of this Ordinance.

203.K. SIDEWALKS AND PEDESTRIAN ACCESS

All uses permitted within this Zone shall also comply with the applicable sidewalk requirements contained within Section 510 of the SALDO.

203.L. SCREENING

Any nonresidential use in the (MU) Zone shall provide for a visual screen along any adjoining lands containing an existing residential use (see Section 321 of this Ordinance).

203.M. LANDSCAPING

Any portion of the site not used for buildings, structures, off-street parking lots, off-street loading spaces, outdoor storage areas, and sidewalks shall be maintained with a vegetative ground cover and other ornamental plantings (see Section 321 of this Ordinance). A minimum five foot (5') wide landscape strip shall be provided along all property lines. Such landscape strip shall only be required where the adjoining lands contain an existing residential use.

SECTION 204 – MINING INDUSTRIAL ZONE (MI)

204.A. PURPOSE OF ZONE

This Zone provides key locations for a mix of limited mining and industrial uses that rely upon or benefit from a rural location. It also provides a remote location for particular uses, which because of their impacts, will be separated from concentrations of population. Five acre individual lot sizes are required and lot coverage is limited to respect the sensitive character of this landscape. Design standards have been imposed to create attractive site designs and moderate the objectionable impacts associated with industrial uses. Substantial setbacks and vegetative buffers and screens are used to protect adjoining residential zones.

204.B. PRINCIPAL USES PERMITTED BY RIGHT

1. **Agriculture and horticulture**, including one single-family detached dwelling contained on the site subject to the applicable requirements contained with 200.G. of this Ordinance. This use shall also expressly exclude **concentrated animal feeding operations (CAFOs)** and **concentrated animal operations (CAOs)** and **commercial produce operations**, all as defined herein.
2. **Group child-care homes and child-care centers**, subject to the requirements of Section 421 of this Ordinance.
3. **Commercial greenhouses.**
4. **Forestry uses** subject to the requirements of Section 200.G. of this Ordinance.
5. **Machine, tool and die, and metal fabrication shops;**
6. **Municipal and governmental uses**, as defined herein.
7. **Offices.**
8. **Parks and playgrounds.**
9. **Public utilities structures**, subject to the requirements of Section 405 of this Ordinance.
10. **Shops, offices and showrooms for contractors** of painting, power-washing, plumbing, heating, air conditioning, electrical, electronic, telephone, antennas and cable, communications, roofing, flooring, drywall and plaster, basement waterproofing, carpet, countertops, glass and windows, insulation, gutters and downspouts, well drilling and septic system installation, maintenance and pumping, woodworking, carpentry and cabinet-making, swimming pools, hot tubs and spas, lawn care and landscaping, masonry, concrete and paving, pest control and snow removal.
11. **Sign makers.**
12. **Single family detached dwellings** including residential accessory uses as found in Section 201B.9 which are clearly incidental to a residential dwelling.
13. **Veterinary offices/Animal hospitals.**
14. **Schools, vocational or technical.**
15. **Welding shops.**
16. **Accessory uses customarily incidental to the principal uses in this zone**, including accessory retail sales of products produced on-site so long as the sales area is no more than ten percent (10%) of the total building area or three thousand (3,000) square feet, whichever is less;
 - a. **Alternate energy production facilities** subject to the requirements of Section 404 of this Ordinance.

- b. **Athletic fields and courts and recreation facilities.**
- c. **Co-located communication antennas upon existing structures**, subject to the requirements of Section 420 of this Ordinance.
- d. **Domestic pets**, subject to the requirements of Section 406 of this Ordinance.
- e. **Fences and walls**, subject to the requirements of Section 435 of this Ordinance.
- f. **Freestanding communication antennas, towers and equipment**, subject to a Special Exception as an accessory use pursuant to the requirements of Section 438 of this Ordinance.
- g. **Helicopter pad, private**, subject to a Special Exception as an accessory use pursuant to the requirements of Section 445 of this Ordinance
- h. **Man-made lakes, dams, ponds, and impoundments**, subject to the requirements of Section 453 of this Ordinance
- i. **Ornamental ponds and wading pools** subject to the requirements of Section 464 of this Ordinance.
- j. **Recycling collection facilities as an accessory use**, provided such facilities are sufficiently enclosed to prevent the scattering of debris, the materials collected are removed at regular intervals, the facility is posted to prohibit the disposal of any material, good or furnishing that cannot be placed within the actual recycling bin, and the total size of the facility is less than three hundred (300) square feet.
- k. **Residential Short-Term Rental**, only conducted as an accessory use to a principal residential use of the property, and subject to the requirements of Section 465 of this Ordinance.
- l. **Satellite dish antennas**, subject to the requirements of Section 481 of this Ordinance.
- m. **Signs** as defined herein, subject to the requirements of Section 322 of this Ordinance.

204.C. PRINCIPAL USES PERMITTED BY SPECIAL EXCEPTION (Subject to the review procedures of Section 704.C. of this Ordinance).

- 1. **Freestanding communication antennas, towers and equipment**, subject to a Special Exception as an accessory use pursuant to the requirements of Section 438 of this Ordinance.
- 2. **Group homes**, subject to the requirements of Section 432 of this Ordinance.
- 3. **Helicopter pad, private**, subject to a Special Exception as an accessory use pursuant to the requirements of Section 445 of this Ordinance;
- 4. **Heavy industrial uses as defined herein**, subject to the requirements of Section 444 of this Ordinance.
- 5. **Historic structure conversions**, subject to the requirements of Section 446 of this Ordinance.
- 6. **Recycling facilities for electronics, paper, plastic, glass and metal products**, subject to the requirements of Section 474 of this Ordinance.
- 7. **Sale of compost, mulch, woodchips and coal** subject to the requirements of Section 480 of this Ordinance.

204.D. PRINCIPAL USES PERMITTED BY CONDITIONAL USE (Subject to the review procedures of Section 805 of this Ordinance).

1. **Adult entertainment uses**, subject to the requirements of Section 402 of this Ordinance.
2. **Airports and heliports**, subject to the requirements of Section 403 of this Ordinance.
3. **Automobile and/or animal racing facility with or without related wagering** subject to the requirements of Section 409 of this Ordinance;
4. **Junkyards**, subject to the requirements of Section 450 of this Ordinance.
5. **Methadone treatment facilities**, subject to the requirements of Section 458 of this Ordinance
6. **Mining, quarrying and related processing operations**, subject to the requirements of Section 459 of this Ordinance.
7. **Sawmills**, subject to the requirements of Section 482 of this Ordinance.
8. **Septage and compost processing and/or commercial mushroom operations**, subject to the requirements of Section 483 of this Ordinance.
9. **Slaughtering, processing, rendering and packaging of food products and their byproducts**, subject to the requirements of Section 485 of this Ordinance.

204.E. LOT AREA, LOT WIDTH, AND LOT COVERAGE REQUIREMENTS - See the following table:

Minimum Lot Area	Minimum Lot Width	Maximum Lot Coverage
5 acres	250 ft.	60%

204.F. MINIMUM SETBACK REQUIREMENTS (Principal and Accessory Uses)

1. **Front yard setback** – All buildings, structures (except permitted signs) shall be set back at least fifty feet (50') from the street right-of-way; off-street parking lots and outdoor storage and display areas shall be set back a minimum of twenty-five feet (25') feet from the street right-of-way.
2. **Side yard setbacks** – All buildings and structures (except permitted signs) shall be set back at least fifty feet (50') from the side lot lines. Off-street parking lots, off-street loading spaces, and outdoor storage and display areas shall be set back at least twenty-five feet (25') from the side lot lines, unless joint off-street parking lots and/or off-street loading spaces are shared by adjoining uses. In such instances, the side yard setbacks are eliminated solely to accommodate the shared off-street parking lots and/or off-street loading spaces.
3. **Rear yard setback** – All buildings, structures, and outdoor storage and display areas shall be set back at least fifty feet (50') from the rear lot line. Off-street parking lots, and off-street loading spaces shall be set back at least twenty-five feet (25') from the rear lot line, unless joint off-street parking lots and/or off-street loading spaces are shared by adjoining uses. In such instances, the rear yard setback is eliminated solely to accommodate the shared off-street parking lots and/or off-street loading spaces.
4. **Residential buffer strip** – Any lot adjoining land within an (LDR, MU, A or C) Zone shall maintain a one hundred (100') foot setback for nonresidential buildings, structures, off-street parking lots, loading areas and outdoor storage and display areas, from the (LDR, MU, A or C) Zone parcels. Such areas shall be improved with a landscape strip and screening in accordance with Sections 204.M. and 204.L., respectively, of this Ordinance.

204.G. HEIGHT REQUIREMENTS

Thirty-five feet (35'), provided a non-habitable structure may extend up to forty-five feet (45') if such structure is setback a horizontal distance at least equal to its height from each side and/or rear lot line.

204.H. OFF-STREET LOADING SPACES

Off-street loading spaces shall be provided as specified in Section 314 of this Ordinance.

204.I. OFF-STREET PARKING

Off-street parking shall be provided as specified in Section 315 of this Ordinance.

204.J. SIGNS

Signs shall be permitted as specified in Section 322 of this Ordinance.

204.K. ACCESS DRIVE REQUIREMENTS

All access drives shall be in accordance with Section 301 of this Ordinance.

204.L. SCREENING

A visual screen must be provided along any adjoining lands within an (LDR, MU, A or C) Zone, or any adjoining land containing an existing residential use, regardless of whether or not the (LDR, MU, A or C) Zone property is developed (see Section 321 of this Ordinance).

204.M. LANDSCAPING

Any portion of the site not used for buildings, structures, off-street parking lots, off-street loading spaces, outdoor storage areas, and sidewalks shall be maintained with a vegetative ground cover and other ornamental plantings (see Section 321 of this Ordinance). A minimum ten foot (10') wide landscape strip shall be provided along all property lines. Such landscape strip can be waived for that portion of the site occupied by a joint off-street parking lot and/or off-street loading space area shared by adjoining uses.

204.N. WASTE PRODUCTS

Dumpsters may be permitted within the side or rear yard, provided such dumpsters are screened from any adjoining roads or properties. All dumpsters shall be set back a minimum of fifty feet (50') from any adjoining (LDR & MU) Zone properties. All waste receptacles shall be completely enclosed within a masonry, wood or framed structures with a separate pedestrian access gate/door which is self-closing and another truck access gate that must be kept closed when not in use.

204.O. OUTDOOR STORAGE AND DISPLAY

Within this Zone, outdoor storage and display is permitted, provided all such areas are screened from adjoining roads and properties, and they comply with all of those setbacks specifically imposed thereon, listed in this section. The outdoor storage and display areas for vehicles sales need not be screened from adjoining roads. Section 317 of this Ordinance lists additional requirements.

204.P. GENERAL PROVISIONS

All uses permitted within this Zone shall also comply with the applicable General Provisions in Article 3 of this Ordinance.

204.Q. ENVIRONMENTAL PROTECTION STANDARDS

All uses permitted within this Zone shall also comply with the applicable Environmental Protection Standards contained within Article 5 of this Ordinance.

SECTION 205 – BUSINESS INDUSTRIAL ZONE (BI)

205.A. PURPOSE OF ZONE

This Zone provides key locations for a mix of various both light and heavier commercial and industrial business uses to diversify the Township's economy and offer valuable employment opportunities. This Zone will principally permit light and small-scale industries as permitted uses but require special exception or conditional use approval for larger uses that pose the potential for greater impact. Required lot sizes have been kept small to accommodate the start-up industries that are likely to emerge; however, larger industries have also been permitted. These areas have been located near existing public utility service areas, other industrial uses and along major roads. Design standards have been imposed to create attractive site designs and moderate the objectionable impacts associated with industrial uses. Substantial setbacks and vegetative buffers and screens are used to protect adjoining residential zones.

205.B. PRINCIPAL USES PERMITTED BY RIGHT

1. **Agriculture and horticulture**, including one single-family detached dwelling contained on the site subject to the applicable requirements contained with 200.G. of this Ordinance. This use shall also expressly exclude **concentrated animal feeding operations (CAFOs)** and **concentrated animal operations (CAOs)** and **commercial produce operations**, all as defined herein.
2. **Group child-care homes and child-care centers**, subject to the requirements of Section 421 of this Ordinance.
3. **Commercial greenhouses.**
4. **Convenience stores**, as defined herein and subject to the requirements of Section 426 of this Ordinance.
5. **Financial institutions.**
6. **Forestry uses** subject to the requirements of Section 200.G. of this Ordinance.
7. **Hotels, motels and similar lodging facilities.**
8. **Laboratories for medical, scientific, or industrial research and development.**
9. **Machine, tool and die, and metal fabrication shops;**
10. **Manufacturing, packaging, storage and/or wholesaling of the following:**
 - a. Furniture, cabinets, plumbing, heating, air conditioning, ventilation and electrical fixtures, ceramic, stone, vinyl, fiberglass and linoleum tiles, carpets and rugs, windows, doors, insulation, ceiling and roofing tiles, household appliances, finished lumber and other household appointments;
 - b. Scientific, medical, optical, specialized, and technical instruments and equipment;
 - c. Audio visual components, computers, vending machines, electronic equipment, software and video games;
 - d. Office equipment, supplies, furnishings, and equipment;
 - e. Packaging materials, supplies and equipment;
 - f. Finished textile products;
 - g. Bookbinding, printing, and publishing operations;
 - h. Cosmetics, drugs, dyes, toiletries, perfumes and other pharmaceuticals;
 - i. Brushes, brooms, and combs;

- j. Hot tubs, spas, saunas, and swimming pools;
 - k. Jewelry, and other precious or semi-precious metals and stones;
 - l. Photographic, lighting, and timekeeping equipment;
 - m. Hand tools, hardware, power tools and small engine equipment and vehicles including but not limited to lawn mowers, chain saws, compressors, power washing equipment, motorcycles, and outboard boat motors;
 - n. Musical instruments, sporting equipment, bicycles and toys; and,
 - o. Small or novelty products from prepared materials (excluding the use of sheet metals).
11. **Medical offices.**
12. **Municipal and governmental uses**, as defined herein.
13. **Offices.**
14. **Parks and playgrounds.**
15. **Personal services**, including: barber and beauty or tanning salons; dry cleaning and laundry pick-up/drop-off facilities tailor shops, shoe repair shops; music, art or photographic studios and repair of clocks, electronics, computers and small appliances. Dry-cleaning, laundries and laundromats shall be subject to the requirements of Section 430 of this Ordinance.
16. **Processing, packaging, bottling, storage and/or wholesaling of food products excluding:**
- a. Pickling processes;
 - b. Rendering or slaughtering operations; and,
 - c. Sugar refineries.
17. **Public utilities structures**, subject to the requirements of Section 405 of this Ordinance.
18. **Repair shops for products permitted to be manufactured in this Zone.**
19. **Restaurants**, subject to the requirements of Sections 203.J. and 429 of this Ordinance.
20. **Sales, storage and/or wholesaling of the following:**
- a. Home and auto-related fuels;
 - b. Nursery and garden materials, and stock;
 - c. Redi-mix concrete;
 - d. Contractor supplies; and,
 - e. Plumbing, heating, air conditioning, electrical, and other structural components of buildings.
21. **Shops, offices and showrooms for contractors** of painting, power-washing, plumbing, heating, air conditioning, electrical, electronic, telephone, antennas and cable, communications, roofing, flooring, drywall and plaster, basement waterproofing, carpet, countertops, glass and windows, insulation, gutters and downspouts, well drilling and septic system installation, maintenance and pumping, woodworking, carpentry and cabinet-making, swimming pools, hot tubs and spas, lawn care and landscaping, masonry, concrete and paving, pest control and snow removal.
22. **Schools, vocational or technical.**

23. **Single family detached dwellings** including residential accessory uses, subject to the requirements of Section 210 of this Ordinance.
24. **Sign makers.**
25. **Small engine repair shops.**
26. **Veterinary offices/Animal hospitals.**
27. **Welding shops.**
28. **Accessory uses customarily incidental to the principal uses in this zone**, including accessory retail sales of products produced on-site so long as the sales area is no more than ten percent (10%) of the total building area or three thousand (3,000) square feet, whichever is less;
 - a. **Alternate energy production facilities** subject to the requirements of Section 404 of this Ordinance.
 - b. **Athletic fields and courts and recreation facilities.**
 - c. **Co-located communication antennas upon existing structures** (e.g., utility transmission towers, observation towers, communication towers, silos, steeples, smokestacks, water towers, flagpoles, and other similar structures), subject to the requirements of Section 420 of this Ordinance.
 - d. **Domestic pets**, subject to the requirements of Section 406 of this Ordinance.
 - e. **Drop lot or drop and hook lot**, subject to a Conditional Use as an accessory use pursuant to the requirements of Section 451 of this Ordinance.
 - f. **Fences and walls**, subject to the requirements of Section 435 of this Ordinance.
 - g. **Freestanding communication antennas, towers and equipment**, subject to a Special Exception as an accessory use pursuant to the requirements of Section 438 of this Ordinance.
 - h. **Helicopter pad, private**, subject to a Special Exception as an accessory use pursuant to the requirements of Section 445 of this Ordinance
 - i. **Man-made lakes, dams, ponds, and impoundments**, subject to the requirements of Section 453 of this Ordinance
 - j. **Ornamental ponds and wading pools** subject to the requirements of Section 464 of this Ordinance.
 - k. **Recycling collection facilities as an accessory use**, provided such facilities are sufficiently enclosed to prevent the scattering of debris, the materials collected are removed at regular intervals, the facility is posted to prohibit the disposal of any material, good or furnishing that cannot be placed within the actual recycling bin, and the total size of the facility is less than three hundred (300) square feet.
 - l. **Residential Short-Term Rental**, only conducted as an accessory use to a principal residential use of the property, and subject to the requirements of Section 465 of this Ordinance.
 - m. **Satellite dish antennas**, subject to the requirements of Section 481 of this Ordinance.
 - n. **Signs** as defined herein, subject to the requirements of Section 322 of this Ordinance.

205.C. PRINCIPAL USES PERMITTED BY SPECIAL EXCEPTION (Subject to the review procedures of Section 804.3. of this Ordinance).

1. **Auction houses**, excluding automobile auctions subject to the requirements of Section 408 of this Ordinance.
2. **Automobile auctions and storage yards**, subject to the requirements of Section 410 of this Ordinance.
3. **Car washes**, subject to the requirements of Section 417 of this Ordinance.
4. **Commercial recreation facilities**, subject to the requirements of Section 423 of this Ordinance.
5. **Convention and conference centers**, subject to the requirements of Section 427 of this Ordinance;
6. **Farmers and/or flea markets**, subject to the requirements of Section 434 of this Ordinance.
7. **Freestanding communication antennas, towers and equipment**, subject to a Special Exception as an accessory use pursuant to the requirements of Section 438 of this Ordinance.
8. **Gas station**, subject to the requirements of Section and 411 of this Ordinance.
9. **Group homes**, subject to the requirements of Section 432 of this Ordinance.
10. **Health, fitness, social, fraternal and other private clubs**, subject to the requirements of Section 442 of this Ordinance.
11. **Heavy equipment leasing, rental, sales, service, repair and warehousing**, subject to the requirements of Section 443 of this Ordinance.
12. **Heavy industrial uses as defined herein**, subject to the requirements of Section 444 of this Ordinance.
13. **Home improvement, equipment rental and building supply stores**, subject to the requirements of Section 447 of this Ordinance.
14. **Mass transit and/or taxicab terminals**, subject to the requirements of Section 456 of this Ordinance.
15. **Storage unit centers**, subject to the requirements of Section 460 of this Ordinance.
16. **Passenger motor vehicle and recreational vehicle sales, service and repair facilities** including, but not limited to, auto mechanics, drive-thru lubrication services, and tire, auto paint, brake, muffler, transmission, windshield, auto body, car radio, and upholstery shops, subject to the requirements of Section 469 of this Ordinance.
17. **Recycling facilities for electronics, paper, plastic, glass and metal products**, subject to the requirements of Section 474 of this Ordinance.
18. **Sale of compost, mulch, woodchips and coal** subject to the requirements of Section 480 of this Ordinance.

205.D. PRINCIPAL USES PERMITTED BY CONDITIONAL USE (Subject to the review procedures of Section 805 of this Ordinance).

1. **Airports and heliports**, subject to the requirements of Section 403 of this Ordinance.
2. **Hospitals and related uses**, subject to the requirements of Section 449 of this Ordinance.
3. **Medical Marijuana facility**, to include both medical marijuana dispensaries and medical marijuana grower/processor facilities, subject to the requirements of Section 437 of this Ordinance.

4. **Power generation facilities**, subject to the requirements of Section 470 of this Ordinance.
5. **Principal waste handling, recycling, processing, transfer and disposal facilities**, subject to the requirements of Section 471 of this Ordinance.
6. **Shopping centers**, subject to the requirements of Section 484 of this Ordinance.
7. **Truck or motor freight terminals**, subject to the requirements of Section 486 of this Ordinance.
8. **Truck stops**, subject to the requirements of Section 487 of this Ordinance.
9. **Warehouses, distribution centers and wholesale trade establishments**, subject to the requirements of Section 489 of this Ordinance.

205.E. LOT AREA, LOT WIDTH, AND LOT COVERAGE REQUIREMENTS - See the following table:

Minimum Lot Area	Minimum Lot Width	Maximum Lot Coverage
2 acres	200 ft.	65%

205.F. MINIMUM SETBACK REQUIREMENTS (Principal and Accessory Uses)

1. **Front yard setback** – All buildings, structures (except permitted signs) shall be set back at least twenty-five feet (25') from the street right-of-way; off-street parking lots and outdoor storage and display areas shall be set back a minimum of fifteen (15') feet from the street right-of-way.
2. **Side yard setbacks** – All buildings and structures (except permitted signs) shall be set back at least twenty-five feet (25') from the side lot lines. Off-street parking lots, off-street loading spaces, and outdoor storage and display areas shall be set back at least ten feet (10') from the side lot lines, unless joint off-street parking lots and/or off-street loading spaces are shared by adjoining uses. In such instances, the side yard setbacks are eliminated solely to accommodate the shared off-street parking lots and/or off-street loading spaces.
3. **Rear yard setback** – All buildings, structures, and outdoor storage and display areas shall be set back at least twenty-five feet (25') from the rear lot line. Off-street parking lots, and off-street loading spaces shall be set back at least ten feet (10') from the rear lot line, unless joint off-street parking lots and/or off-street loading spaces are shared by adjoining uses. In such instances, the rear yard setback is eliminated solely to accommodate the shared off-street parking lots and/or off-street loading spaces.
4. **Residential buffer strip** – Any lot adjoining land within an (LDR, MU or A) Zone shall maintain a fifty (50') foot setback for nonresidential buildings, structures, off-street parking lots, loading areas and outdoor storage and display areas, from the (LDR, MU or A) Zone parcels. Such areas shall be improved with a landscape strip and screening in accordance with Sections 205.N. and 205.M., respectively, of this Ordinance.

205.G. HEIGHT REQUIREMENTS

Thirty-five feet (35'), provided a non-habitable structure may extend up to forty-five feet (45') if such structure is setback a horizontal distance at least equal to its height from each side and/or rear lot line.

205.H. OFF-STREET LOADING SPACES

Off-street loading spaces shall be provided as specified in Section 314 of this Ordinance.

205.I. OFF-STREET PARKING

Off-street parking shall be provided as specified in Section 315 of this Ordinance.

205.J. SIGNS

Signs shall be permitted as specified in Section 322 of this Ordinance.

205.K. ACCESS DRIVE REQUIREMENTS

All access drives shall be in accordance with Section 301 of this Ordinance.

205.L. SIDEWALKS AND PEDESTRIAN ACCESS

All properties shall be required to provide for a safe and convenient system of sidewalks that connect all public areas of the site with the required streetscape sidewalk and/or any other designated pedestrian facility that adjoins or extends onto the site. Such facilities shall comply with Section 510 of the SALDO.

205.M. SCREENING

A visual screen must be provided along any adjoining lands within an (LDR, MU or A) Zone, or any adjoining land containing an existing residential use, regardless of whether or not the (LDR, MU or A) Zone property is developed (see Section 321 of this Ordinance).

205.N. LANDSCAPING

Any portion of the site not used for buildings, structures, off-street parking lots, off-street loading spaces, outdoor storage areas, and sidewalks shall be maintained with a vegetative ground cover and other ornamental plantings (see Section 321 of this Ordinance). A minimum ten foot (10') wide landscape strip shall be provided along all property lines. Such landscape strip can be waived for that portion of the site occupied by a joint off-street parking lot and/or off-street loading space area shared by adjoining uses.

205.O. WASTE PRODUCTS

Dumpsters may be permitted within the side or rear yard, provided such dumpsters are screened from any adjoining roads or properties. All dumpsters shall be set back a minimum of fifty feet (50') from any adjoining (LDR & MU) Zone properties. All waste receptacles shall be completely enclosed within a masonry, wood or framed structures with a separate pedestrian access gate/door which is self-closing and another truck access gate that must be kept closed when not in use.

205.P. OUTDOOR STORAGE AND DISPLAY

Within this Zone, outdoor storage and display is permitted, provided all such areas are screened from adjoining roads and properties, and they comply with all of those setbacks specifically imposed thereon, listed in this section. The outdoor storage and display areas for vehicles sales need not be screened from adjoining roads. Section 317 of this Ordinance lists additional requirements.

205.Q. GENERAL PROVISIONS

All uses permitted within this Zone shall also comply with the applicable General Provisions in Article 3 of this Ordinance.

205.R. ENVIRONMENTAL PROTECTION STANDARDS

All uses permitted within this Zone shall also comply with the applicable Environmental Protection Standards contained within Article 5 of this Ordinance.

SECTION 206 – BILLBOARD SIGN OVERLAY ZONE (BS)

206.A. PURPOSE OF ZONE

This Overlay Zone provides the sole locations for the placement and use of Billboards within the Township as an accessory use.

206.B. LOCATION

The Billboard Sign (BS) Overlay Zone is depicted on the Dickinson Township Zoning Map and is more particularly bounded and described as follows: on the west by the western boundary of Dickinson Township; on the east by the eastern boundary of Dickinson Township; on the north by a line parallel to and 150 feet north of the northern right-of-way of U.S. Interstate Route 81; and on the south by a line parallel to and 150 feet south of the southern right-of-way of U.S. Interstate Route 81.

206.C. QUALIFICATION

Within the BS Zone, only those lands which are located within an Agricultural (A) District, or which are principally used for farm purposes, shall qualify for the placement of Billboard signs.

206.D. COMPLIANCE

All billboard signs shall comply with the, and be subject to, the requirements of Section 414 of this Ordinance.

Article 3

General Provisions

The regulations contained within Article 3 shall apply to all uses within the Township.

SECTION 301 ACCESS DRIVE REQUIREMENTS (NON-SINGLE-FAMILY DWELLING)

- 301.A.** Access drives shall be provided in accordance with Section 506 of the SALDO.
- 301.B.** Deviations from the requirements of Section 506 of the SALDO that are proposed during the subdivision / land development process shall be permitted as a waiver according to Section 205 of the SALDO and, when granted, will not also require the grant of a variance under the terms of this Ordinance; and,
- 301.C.** Deviations from the requirements of Section 506 of the SALDO that are proposed during the zoning permit process that do not involve subdivision / land development review shall be permitted as a variance according to Section 704.D. of this Zoning Ordinance.

SECTION 302 ACCESS TO PROPERTIES & STRUCTURES

- 302.A.** Every new principal use created and/or building hereafter erected or moved shall be on a lot with frontage along a public street or approved private street.
- 302.B.** Outparcel lots are also permitted provided that they have adequate vehicular access in accordance with this Section and such uses shall be accompanied by a cross access easement in a form acceptable to the Township Solicitor. Outparcels relying upon an internal vehicular road network shall be designed to avoid excessive queuing across parking aisles.
- 302.C.** All structures shall be sited on lots in such manner to provide for safe and convenient access for servicing, fire protection, waste collection, required off-street parking and loading spaces.
- 302.D.** Approved access shall be in accordance with Section 502.L. of the SALDO, for street design or as subsequently provided for by the Township. Access to lots containing single-family dwellings and farms shall be via driveways (see Section 305); access to lots containing other uses shall be via access drives (see Section 301).

SECTION 303 CLEAR SIGHT TRIANGLE

- 303.A.** Clear sight triangles shall be provided in accordance with Section 502.I.5. of the SALDO.
- 303.B.** Deviations from the requirements of Section 502.I.5. of the SALDO that are proposed during the subdivision / land development process shall be permitted as a waiver according to Section 205 of the SALDO and, when granted, will not also require the grant of a variance under the terms of this Ordinance; and,
- 303.C.** Deviations from the requirements of Section 502.I.5. of the SALDO that are proposed during the zoning permit process that do not involve subdivision / land development review shall be permitted as a variance according to Section 704.D. of this Zoning Ordinance.

SECTION 304 COMMON OPEN SPACE REQUIREMENTS

304.A. In those instances where open space is required elsewhere in this Ordinance, or when an applicant proposes the use of open space, such open space shall comply with the following:

304.B. REQUIRED OPEN SPACE DESIGN

Required open space shall be designed and arranged to achieve at least one of the following objectives, and the applicant shall demonstrate those specific measures employed to achieve these objectives:

1. Protection of important natural resources (e.g., streams, ponds, wetlands, steep slopes, woodlands, unique geologic features, wildlife habitats, aquifer recharge areas, sinkhole, etc.);
2. Protection of important historical and/or archaeological sites;
3. Provision of usable play and recreation areas that are conveniently accessible to residents within the development and the Township; and,
4. Integration of greenbelts throughout the development that link residences with on-site or adjoining parks, schools or other similar features.

304.C. OWNERSHIP AND MAINTENANCE

An essential element of the provision of open space is a written description regarding its ownership and/or disposition. Such ownership and/or disposition shall be accomplished through any of the following:

1. An offer of dedication to the Township. The Township shall not be obligated to accept dedication of the common open space;
2. With permission of the Township, and with an appropriate conservation easement as specified in Section 304.D. of this Ordinance, the developer may transfer ownership of the common open space or a portion thereof to a private, nonprofit organization among whose purposes is the preservation of open space land and/or natural resources. The organization shall be a bona fide conservation organization with a perpetual existence, the conveyance must contain appropriate provision for reverter or retransfer if the organization is unable to maintain the land, and the organization must enter into a maintenance agreement with the Township; and/or,
3. The developer shall provide for and establish an organization for the ownership and maintenance of the common open space which shall be generally consistent with the requirements for unit owners; associations found in the Pennsylvania Uniform Condominium Act or the Pennsylvania Planned Community Development Act. If such an organization is created, the agreements of sale and deeds for all lots shall contain the following requirements in language acceptable to the Township Solicitor:
 - a. Such organization shall not dispose of the common open space by sale or otherwise, except to the Township unless the Township has given prior written approval. Such transfer shall be made only to another organization which shall maintain the common open space in accordance with this Ordinance;
 - b. The organization and all lot owners shall enter into a maintenance agreement with the Township and shall agree to be bound by the provisions of Article VII of the

Pennsylvania Municipalities Planning Code relating to the maintenance of deteriorating common open space by municipalities; and,

- c. The Township may require the establishment of a reserve fund to which the Township shall be named designated beneficiary, to provide for maintenance of or capital improvements to the common open space.

304.D. PERMANENT PROTECTION OF COMMON OPEN SPACE

Required common open space shall be subject to permanent conservation easements in a form that is acceptable to the Township Solicitor. Such conservation easement shall limit future development and define the range of permitted activities. (For example, the clearing of woodland habitat shall generally be prohibited, except as necessary to create trails, active recreation facilities, and/or to install subsurface septic disposal systems or spray irrigation facilities.)

SECTION 305 DRIVEWAY REQUIREMENTS (SINGLE-FAMILY DWELLING)

305.A. NUMBER PER LOT


No more than two (2) driveway connections per lot frontage shall be permitted;

305.B. SETBACKS

Driveways shall not connect with a public street within forty (40) feet of the right-of-way lines of any intersecting streets; except that driveways may connect with a local street as listed in Section 320 of this Ordinance directly opposite another local street or access drive. Driveways shall not connect with a public street within five (5) feet of a fire hydrant. Furthermore, no part of a driveway shall be located within five (5) feet from any adjoining side lot line, except as permitted in Sections 305.K., 305.L., 305.M., and 305.N. of this Ordinance;

305.C. CLEAR-SIGHT TRIANGLE

Driveways shall be located and constructed so that a clear-sight triangle of seventy-five (75) feet as measured along the street centerline and five (5) feet along the driveway centerline is maintained; no permanent obstructions and/or plant materials over thirty inches (30") high shall be placed within



this area;

305.D. ADEQUATE SIGHT DISTANCE

Adequate sight distance shall be provided in accordance with prevailing PennDOT standards. Deviations from these requirements that are proposed during the subdivision / land development process shall be permitted as a waiver according to Section 205 of the SALDO and, when granted, will not also require the grant of a variance under the terms of this Ordinance. Deviations from these requirements that are proposed during the zoning permit process that do not involve subdivision / land development review shall be permitted as a variance according to Section 704.D. of this Zoning Ordinance.

305.E. SLOPE

A driveway shall not exceed a slope of five percent (5%) within twenty-five (25) feet of the street right-of-way lines, nor fifteen percent (15%) at any point.

305.F. ROAD CLASSIFICATION

Driveway access shall be provided to the street of lesser classification when there is more than one street classification involved.

305.G. DRIVEWAY SURFACE, WIDTH & APRON

No driveway shall provide a curb cut exceeding twenty-four (24) feet in width between the abutting street cartway and the street right-of-way. All driveways shall be paved or be constructed with a paved apron that extends from the street cartway to a depth of at least twenty-five feet (25') feet onto the subject property. Beyond the paved apron all driveways shall be provided with a dust free surface or in the alternative a fifty foot (50') long gravel section of driveway shall be placed just beyond the preceding paved apron to help collect any mud that may have attached to a vehicle's wheels;

305.H. REQUIRED PERMIT

Any driveway intersecting with a State-owned road shall require the issuance of a highway occupancy permit from the Pennsylvania Department of Transportation. Any driveway intersecting with a Township-owned road shall require the issuance of a driveway permit from the Township in accordance with §174-10 of the Code of Dickinson Township.

305.I. DRAINAGE

Driveways shall be constructed in a manner consistent with the design, maintenance, and drainage of the street.


305.J. VERTICAL CLEARANCE

Driveways shall maintain a height of at least twelve (12) feet that is clear of obstructions and vegetation to facilitate emergency vehicle access.

305.K. Townhouses on individual lots are permitted to utilize front-yard driveways and garages, if such driveways are only connected to local roads, and comply with the following regulations as depicted in the following diagram:


1. Such driveways must be separate on each lot and shall accommodate at least two (2) of the required three (3) off-street parking spaces;
2. Such driveway shall be at least forty feet (40') in length when single-width driveways are

- used without a garage (see LOT 7);
3. Such driveway shall be at least twenty feet (20') in length when single-width driveways are used with a garage (see LOT 4);
 4. Such driveway shall be at least twenty feet (20') in length when double-width driveways are used with or without a garage (see LOT 3);
 5. Such driveways must be set back at least:
 - a. two feet (2') from any lot line of an adjoining townhouse (see common lot lines between LOTS 1 & 2 and 5 & 6 and see the inset in the following diagram);
 - b. thirty feet (30') from the right-of-way of any street or alley which does not connect with the driveway (see LOT 1);
 - c. twenty feet (20') from the lot line of an end unit that abuts another end unit or a non-townhouse use (see LOT 7); and,
 - d. five feet (5') from the closest point of any building other than a garage (see LOT 1).
 6. No individual driveway shall be narrower than ten feet (10') (see LOT 7);
 7. Garages must be attached to, and rely upon, a driveway as permitted above;
 8. Garages must be set back at least:
 - a. twenty feet (20') from the street right-of-way (see LOT 4);
 - b. five feet (5') from any lot line of an adjoining townhouse that does not share an attached garage (see common property line between LOTS 4 & 5);
 - c. five feet (5'), from the townhouse building when the garage is a freestanding building (see LOTS 3 & 4); and,
 - d. twenty feet (20') from the lot line of an end unit that abuts another end unit or a non-townhouse use (see LOT 7).



305.L. Townhouses on individual lots are permitted to utilize rear yard driveways and garages, if such driveways and garages comply with the following requirements as depicted in the following diagram:

1. Such driveways must be separate on each lot and shall accommodate at least two (2) of the required three (3) off-street parking spaces;
2. Such driveway shall be at least forty feet (40') in length when single-width driveways are used without a garage (see LOT 7);
3. Such driveway shall be at least twenty feet (20') in length when single-width driveways are used with a garage (see LOT 4);
4. Such driveway shall be at least twenty feet (20') in length when double-width driveways are used with or without a garage (see LOT 3);




5. Such driveways must be set back at least:
 - a. two feet (2') from any lot line of an adjoining townhouse (see common lot lines between LOTS 1 & 2 and 5 & 6);
 - b. thirty feet (30') from the right-of-way of any street or alley which does not connect with the driveway (see LOT 1);
 - c. twenty feet (20') from the lot line of an end unit that abuts another end unit or a non-townhouse use (see LOT 7); and,
 - d. five feet (5') from the closest point of any building other than a garage.
6. No individual driveway shall be narrower than ten feet (10') (see LOT 7);
7. Garages must be attached to, and rely upon, a driveway as permitted above;
8. Garages must be set back at least:
 - a. twenty feet (20') from the rear lot line or alley cartway whichever provides the greater setback (see LOT 4);

- b. five feet (5') from any lot line of an adjoining townhouse that does not share an attached garage (see common property line between LOT 5);
- c. five feet (5'), from the townhouse building when the garage is a freestanding building (see LOT 6); and,
- d. twenty feet (20') from the lot line of an end unit that abuts another end unit or a non-townhouse use (see LOT 7).

305.M. Townhouses on common property are permitted to utilize front-yard driveways and garages, if such driveways are only connected to local roads, and comply with the following requirements as depicted in the following diagram:

1. Such driveways must be separate for each unit and shall accommodate at least two (2) of the required three (3) off-street parking spaces;
2. Such driveway shall be at least forty feet (40') in length when single-width driveways are used without a garage (see UNIT 7);
3. Such driveway shall be at least twenty feet (20') in length when single-width driveways are used with a garage (see UNIT 4);
4. Such driveway shall be at least twenty feet (20') in length when double-width driveways are used with or without a garage (see UNIT 3);
5. Such driveways must be set back at least:
 - a. four feet (4) from any other driveway of an attached townhouse (see between UNITS 1 & 2 and 5 & 6 in the following diagram);
 - b. thirty feet (30') from the right-of-way of any street or alley which does not connect with the driveway (see UNIT 1);




- c. twenty feet (20') from a property line or a non-townhouse use or forty feet (40') from any other driveway of an end unit that abuts another end unit (see UNIT 7); and,
- d. five feet (5') from the closest point of any building other than a garage

(see UNIT 1).

6. No individual driveway shall be narrower than ten feet (10') (see UNIT 7);
7. Garages must be attached to, and rely upon, a driveway as permitted above;
8. Garages must be set back at least:
 - a. twenty feet (20') from the street right-of-way (see UNIT 4);
 - b. ten feet (10') from any garage of an adjoining townhouse that does not share an attached garage (see UNITS 4 & 5);
 - c. five feet (5'), from the townhouse building when the garage is a freestanding building (see UNITS 3 & 4); and,
 - d. twenty feet (20') from a property line or a non-townhouse use or forty feet (40') from any other driveway of an end unit that abuts another end unit (see UNIT 7).

305.N. Townhouses on common property are permitted to utilize rear yard driveways and garages, if such driveways are designed and constructed to comply with the following requirements depicted in the following diagram:

1. Such driveways must be separate for each unit and shall accommodate at least two (2) of the required three (3) off-street parking spaces;
2. Such driveway shall be at least forty feet (40') in length when single-width driveways are used without a garage (see UNIT 7);
3. Such driveway shall be at least twenty feet (20') in length when single-width driveways are used with a garage (see UNIT 4);
4. Such driveway shall be at least twenty feet (20') in length when double-width driveways are used with or without a garage (see UNITS 2 & 3);
5. Such driveways must be set back at least:
 - a. four feet (4) from any other driveway of an attached townhouse (see between UNITS 1 & 2 and 5 & 6 and see the inset in the above diagram);
 - b. thirty feet (30') from the right-of-way of any street or alley which does not connect with the driveway (see UNIT 1);
 - c. twenty feet (20') from a property line or a non-townhouse use or forty feet (40') from any other driveway of an end unit that abuts another end unit (see UNIT 7); and,
 - d. five feet (5') from the closest point of any building other than a garage (see UNIT 6).
6. No individual driveway shall be narrower than ten feet (10') (see UNIT 7);
7. Garages must be attached to, and rely upon, a driveway as permitted above;
8. Garages must be set back at least:
 - a. twenty feet (20') from the rear lot line or alley cartway whichever provides the greater setback (see UNIT 4);
 - b. ten feet (10') from any garage of an adjoining townhouse that does not share an attached garage;
 - c. five feet (5'), from the townhouse building when the garage is a freestanding building (see UNITS 3 & 4); and,
 - d. twenty feet (20') from a property line or a non-townhouse use or forty feet (40') from any other driveway of an end unit that abuts another end unit (see UNIT 7).



SECTION 306 ESTABLISHMENT OF MORE THAN ONE PRINCIPAL USE ON A LOT

- 306.A.** Notwithstanding Section 107, more than one principal use may be established on a single lot only when each use complies with: (i) all of the lot area, yard and other requirements of this Ordinance (including but not limited to Section 302 of this Ordinance) as though it were on an individual lot, (ii) all of the requirements for an individual lot under the SALDO as though it were on an individual lot, (iii) each use provides for its own septic and water source, including a hydrology study where required Township regulations; and (iv) a plan has been recorded in compliance with the SALDO.
- 306.B.** An applicant for more than one principal use on a lot shall be required to submit information and detailed plans that demonstrate compliance with this Section. Such plan and information shall depict a hypothetical illustration of how the proposed use would be located upon its own separate lot using ghost property lines and related setbacks, accompanying lot coverage calculations, etc.

SECTION 307 FRONT YARD EXCEPTIONS

When an unimproved lot is situated between two (2) improved lots with front yard dimensions less than those required for the Zone, the front yard required may be reduced to a depth equal to the average of the two (2) adjoining lots, provided that in no case shall the front yard be less than twenty (20) feet from an abutting street right-of-way line within the (C, A, LDR, MU, MI and BI) Zones.

SECTION 308 ACCESS DRIVES

Access drives are improved cart ways designed and constructed to provide for vehicular movement between a street and the off-street parking and/or loading area for any use other than one single-family dwelling unit or farm. Access drives shall conform to the following:

- 308.A.** The standards contained in the Township SALDO at Section 506.
- 308.B.** Access drive intersections with a State Route shall be subject to the approval of PennDOT.

SECTION 309 HEIGHT LIMIT EXCEPTIONS

309.A. The height regulations do not apply to the following structures or projections provided such structures or projections are set back a horizontal distance at least equal to their height from any property line, are not used for habitable floor space, comply with applicable FAA regulations and are constructed in accordance with the prevailing Uniform Construction Code:

1. Water towers, utility poles, smokestacks, chimneys, farm silos, windmills, flagpoles, clock or bell towers, spires, steeples, belfries, cupolas, monuments, dormers, satellite dishes, electrical transmission lines and structures, conveyors, derricks, skylights, solar energy collectors and other similar structures;
2. Roof-top structures for the housing of elevators, stairways, water storage tanks, ventilating fans, and other mechanical appurtenances;
3. Parapet walls or cornices used solely for ornamental purposes if not in excess of five (5) feet above the roof line; and,
4. Church or school roofs.

309.B. In no case shall any freestanding or roof-top structure above the maximum permitted height be used for the purpose of providing additional floor space for any use; and,

309.C. In lieu of this section, telecommunications towers, wireless communication facilities, and similar antennae shall be subject to the regulations of Sections 420 and 438 of this Ordinance.

SECTION 310 OUTDOOR LIGHTING

310.A. Outdoor lighting shall be provided in accordance with Section 513 of the SALDO.

310.B. Deviations from the requirements of Section 513 of the SALDO that are proposed during the subdivision / land development process shall be permitted as a waiver according to Section 205 of the SALDO and, when granted, will not also require the grant of a variance under the terms of this Ordinance; and,

310.C. Deviations from the requirements of Section 513 of the SALDO that are proposed during the zoning permit process that do not involve subdivision / land development review shall be permitted as a variance according to Section 704.D. of this Zoning Ordinance.

SECTION 311 RESERVED

SECTION 312 MINIMUM HABITABLE FLOOR AREA

312.A. All dwelling units must conform to the minimum habitable floor area following:

1. Single-family, duplex, two-family and townhouse dwelling units: seven hundred (700) square feet per dwelling unit.
2. Multi-family dwellings and conversion apartments: four hundred (400) square feet per dwelling unit.

SECTION 313 MATERIALS AND WASTE STORAGE, HANDLING AND DISPOSAL

313.A. All principal commercial, industrial, institutional, and health-care related uses shall be required to provide detailed information regarding materials and waste handling, including:

1. Listing of all materials to be used and/or produced on the site;

2. Listing of all wastes generated on the site; and,
 3. Written evidence that the storage, treatment, processing, transfer, and disposal of all materials and wastes shall be accomplished in a manner that complies with all applicable Federal, State, County, and municipal requirements, including, but not limited to, the following:
 - a. the Pennsylvania Municipal Waste Planning, Recycling and Waste Reduction Act (Act 101);
 - b. the Pennsylvania Solid Waste Management Act (Act 97);
 - c. the Federal Emergency Management Act;
 - d. the Federal Superfund Amendment and Reauthorization Act;
 - e. the Pennsylvania Hazardous Materials Emergency Planning and Response Act; and,
 - f. the Pennsylvania Low-Level Radioactive Waste Disposal Act.
 4. No flammable or explosive liquids, solids, or gases shall be stored above ground, except within receptacles which meet all local, State, and/or Federal regulations unless restricted or prohibited by other regulatory controls contained within this ordinance.
 5. All storage facilities for fuel stored outdoors shall be enclosed by a security fence and screened from adjoining roads and properties.
 6. All storage facilities for fuel stored outdoors shall be located in accord with any State and/or Federal regulatory requirements for separation distances.
 7. Highly flammable or toxic or hazardous or explosive liquids, solids, or gases shall be stored above-ground in leakproof double walled containment vessels which accommodate testing for leaks and all such containment vessels and facilities shall be suitably screened by natural plantings so that they are not visible from lot lines.
 8. No substance which has the potential to contaminate groundwater or surface waters shall be permitted to be stored outdoors unless the property owner and/or proprietor provides safeguards from potential contamination satisfactory to the Township based upon State and Federal requirements.
 9. No materials or wastes shall be stored or deposited upon a lot in such form or manner that they:
 - a. may be transferred off the lot by natural causes or forces;
 - b. can contaminate a stream or watercourse;
 - c. render a stream or watercourse undesirable as a source of water supply or recreation; or,
 - d. will destroy aquatic life.
 10. All materials or wastes which might cause fumes or dust or which constitute a fire hazard or which may be edible or otherwise attractive to vermin shall be stored only if enclosed in containers which are adequate to eliminate such hazards.
 11. Dumpsters are permitted within the side or rear yard, provided such dumpsters are screened from any adjoining roads or properties. Unless specified elsewhere within this Ordinance dumpsters shall comply with all side and rear yard setbacks imposed upon the principal use. All waste receptacles shall be completely enclosed within a masonry or framed enclosure with a self-closing door or gate.
- 313.B. All uses must properly dispose of wastes in accordance with all applicable laws and regulations.

SECTION 314 OFF-STREET LOADING

314.A. SCHEDULE OF REQUIRED OFF-STREET LOADING SPACES – All uses shall provide required off-street loading in accordance with the following schedule:

USE	GROSS FLOOR AREA (SQARE FEET)	NUMBER OF SPACES
Commercial, wholesale, manufacturing, hospital, laundry, institutional or similar uses	Under 8,000	1
	8,000 to 40,000	2
	Over 40,000 to 100,000	3
	Over 100,000 to 250,000	4
	Each additional 250,000	1
Offices, hotels or similar lodging	Under 100,000	1
	Over 100,000 to 300,000	2
	Over 300,000	3

314.B. Off-street loading shall be designed and constructed in accordance with Section 509 of the SALDO.

314.C. Deviations from the requirements of Section 509 of the SALDO that are proposed during the subdivision / land development process shall be permitted as a waiver according to Section 205 of the SALDO and, when granted, will not also require the grant of a variance under the terms of this Ordinance; and,

314.D. Deviations from the requirements of Section 509 of the SALDO that are proposed during the zoning permit process that do not involve subdivision / land development review shall be permitted as a variance according to Section 704.D. of this Zoning Ordinance.

SECTION 315 OFF-STREET PARKING

315.A. PARKING FOR SINGLE-FAMILY DETACHED DWELLINGS

- Every single-family dwelling shall be required to provide at least two (2) off-street parking spaces that are each rectangular and a minimum of ten feet (10') wide and twenty feet (20') long. Such spaces must be provided behind the street right-of-way line and may be within garages, carports, and/or driveways. Additional regulations pertaining to driveways are contained in Section 305 of this Article.
- Residents in all Zones are permitted to park one (1) commercial vehicle upon their property, provided such commercial vehicle does not exceed a gross vehicle weight of twenty thousand (20,000) pounds and such vehicle is either used on the property or is assigned to one resident of the property for employment purposes. The weight limitation set forth in herein shall not apply to the (C, A, MI, and BI) Zones
- The following regulations contained in Section 315.B. of this Ordinance do not apply to off-street parking facilities serving one (1) single-family dwelling.

315.B. PARKING REQUIREMENTS FOR USES OTHER THAN SINGLE FAMILY DETACHED DWELLINGS

- Off-street parking shall be designed and constructed in accordance with Section 508 of the SALDO.

2. Deviations from the requirements of Section 508 of the SALDO that are proposed during the subdivision / land development process shall be permitted as a waiver according to Section 205 of the SALDO and, when granted, will not also require the grant of a variance under the terms of this Ordinance; and,
3. Deviations from the requirements of Section 508 of the SALDO that are proposed during the zoning permit process that do not involve subdivision / land development review shall be permitted as a variance according to Section 704.D. of this Zoning Ordinance.

315.C. SCHEDULE OF REQUIRED PARKING SPACES

1. Except as provided for in Sections 315.C.2. and 315.C.4., the minimum number of off-street parking spaces to be provided for each land use type shall be as indicated on following chart. Any use involving a combination of several uses shall provide the sum of the number of spaces required for each individual use. When a calculation results in a fraction, any fraction below one-half ($\frac{1}{2}$) may be disregarded, and any fraction of one-half ($\frac{1}{2}$) or more shall require an additional full space.

COMMERCIAL USES	
Type of Use	Minimum of One Passenger Parking Space for Each
Auction houses, excluding automobile auctions	Two persons of legal occupancy plus one per employee
Auditorium, banquet, conference, and meeting facilities; theater, and other such places of public assembly	Three (3) seats of legal occupancy plus 1 per employee on largest shift
Automobile, truck, trailer, bus, passenger motor vehicle and recreational vehicle service, repair and washing facilities	$\frac{1}{4}$ service and/or washing bay (i.e. 4 per bay)
Automobile, boat, and trailer sales	400 square feet of gross indoor and outdoor display area
Banks, credit unions & other similar financial uses	200 square feet of gross floor area
Bed and breakfast	Room for rent plus those required for the dwelling unit
Car wash	See Section 417
Carpeting, drapery, floor covering, and wall covering sales	500 square feet of gross floor area
Casinos, off-track betting parlors, slot machine parlors	65 square feet of gross floor area
Clinics and professional offices of veterinarians, physicians, dentists, opticians, counselors and etc.	220 square feet of gross floor area
Clubs, lodges and other similar places	100 square feet of gross floor area plus 1 per employee on largest shift
Commercial recreation facilities	See Section 423
Convenience stores	350 square feet of gross floor area
Convention and conference centers	See Section 427
Child care (group home or centers), excluding family child care homes	6 persons enrolled
Drive-thru and/or fast-food restaurants	67 square feet of gross floor area
Dry cleaners, laundries and laundromats	400 square feet of gross floor area
Farmers and/or flea markets	200 square feet of retail sales area

COMMERCIAL USES	
Type of Use	Minimum of One Passenger Parking Space for Each
Food markets and grocery stores	150 square feet of gross floor area
Funeral homes	50 square feet of gross floor area
Furniture sales	400 square feet gross floor area
Gas stations as a principal or accessory use	2 parallel spaces arranged in a stacked configuration for each fuel dispensing location plus 4 per service or washing bay
Health, fitness, social, fraternal and other private clubs	See Section 442
Home improvement and building supply stores	250 square feet of interior retail sales area, plus one space for each 500 square feet of exterior retail sales area
Home occupation	nonresident employee and patron on site at one time
Hotels, motels and similar lodging facilities	Guest sleeping room and one per each employee (Restaurants and other accessory uses shall add to this requirement.)
Kennels & horse boarding stables	10 animals of occupancy plus and one per each employee on two largest shifts
Office buildings	250 square feet of gross floor area
Personal services (e.g. barbers, beauticians, masseuse, tanning salon, tattoo parlor, photographer, etc.)	4 spaces per practitioner or 2 spaces per service station whichever produces the greater number
Retail stores or shops (except those listed above) and personal service uses	200 square feet of gross floor area plus one per each employee on two largest shifts
Restaurants	67 square feet of gross floor area
Storage unit centers	50 units plus two per any resident manager
Shopping centers or malls with up to 400,000 square feet of gross floor area	250 square feet of gross floor area
Shopping centers or malls with more than 400,000 but less than 600,000 square feet of gross floor area	235 square feet of gross floor area
Shopping centers or malls with more than 600,000 square feet of gross floor area	222 square feet of gross floor area
Other commercial uses	360 square feet of gross floor area
Auditorium, banquet, conference, and meeting facilities; theater, and other such places of public assembly	Three (3) seats. For uses without permanent seats, 50 square feet of are used for assembly purposes

INDUSTRIAL USES	
Type of Use	Minimum of One Passenger Parking Space for Each
Automobile, truck, trailer, bus, passenger motor vehicle and recreational vehicle service, repair and washing facilities	¼ service and/or washing bay (i.e. 4 per bay)

INDUSTRIAL USES	
Type of Use	Minimum of One Passenger Parking Space for Each
Industrial and heavy manufacturing establishments	540 square feet plus those associated with any office, sales or similar related uses when said uses exceed 10% of the gross floor area
Truck or motor freight terminal	2000 square feet
Truck stops	See Section 487
Warehousing, distribution and wholesale trade	1500 square feet
Other industrial uses	Two employees on the two largest shifts or at least one space per each 1,000 square feet of gross floor area, whichever is the greatest number

RECREATIONAL USES	
Type of Use	Minimum of One Passenger Parking Space for Each
Baseball, soccer, field hockey, lacrosse, rugby, football and other athletic fields	1/12 field (12 per field) plus one (1) per each four (4) seats of spectator seating
Basketball and volleyball courts	1/8 court (8 per court) plus one (1) per each four (4) seats of spectator seating.
Bowling alleys, billiards rooms	1/4 lane/table (i.e., 4 per lane/table) and one per each two employees
Campgrounds	Campsite, plus one per employee, plus 50% of the spaces normally required for accessory uses
Golf courses	1/2 hole (i.e., 2 per hole), plus one per employee, plus 50% of the spaces normally required for accessory uses
Golf driving ranges	One per tee and one per employee
Gymnasiums	1/8 court (8 per court) plus one (1) per four (4) seats of spectator seating.
Health, fitness, social, fraternal and other private clubs	See Section 442
Miniature golf courses	1/2 hole (i.e., 2 per hole) and one per employee
Outdoor shooting range	0.75 firing stations, but not less than one (1) space for each four (4) seats
Riding schools or horse stables	Two stalls plus one per every four seats of spectator seating
Picnic areas	Per table
Skating rinks	Four persons of legal occupancy
Swimming pools (other than one accessory to a residential development)	Four persons of legal occupancy
Tennis or racquetball clubs	1/4 court (i.e., 4 per court), plus one per employee plus 50% of the spaces normally required for accessory uses

RESIDENTIAL USES	
Type of Use	Minimum of One Passenger Parking Space for Each
Single-family detached dwellings and two-family conversions	1/2 dwelling unit (i.e., two spaces per dwelling unit)
Boarding houses	Room for rent
Group homes, orphanages, dormitories, rectories methadone treatment facility, and etc.	Bedroom
Duplex, two-family, townhouse and multiple-family, dwellings	1/3 dwelling unit (i.e., three spaces per dwelling unit). Such parking spaces can take the form of private driveways, or garages and/or common parking lots, provided all spaces required are within 150 feet of the unit served.
Medical residential campus, nursing rest or retirement homes	0.75 dwelling units with individual kitchens, plus 1 for each 6 care beds, plus 1 for each employee on largest shift
Mobile home parks	½ dwelling unit (i.e. 2 spaces per unit) plus 1 on-street or in common visitor parking lot

SOCIAL AND INSTITUTIONAL USES	
Type of Use	Minimum of One Passenger Parking Space for Each
Auditorium, banquet, conference, and meeting facilities; theater, and other such places of public assembly	Three (3) seats of legal occupancy plus 1 per employee on largest shift
Churches	5 seats in sanctuary or auditorium, or if no fixed seats 1 per 40 square feet of gross floor area
Clubs, lodges and other similar places	100 square feet of gross floor area plus 1 per employee on largest shift
Medical residential campus, nursing rest or retirement homes	0.75 dwelling units with individual kitchens, plus 1 for each 6 care beds, plus 1 for each employee on largest shift
Health, fitness, social, fraternal and other private clubs	See Section 442
Hospitals, sanitariums	Spaces shall be provided for visitors, at the rate of at least one space per each 1.5 accommodations (beds). Such spaces shall be in addition to those necessary for those personnel employed or practicing on the site at one time.
Museums, art galleries, cultural centers, libraries	400 square feet of gross floor area
Rehabilitation centers (without overnight accommodations)	per employee and 1 per each three patients
Schools below grade ten, including principal day-care and kindergarten	Six students enrolled
Schools, tenth grade and above, including colleges with on-site housing for a majority of students enrolled	Three students enrolled
Colleges that do not offer on-site housing for a majority of students enrolled	1.5 students enrolled
Vocational training and adult education facilities	1.5 students enrolled

2. All other uses not specifically mentioned above shall provide off-street parking spaces to accommodate one (1) space for the maximum number of persons regularly employed,

having business, and/or resident upon the premises at any given time.

3. For commercial and industrial uses, no off-street parking area shall accommodate more than one hundred twenty (120) percent of the minimum requirement, regardless of whether such additional spaces are provided with pervious surfacing, except as provided for below by Section 315.C.4. of this Ordinance.
4. Alternative off-street parking standards to those provided in this Section may be permitted by the Zoning Hearing Board as a special exception in accordance with Section 704.C. of this Ordinance. The applicant shall establish by credible evidence that adequate parking is provided for all uses within the development. Such evidence shall include, but not necessarily be limited to, the following:
 - a. Estimates of required parking needs based upon actual traffic or parking surveys for existing similar land uses located in comparable settings.
 - b. Analysis of shared parking facilities with other uses that routinely experience peak parking demands at different times of the day, week, or season, and where the parking spaces required by one use can also accommodate another nearby use.
 - c. Analysis of the possible use of permeable surfaces for overflow parking where such overflow parking area would be used sparingly and where the applicant can show that the permeable surfaces will be constructed of stable materials and will be environmentally beneficial to the community.
 - d. Analysis of the likelihood of the use of bus service (both public transit and charter service) by a significant volume of patrons.
 - e. Any other specific characteristics of the proposed use that, in the opinion of the Zoning Hearing Board, justifies a different required parking ratio.

315.D. SHARED OFF-STREET PARKING

1. Notwithstanding any other parking requirement, when any parcel of land is proposed to be used for two or more land uses, the Township may allow the minimum number of parking spaces required to serve the combination of all uses to be established in accordance with the following formula:
 - a. Determine the minimum amount of parking required for each use as though it were a separate use.
 - b. Multiply each such amount by the corresponding percentage for each applicable time period showing in the following schedule.

PARKING CREDIT SCHEDULE					
Uses	Weekdays			Weekends	
	Nights Midnight- 6AM	Days 9AM – 4PM	Evenings 6PM - Midnight	Days 9AM – 4PM	Evenings 6PM - Midnight
Commercial / Retail	5%	50%	90%	100%	70%
Hotel / Lodging	80%	80%	100%	80%	100%
Office / Industrial	5%	100%	10%	10%	5%

Restaurant	10%	50%	100%	50%	100%
Entertainment / Recreation	10%	40%	100%	80%	100%
All other uses	100%	100%	100%	100%	100%

- c. Calculate the column total for each time period.
 - d. The column total with the highest value is the parking space requirement.
2. In determining whether to approve an adjustment for shared parking, the Township shall consider all relevant factors, including:
 - a. Location of the shared parking in the same Zone as the parking generator.
 - b. The characteristics of each use and the differences in projected peak parking demand, including days or hours of operation.
 - c. Potential reduction in vehicle movements afforded by multipurpose use of the parking facility.
 - d. Potential improvements in parking facility design, circulation and access afforded by a joint parking facility.
 - e. Whether space will be conveniently usable without causing unreasonable hazard to pedestrians, hazard to vehicular traffic, traffic congestion, interference with safe and convenient access to other parking areas in the vicinity and detriment to adjoining neighborhood.
 - f. The degree of certainty regarding the continued availability of the shared parking facilities for the uses they are intended to serve, and,
 - g. The report and recommendation of the Township engineer.
 3. All requirements and conditions herein imposed upon the shared parking facility, including adequate assurance of the continued availability of the shared parking facilities for the uses they are intended to serve, shall be set out in either of the following ways:
 - a. Memorandum of lease covering the shared parking facilities restricting the use of said shared parking area for parking purposes only; or
 - b. A reciprocal easement agreement specifically setting forth the areas which will be used exclusively as parking areas. Such assurance shall be in a form and of a substance approved by the Township solicitor. The applicable instrument shall be submitted with the plan that includes a shared parking facility. This instrument shall serve as notice to all subsequent purchasers of the existence of a shared parking facility and all requirements associated therewith. If the assurance is removed or superseded in any way by the parties or their successors or assigns, substitute off-street parking must be provided in conformance with the requirements of this Section. If no alternate parking facilities are provided as required by this Ordinance within 90 days of notice from the Township that substitute parking is required, the Township may revoke the approvals for the applicable uses then existing.

4. Public entrances to all uses shall be no more than 500 feet from the closest entrance to the shared parking facility; provided, however, that parking areas designated for employee parking only may be up to 500 feet from an employee entrance to the structure.
5. Parking spaces reserved or to be reserved on a twenty four hour basis shall be designated on the plan. These spaces shall not be included in the calculation of available spaces to meet the minimum parking space requirements for a shared parking facility.
6. Residential use is not eligible for a shared parking adjustment.
7. Where a shared parking facility is approved, the developer shall provide signage providing information clearly indicating the availability of this facility for patrons of participating uses.
8. After a shared parking facility has been approved, any subsequent change, addition or deletion in the original uses, or any significant change in intensity of use of such uses shall require a revised plan approval. No approval of the changed uses shall be issued without a revised approval for the revised shared parking facility.

315.E. PROHIBITION OF PARKING OF UNLICENSED / UNINSPECTED VEHICLES

Except upon property used for the sale and service of motor vehicles or trailers or upon property used for a junkyard, motor vehicles or trailers of any kind or type without current license plates and current inspection stickers shall not be parked or stored upon any property other than in a completely enclosed garage or other accessory building. This requirement shall not apply to implements and other vehicles not normally used as conveyances on the public streets, nor shall it apply to vehicles routinely used in the operation of an ongoing agricultural use.

315.F. PARKING OF DUMPSTERS AND PODS

Upon any property, the use of dumpsters and or other portable storage containers and pods is limited to temporary periods during events such as construction, remodeling, moving and similar activities. The use of dumpsters and or other portable storage containers and pods for permanent storage and/or waste containment is expressly prohibited. The use of dumpsters and or other portable storage containers and pods shall not exceed sixty (60) days during any calendar year and only following the issuance of a zoning permit. Such containers must be located so as not to block any required clear sight triangles and be at least ten (10) feet from all lot lines. The Zoning Officer may issue an one-time extension to the zoning permit, if the applicant can demonstrate that the nature of the proposed activity: (i) is ongoing; (ii) is making reasonable progress; (iii) requires additional time; and, (iv) has a definitive ending date identified by the applicant beyond which the use shall cease.

Notwithstanding the forgoing, any commercial use may maintain a permanent dumpster on premises if permitted by the trash-hauler and approved by the Zoning Officer. Such applicant must establish that the permanent dumpster will be located on the property so it will not be seen by neighbors or the general public, will not create a safety hazard, will not create any noxious odor, and otherwise complies with Section 316 below.

315.G. PARKING OF RECREATIONAL VEHICLES & PERSONAL CARGO TRAILERS - Refer to Section 468 of this Ordinance.

315.H. PROHIBITED USES OF A PARKING LOT

Parking lots are for the sole purposes of accommodating the passenger vehicles of persons associated with the use which requires them. Parking lots shall not be used for the following

and/or loading purposes:

1. The sale, display, or storage of automobiles or other merchandise, except as otherwise permitted by this Ordinance;
2. Parking vehicles accessory to the use;
3. Performing services (including services to vehicles);
4. The placement or storage of trailers, trucks, portable storage containers, palettes or other similar structures, vehicles, items or materials; or,
5. Loading and unloading purposes except during hours when business operations are suspended.

SECTION 316 OPERATIONS AND PERFORMANCE STANDARDS

316.A. PERFORMANCE STANDARDS. The Township's Nuisance Ordinance, as amended, is incorporated herein by reference as if fully reproduced herein. The Township's Nuisance Ordinance shall be the performance standards for the Township's zoning purposes, meaning that all criteria and standards to establish a nuisance in said Nuisance Ordinance shall be deemed as the minimal performance standards applied to any use permitted by right, accessory, special exception, conditional use and/or variance within the Township.

316.B. APPLICATION TO ZONING. Any use or person that fails to comply with the standards, criteria and limitations set forth in the Township's Nuisance Ordinance, shall, in addition to any violation of said ordinance, also be deemed as a zoning violation for failing to comply with the performance standards of the Township.

SECTION 317 OUTDOOR STORAGE AND DISPLAY REQUIREMENTS

317.A. SHOPPING CART STORAGE

For grocery stores and other stores containing grocery departments, variety stores, home improvement and building supply stores, and other uses that provide shopping carts for use by customers, the outdoor storage and collection of shopping carts is permitted subject to the following.

1. Shopping carts may be collected and stored immediately in front of the storefront (upon sidewalks, or under a canopy) and/or within the parking lot.
2. In no case shall such designed shopping cart storage and collection areas be located upon any facilities used for vehicle circulation, required parking and loading areas, or emergency vehicle access provisions (e.g., fire lanes).
3. Shopping cart storage and collection areas shall be situated to provide clear pedestrian access (sidewalk or other area) at least eight (8) feet wide adjoining the storefront.
4. Signage for shopping cart storage and collection areas shall be governed by those regulations pertaining to on-site directional and informational signs as regulated by Section 322.D.8. of this Ordinance.

317.B. SEASONAL SIDEWALK DISPLAYS

For commercial uses, seasonal sidewalk displays related to retail sales are permitted subject to the following:

1. Only seasonal merchandise may be displayed, and shall be limited to the periods from

April 1 to October 1 and November 25 to January 5.

2. The location of such outdoor displays shall be limited to sidewalks, under canopies, and other areas immediately in front of the building/storefront. The stacking or display of such items shall be arranged to provide clear pedestrian access (sidewalk or other area) at least eight (8) feet wide.
3. In no case shall the location of such sidewalk display areas occur within any area used for vehicular circulation, required parking and loading areas, or emergency vehicle access provisions (e.g., fire lanes).
4. In no case shall such sidewalk display area exceed fifty (50) percent of the linear area of the storefront. For example, a storefront two hundred (200) feet long could have a sidewalk display directly in front of the store with a maximum length of one hundred (100) feet.
5. Signage for seasonal sidewalk sales shall comply with the applicable requirements contained within Section 322.D.14. of this Ordinance.
6. The applicant shall submit a working plan to the Township for the cleanup of litter and debris which may result from such outdoor display. Also, the applicant shall depict intended sidewalk display areas upon any permit applications and/or plans required by the Township. No additional permits shall be required, unless such area is to change location or size.

317.C. SPECIAL EVENT SALES

For commercial uses, special events are permitted subject to the following:

1. In addition to the other provisions of this Section, four (4) special event sales shall be permitted per calendar year. Such special event sales shall be limited to no more than a total of thirty (30) days per calendar year.
2. Areas used for special event sales displays shall be sited to comply with the setback requirements for a principal structure or principal use, whichever is greater.
3. Special event sales may be located within the parking lot, provided that such location does not contribute to congestion within the parking lot and upon the access drives that provide direct access to public roads. Within parking lots, such display areas shall be clearly delineated from the adjoining parking lot by the use of identifiable barriers (such as tents, canopies, temporary fences, or ropes). Additionally, location within the parking lot shall only be permitted insofar that the remaining parking spaces available for use are greater than or equal to the number of such spaces required for the principal use by this Ordinance.
4. The area devoted to special event sales displays shall not exceed twenty (20) percent of the gross leasable floor area of the use(s) conducting the special event sale.
5. Reserved.
6. All uses conducting a special event sale shall be responsible for the ongoing cleanup of litter and debris. Also, no exterior public address or lighting systems shall be used that produce glare or noise impacts discernable at, or beyond, the property line.
7. Signage for special event sales shall comply with the applicable requirements contained within Section 322.D.14. of this Ordinance.

SECTION 318 RESERVED

SECTION 319 REQUIRED TRAFFIC IMPACT STUDY STANDARDS

- 319.A.** Where a traffic impact study is required elsewhere in this Ordinance, it shall be provided in accordance with Section 302.G.5. of the SALDO;
- 319.B.** Deviations from the requirements of Section 302.G.5. of the SALDO that are proposed during the subdivision / land development process shall be permitted as a waiver according to Section 205 of the SALDO and, when granted, will not also require the grant of a variance under the terms of this Ordinance; and,
- 319.C.** Deviations from the requirements of Section 302.G.5. of the SALDO that are proposed during the zoning permit process that do not involve subdivision / land development review shall be permitted as a variance according to Section 704.D. of this Zoning Ordinance.

SECTION 320 ROADWAY CLASSIFICATIONS

For the purposes of this Ordinance, the roads, streets and cart ways located within the Township shall be classified in the following categories:

Arterial Road	Collector Roads	Local Roads
Interstate 81 Carlisle Road Ritner Highway	Goodyear Road Pine Road Pine Grove Road Walnut Bottom Road West Old York Road	All other roads not listed in other two categories.

SECTION 321 SCREENING AND LANDSCAPING REQUIREMENTS

- 321.A.** Screening and landscaping shall comply with Section 520 of the SALDO;
- 321.B.** Deviations from the requirements of Section 520 of the SALDO that are proposed during the subdivision / land development process shall be permitted as a waiver according to Section 205 of the SALDO and, when granted, will not also require the grant of a variance under the terms of this Ordinance; and,
- 321.C.** Deviations from the requirements of Section 520 of the SALDO that are proposed during the zoning permit process that do not involve subdivision / land development review shall be permitted as a variance according to Section 704.D. of this Zoning Ordinance.

SECTION 322 SIGNS

322.A. PURPOSE.


1. To provide for signs as a means of effective visual communication.
2. To promote adopted comprehensive planning and zoning objectives.
3. To assure compatibility of signs with land uses and buildings in the vicinity of the signs and in the community as a whole.
4. To improve the safety of pedestrians, vehicular traffic, and property.
5. To enhance the economic value of the community.
6. To enhance the aesthetic environment.
7. To minimize adverse effects of signs on nearby property.

8. To otherwise promote the public health, safety, morals, and general welfare of the community.
9. To regulate the use of signs through a sign permitting process.
10. To enable the fair and consistent enforcement of these sign regulations.

322.B. SIGN AREA AND HEIGHT

The following guidelines shall apply when interpreting area and height regulations in this Section.

1. Area - The area of a sign shall be the area of the smallest rectangle, triangle, or circle that will encompass all elements of the sign, such as letters, figures, symbols, designs, or other display.
 - a. When the sign is a separate unit, the area shall include any borders, framing, trim, decorative attachments, background, and space between elements; it shall not include any supporting structure unless that structure is illuminated, is in the form of a symbol, or contains advertising elements.
 - b. When the sign is applied to a wall or otherwise has no definable edges, the area shall include all color, artwork, or other means used to differentiate the sign from the surface upon which it is placed.
 - c. When a single sign structure has more than one (1) face with the same message, and no two (2) sign faces are more than three (3) feet apart at any point, the area shall be computed by determining the greatest total area of all sign faces visible from any single location.



2. Height - The height of a sign shall be measured from the average ground level beneath the sign to the highest point of the sign. The ground level shall be the lower of the ground level existing at the time of construction or the ground level existing prior to construction and prior to any earth disturbance at the site. This prior ground level may be established by any reliable source, including, without limitation, existing topographic maps, aerial photographs, photographs of the site, or affidavits of people who are personally familiar with the site. No person(s) shall artificially increase the maximum height of a sign by altering the grade at the base of the sign by any means.
 - a. No sign shall be higher than the height limitation imposed by this Ordinance.
 - b. The height of freestanding signs shall be controlled by the standards in Tables 1, 2 and 3 listed in Section 322.D. of this Ordinance.
 - c. Wall signs may be at any height on the wall to which they are attached, except that they may not extend higher than the top of the wall.

- d. Roof signs may extend no more than five (5) feet above the lowest point where they are attached to the building and may not extend above the highest point of the roof.

322.C. GENERAL REGULATIONS

The following regulations shall apply to all signs, in addition to the specific regulations contain in the following provisions of this Section. Where these general regulations are contradicted by a specific regulation, the specific regulation shall control.

1. All signs shall be constructed of durable materials, maintained in good condition, and secured in a safe manner.
2. When a sign becomes unsafe, the Zoning Officer shall give written notice to the owner of the premises on which the sign is located that the sign must be made safe or removed immediately.
3. The areas surrounding all signs shall be maintained in a neat, clean, and attractive condition.
4. All signs shall be removed within twelve (12) months if the purpose for which they were erected no longer exists.
5. Each property that displays one (1) or more permanent freestanding signs and that is in an area where street addresses have been assigned, must prominently display the address on one (1) permanent freestanding sign visible from the street. The address must include the street number; the street name is optional. The area taken up by the address does not count as part of the sign area. The numbers shall be Arabic numbers, of a uniform size, and shall be of durable, reflective materials. Each digit or letter shall be at least four inches in height. The color shall contrast with the immediate background so as to be easily readable.
6. No permanent, temporary or planned center signs shall be permitted except as authorized by this Section.
7. No sign shall be located within a street right-of-way or clear sight triangle at an intersection.
8. All freestanding signs shall be setback a minimum distance equal to the sign height from each lot line. No sign within the clear sight triangle shall obstruct vision between the heights of thirty (30) inches and eight (8) feet above the elevation of the centerline of the street.
9. No signs shall be painted, pasted, nailed, stapled, or otherwise attached to utility poles, trees, fences, fire hydrants, or in an unauthorized manner to walls or other signs, except insofar as such signs comply with generally applicable rules, regulations, or policies formally adopted by the Board of Supervisors. Notwithstanding the foregoing, a property owner shall be permitted to place signs on fences or trees which he/she/it owns, provided such signs comply with the other provisions of this Zoning Ordinance.
10. No sign shall be placed so as to obstruct any door, stairway, window, fire escape, or other means of egress or ingress.
11. No sign shall be placed so as to obstruct ventilation or light from a building.

12. No overhead sign shall have a clearance of less than eight (8) feet between any pedestrian walk and the lowest part of the sign nor less than seventeen (17) feet six (6) inches between any roadway and the lowest part of the sign.
13. No flat wall sign shall project more than eighteen (18) inches from the face of the wall to which it is attached over a public sidewalk.
14. No wall projecting sign shall project more than forty-eight (48) inches from the face of the wall to which it is attached over a public sidewalk.
15. No sign shall have lights or other illuminating devices that constitute a public safety or traffic hazard.
16. No sign shall be permitted which imitates or which might be confused with an official traffic sign or signal, such as by containing the words "Stop" or "Danger" or by including red, green, or yellow lights.
17. No sign or window display shall include a revolving beam or beacon of light resembling an emergency vehicle or facility. Rotating, traveling, pulsing, flashing, or oscillating light sources, lasers, beacons, or strobe lighting shall not be permitted except within the (BI) Zone and not within five hundred (500) feet of a signalized traffic intersection, a residential use or a (LDR or MU) Zone.
18. No sign shall advertise activities or products that are illegal under Federal, State, or local municipal laws or regulations.
19. No sign shall include statements, words, or pictures that are considered to be vulgar, obscene, or pornographic. No sign shall depict "specified anatomical areas" or "specified sexual activities", both as defined herein.
20. No streamers, pennants, spinners, reflectors, ribbons, tinsel, balloons or similar materials shall be displayed outside a building.
21. In addition to any other signs permitted by this Section, each principal use may display one (1) flag not to exceed the size and height of a permanent sign permitted by Section 322.D. Of this Ordinance. Such flag shall not be used to convey any commercial message or advertising.
22. No sign shall emit smoke, visible vapors, particles, sound, or odor.
23. No sign shall be placed on an automobile, truck, or other vehicle if that vehicle is being used primarily for displaying such sign.
24. No inflatable signs shall be permitted.
25. No open flames shall be permitted as part of a sign or in any other way to attract attention.
26. Advertising painted upon or displayed upon a barn or other structure shall be considered a sign and shall comply with this Section.
27. Signs that are located on the inside of a window shall be counted as a sign if they are legible from an adjoining road or adjoining property.
28. Any sign may be exempted from the regulations of Section 322.D. of this Ordinance as a

special exception, if the applicant can demonstrate to the satisfaction of the Zoning hearing Board that the sign has been authenticated as historically significant and accurate for its specific location, whether original or a replica.

29. The lighting of all signs shall comply with Section 310 of this Ordinance.
30. Billboards shall comply with Section 414 of this Ordinance.
31. Signs incorporating LCD, LED, plasma, CRT, pixelized lights or other animated and/or video-like displays shall be limited to the (MU and BI) Zones and shall comply with the following requirements:
- a. Such signs shall employ lettering and/or symbols for immediate recognition by motorists with a height not less than twelve (12') inches;
 - b. Such signs shall display simple and static messages for immediate recognition by motorists. Messages shall be complete in each display cycle and shall not require viewers to see multiple display cycles to derive its meaning;
 - c. Such signs shall use instantaneous transitions from one message display cycle to the next with no blank-outs, scrolling, fading, streaming, zooming, flashing or any other animated effect to facilitate immediate recognition by motorists;
 - d. All properties utilizing a dynamic message display sign must remove all exterior promotional banners, sandwich board signs, and may not use any temporary signage; and,
 - e. Each message display cycle shall comply with the following minimum time standards based upon the lowest speed limit of the road travel lane from which the sign is visible:

Required Minimum Message Display Cycles (seconds)			
Speed Limit (miles per hour)	Total sign area with up to 64 square feet	Total sign area with between 64 and 300 square feet	Total sign area with more than 300 square feet
25 mph	17 sec.	28 sec.	56 sec.
30 mph	14 sec.	24 sec.	48 sec.
35 mph	12 sec.	20 sec.	40 sec.
40 mph	11 sec.	18 sec.	36 sec.
45 mph	10 sec.	16 sec.	32 sec.
50 mph	9 sec.	14 sec.	28 sec.
55+ mph	8 sec.	12 sec.	24 sec.

322.D. SPECIFIC SIGN REQUIREMENTS

The following three (3) tables provide requirements imposed upon permanent, temporary and

planned center signs as permitted within the Township, solely for purposes of such tables, the below definitions shall apply: (i) common residential property shall mean a residential property with at least (1) common wall; (ii) individual residential property shall mean a residential property with no common wall; (iii) common nonresidential property shall mean a nonresidential property with at least (1) common wall; and (iv) individual nonresidential property shall mean a nonresidential property with no common wall.

§322.D. - PERMANENT SIGN REQUIREMENTS (TABLE 1)

Sign Type	Maximum Permitted Number	Maximum Permitted Sign Area	Maximum Height of Freestanding Signs	Maximum Height of Wall, Window and Roof signs	Maximum Projection from Wall/Roof Projecting Signs	Permitted Zones	Other Requirements	Zoning Permit Required
1. Signs for lawfully conducted activities associated with and on the premises of an individual residence or farm, including accessory uses.	1 freestanding sign per principal use, unlimited wall or roof signs	4 square feet, <u>plus</u> 1 square foot per 25 lineal feet of lot frontage, not to exceed 8 square feet of total sign area.	5 feet	Flat wall and wall projecting signs shall not extend higher than the top of the wall to which they are attached. Flat roof and roof projecting signs may extend no more than five (5) feet above the lowest point where they are attached to the building and may not extend above the highest point of the roof.	5 feet, but not closer than 10 feet from any lot line.	All	No flat wall, wall projecting, flat roof, roof projecting or window sign shall be larger than 15% of the surface area (i.e. wall, windows and/or roof) to which the sign is attached.	No
2. Signs for lawfully conducted activities upon common residential property	1 per vehicle entrance; maximum two signs	16 square feet, <u>plus</u> 1 square foot per each dwelling unit in excess of 16 units, not to exceed 48 square feet per sign.	15 feet		C, A, LDR & MU	Yes		
3. Signs for lawfully conducted activities associated with and on the premises of an individual non-residential principal use.	1 freestanding sign per principal use, unlimited wall, window or roof signs	24 square feet, <u>plus</u> 2 square feet per 5 lineal feet of lot frontage, not to exceed 64 square feet of total sign area.	15 feet		MI & BI	Yes		
4. Signs for lawfully conducted activities upon common non-residential property	1 per vehicle entrance; maximum two signs	24 square feet, <u>plus</u> 2 square feet per 5 lineal feet of lot frontage, not to exceed 64 square feet per sign.	15 feet		No wall projecting sign shall project more than forty-eight (48) inches from the surface to which it is attached over a public sidewalk.	Yes		
5. Signs for lawfully conducted activities associated with and on the premises of an individual non-residential principal use.	1 freestanding sign per principal use, unlimited wall, window or roof signs	4 square feet, <u>plus</u> 1 square foot per 10 lineal feet of lot frontage, not to exceed 8 square feet of total sign area.	15 feet		C & A	Yes		
6. Signs for lawfully conducted activities associated with and on the premises of an individual non-residential principal use.	1 freestanding sign per principal use, unlimited wall, window or roof signs	16 square feet, <u>plus</u> 1 square foot per 10 lineal feet of lot frontage, not to exceed 32 square feet of total sign area.	15 feet		MU	Yes		
7. Signs for lawfully conducted activities upon common non-residential property	1 per vehicle entrance; maximum two signs	4 square feet, <u>plus</u> 1 square foot per 10 lineal feet of lot frontage, not to exceed 8 square feet of total sign area.	15 feet		MU	Yes		

§322.D. - PERMANENT SIGN REQUIREMENTS (TABLE 1)

Sign Type	Maximum Permitted Number	Maximum Permitted Sign Area	Maximum Height of Freestanding Signs	Maximum Height of Wall, Window and Roof signs	Maximum Projection from Wall/Roof Projecting Signs	Permitted Zones	Other Requirements	Zoning Permit Required
8. On-site directional, directory, entrance, exit, rest room, and other informational signs.	4 per principal use	2 square feet per sign; 8 square feet if the sign is not legible from an adjoining road or adjoining property.	5 feet		2 feet	All		No
9. Residential nameplates identifying name of home, its occupant, or both, not including name listing on mailbox.	1 per dwelling unit	2 square feet	5 feet	10 feet	Not Permitted	All		No
10. Property control signs (e.g., "No Trespassing," "Private Property," "No Hunting or Fishing," "Posted," "Private Drive," or similar type signs).	1 per 25 lineal feet of property line	2 square feet per sign	5 feet	Not Permitted	Not Permitted	All	Spacing at no less than 25 foot intervals.	No

§322.D. - TEMPORARY SIGN REQUIREMENTS (TABLE 2)

Sign Type	Maximum Permitted Number	Maximum Permitted Sign Area	Maximum Height of Freestanding Signs	Maximum Height of Wall, Window and Roof signs	Maximum Projection from Roof/Wall for Projecting Signs	Permitted Zones	Other Requirements	Zoning Permit Required
11. Signs for lawfully conducted activities associated with an individual residence or farm, including but not limited to signs for roadside stands, real estate, open house, yard sale, political and etc.	1 sign per principal use	4 square feet per sign.	5 feet	Flat wall, window and wall projecting signs shall not extend higher than the top of the wall to which they are attached. Flat roof and roof projecting signs may extend no more than five (5) feet above the lowest point where they are attached to the building and may not extend above the highest point of the roof.	5 feet, but not closer than 10 feet from any lot line.	All	Such signs shall be removed within 7 days after the purpose for the sign no longer exists. In the case of temporary non-residential signs (other than political signs), such signs shall be limited to no more than 30 continuous days and no more than sixty days during each calendar year. Should a sign be left on-site beyond allowable time period, the Township may impound it and recover a fee from owner equal to cost of impoundment and storage.	No, unless a commercial message is displayed in which case a permit is required.
12. Signs for lawfully conducted activities associated with an individual non-residential principal use including but not limited to signs for special event sales, real estate, open house, political and etc.	1 sign per principal use	6 square feet, <u>plus</u> 2 square feet per 10 lineal feet of lot frontage, not to exceed 12 square feet per sign.	10 feet		20 feet, but not closer than 10 feet from any lot line.	MU		
13. Signs for lawfully conducted activities associated with an individual non-residential principal use including but not limited to signs for special event sales, real estate, open house, political and etc.	1 sign per principal use	4 square feet, <u>plus</u> 1 square feet per 10 lineal feet of lot frontage, not to exceed 8 square feet per sign.	10 feet		No wall projecting sign shall project more than forty-eight (48) inches from the surface to which it is attached over a public sidewalk.	C & A		
14. Signs for lawfully conducted activities associated with an individual non-residential principal use including but not limited to signs for special event sales, real estate, open house, political and etc.	1 sign per principal use	16 square feet, <u>plus</u> 1 square feet per 10 lineal feet of lot frontage, not to exceed 32 square feet per sign.	10 feet			MI & BI		

§ 322.D. – PLANNED CENTER SIGN REQUIREMENTS (TABLE 3)

Sign Type	Maximum Number Permitted	Maximum Permitted Sign Area	Maximum Permitted Height	Other Requirements	Zoning Permit Required
15. Freestanding planned center sign	1 per street frontage with entrance or exit	1 square foot for each 4 lineal feet of frontage within the shopping center, with a maximum of 100 square feet	20 feet	This sign shall devote no less than 50% of the total sign area (per side) to the advertisement of the planned center's name.	Yes
16. Anchor tenant sign for each use containing more than 150 lineal feet of store-front.	Unlimited within the allowable total sign area	If sign is less than 300 feet from facing street, then sign can be up to a maximum of 100 square feet. If sign is more than 300 feet from facing street, then sign can be up to a maximum of 150 square feet.	Height of wall to which sign is attached.	These signs shall only be provided as flat wall, window, wall projecting, flat roof or roof projecting signs.	Yes
17. Storefront sign for each use containing up to 150 lineal feet of storefront.	Unlimited within the allowable total sign area	2 square feet per lineal foot of storefront up to a maximum of 75 square feet	Height of wall to which sign is attached.	These signs shall only be provided as flat wall, window, wall projecting, flat roof or roof projecting signs.	Yes
18. Storefront under-canopy signs for all principal uses.	1 per use with less than 150 lineal feet of storefront. 2 per use with more than 150 lineal feet of storefront.	8 square feet	To base of canopy, or where no canopy is provided, 10 feet.	No under-canopy sign shall have a vertical dimension of more than 18 inches from its lowest to highest point. The base of an under-canopy sign shall be no less than 8 feet, 6 inches above the finished grade below such sign.	Yes
19. Outparcel signs for principal freestanding uses sharing common ingress and egress to planned center.	2 per principal use, but only 1 per wall	75 square feet per sign, not exceeding 20% of wall area to which sign is attached.	Height of wall to which sign is attached.	These signs shall only be provided as flat wall, window, wall projecting, flat roof or roof projecting signs.	Yes

322.E. COORDINATED SIGNS

As an alternative to separate freestanding signs, uses may provide for coordinated freestanding signage among several principal uses. In so doing each tenant is permitted 60 percent of their respective freestanding sign area upon the coordinated freestanding sign plus the ability to erect a flat wall, window or wall projecting sign at 60 percent that otherwise permitted for the use under Section 322.D. of this Ordinance. Such coordinated signage must be located no less than 10 feet from the street right of way, not exceed 15 feet in height and include a sign easement agreement in language acceptable to the Township solicitor which assures each use adequate sign display and ensures adequate sign maintenance.

322.F. NON-CONFORMING SIGNS

Non-conforming signs may continue to be displayed as long as there is compliance with the following limitations and conditions.

1. There shall be no expansion or increase in the non-conforming aspect in any way.
2. Maintenance and repair of the sign are permitted. If necessary, up to fifty (50) percent of the entire area of a sign and its supporting structure may be replaced in the event of damage. Any such replacement must be completed within six (6) months of the damage occurring.
3. The sign must be brought into conformity if, for a period of at least twelve (12) months, the message has no longer applied to an activity on the premises (this does not apply to billboards).

322.G. PERMITTING PROCEDURES AND FEES

Permits for the placement of signs are required as indicated by the last column in the Tables listed in Section 322.D. of this Ordinance. All signs requiring permits must have such permit prior to the erection, installation, or alteration of the sign. Sign permit applications, forms, plan requirements, and fees shall be established by resolution of the Board of Supervisors.

1. Application for permit shall be made in writing to the Zoning Officer and shall contain all information necessary for such Officer to determine whether the proposed sign, or the proposed alterations, conform to the requirements of this Ordinance. All applications for sign permits shall be accompanied by scaled plans or diagrams showing the following:
 - a. exact dimensions of the lot including any right-of-way lines or building upon which the sign is proposed to be erected;
 - b. exact size, dimensions, and location of the said sign on the lot or building together with its type, construction, materials to be used, and the manner of installation; and
 - c. any other lawful information that may be required of the applicant by the Zoning Officer.
2. No zoning permit shall be issued except in conformity with the regulations of this Ordinance, except upon order of the Zoning Hearing Board, granted pursuant to the procedures established for the issuance of a variance.

SECTION 323 ZONING REQUIREMENTS FOR USE OF ON-LOT SEWAGE DISPOSAL SYSTEMS

323.A. TWO DISPOSAL SITES REQUIRED

As of the effective date of this Ordinance, all newly created lots that rely upon on-lot sewage disposal systems shall be required to provide for a primary and back-up site location in compliance with the Dickinson Township Sewage Facilities Management Ordinance (Chapter 159 of the Dickinson Township Code of Ordinances.)

323.B. MINIMUM LOT AREA

Regardless of any maximum lot area requirements listed elsewhere in this Ordinance, the minimum required lot size may be increased to ensure an acceptable level of nitrate-nitrogen in the adjoining groundwaters. Such determinations will be made by the PA DEP, through its sewer module review process. In those cases where applicable maximum lot area requirements are exceeded to protect groundwater quality, the applicant shall furnish evidence that the amount of land needed to protect local groundwater is the minimum necessary for such protection.

323.C. DISPOSAL PLUME EASEMENT

In the Agricultural Zone and in lieu of the increased lot size described in the previous Section 323.B., an applicant who intends to make use of an on-lot sewage disposal system may secure and protect a sewage disposal plume easement to insure an acceptable level of nitrate-nitrogen in the adjoining groundwaters. Such easement shall be in a form acceptable to the Township Solicitor and the size and extent of the sewage plume easement shall be approved by the PA DEP, through its sewer module review process. Any agricultural land preserved in the Cumberland County Farmland Preservation Program is not eligible for the disposal plume easement.

Article 4

Specific Criteria

Section 401 Specific Criteria for Permitted Uses, Special Exceptions and Conditional Uses

401.A. APPLICABILITY

It is the intent of this Article to provide special controls and regulations for particular uses that are permitted by right, special exception, or conditional use within the various Zones established in this Ordinance. All uses must comply with the standards expressed within the underlying Zone and all other applicable sections of this Ordinance and the SALDO, unless those standards expressed within this Article differ; in such case, the specific standards listed within this Article shall apply.

401.B. PERMITTED USES

For uses permitted by right, these standards must be satisfied prior to approval of any application for a land development (when applicable) or a zoning permit. The applicant shall have the burden of proof that the proposed use is in compliance with these standards and all applicable regulations contained within this Ordinance and must furnish whatever evidence is necessary to demonstrate such compliance.

401.C. SPECIAL EXCEPTIONS

For uses permitted by special exception, this Article sets forth standards that shall be applied to each respective special exception. The applicant shall have the burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and those contained within this Article 4. The applicant shall also submit competent evidence demonstrating a substantial likelihood of compliance with the requirements of Article 5 of this Ordinance. These standards must be satisfied prior to approval of any application for a special exception by the Zoning Hearing Board.

401.D. CONDITIONAL USES

For uses permitted by conditional use, this Article sets forth standards that shall be applied to each respective conditional use. The applicant shall have the burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and those contained within this Article 4. The applicant shall also submit competent evidence demonstrating a substantial likelihood of compliance with the requirements of Article 5 of this Ordinance. These standards must be satisfied prior to approval of any application for a conditional use by the Board of Supervisors.

401.E. SETBACK MEASUREMENTS

For the purposes of this Article 4, any required setbacks imposed upon any use, building and/or structure, may be measured from the boundary line of the site for which the proposed use, building and/or structure is requested, regardless of whether or not this line corresponds to a property line or a lease line.

Section 402 Adult Entertainment Uses

402.A. Within the (MI) Zone, adult entertainment uses are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:

402.B. An adult entertainment use shall not be permitted to be located within one thousand feet (1,000') of any other adult-related use;

402.C. No adult entertainment use shall be located within one thousand feet (1000') of any land within the (LDR and MU) Zones;

402.D. No adult entertainment use shall be located within one thousand feet (1000') of any parcel of land which contains any one or more of the following specified land uses:

1. Amusement park;
2. Camp (for minors' activity);
3. Childcare facility;
4. Church or other similar religious facility;
5. Community center;
6. Museum;
7. Park;
8. Playground;
9. School; or
10. Other lands where minors congregate.

402.E. The distance between any two adult entertainment uses shall be measured in a straight line, without regard to intervening structures, from the closest point on the exterior property line of each establishment. The distance between any adult entertainment use and any land use specified above shall be measured in a straight line, without regard to intervening structures, from the closest point on the exterior property line of the adult-related use to the closest point on the property line of said land use;

402.F. No materials, merchandise, or film offered for sale, rent, lease, loan, or for view upon the premises shall be exhibited or displayed outside of a building or structure;

402.G. Any building or structure used and occupied as an adult use shall be windowless, or have an opaque covering over all windows or doors of any area in which materials, merchandise, or film are exhibited or displayed, and no sale materials, merchandise, or film shall be visible from outside of the building or structure;

402.H. No sign shall be erected upon the premises pictorially depicting or giving a visual representation of the type of materials, merchandise or film offered therein;

402.I. Each entrance to the premises shall be posted with a notice specifying that persons under the age of eighteen (18) years are not permitted to enter therein and warning all other persons that they may be offended upon entry;

- 402.J. No adult use may change to another adult entertainment use, except upon approval of an additional conditional use;
- 402.K. The use shall not create an enticement for minors because of its proximity to nearby uses where minors may congregate;
- 402.L. No unlawful sexual activity or conduct shall be permitted; and,
- 402.M. No more than one adult entertainment use may be located within one building or industrial park.

Section 403 Airports/Heliports

- 403.A. Within the (M1 and B1) Zones, airports/heliports are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:
- 403.B. **MINIMUM LOT AREA** - Thirty (30) acres for airports and five (5) acres for heliports;
- 403.C. All facilities shall be designed in strict compliance with all applicable State and Federal laws and regulations;
- 403.D. The applicant shall furnish evidence of the obtainment of a license from the Pennsylvania Department of Transportation, Bureau of Aviation, prior to the approval of the conditional use application;
- 403.E. The applicant shall furnish evidence of the techniques that will be used to employ “fly-neighborly” guidelines to avoid adverse audio-visual impacts to nearby residents and livestock; and,
- 403.F. No part of the take-off/landing strip and/or pad shall be located nearer than three hundred feet (300') from any property line.

Section 404 Alternative Energy Systems

- 404.A. Within every Zone, alternate energy systems are permitted accessory uses by right, subject to the following requirements:
- 404.B. Alternate energy systems constructed prior to the effective date of this Ordinance shall not be required to meet the requirements specified under this section of the Zoning Ordinance. Any physical modification to an existing alternate energy system that materially alters the size, type and quantity of the facilities shall require a zoning permit and shall comply with the applicable provisions specified under this section of the Zoning Ordinance.
- 404.C. Alternate energy systems shall be primarily utilized by the principal use of the lot upon which it is located, and energy generated must first be used to meet the demand on-site. Surplus energy may be exchanged, transferred and/or sold to a public or private utility company, if the applicant submits written expert evidence that the proposed alternate energy system is designed not to exceed the following energy generating parameters:
 - 1. The maximum energy generated for a residential use shall not exceed 1.5 times the annual energy needs of the principal residential use upon whose site the alternate energy system is located.
 - 2. The maximum energy generated for a commercial use shall not exceed 2.0 times the annual energy needs of the principal commercial use upon whose site the alternate

energy system is located.

3. The maximum energy generated for an industrial use shall not exceed 3.0 times the annual energy needs of the consumer of the principal industrial use upon whose site the alternate energy system is located.
4. The maximum energy generated for a governmental, school, hospital, church and/or other similar institutional use shall not exceed 4.0 times the annual energy needs of the consumer of the principal use upon whose site the alternate energy system is located.
5. The maximum energy generated for a municipal use shall not exceed 5.0 times the annual energy needs of the consumer of the municipal use upon whose site the alternate energy system is located

404.D. The owner of any alternate energy system connected to an electric utility grid shall provide the Township with written authorization from the utility acknowledging and approving such connection.

404.E. Alternate energy systems may be erected as detached accessory structures or attached to a building provided that the structural components of such systems do not exceed the permitted height requirements of the Zone in which it is located except that:

1. the total height of a building or structure with solar panels shall not exceed by more than one (1) foot the maximum permitted height in the applicable zone;
2. ground-mounted solar panels shall not exceed a height of 20 feet at the highest point of the structure;
3. the maximum height of a freestanding wind turbine and any supporting structure shall be fifty (50) feet for non-agricultural uses and one-hundred fifty feet (150) for agricultural uses, as measured from the ground surface to the tip of the blade at its highest turning movement;
4. the maximum height of a roof-mounted wind turbine and any supporting structure shall be ten feet (10') as measured from the highest roof surface to the tip of the blade at its highest turning movement; and,
5. all structures that exceed the maximum permitted height within its respective Zone shall demonstrate compliance with Section 309 of this Ordinance.

404.F. Except as noted in Section 404.O.7.B. of this Ordinance, alternate energy systems may be erected as detached accessory structures or attached to a building provided that the structural components of such systems (along with other site improvements) do not exceed the maximum permitted lot coverage requirements of the Zone in which it is located.

404.G. Alternate energy systems may be erected as detached accessory structures or attached to a building provided that the structural components of such systems comply with all applicable setbacks of the zone in which it is located. Detached accessory systems shall comply with applicable accessory use setbacks. Systems attached to a principal structure will be required to comply with principal use setbacks. In Zones with no accessory use setbacks, principal use setbacks shall apply.

404.H. Above-ground alternate energy systems shall be clear-coated, transparent, and/or be designed with a non-obtrusive color such as white, off-white or gray. All such facilities shall not be artificially lighted, except to the extent required by the Federal Aviation Administration or other applicable authority that regulates air safety.

404.I. On-site electrical transmission and power lines connected to or associated with the alternate energy system that are not contained within a building shall be located underground.

- 404.J.** Clearly visible warning signs concerning voltage must be placed at the base of all above-ground transformers and substations. Visible, reflective, colored objects, such as flags, reflectors, or tape shall be placed on the anchor points of guy wires and along the guy wires up to a height of ten (10) feet from the ground.
- 404.K.** The applicant shall provide written evidence that the proposed alternate energy system shall comply with the noise standards as referenced and incorporated through Section 316 of this Ordinance. A manufacturer's certificate of specification may be used to demonstrate compliance with this standard.
- 404.L.** The applicant shall make reasonable efforts to avoid any disruption or loss of radio, telephone, television or similar signals, and shall mitigate any harm caused by the alternate energy system.
- 404.M.** The applicant shall provide written evidence from the Chief of the "first-due" fire company that the proposed use can be adequately protected and that, if necessary, a suitable emergency response plan has been implemented to serve the proposed use.
- 404.N.** The design and installation of the alternate energy system shall conform to applicable industry standards, including those of the American National Standards Institute and the Uniform Construction Code and be subject to all applicable permit requirements thereof as well as all other applicable laws, codes and regulations.
- 404.O.** In addition to those materials required in Section 801 for a zoning permit, applicants for alternate energy systems shall be required to submit:
1. a narrative describing the system and its principal components including, but not limited to related ancillary facilities;
 2. information about its potential energy generating capacity and anticipated generation; and,
 3. a site plan depicting the system and its principal components including, but not limited to related ancillary facilities as they relate to property lines, required setbacks, adjoining roads, utility rights-of-way and lines, and on-site buildings and structures. Such information shall be depicted upon the site plan even if it is located underground.
- 404.P. SOLAR ENERGY SYSTEMS SHALL COMPLY WITH THE FOLLOWING REQUIREMENTS:**
1. Solar energy panels shall be designed and located in order to minimize reflective glare towards any adjoining use and/or road.
 2. All solar energy system installations must be performed by installers certified by a professional firm from a list of approved Pennsylvania solar electric installers provided on the North American Board of Certified Energy Practitioners website.
 3. Solar energy systems shall not be used for displaying advertising except for reasonable identification of the manufacturer of the system. In no case shall such identification exceed 200 square inches.
 4. When a building is necessary for the storage of cells and/or equipment or components related to the solar energy system, the building must not exceed 400 square feet in area, must not exceed fifteen (15) feet in height and must comply with all applicable accessory use setbacks. Where no accessory use setbacks apply, principal use setbacks shall apply.
 5. All owners of property upon which a solar energy system is installed shall be required, as a condition of the issuance of the zoning permit to acknowledge in writing to the Township that the issuance of a zoning permit for a solar energy system shall not and

does not create in the property owner, its, his, her or their successors and assigns in title or, create in the property itself:

- a. the right to remain free of shadows and/or obstructions to solar energy caused by development of adjoining or other property or the growth of any trees or vegetation on such property; or,
- b. the right to prohibit the development on, or growth of any trees or vegetation on, such property.

6. **Roof-mounted solar energy systems shall comply with the following requirements:**

- a. Solar panels shall not extend beyond any portion of the roof's horizontal edge.
- b. A written structural roof analysis, approved and stamped by a certified engineer pursuant to UCC requirements, shall be required for all roof-mounted solar energy systems.
- c. Other than those integrated into the roof or mounted flush with the roof, solar panels shall be located only on rear or side-facing roofs as viewed from any adjacent street unless the proposed location prevents the solar energy system from operating as designed, as certified in writing by the manufacturer or installer. Removal of potential obstructions such as vegetation shall not be considered sufficient cause for permitting panel installation on a front-facing roof.

7. **Ground-mounted solar energy systems shall comply with the following requirements:**

- a. Ground-mounted solar energy systems (also referred to as "ground arrays") shall be located so that any sun reflection is directed away from or is properly screened from adjoining property.
- b. The surface area of a ground-mounted solar energy system, regardless of the mounted angle of any solar panels, shall be considered part of and calculated in the lot coverage of the lot on which the system is located. The surface area of a ground-mounted solar energy system shall not exceed three percent (3 %) of maximum lot coverage of the lot. For panels that self-adjust, the lot coverage of each solar panel shall be calculated at that angle with the greatest horizontal exposure.
- c. Solar panels shall not be mounted on any pole or tower such that the closest point of the solar panel is more than one (1') foot above the grade directly below the solar panel.
- d. Unless no other suitable location exists upon a property, a solar energy system, or part thereof, may be located within the front yard provided it is located behind the required building setback line and vegetative screening is provided to serve as a barrier to visibility and glare, subject to the following standards:
 - i. All vegetative materials shall reach a minimum height of six feet above finished grade within two years of planting. However, all vegetative materials used for screening of an industrial use shall be six feet at initial planting.
 - ii. The vegetative screen shall be permanently maintained in order to ensure effective screening and replaced when necessary.
 - iii. The vegetative screen must be comprised of plant material that will provide a minimum opacity of 80% year-round. One of the following arrangements shall be utilized:
 - [a] Screen planting shall contain three staggered rows of vegetative

material. This screen planting shall consist of one row of fast-growing needled evergreens spaced not more than 12 feet on center and two rows of deciduous trees, with a minimum height potential of 20 feet, spaced not more than 25 feet on center.

[b] Screen planting shall contain two staggered rows of vegetative material. Seventy-five percent shall be fast-growing needled evergreens planted 10 feet on center and staggered for effective screening. The remaining 25% shall be deciduous trees planted in staggered clusters with 25 feet being the maximum spacing between trees.

[c] Screen planting shall contain two staggered rows of vegetative material. Seventy-five percent shall be fast-growing needled evergreens planted 10 feet on center and staggered for effective screening. Fifteen percent shall be deciduous trees planted in staggered clusters 25 feet on center. The remaining 10% shall be staggered shrub masses used as understory plants and in combination with deciduous tree clusters. The maximum spacing for shrubs shall be four feet on center. The deciduous trees and shrubs are suggested to break up the straight-line planting of one type of plant material.

iv. Prior to issuance of a zoning permit, a sketch plan showing the proposed arrangement, placement, species and size of all screen planting material shall be submitted for approval to the Dickinson Township Zoning Officer. Only those specific plant arrangements listed above in Section 404.O.7.D.3.a.-c. of this Ordinance may be used for vegetative screening. All such plant materials shall comply with Section 321 of this Ordinance.

404.Q. THE FOLLOWING PROVISIONS SHALL SPECIFICALLY APPLY TO WIND TURBINES:

1. Only one wind turbine shall be permitted per principal use, except that agricultural uses may have up to two, all of which must be accessory to the principal use of the site.
2. Wind turbines may only be permitted upon lots with a minimum of two and one-half (2½) acres.
3. The minimum height of a wind turbine shall be such that there shall be maintained a minimum of fifteen (15) feet ground clearance, as measured between the ground surface and the tip of the blade at its closest point of the turning movement.
4. Wind turbines shall be setback the following distances as measured from the center of the wind turbine base to the nearest point of the respective feature listed below:

Feature	Minimum setback
Occupied building on site	Turbine height plus ten feet
Above ground utility line right-of-way	Turbine height plus ten feet
Adjoining property	1.5 times turbine height
Adjoining road right-of-way*	1.5 times turbine height

*This Section shall not be interpreted to permit the location of a wind turbine in the front yard if such structure is not permitted in the front yard within its respective Zone.

5. A wind turbine and any supporting structure shall be enclosed by a six (6) foot fence with locking gate or the base of the wind turbine and any supporting structure shall not be climbable for a minimum height of twelve (12) feet. All access doors to wind turbines and electrical equipment shall be locked or fenced, as appropriate, to prevent entry by non-authorized persons.
6. All wind turbines and wind energy systems shall be equipped with a redundant braking system, which shall include both aerodynamic over-speed controls (including variable pitch, tip, and other similar systems) and mechanical brakes. Mechanical brakes shall be operated in a fail-safe mode. Stall regulation shall not be considered a sufficient braking system for over-speed protection.
7. The applicant shall make reasonable efforts to minimize shadow flicker to adjoining properties.
8. No wind turbine shall cause ground vibrations perceptible beyond the property line of the site.
9. No wind turbine shall cause ice to be thrown or shredded beyond the property line of the site.
10. No trees or landscaping required by Township Ordinance, or as otherwise required by the Board of Supervisors or Zoning Hearing Board as a condition of approval for any plan, application or permit may be removed to facilitate installation or operation of a wind turbine.

404.R. THE FOLLOWING PROVISIONS SHALL SPECIFICALLY APPLY TO GEOTHERMAL SYSTEMS:

1. Any open discharge system must discharge water back into well to promote groundwater recharge. Any geothermal system plan must be pre-approved by the Township for appropriate disposal or reuse of water.
2. Prior to installation, all installation specifications and drawings for the geothermal system must be certified by a registered engineer within the Commonwealth of PA as conforming to the International Ground Source Heat Pump Association (IGSHPA) installation standards;
3. The vertical geothermal system well (or wells) installation will be made only by a Pennsylvania-licensed well driller;
4. No geothermal system sub-surface loops will be located closer than twenty feet (20') from any existing or planned drinking water wells;
5. The vertical loop in a geothermal system well (or wells) shall be pressure-grouted bottom to top with a bentonite-based or cement-based material of 0.0000001 centimeter per second or lower permeability; and
6. With respect to each geothermal system well installation, the Pennsylvania-licensed well driller and/ or system installer shall provide to the Township, before activation of the system copies of:
 - a. Accurate written records and a written geologic log;
 - b. Accurate records with respect to grouting for each such well;
 - c. "As-built" plans and related documentation for each such system and well

location;

- d. Written documentation of the geothermal system testing and certification; and
- e. A written "plan" for the operation of the geothermal system proposed by the applicant and approved by the system installer which, among other matters, provides that:
 - i. Any geothermal system leaks or releases will be reported by the applicant (and subsequent owner) to the Township Zoning Officer within twenty-four (24) hours of the discovery of same, and the applicant (and subsequent owner) covenants and agrees to take appropriate action to minimize any fluid release to the ground and to promptly repair any system leaks; and
 - ii. In the event of the proposed discontinuance of the use of the geothermal system, a system closure plan will be prepared and submitted to the Township for its approval by the landowner prior to the conveyance by the landowner of the land to any third party.

404.S. Manure digester facilities shall only be permitted as an accessory use to an agricultural or horticultural use.

Section 405 Public Utility Structures

- 405.A.** Within the (MU, MI and BI) Zones, public utilities structures are permitted by right provided that the owner/occupier's use complies with all applicable regulations contained within this Ordinance and specifically this section.
- 405.B.** All equipment not housed within a structure shall be enclosed with a fence or wall not less than six feet in height, which shall be so constructed as not to have openings, holes or gaps larger than six inches in any dimension. In the MU Zone, such fence must be surrounded by evergreen plantings.
- 405.C.** When the equipment is totally enclosed within a structure, no fence or screen planting shall be required, and the yard shall be maintained in conformity with the zone in which the structure is located.
- 405.D.** In the MU Zone, any public utilities structures shall not include the storage of vehicles or equipment used in the maintenance of any utility, and no equipment causing excessive noise, vibration, smoke, odor or hazardous effect shall be installed.
- 405.E.** Land development plans of the public utilities structure shall be submitted to the Township for review and approval, and as required in the Township's SALDO.
- 405.F.** Improved access shall be provided to the site in accordance with the specific requirements of the Board of Supervisors. Access shall be by way of a portion of the lot which it serves, minimum 20 feet wide, or by an easement or right-of-way.

Section 406 Domestic Pets

- 406.A.** Within all Zones of the Township, the noncommercial keeping of domestic pets, as defined in Section 112, is a permitted accessory use to any residential dwelling use subject to the following criteria:
- 406.B.** No more than 10 domestic pets may be kept in a residential dwelling unit as an accessory use.

406.C. The above number limitations shall not apply to any domestic pet that has given birth, provided that any offspring kept into adulthood as a domestic pet shall then be included in the total number of domestic pets. Such offspring may be given away to new homes, or for a nominal rehoming fee. However, the commercial breeding of domestic pets under this Section 406 shall be strictly prohibited.

406.D. The noncommercial keeping of domestic pets, regardless of the Zone, shall be done pursuant to the provisions set forth in Chapter 58, entitled "Animals," of the Code.

Section 407 Animal Hospitals and Veterinary Offices

407.A. Within the (MU, MI and BI) Zones, animal hospitals and veterinary offices are permitted by right provided that the owner/occupier's use complies with all applicable regulations contained within this Ordinance and specifically this section.

407.B. Within the (MU) Zone no outdoor keeping of animals is permitted;

407.C. All animal boarding buildings that are not completely enclosed, and any outdoor animal pens, stalls, or runways shall be located within the rear yard;

407.D. All animal boarding buildings that are not completely enclosed, and any outdoor animal pens, stalls, or runways shall be setback a minimum of one hundred (100) feet from all property lines.

Section 408 Auction House, Excluding Automobile Auctions

408.A. Within the (BI) Zone, auction houses, excluding automobile auctions, are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:

408.B. All auction activities shall be conducted within a completely enclosed building.

408.C. No outdoor storage or display is permitted.

408.D. Off-street parking shall be provided at the rate of one (1) space per each two (2) persons of legal occupancy within the auction house, plus one (1) space per employee on the site at any one time.

408.E. A minimum of four off-street loading spaces shall be provided, subject to increases in accordance with the schedule listed in Section 314 of this Ordinance.

408.F. Should the proposed use include a cafeteria or refreshment counter, the applicant shall furnish and continuously implement an acceptable working plan for the collection of litter and debris.

Section 409 Automobile and/or Animal Racing Facility With or Without Related Wagering

409.A. Within the (MI) Zone, automobile and/or animal racing facilities with or without related wagering are permitted by conditional use provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:

409.B. PURPOSE

This Section provides for a two-stage review process for large-scale amusement uses that is consistent with the Pennsylvania Municipalities Planning Code by encouraging innovation and promoting flexibility, economy and ingenuity in the development process. Specifically, applications submitted under this Section will be required to obtain a conditional use approval of a Master Concept Plan that will require detailed explanation of the proposed use's design, operation and impacts. Then once the Master Concept Plan is approved, subsequent revisions or adjustments that were contemplated under the approved Master Concept Plan will be regulated as permitted uses. Subsequent alterations that were not contemplated by the previously approved Master Concept Plan will require another conditional use approval.

409.C. DESIGN AND OPERATIONAL OBJECTIVES

Applications submitted pursuant to this Section are required to demonstrate to the satisfaction of the Board of Supervisors that:

1. The proposed uses are coordinated to function as a single site;
2. The proposed design will provide for efficient functioning of the proposed use amid its surroundings without creating undue adverse impact;
3. The proposed use has access to adequate utilities and public services to ensure the public welfare upon the site and will not overburden such utilities and services to the detriment of the rest of the Township;
4. The proposed use is designed, where practicable, to properly integrate and protect important natural features contained upon the site both during and after construction and during subsequent operation of the use;
5. The applicant has a management structure and capacity that can ensure that these preceding objectives will be continuously satisfied.

409.D. STAGE 1- CONCEPT MASTER PLAN

Prior to, or coincidental with, the approval of a land development for any of the uses regulated in this Section, the applicant shall submit a Concept Master Plan for conditional use approval by the Board of Supervisors in accordance with Section 805 of this Ordinance. The requirements of this Section 409 shall be used as the specific criteria for evaluating the conditional use application. Such Concept Master Plan shall be submitted by the applicant and shall include a textual and/or graphic description of the following items:

1. The location, boundaries, dimensions, acreage, and ownership of the land to be included within the proposed use;
2. The specific types and mixture of uses proposed for the land to be included within the proposed use. This will require submission of a schematic drawing of proposed use types within their respective areas along with a disturbance envelope within which all development activities will be confined;
3. A listing of the relevant design standards applied to the use as required by the Zoning Ordinance and a determination of the proposed use's compliance with such standards. Should the Board of Supervisors attach a condition of approval, pursuant to Section 905.C. of this Ordinance that imposes a different standard than that of the Zoning Ordinance, such conditioned standard shall be listed along with the use's determination of compliance;

4. The circulation network contained upon the land to be included within the proposed use including roads, sidewalks, off-street parking lots, unimproved overflow parking areas, off-street loading areas, emergency access points, major intersections and any traffic improvements proposed to accommodate the proposed use;
5. The name, location, centerline and present right-of-way width of all abutting streets;
6. The natural and cultural features information as required by Article 5 of this Ordinance.
7. Any regional facilities that are proposed and will serve more than one lot within the proposed development. Examples of such facilities could include storm water management devices, open space areas, pedestrian pathways, signs, and wastewater or water facilities;
8. Qualified expert testimony and impact reports that demonstrate compliance with each of the following requirements and provide for an upset limit of impact regarding each requirement (e.g. maximum traffic volume, maximum sound pressure, maximum structure height, maximum glare, etc.)
9. A traffic impact study as required by Section 319 of this Ordinance;
10. Access management so as not to cause traffic backup onto adjoining roads during peak entrance and exit periods. This shall require special attention to, and description of, the on-site stacking volumes caused by toll booth locations and the number, location, and times of traffic control personnel posting;
11. Noise standards as referenced and incorporated through Section 316 of this Ordinance.;
12. Lighting as regulated by Section 310 of this Ordinance;
13. Hours of public operation which will be limited between noon and 10:00 PM;
14. Methods of water supply and sanitary sewage disposal in accordance with applicable state regulations. If public water and/or sewer is to be used, documentation by the respective agency of the adequacy of such system to serve the proposed use;
15. Methods of policing and security to include a written statement from the ranking police officer that adequate police protection is available to serve the proposed use. Also the applicant is required to provide expert evidence regarding security measures that will be used on the site to ensure adequate public safety during and after conduct of the proposed use;
16. Methods of fire protection and ambulance service to include written statements from the chiefs of the first-due fire company and ambulance company that will serve the proposed use that attest that adequate fire protection and ambulance service are available to serve the proposed use;
17. Capacity of off-street parking lots and off-street loading areas in relation to the required spaces listed in Sections 315 and 314, respectively, of this Ordinance. In addition, an unimproved grassed overflow parking area shall be provided for peak use periods. Such overflow parking areas shall be accessible only from the interior access drives of the permanent parking lot. Overflow parking areas shall contain fencing to confine vehicles on the site;
18. The handling and disposal of materials and wastes as required by Section 313 of this Ordinance;

19. Methods used to contain, collect and dispose of litter on the site. This shall include a written description of an acceptable working plan for litter clean-up;
20. For uses involving the keeping of animals, a written plan that describes the methods used to: (1) contain and prevent their escape; (2) dispose of deceased animals in compliance with applicable State laws; (3) handle, and dispose of animal wastes in a manner that is compatible with surrounding uses both on and off of the site; and, (4) offer the humane treatment and care of animals at all times.
21. Scaled graphic representations of those signs used to attract the public onto the site in accordance with Section 322 of this Ordinance; and,
22. Exterior areas used for the storage of automobiles or other vehicles shall be completely enclosed by a six-foot (6') high fence and shall be subject to the (BI) Zone's setback, landscaping and screening requirements imposed upon off-street parking lots. The outdoor storage of vehicle parts, lubricants and fuels, or other materials or equipment used in the service of motor vehicles and the demolition or junking of vehicles is prohibited.
23. Maximum permitted height for uses regulated by this Section can exceed forty-five (45) feet provided:
 - a. That the proposed structure is setback a horizontal distance at least equal to its height from each property line;
 - b. The applicant must demonstrate that adequate local rescue and fire-fighting capacity exists to ensure the safety of those who might be located above forty-five (45) feet by reason of adequate emergency vehicles and equipment and/or employed fire suppression measures;
 - c. The applicant must submit that the proposed structure does not violate Federal Aviation Regulations No. 77, as may be amended, or any successor regulation;
 - d. The applicant must demonstrate compliance with the BOCA National Fire Prevention Code, 1999 as may be amended;
 - e. If applicable, the applicant must demonstrate compliance with the American Society of Testing Materials (ASTM) F770-88 Standard Practice for Operation Procedures for Amusement Rides and Devices;
 - f. An integrated telephone system that has a two-hour fire rating shall be provided on all floors;
 - g. If proposed, standpipe and sprinkler connection fixtures shall be located so as to be readily accessible to firefighting personnel and hose pre-connects for full access to each floor shall be provided;
 - h. Knox boxes shall be provided where any automatic fire alarm, detection or suppression systems are used; and,
 - i. Forcible entry tools including a pick head axe, Halligan, K-tool and Rabbit tool shall be provided on each floor.

409.E. MODIFICATIONS OF STANDARDS

As part of the Master Concept Plan conditional use review, the Board of Supervisors may permit the modification of the standards applied to the proposed use in order to encourage the use of

innovative design. An applicant desiring to obtain such approval shall, when making application for the Master Concept Plan, also make application for modification under this Section. The Board of Supervisors shall consider both requests simultaneously. Any modification of the standards shall be subject to the following standards:

1. Such modifications of standards better serve the design and operational objectives listed in Section 409.C. of this Ordinance;
2. Such modifications of standards would not result in adverse impact to adjoining properties, nor future potential inhabitants within the vicinity;
3. Such modifications will not result in an increase in permitted lot coverage for the site; and,
4. The extent of modification provides the minimum amount of relief necessary to ensure compliance with the requirements of this Section 409 of the Zoning Ordinance.

409.F. STAGE 2 SITE DEVELOPMENT PLAN

Upon approval of a conditional use for the Concept Master Plan, the applicant must apply for a zoning permit before constructing the proposed use pursuant to Section 801 of this Ordinance. As part of the granting of a zoning permit for uses proposed and contained in the Concept Plan, the Zoning Officer shall review an application submitted by the applicant. Such application shall include but not be limited to the following:

1. Any information necessary to demonstrate compliance with all applicable regulations contained within this Ordinance plus any conditions of approval imposed upon the use; and,
2. A scaled site plan that demonstrates the proposed uses' compliance with the approved Master Concept Plan, plus any conditions of approval attached to the grant of the Master Concept Plan. The Zoning Officer may require additional review by other Township staff or Township-appointed consultants. Such zoning permit shall be approved and issued in accordance with the time limits of Section 901.A.11. of this Ordinance provided that:
 - a. the proposed uses are consistent with those contemplated in the Master Concept Plan;
 - b. the area to be disturbed for each use is consistent with the respective disturbance area depicted on the Master Concept Plan;
 - c. the application complies with the applicable design standards and regulations of this and other Township ordinances plus and conditions of approval attached to the grant of the Master Concept Plan; and,
 - d. the impact of the proposed uses is consistent with that upset limit of impact authorized in the Master Concept Plan.

Section 410 Automobile Auctions and Storage Yards

410.A. Within the (BI) Zone, automobile auctions and storage yards are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:

410.B. The subject property must front upon and have direct vehicular access to a collector or arterial road

as listed in Section 320 of this Ordinance.

- 410.C.** The applicant shall be required to submit an expert-prepared on-site circulation plan prepared by a professional traffic engineer certified by the Commonwealth of Pennsylvania. Such circulation plan must fully describe the location and manner in which vehicles for auction arrive, are registered, are stored, are displayed, are readied for sale, are stacked for sale, are sold, are road tested, are stored post-sale and then depart the site. It is incumbent upon the applicant to demonstrate that the proposed circulation pattern can be operated safely and will not interfere with the on-site circulation and parking of customers and employees or the flow of traffic on adjoining streets. Such plan shall clearly delineate exterior areas of the site that are to be used solely for the storage of vehicles as opposed to display and sales areas and required off-street parking spaces.
- 410.D.** Exterior areas used solely for the storage of vehicles shall be connected to other areas of the site and the adjoining street via one or more access drives in accordance Section 301 of this Ordinance.
- 410.E.** Exterior areas used solely for the storage of vehicles shall comply with the off-street parking design requirements of Section 315 of this Ordinance, except that such areas:
1. may be arranged with blocks of horizontally stacked vehicles/equipment that do not provide for the independent movement of each vehicle. No vehicle or piece of heavy equipment shall be located more than one hundred feet (100') from an on-site interior drive. Such interior drives must be a minimum of eighteen (18) feet wide;
 2. may employ vertical stacking of vehicles. Vehicles stacked vertically shall either be located within an enclosed structure or be located at least one hundred feet (100') from the closest property line. Vertical stacking shall not exceed fifteen (15') feet;
 3. need not be paved, but must have an all-weather and dust-free surface;
 4. shall be completely enclosed by a six-foot (6') high fence, which shall be subject to the (BI) Zone's setback requirements imposed upon off-street parking lots;
 5. shall be lighted to provide an average of minimum one (1) foot candle level of illumination at an elevation of three (3) feet above grade for the detection of suspicious movement. All such lighting shall be arranged as to reflect the light away from adjoining properties and roads; and,
 6. need not comply with the interior landscaping requirements but must be screened from adjoining roads and properties.
- 410.F.** Exterior areas used for the display and sales of automobiles shall comply with the off-street parking design requirements of Section 315 of this Ordinance.
- 410.G.** Areas to be used by employees or customers after dusk, shall be lighted to provide an average of minimum two (2) foot candles level of illumination at an elevation of three (3) feet above grade for the safe movement of vehicles and pedestrians. All such lighting shall be arranged as to reflect the light away from adjoining properties and roads.
- 410.H.** If an exterior amplified public address system is to be utilized, the applicant shall submit qualified expert evidence that the proposed public address system will be designed and operated in a manner to comply with the noise standards provided, as referenced and incorporated, in Section 316 of this Ordinance.
- 410.I.** The applicant shall prepare, submit and explain, and continuously implement an acceptable working plan of the collection and proper disposal of litter and debris. Exterior trash receptacles

shall be provided amid any exterior sales and/or display area. Such trash receptacles shall be routinely emptied so as to prevent the scattering of litter and debris.

410.J. The proposed use must be connected to public utilities and all on-site rest rooms, comfort facilities and toilets must rely upon public sewer for disposal of human waste. No “porta-potties” are permitted.

410.K. The subject property may contain facilities for the service, repair and reconditioning of vehicles provided:

1. All service, repair and reconditioning uses involving drive-thru service shall provide sufficient on-site stacking lanes to prevent vehicle back-ups on adjoining roads and such stacking lanes will be fully integrated within the site’s on-site circulation plan as required in Section 410.C. of this Ordinance;
2. All service, repair and/or reconditioning activities shall be conducted within a completely enclosed building and shall be limited to vehicles that are to be auctioned on the site;
3. No outdoor storage of parts, equipment, lubricants, fuel or other materials, new, used or discarded, as part of the service, repair and/or reconditioning operation, shall be permitted; and,
4. The demolition and/or junking of vehicles is prohibited. No vehicle shall remain on the site for more than one (1) year.

410.L. The subject property shall contain a road test track which shall be conveniently linked to the sales area. The test track shall be strictly operated so that customers must use the track for test drives rather than the site’s circulation system and adjoining roads. The applicant must demonstrate the means by which patrons will be directed and required to conduct road tests on the site’s test track. The test track shall be setback at least twenty (20) feet from adjoining property lines and fifty (50) feet from adjoining roads. If such test track is to be used after dusk, it shall be lighted to provide an average of minimum two (2) foot candles level of illumination at an elevation of three (3) feet above grade for the safe movement of vehicles and pedestrians. All such lighting shall be arranged to reflect the light away from adjoining properties and roads.

410.M. The applicant shall furnish evidence that the disposal of all materials and wastes will be accomplished in a manner that complies with all applicable State and Federal regulations.

410.N. No part of the subject property shall be located within three hundred feet (300') of any land within the (LDR and MU) Zones.

410.O. A traffic impact study shall be prepared in accordance with Section 319 of this Ordinance and shall devote particular emphasis on movements of vehicles that may be moving between the subject property and other nearby uses that assist in making vehicles ready for sale.

410.P. One truck driver lounge with comfort and bathing facilities, a restaurant, cafeteria or refreshment counter and a filling station are permitted accessory uses provided such use are located, designed and operated in a manner that is meant to serve those persons directly associated with the principal uses while they are on the site. No entrances and/or signage shall be oriented towards attracting patrons from off of the site. Should the proposed use include a restaurant, cafeteria or refreshment counter, the applicant shall furnish and continuously implement an acceptable working plan for the collection of litter and debris.

410.Q. One off-street parking space shall be provided for each 1000 square feet of total interior and exterior display, sales and storage area for vehicles. In addition, an unimproved grassed overflow parking area shall be provided for peak use periods. Such overflow parking areas shall be

accessible only from the interior access drives of the permanent parking lot. Overflow parking areas shall contain fencing to confine vehicles on the site.

Section 411 Gas Stations (Including Minor Incidental Repair)

- 411.A.** Within the (BI) Zone, gas stations (including minor incidental repair) are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:
- 411.B. MINIMUM LOT WIDTH** - One hundred twenty-five feet (125');
- 411.C.** The subject property shall front on an arterial or collector road;
- 411.D.** The subject property shall be set back at least five hundred feet (500') from any lot containing a school, day care facility, park or playground, library, hospital or nursing, rest or retirement home;
- 411.E.** The outdoor storage of any motor vehicles (whether capable of movement or not) for more than one (1) month is prohibited. Any vehicle stored outside of a completely enclosed building must be awaiting needed parts to perform needed repair, located within a side or rear yard and be screened from adjoining roads and properties;
- 411.F.** All structures (including air compressors, kiosks, gasoline pump islands, but not permitted signs) shall be set back at least thirty feet (30') from any street right-of-way line;
- 411.G.** No outdoor storage of auto parts shall be permitted;
- 411.H.** Access driveways shall be a minimum of twenty-eight feet (28') and a maximum of thirty-five feet (35') wide and separated by seventy-five feet (75') from one another if located along the same frontage as measured from edge to edge;
- 411.I.** All ventilation equipment associated with fuel storage tanks shall be set back one hundred feet (100') and oriented away from any land within an (LDR and MU) Zone; and,
- 411.J.** The applicant shall furnish evidence that the storage, dispensing and disposal of materials will be accomplished in a manner that complies with State and Federal regulations.

Section 412 Bed and Breakfasts

- 412.A.** Within the (C, A, LDR and MU) Zones, bed and breakfasts are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:
- 412.B.** Bed and breakfasts shall only be permitted within single-family detached dwellings that existed on the effective date of this Ordinance;
- 412.C.** Any modifications to the external appearance of the building (except fire escapes) shall complement its residential character;
- 412.D.** All floors above or below grade shall have a permanently affixed direct means of escape to ground level;
- 412.E.** One (1) off-street parking space shall be provided for each room available for rent, in addition to

those required for the dwelling unit;

- 412.F. All parking areas shall be set back a minimum of ten feet (10') from all property lines and shall be screened from adjoining lots and streets;
- 412.G. A bed and breakfast may erect one (1) sign no larger than eight (8) square feet in size which must be set back ten feet (10') from all lot lines;
- 412.H. Breakfast is the only meal that can be served associated with a bed and breakfast, and then only to registered overnight guests;
- 412.I. The applicant shall furnish evidence that an approved means of sewage disposal and water supply shall be used; and,
- 412.J. The applicant shall furnish proof of any needed approval from the PA Department of Labor and Industry.

Section 413 Beekeeping

- 413.A. Within the (C and A) Zones, beekeeping is a permitted accessory use to an agricultural or horticultural use or single-family detached residence subject to the following criteria:
- 413.B. **MINIMUM LOT AREA** - One (1) acre;
- 413.C. It shall be the duty of the applicant to maintain each colony so as to not create a public nuisance;
- 413.D. Colonies shall be maintained in movable hives;
- 413.E. Hives shall be situated to maximize sunshine exposure and/or natural wind protection;
- 413.F. In no case shall hives be located within twenty-five feet (25') of any property line;
- 413.G. All beehives must be registered in accordance with the PA Department of Agricultural, Entomology Section; and,
- 413.H. Hives shall not be oriented to children's play areas either on the site or an adjoining property.

Section 414 Billboards

- 414.A. Within the Billboard Sign Overlay Zone, billboards are permitted by right, subject to the following criteria:
- 414.B. Every Billboard shall be identified on the structure with the name of the owner.
- 414.C. All Billboards approved for erection or construction shall comply with duly adopted building and construction regulations of the Township and any other applicable federal, state or local laws, regulations or ordinances.
- 414.D. All Billboards shall be attached to the ground by a single supporting monopole or vertical metal or concrete post, pillar, pole or column.
- 414.E. No Billboard shall obstruct the view of motorists on adjoining roads or the ability of the public to view the identification of adjoining commercial or industrial uses.
- 414.F. Billboards may be illuminated, but no direct ray of light shall extend beyond the face of the sign.

Lighting fixtures used to illuminate a Billboard shall be mounted on the top of the Billboard structure. Bottom-mounted lighting is not permitted. All such Billboard lighting fixtures shall be constructed to prevent direct light from being directed toward residential buildings on adjacent or nearby land and to prevent glare perceptible to persons operating motor vehicles on public ways.

- 414.G.** All properties upon which a Billboard is erected shall be regularly maintained so as not to create a nuisance by means of weeds, litter, vector habitation or violations of any other applicable federal, state or local laws, regulations or ordinances.
- 414.H.** No portion of any Billboard shall exceed a height of 35 feet above ground elevation, as measured at any point within 15 feet in a circle around the base of the supporting monopole or other support for the Billboard. "Ground elevation" is defined as the existing natural ground elevation prior to any earthmoving activities.
- 414.I.** All Billboards shall be set back a minimum distance of 40 feet from any utility easement line and a minimum distance of 40 feet from any property line, including but not limited to property boundary lines, right-of-way lines or easement boundaries, except only a property line adjacent to or within the right-of-way of Interstate 81, subject, however, to the location restrictions provided in this Section 414.
- 414.J.** Except for Interstate 81, all Billboards shall be located not less than 40 linear feet from the legal right-of-way of any existing street, road or highway or from the dedicated right-of-way line of any street, road or highway.
- 414.K.** No Billboard shall be located less than 1,000 linear feet from any building used for residential purposes, including but not limited to single dwelling units and other buildings used for residential purposes, such as but not limited to apartment houses, boardinghouses, nursing, rest, convalescent or retirement homes, group homes, hotels, lodging houses and motels.
- 414.L.** The minimum distance required between all Billboards shall be 2,640 feet (1/2 mile) as measured along the center line of the abutting roadway. This requirement shall be applicable with respect to Billboards located on the opposite sides of a road or highway or in an adjacent municipality. In addition, no Billboard shall be erected within 250 feet of any existing freestanding sign which advertises a use conducted on the same premises.
- 414.M.** The maximum area for any one Billboard face shall not exceed 14 feet in vertical measurement or 48 feet horizontally and in no event to exceed 672 square feet per facing (inclusive of any border, trim or embellishment, which embellishment shall not exceed 28 square feet of area, but excluding the base or apron, supports and other structural members). The terms "face" and "facing" as used herein shall mean the surface area or surface areas of the structure containing the message of the Billboard(s).
1. The Billboard face area shall be measured by the smallest square, rectangle, triangle, circle or combination thereof which will encompass the entire Billboard face above ground level.
 2. A Billboard structure shall contain no more than two facings with only one advertising message being displayed at any one time per face, which facings may be placed only back-to-back or V-shaped at an interior angle of less than 90°.
- 414.N.** Billboards incorporating LCD, LED, plasma, CRT, pixelized lights or other animated and/or video-like display shall comply with Section 322.C.31. of this Ordinance; and,

Section 415 Boarding Houses

- 415.A.** Within the (MU) Zone, boarding houses are permitted by conditional use, provided that the

applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:

415.B. Boarding houses must include a full-time on-site resident manager who is not a border upon the site;

415.C. The following minimum lot area requirements shall be provided:

Minimum Required Lot Size (up to 4 boarders)	plus	Additional Lot Area Per Boarder (up to 10 boarders)
10,000 sq. ft.	plus	2500 sq. ft./ boarder over four

415.D. The applicant shall furnish evidence that approved systems for public sewage disposal and water supply shall be used;

415.E. No modifications to the external appearance of the building (except fire escapes) which would alter its residential character shall be permitted;

415.F. All floors above and/or below grade shall have a permanently affixed direct means of escape to ground level;

415.G. One (1) off-street parking space shall be provided for each room available for rent;

415.H. One (1) sign, not to exceed eight (8) square feet, shall be permitted provided such sign is not a freestanding sign as defined herein; and,

415.I. The applicant shall furnish proof of any needed approval from the PA Department of Labor and Industry.

415.J. Upon approval of a conditional use for a boarding house, the Zoning Officer shall issue a temporary zoning permit. Such permit shall be reviewed every twelve (12) months until such time as the boarding house ceases to exist. At such time the applicant shall be required to furnish a list of those occupants of the boarding house on a form provided by the Township. A fee, in the amount to be set by the Board of Supervisors, shall be paid by the landowner upon each renewal of the temporary zoning permit. Such fee shall be based upon the cost of the annual review of the permit.

Section 416 Campgrounds

416.A. Within the (C) Zone, campgrounds are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:

416.B. MINIMUM LOT AREA - Ten (10) acres;

416.C. SETBACKS

All campsites shall be located at least fifty feet (50') from any side or rear property line and at least one hundred feet (100') from any public street line;

- 416.D.** Each campsite shall be at least three thousand (3,000) square feet in size and shall either provide parking space for one (1) automobile which will not interfere with the convenient and safe movement of traffic, or equivalent parking shall be provided in a common parking area;
- 416.E.** A private road system shall be provided in accordance with the SALDO (Section 502.N.);
- 416.F.** All outdoor play areas shall be set back one hundred feet (100') and screened from adjoining properties. Such outdoor play areas shall be used exclusively by registered guests and their visitors;
- 416.G.** All campgrounds shall furnish centralized sanitary and garbage collection facilities that shall be set back a minimum of one hundred feet (100') and screened from adjoining properties. Such facilities shall be designed and maintained so as to be secure from native animals such as raccoon, bears, etc.;
- 416.H.** Any accessory retail or service commercial uses shall be set back a minimum of one hundred feet (100') from any property line. Such accessory commercial uses shall be solely designed and constructed to serve the campground's registered guests and their visitors. Any parking spaces provided for these commercial uses shall only have vehicular access from the campground's internal road, rather than the public street. All accessory commercial uses and related parking shall be screened from adjoining parcels;
- 416.I.** All campgrounds containing more than one hundred (100) campsites shall have vehicular access to an arterial or collector street as listed in Section 320 of this Ordinance;
- 416.J.** A campground may construct one freestanding or attached sign containing no more than thirty-two (32) square feet. Any reference to accessory commercial or recreational facilities shall remain secondary in size to the reference of the principal campground use. Such sign shall be set back at least ten feet (10') from the street right-of-way line, at least one hundred feet (100') from any adjoining lot lines;
- 416.K.** A minimum of twenty percent (20%) of the gross area of the campground shall be devoted to active and passive recreational facilities, which shall not be located within one hundred feet (100') of any property line. Responsibility for maintenance of the recreation area shall be with the landowner;
- 416.L.** During operation every campground shall have an office in which shall be located the person responsible for operation of the campground; and,
- 416.M.** The applicant shall furnish evidence that all water facilities, sewage disposal systems, rest rooms, solid waste disposal and vector control shall be approved and maintained in accordance with the requirements of the PA DEP.

Section 417 Car Washes

- 417.A.** Within the (BI) Zone, car washes are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:
- 417.B.** Gray water recycling is required;
- 417.C.** For automatic and self-service car washes, each washing bay shall provide a minimum one hundred foot (100') long on-site stacking lane which precedes the washing process. For full-service car washes, such on-site stacking shall be a minimum of three hundred feet (300') per lane;

- 417.D.** For full-service car washes, a post-washing drying area shall be provided for no less than three (3) vehicles per washing lane;
- 417.E.** All structures housing washing apparatuses shall be set back one hundred feet (100') from any street right-of-way line, fifty feet (50') from any rear property line, and twenty feet (20') from any side lot line;
- 417.F.** Trash receptacles shall be provided and routinely emptied to prevent the scattering of litter, and the applicant shall furnish and implement an acceptable working plan for the cleanup of litter and debris;
- 417.G.** The subject property shall front on an arterial or collector road as listed in Section 320 of this Ordinance; and,
- 417.H.** The applicant shall demonstrate adequate provision for the collection and disposal of greases and wastes.

Section 418 Cemeteries.

- 418.A.** Within the (C, A and MU) Zones, cemeteries, including pet cemeteries, are permitted by right, subject to the below criteria, and are permitted as an accessory use to a church, also subject to the following criteria:
- 418.B.** All area and bulk regulations of the prevailing zoning district shall apply with the following exceptions:
 - 1. The minimum size of a cemetery created after the effective date of this Ordinance shall be three (3) acres, and for accessory cemetery uses, the portion of any lot designated for the cemetery shall have an area of three (3) acres.
 - 2. The minimum front, side and rear yards shall be 100 feet.
 - 3. The maximum lot coverage (excluding headstones but including buildings, structures, driveways, parking areas and other paved surfaces) shall be 20%.
- 418.C.** In areas not served by public water, the owner or occupier must have written evidence readily available to establish that water supplies of surrounding properties will not be contaminated by burial activity within the proposed cemetery; and,
- 418.D.** No burial plots or facilities are permitted in any floodplain as defined herein.
- 418.E.** A suitably screened or landscaped buffer zone at least 15 feet wide, which buffer strips shall be set back 15 feet from the property line, shall be provided by the owner along all the property and street boundary lines separating the use from adjacent districts. Screen planting shall be such that will reasonably be expected to reach a height of five feet in three years and a minimum height of 10 feet in eight years, and shall be planted in a pattern and proximity which shall block visibility, glare, noise, fumes, dust, and other harmful effects, within five years. Said screen planting shall be properly maintained by the owner, including maintenance and trimming to avoid and prevent the blocking of visibility for traffic clear sights.

Section 419 Churches and Related Uses

- 419.A.** Within the (C, A and MU) Zones, churches and related uses are permitted by right, subject to the following criteria:

419.B. Reserved.

419.C. CHURCH RELATED RESIDENCES (RECTORIES AND CONVENTS):

1. All residential uses shall be accessory, and located upon the same lot or directly adjacent to a lot containing a house of worship; and,
2. All residential uses shall be governed by the location, height and bulk standards imposed upon other residences within the respective Zone, except that any number of church-related persons (pastors, priests, rabbis, ministers, nuns, caretakers, employees) may share group quarters.
3. All residential uses shall provide for an individual septic system separate from the main Church or religious structure. Such individual septic system shall comply with all applicable Township ordinances and regulations.

419.D. CHURCH-RELATED SCHOOLS OR DAY CARE FACILITIES:

1. All schools or day care uses shall be accessory, and located upon the same lot as a house of worship;
2. If school or day care is offered below the college level, an outdoor play area shall be provided, at a rate of sixty-five (65) square feet per individual enrolled. Off-street parking lots shall not be used as outdoor play areas. Outdoor play areas shall not be located within the front yard and must be set back twenty-five feet (25') from all property lines. Outdoor play areas shall be completely enclosed by a minimum four foot (4') high fence, and screened from adjoining residentially-zoned properties. Any vegetative materials located within the outdoor play areas shall be of a non-harmful type (poisonous, thorny, allergenic, etc.). All outdoor play areas must provide a means of shade, such as a shade tree(s) or pavilion(s);
3. Enrollment shall be defined as the largest number of students and/or children under day care supervision at any one time during a seven-day period; provided that such enrollment shall not exceed the sewer or septic capacity approved for the structure as established by the Township SEO unless additional approvals and upgrades to the septic system are made to accommodate additional capacity;
4. Passenger "drop-off" areas shall be provided and arranged so that passengers do not have to cross traffic lanes on or adjacent to the site; and,
5. Unless the applicant can demonstrate that the off-street parking associated with the house of worship is sufficient for the proposed use, one (1) off-street parking space shall be provided for each six (6) students enrolled.

419.E. CEMETERIES:

Cemeteries may be considered an accessory use to a church, so long as the cemetery meets all of the requirements set forth in Section 418 of this Ordinance.

Section 420 Communication Antennas that are Co-located Upon Existing Structures

420.A. Within all Zones, communication antennas that are co-located upon existing structures (e.g., utility transmission towers, observation towers, communication towers, silos, steeples, smokestacks, water towers, flagpoles, and other similar structures) are permitted by right as an accessory use to

the principal use, regardless if such accessory use is owned by a party that does not own the principal use. Such use shall be subject to the following criteria:

- 420.B.** The applicant submits a copy of the written agreement with the landowner upon whose structure the antenna is to be located;
- 420.C.** The applicant shall be required to demonstrate that it is licensed by the Federal Communications Commission to operate the proposed use;
- 420.D.** The applicant shall demonstrate that the proposed use will comply with the applicable standards governing human exposure to electromagnetic radiation by the Federal Communications Commission;
- 420.E.** The applicant shall demonstrate that the proposed use will comply with all Federal Aviation Administration and Commonwealth Bureau of Aviation regulations governing structural height;
- 420.F.** The applicant shall submit, from a structural engineer registered in the Commonwealth of Pennsylvania, a written certification of the existing structure's and the antenna's ability to meet the structural standards required by either the Electronic Industries Association or the Telecommunication Industry Association and that the construction methods or other measures used will prevent the toppling of any communication antenna onto adjoining properties and/or roads, and prevent the wind-borne scattering of ice onto adjoining properties and/or roads; and,
- 420.G.** When one (1) or more freestanding telecommunication and wireless communications antennas are to be located on an existing structure and the general public has access to the structure on which the freestanding telecommunication and wireless communications facilities are to be located, the applicant shall provide engineering details showing what steps have been taken to prevent microwave binding to wiring, pipes, and other metals. For purposes of this subsection, the term "microwave binding" shall refer to the coupling or joining of microwave energy to electrical circuits, including but not limited to power lines and telephone wires, during which process the transference of energy from one to another occurs.
- 420.H.** In the event of approval and erection, Applicant shall certify to the Township, on an annual basis, that the antenna is still in use. Applicant shall remove any and all freestanding telecommunication and wireless communications antennas within two (2) months of such antennas no longer being in use.

Section 421 Child Day Care Facilities

- 421.A.** 1. Within the (MI and BI) Zones, group child-care homes and child-care centers are permitted by right subject to the following criteria and within the (MU) Zone, group child-care homes and child-care centers are permitted by special exception provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as set forth below.
- 2. Within the (C, A, LDR and MU) Zones, family child-care homes are permitted as an accessory use, subject to the criteria set forth below.
- 421.B.** All child day-care facilities shall comply with all current Pennsylvania Department of Public Welfare (herein referred to as "DPW") regulations applicable thereto, including those standards governing adequate indoor space, accessible outdoor play space and any applicable state or local building and fire safety codes. A copy of the DPW license and any other license or certification must be provided to the Township upon issuance of a use or occupancy certificate by the Township, and such licenses must, at all times, be kept current. A use or occupancy permit may be issued

conditioned on receipt of a DPW license if such permit is required for issuance of the DPW license. Any subsequent changes and/or recertifications shall also be provided to the Township.

421.C. CHILD DAY-CARE FACILITIES.

Any child day care facility must meet the applicable standards and requirements, for both the Township Code and DPW regulations, for either a child-care center, a group child-care home, or a family child-care home.

421.D. GENERAL REQUIREMENTS FOR CHILD DAY-CARE FACILITIES.

1. No portion of a child day-care facility shall be located within 300 feet of any potentially hazardous land use or activity which could pose a threat to the safety of the occupants of the facility.
2. An outdoor activity area shall be provided at a rate of sixty-five (65) square feet per child enrolled. Off-street parking lots shall not be used as outdoor play areas. Enrollment shall be defined as the largest number of children under supervision at any one time during a seven-day period. All outdoor activity areas must provide a means of shade, such as a shade tree(s) or pavilion(s).
3. Outdoor activity areas shall be sufficiently fenced (by a minimum four foot (4') high fence), screened and buffered to protect both children or adults served and the neighborhood at large from excessive noise and disturbance. Hours of outside play shall be limited to 8:00 a.m. until sunset, as defined by the National Weather Service.
4. All child day-care facilities shall provide an outdoor play area in compliance with DPW regulations, which shall not be located within the front yard.
5. When applying for a special exception, or a use or occupancy permit where a special exception is not necessary, the applicant shall submit a plan showing any existing or proposed outdoor play areas, outdoor play equipment, fencing, access drives, adjacent streets, adjacent hazardous land uses, on-site hazardous areas (as previously defined), merchandise delivery areas, parking spaces and drop-off/pickup areas.

421.E. ADDITIONAL REQUIREMENTS FOR GROUP CHILD-CARE HOMES.

1. At least one off-street parking space shall be provided for each person employed.
2. At least one off-street parking space for each person employed, plus one off-street parking space for each six (6) children to be served by the center, shall be provided.

421.F. ADDITIONAL REQUIREMENTS FOR CHILD-CARE CENTERS.

1. Applicant shall provide evidence that an approved means of water supply and sewage disposal shall be provided to the center, in amounts adequate based on the number of children and employees to utilize such services at the center on a daily basis.
2. At least one off-street parking space for each person employed, plus one off-street parking space for each six (6) children to be served by the center, shall be provided.
3. Passenger "drop-off" and "pick-up" areas shall be provided on site and arranged so that the passengers do not have to cross traffic lanes on or adjacent to the site.

421.G. ADDITIONAL REQUIREMENTS FOR FAMILY CHILD-CARE HOMES.

Family child-care homes must be conducted within detached dwellings having a minimum lot size of twenty thousand (20,000) square feet;

Section 422 Commercial Produce Operations

422.A. Within the (A) Zone, commercial produce operations are permitted by special exception provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and the following specific criteria:

422.B. MINIMUM LOT AREA - Ten (10) acres, except that this may be reduced if the applicant can demonstrate compliance with the Pennsylvania Right-to-Farm Law;

422.C. The maximum permitted lot coverage is thirty percent (30%) (lot coverage shall mean all impervious surfaces);

422.D. If applicable, the applicant shall submit written evidence from the appropriate review that the proposed use has an approved nutrient management plan. All subsequent operations and activities shall be conducted in accordance with such plans. If, at any time, the nutrient management plan is amended, the applicant must again submit written evidence of plan approval to the Zoning Officer;

422.E. The applicant shall furnish evidence of his/her Agricultural Erosion and Sedimentation Pollution Control Plan under State law. All subsequent operations and activities shall be conducted in accordance with such plan;

422.F. The applicant shall abide by, and demonstrate a working knowledge of, those methods that will be employed to comply with the above-required nutrient management plan and conservation plan;

422.G. If greenhouses, or other buildings with substantially clear or translucent surfaces, are used, the applicant shall submit information that demonstrates compliance with Section 310 of this Ordinance;

422.H. Any exhaust or ventilation fans employed shall be oriented and directed such that no direct exhaust velocity is perceptible at any adjoining property lines;

422.I. Any driveway or access drive providing for vehicular access to the proposed use shall be paved and shall maintain a fifty foot (50') wide radius for all turns and intersections;

422.J. Any on-site materials and/or waste storage facilities shall comply with the requirements of Section 313 of this Ordinance;

422.K. While a commercial produce operation exists, no subdivision or land development that would create an additional principal dwelling unit shall be permitted on the subject property;

422.L. The applicant shall submit an analysis of raw water needs (groundwater or surface water) from either private or public sources, indicating quantity of water required. If the source is from a municipal system, the applicant shall submit documentation that the public authority will supply the water needed;

1. In addition, if the facility is to rely upon non-public sources of water, a water feasibility study will be provided to enable the Township to evaluate the impact of the proposed

development on the groundwater supply and on existing wells. The purpose of the study will be to determine if there is an adequate supply of water for the proposed development to estimate the impact of the new development on existing wells in the vicinity.

2. A water system which does not provide an adequate supply of water for the proposed development, considering both quantity and quality, or does not provide for adequate groundwater recharge, considering the water withdrawn by the proposed development, shall not be approved by the Township.
3. A water feasibility study shall include the following information:
 - a. calculations of the projected water needs;
 - b. a geologic map of the area, with a radius of at least one mile from the site;
 - c. the location of all existing and proposed wells within one thousand feet (1,000') of the site, with a notation of the capacity of all high-yield wells;
 - d. the location of all existing on-lot sewage disposal systems within one thousand feet (1,000') of the site;
 - e. the location of all streams within one thousand feet (1,000') of the site and all known point sources of pollution;
 - f. a determination of the long-term safe yield based on the geologic formation(s) underlying the site;
 - g. a determination of the effects of the proposed water supply system on the quantity and quality of water in nearby wells, streams and the groundwater table; and,
 - h. a statement of the qualifications and the signature(s) of the person(s) preparing the study.

422.M. Should the proposed use not make use of public water, and require more than 100,000 gallons of water per day, the applicant shall furnish written evidence of approval from the Susquehanna River Basin Commission;

422.N. The applicant shall be required to obtain an approved land development under the requirements of the SALDO;

422.O. The applicant shall be required to submit a traffic impact study, in accordance with Section 319 of this Ordinance;

422.P. The applicant shall be required to submit a written qualified plan for the removal of all buildings and the reclamation of all topsoil in the event of discontinuance of the commercial produce operation. If the site is graded during construction and operation of the commercial produce operation, all topsoil shall remain on the site in a manner which makes it conveniently accessible for reclamation. In lieu of building removal, the applicant can propose conversion of the building for agricultural purposes;

422.Q. The site shall include one (1) off-street parking space for each employee during the largest work shift;

422.R. The applicant may conduct a roadside stand, as defined herein within one of the permanent buildings, but such use shall be limited to no more than three hundred (300) square feet of display area;

422.S. All buildings and storage/processing structures shall be set back at least one hundred feet (100') from adjoining roads and properties, and all off-street parking and loading spaces, outdoor

storage areas and dumpsters shall be set back at least fifty feet (50') and screened from adjoining roads and properties;

422.T. One (1) sign, as provided for in Section 322, shall be permitted; and,

422.U. The applicant shall be required to install and maintain a riparian buffer along any watercourse that is located upon the subject property according to those specifications listed in Section 511 of this Ordinance.

Section 423 Commercial Recreation Facilities

423.A. Within the (BI) Zone, commercial recreation facilities are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:

423.B. If the subject property contains more than two (2) acres, it shall front on an arterial or collector road;

423.C. Those uses involving extensive outdoor activities shall provide sufficient screening and/or landscaping measures to mitigate any visual and/or audible impacts on adjoining properties;

423.D. Maximum permitted height for structures regulated by this Section can exceed forty-five (45) feet provided:

1. that such structures shall not be used for occupancy;
2. that the proposed structure is setback a horizontal distance at least equal to its height from each property line;
3. the applicant must demonstrate that adequate emergency vehicles and equipment and/or employed fire suppression measures are available; and,
4. the applicant must demonstrate compliance with the BOCA National Fire Prevention Code, 1999 as may be amended;

423.E. The applicant shall furnish qualified written evidence regarding the character of the proposed use and management strategies to assure that activities conducted upon the site will not be detrimental to the use of adjoining properties due to hours of operation, noise, light, litter, dust and pollution;

423.F. Required parking will be determined based upon the types of activities proposed and the schedule listed in Section 315 of this Ordinance. In addition, the Zoning Hearing Board may require an unimproved grassed overflow parking area to be provided for peak use periods. Such overflow parking areas shall be accessible only from the interior driveways of the permanent parking lot. Overflow parking areas shall contain fencing to prevent vehicles from crossing adjoining properties or directly accessing adjoining roads;

423.G. Any booths or other structures used for the collection of admission and/or parking fees shall be set back and arranged to prevent vehicle back-ups on adjoining roads during peak arrival periods. Any other collection of fees (roaming parking lot attendants) shall be conducted in a manner to prevent vehicle back-ups on adjoining roads. If, at any time after the opening of the commercial recreation facility, the Supervisors determine that traffic back-ups are occurring on adjoining roads, and such back-ups are directly related to the means of access to the subject property, the Supervisors can require the applicant to revise means of access to relieve the undue congestion; and,

423.H. Any outside pedestrian waiting lines, shall be provided with a means of shade.

Section 424 Concentrated Animal Feeding Operations (CAFOs) and Concentrated Animal Operations (CAOs)

424.A. Within the (A) Zone, concentrated animal feeding operations (CAFOs) and concentrated animal operations (CAOs) are permitted by right, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those specifically as follows:

424.B. Any building, or area used for the housing, feeding, watering, or running of livestock or poultry shall be set back at least five hundred (500) feet from any land within the (LDR and MU) Zones;

424.C. Any building, or area used for the housing, feeding, watering, or running of livestock or poultry shall be set back at least one hundred fifty (150) feet from all permanent surface waters, wetland areas, and wells that provide water for human consumption;

424.D. Any new concentrated animal feeding operation and all expansions to existing operations shall be required to submit a plan for control of erosion and sedimentation prepared by a Professional Engineer and consistent with the requirements of the Nutrient Management Act. This plan shall be required even if not required by the provisions of the Nutrient Management Act itself; All subsequent operations and activities shall be conducted in accordance with such plans. If at any time, the nutrient management plan is amended, the applicant must submit written evidence of plan approval to the Zoning Officer;

424.E. The applicant shall furnish evidence from the local field office of the Natural Resources and Conservation Service (NRCS) that the proposed use has a certified conservation plan that meets NRCS standards and specifications. All subsequent operations and activities shall be conducted in accordance with such conservation plan. If, at any time, the conservation plan is amended, the applicant must again furnish evidence from the (NRCS) that the amended plan has been approved;

424.F. The applicant shall furnish evidence from the Cumberland County Conservation District that the proposed use has an approved Nutrient Management Plan. All subsequent operations and activities shall be conducted in accordance with such Nutrient Management Plan. If, at any time, the Nutrient Management Plan is amended, the applicant must again furnish evidence from the Cumberland County Conservation District that the amended plan has been approved;

424.G. The applicant shall submit, and abide by written qualified evidence describing those methods that will be employed to:

1. minimize odor on nearby properties in accordance with an approved odor management plan under PA Nutrient Management Act;
2. dispose dead animals according to the regulations of the Pennsylvania Department of Agriculture. In the event of a catastrophic event in which mass disposal is warranted the Pennsylvania Department of Agriculture can require whatever disposal methods are deemed appropriate to safeguard animal and public health; and,
3. comply with the above-required nutrient management plan and conservation plan;

424.H. Any exhaust or ventilation fans employed shall be oriented and directed such that no direct exhaust velocity is perceptible at any adjoining property lines;

424.I. Any driveway or access drive providing for vehicular access to the proposed use shall maintain a

fifty (50) foot wide radius for all turns and intersections;

- 424.J.** Any on-site manure storage facilities comply with the requirements of Section 455 of this Ordinance;
- 424.K.** All buildings used for the housing of livestock shall be fitted with a solid concrete slab or slotted floor;
- 424.L.** The property whereupon the concentrated animal feeding operation is located shall be graded such that runoff from the area of the operation is not discharged onto surrounding properties, onto public roads, or into any permanent surface water;
- 424.M.** Applicants for any new concentrated animal feeding operation and all expansions to existing such operations must demonstrate compliance with all State and Federal regulations governing the specific operation; and,
- 424.N.** The applicant shall establish and maintain a riparian buffer along any watercourse that is located upon the subject property in accordance with Section 511 of this Ordinance.

Section 425 Conservation Design Developments

425.A. Within the (C, A, MU and LDR) Zones, conservation design developments are permitted by right, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance during the applicable subdivision and/or land development process:

425.B. PURPOSE

This use is intended to blend various residential development types amid substantial areas of the Township that are characterized by productive farmlands, natural sensitivity and/or public parklands. It is the express purpose that this Section will offer the highest densities and the most flexible design standards available within each respective Zone as enabled in the Act when a proposed development successfully integrates the preservation and protection of natural-cultural features and/or the provision of public accessible common open space.

425.C. REQUIRED COMMON OPEN SPACE

Conservation design developments are characterized by required common open space as defined herein. In the case of conservation design developments that abut the (A) Zone and/or properties subject to permanent agricultural easement, applicants may opt to provide for future agricultural use common open space provided that the site planning considerations of Section 201.F. of this Ordinance are followed and suitable permanent agricultural preservation easements are recorded in a form acceptable to the Township solicitor. Common open spaces can also be used for public utilities and public facilities provided such uses are suited, designed and operated in a manner compatible with the permanent protection of the common open space without adverse impact to the environment or the general public. The applicant shall be required to include a note on the record plan for any approved conservation design development that perpetually limits the use of proposed common open spaces for their approved purposes. The following lists the minimum common open space requirements for each Zone in which Conservation Design developments are permitted:

Minimum Required Common Open Space		
C Zone	A Zone	LDR Zone
50% of the total lot area*	65% of the total lot area*	35% of the total lot area*
<p>* This figure is the minimum permitted within a conservation design development; however, the extent and location of mandatory and suggested conservation features, golf courses and/or parklands as listed in §425.C.2., §425.C.3., §425.C.8. and §425.C.9., respectively, can increase the amount of common open space.</p>		

1. Identification of Required Common Open Space - As part of the site planning process for conservation design developments, the applicant shall be required to conduct an investigation that identifies all natural and cultural features located on the subject property. Such investigation shall include literary research, aerial photograph interpretation and on-site verification. It is noted that the Township has preliminarily identified specific natural and cultural features as depicted upon the Dickinson Township Natural and Cultural Features Map which is incorporated as part of this Ordinance. However, other known sources and inventories shall also be used as needed (e.g. soil surveys, GIS data, topographic maps, geologic maps and reports, well drilling reports, etc.) Such investigation shall be comprehensive, detailed and conducted using professional and generally-accepted practices by qualified personnel with demonstrated knowledge and expertise in the subject for each respective natural and/or cultural feature.

2. Mandatory Conservation Features - The following features **must** be undisturbed and successfully integrated within the Conservation Design development's common open space:
 - floodplains as regulated by Section 502 of this Ordinance;
 - riparian buffers as regulated by Section 503 of this Ordinance;
 - wetlands, streams, ponds, or other waterways as regulated by Section 504 of this Ordinance;
 - any area 500 square feet or larger with very steep slopes [greater than twenty-five percent (25%)] as regulated by Section 505 of this Ordinance;
 - threatened or endangered species habitats, not required by the PNDI;
 - Scenic river corridors as regulated by Section 527 of the SALDO; and,
 - The Appalachian Trail as regulated by Section 506 of this Ordinance.

3. Suggested Conservation Features - The following features **should** be undisturbed and successfully integrated within the Conservation Design development's common open space. Such features may only be excluded if an applicant can demonstrate to the satisfaction of the Board of Supervisors that their inclusion would reduce the effective development potential below that permitted by this Ordinance using all available dwelling unit types and mixes.
 - any area 500 square feet or larger with steep slopes [greater than fifteen percent (15%)] as regulated by Section 505 of this Ordinance;
 - significant geologic features;
 - scenic vistas;
 - natural habitats, as regulated by Section 526 of the SALDO
 - Carbonate Areas (such as sinkholes, caves, or rock outcroppings) as regulated by Section 525 of the SALDO; and,
 - historic and archaeological resources; and,
 - significant stands of mature trees.

4. Disputes Over the Presence/Location of Natural or Cultural Features - Should a dispute concerning the presence, extent and/or location of a particular natural or cultural feature

arise, the initial determination of the Zoning Officer may be appealed to the Zoning Hearing Board in accordance with Section 704.E. of this Ordinance. In such instances, the burden of proof shall rest with the applicant.

5. Natural and Cultural Features Site Plan and Report - Next, the applicant shall be required to prepare a detailed natural and cultural features site plan depicting the extent and location of the various natural and cultural features as regulated by this Section 425.C. Such natural and cultural features site plan shall be prepared to the specifications and at the same scale as required for a sketch/preliminary plan as regulated by the SALDO. In addition, the applicant shall prepare a report that demonstrates compliance with all applicable requirements of Article 5 of this Ordinance. Such natural and cultural features site plan and report shall be prepared by qualified personnel with demonstrated knowledge and expertise in the subject for each respective natural and/or cultural feature. The sources of all discovered natural and cultural features should be documented upon the natural and cultural features site plan and contained within the report as well as the qualifications of the preparer.
6. Management Report - Depending upon the presence of those natural and cultural features contained upon the site, the applicant shall be required to submit a written management report detailing the specific actions being employed to protect and manage the respective features. Such management report shall be prepared under the responsible charge of a Pennsylvania-licensed professional and shall be signed and sealed by such professional for each respective natural and/or cultural feature and include the following minimum requirements.
 - a. Description of methods used to ensure the perpetual protection of those natural and cultural features contained on the site in accordance with the regulations of this Article 5 of this Ordinance.
 - b. Description of methods used to protect those vulnerable natural and cultural features from grading and construction activities during any proposed development or disturbance on the site.
 - c. Description of suitable long-term maintenance and management strategies of any required improvements, plantings, mitigating features and/or any other methods required under this Article 5 of this Ordinance.
 - d. Description of ownership and maintenance responsibilities and methods to enforce compliance with the requirements of Section 425.C.10. of this Ordinance.
7. Review of Natural and Cultural Features Site Plan and Report and Management Report - The natural and cultural features site plan and report and management report shall be submitted as part of the information to be shown on or submitted with subdivision and/or land development plans specified in Article 3 of the SALDO. Such materials shall be evaluated in accordance with the procedures contained within the SALDO.
8. Golf Courses - In addition, the applicant can include a proposed golf course subject to the requirements of Section 441 of this Ordinance, provided such golf course is available for use by the general public or is only devoted for use by the residents of the conservation design development;
9. Parklands - In addition, the applicant can include proposed parklands within required common open space (which may be counted towards the required mandatory dedication of parkland and open space as required within the SALDO) **only** if such parkland complies with the following:

- a. The parkland shall be located and designed so that safe and convenient access shall be provided to all existing and proposed inhabitants. Additionally, each site shall have at least one (1) area available for vehicular access that is no less than twenty-four feet (24') in width;
 - b. The parkland shall be sized and configured so as to accommodate its intended uses. Sufficient lot width/depth dimension shall be provided so as to accommodate, where practicable, ball fields, courts and other open play areas. Furthermore, should a development be proposed at a location contiguous to an existing park, parklands should be provided, where practicable, as an expansion of the existing facility;
 - c. The parkland shall have suitable topography and soil conditions for use and development as active play areas. No more than twenty-five percent (25%) of the site shall be comprised of floodplains, storm water management facilities and/or slopes exceeding three percent (3%). Any unimproved area of the site that will be used as open play area shall be provided with a healthy and vibrant grass ground cover;
 - d. The parkland shall be located and designed to conveniently access needed proximate public utilities (e.g., sewer, water, power, etc.). However, no part of any overhead utility easement, nor any above ground protrusion of an underground utility should be permitted in active play areas of the site;
 - e. No part of the parkland shall be calculated as part of any required setback, yard and/or open space for adjoining lots or uses as regulated by the Zoning Ordinance; and,
10. A written description regarding common open space ownership and/or disposition shall be provided in accordance with Section 304 of this Ordinance.
11. Permanent Protection of Common Open Space - Required common open space shall be subject to permanent conservation easements in a form that is acceptable to the Township Solicitor. Such conservation easement shall limit future development and define the range of permitted activities. (For example, the clearing of woodland habitat shall generally be prohibited, except as may be necessary to create trails or active recreation facilities.)
12. Endowment of Common Open Space and Provision of Desired Trail Features - The Board of Supervisors may grant a density bonus during the land development review of any conservation design development subject to the following conditions. The decision whether to offer a density bonus and the extent of any density bonus shall be at the sole discretion of the Board of Supervisors. Density bonuses shall only be granted to help defray the costs of:
- a. an endowment fund with suitable features and protections that ensure the perpetual management and maintenance of common open space that serves residents of the Township located beyond the confines of the proposed conservation design development; and/or,
 - b. the successful integration of an improved trail across the site that links with, and is part of, a larger community trail system identified within the Township Comprehensive Plan or any other local, county or regional plan that has been officially adopted or as otherwise determined to be suitable by the Board of Supervisors.

In order to assist the Board of Supervisors determine the extent to which a density bonus may be granted, the applicant shall be required to submit evidence of the additional costs incurred to accomplish the preceding objectives along with a calculation of the value of any proposed additional dwelling units that are being requested to defray the costs thereof.

425.D. PERMITTED DENSITIES WITHIN THE (C) ZONE

The following table shall be used to determine the permissible number of lots which may be subdivided, or the number of new dwelling units that may be established, respectively, within a conservation design development. The “Lot Area” calculation contained within the following table shall be based upon all contiguous land within the (C) Zone held in single and separate ownership, which was held by the landowner or his/her predecessor(s) in title on the effective date of this Ordinance. If land is added to the (C) Zone after the effective date of this Ordinance, the “Lot Area” calculation shall be based upon the contiguous land held in single and separate ownership on the date such land was first rezoned to the (C) Zone. For the purposes of this section, land held in single and separate ownership shall be considered to be contiguous regardless of whether:

1. such land is divided into one or more lots, parcels, purparts or tracts;
2. such land was acquired by the landowner at different times or by different deeds or other means; and,
3. such land is separated by public or private streets or rights-of-way.

Lot Area (Acres)		Total number of permitted lots and/or dwellings that maybe created.
At least	Less than	
5	8	5
8	11	6
11	14	7
14	17	8
17	20	9
20	23	10
23	26	11
26	29	12
29 or more		12, plus 1 per each 3 acres in excess of 29 acres
* These densities are subject to the bonuses described in Sections 425.C.12. of this Ordinance.		

425.E. PERMITTED DENSITIES WITHIN THE (A) ZONE

The following table shall be used to determine the permissible number of lots which may be subdivided, or the number of new dwelling units that may be established, respectively, within a conservation design development. The “Lot Area” calculation contained within the following table shall be based upon all contiguous land within the (A) Zone held in single and separate ownership, which was held by the landowner or his/her predecessor(s) in title on the effective date of this Ordinance. If land is added to the (A) Zone after the effective date of this Ordinance, the “Lot Area” calculation shall be based upon the contiguous land held in single and separate ownership on the date such land was first rezoned to the (A) Zone. For the purposes of this section, land held in single and separate ownership shall be considered to be contiguous regardless of whether:

1. such land is divided into one or more lots, parcels, purparts or tracts;
2. such land was acquired by the landowner at different times or by different deeds or other means; and,

3. such land is separated by public or private streets or rights-of-way.

Lot Area (Acres)		Total number of lots that may be subdivided and/or dwellings that may be created
At least	Less than	
2	5	2
5	10	3
10	20	4
20	30	5
30	40	6
40	50	7
50	60	8
60	70	9
70 or more		9, plus 1 per each 10 acres in excess of 70 acres
* These densities are subject to the bonuses described in Sections 425.C.12. of this Ordinance.		

425.F. PERMITTED DENSITIES WITHIN THE (LDR) ZONE

The maximum permitted density within conservation design developments within the LDR Zone shall be one (1) dwelling unit per acre of lot area.

425.G. REQUIRED RATIO HOUSING TYPES

The following tabulates the percentages of permitted residential structure types within conservation design developments by the amount of proposed common open space:

Zone	Minimum Proposed Common Open Space (% of Total Site Area)	Percentage of Dwelling Units Required by Structural Type		
		Single-Family Detached	Duplex	Townhouses or Multiple-Family Dwellings
C	Minimum 50%	No less than 100%	NA	NA
	Minimum 60%	No less than 75%	No more than 25%	No more than 25%
	Minimum 70%	No less than 50%	No more than 50%	No more than 50%
A	Minimum 65%	No less than 100%	NA	NA
	Minimum 75%	No less than 75%	No more than 25%	No more than 25%
	Minimum 85%	No less than 50%	No more than 50%	No more than 50%
LDR	Minimum 30%	No less than 100%	NA	NA
	Minimum 40%	No less than 75%	No more than 25%	No more than 25%
	Minimum 50%	No less than 50%	No more than 50%	No more than 50%

425.H. REQUIRED DESIGN STANDARDS

The following table and its footnotes present applicable design standards applied to the various dwellings/lots:

FIGURE 425.H. CONSERVATION DESIGN DEVELOPMENT DESIGN STANDARDS									
Use	Minimum Lot Area	Maximum Permitted Height	Minimum Lot Width at Building Setback & Frontage		Maximum Lot Coverage	Minimum Required Yards ^{4,6}			
						Front ³	One Side	Both Sides	Rear
Developments with on-lot sewer and on-lot water⁵									
Single-Family Detached Dwelling	43,560 sq. ft.	35 ft.	150 ft.	100 ft.	30%	35 ft.	15 ft. ³	30 ft.	30 ft.
Developments with on-lot sewer and public water, or public sewer and on-lot water⁵									
Single-Family Detached Dwelling	32,000 sq. ft.	35 ft.	120 ft.	80 ft.	35%	35 ft.	10 ft. ³	20 ft.	25 ft.
Developments with public sewer and public water									
Single-Family Detached Dwelling	10,000 sq. ft.	35 ft.	80 ft.	65 ft.	40%	25 ft.	5 ft. ³	10 ft.	15 ft.
Duplexes	3,500 sq. ft. per unit ⁶	35 ft.	45 ft. / unit	40 ft. / unit	60%	25 ft.	10 ft.	N/A	15 ft.
Townhouses ¹	2,400 sq. ft. per unit ⁶	35 ft.	24 ft.	24 ft. / unit	70%	25 ft.	10 ft.	(End Units)	15 ft.
Multiple- Family ²	43,560 sq. ft. ⁶	35 ft.	150 ft.	200 ft.	60%	35 ft.	30 ft.	60 ft.	35 ft.

¹ No townhouse building shall contain more than eight (8) units. For each townhouse building containing more than four (4) units, no more than sixty percent (60%) of such units shall have the same front yard setback; the minimum variation of setback shall be two feet (2'). In addition, no more than two (2) contiguous units shall have identical roof lines that generally parallel the ground along the same horizontal plane. All townhouse buildings shall be set back a minimum of fifteen feet (15') from any interior access drives, or parking facilities contained on commonly held lands. All townhouse buildings shall be set back at least thirty feet (30') from any perimeter boundary of the conservation design development site. In those instances where several townhouse buildings are located on the same lot, the following footnote 2 shall apply.

² In those instances where several multiple-family dwelling buildings and/or townhouse buildings are located on the same lot, the following separation distances will be provided between each building:

- a. Front to front, rear to rear, or front to rear, parallel buildings shall have at least fifty feet (50') between faces of the building. If the front or rear faces are obliquely aligned, the above distances may be decreased by as much as ten feet (10') at one end if increased by similar or greater distance at the other end.
- b. A minimum yard space of thirty feet (30') is required between end walls of buildings. If the buildings are at right angles to each other, the distance between the corners of the end walls of the building may be reduced to a minimum of twenty feet (20').
- c. A minimum yard space of thirty feet (30') is required between end walls and front or rear faces of buildings.
- d. All multiple-family dwelling buildings shall be set back a minimum of fifteen feet (15') from any interior access drives or parking facilities contained on commonly held lands. All multiple-family dwelling buildings shall be set back at least thirty feet (30') from any perimeter boundary of the conservation design development site.

³ If the property abuts an arterial road, the minimum front yard setback shall be forty feet (40') from the right-of-way line. Except for multiple-family dwellings, the minimum front yard setback for accessory residential garages shall be twenty feet (20').

⁴ No part of a principal residence or other principal building shall be located within one hundred feet (100') of any adjoining property within the Agricultural Zone, unless such adjoining property is developed for non-agricultural purposes. No part of a residential or other accessory structure shall be located within fifteen feet (15') of any adjoining property within the Agricultural Zone, unless such adjoining property is developed for non-agricultural purposes.

⁵ All uses relying upon on-lot sewers shall comply with Section 323 of this Ordinance.

⁶ All accessory structures shall comply with the applicable setbacks listed in the underlying Zone.

Section 426 Convenience Stores

426.A. Within the (BI) Zone, convenience stores are permitted by right, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those specifically as follows:

426.B. All uses must comply with applicable standards contained throughout this Ordinance. When any of the following uses require a special exception or conditional use, such approvals shall be obtained prior to application for the zoning permit for the convenience store. The zoning permit must also demonstrate compliance with any conditions of approval imposed upon any of the specific uses. The following lists some of those typically associated with convenience stores and their respective requirements:

Use	Section No.
Gas station	411
Car wash	417

426.C. The applicant must furnish evidence as to how the use will be controlled so as to not constitute a nuisance due to noise or loitering outside the building;

426.D. The convenience store shall provide for one off-street parking space for each 350 square feet of gross floor area; and,

426.E. An acceptable working plan for the cleanup of litter shall be furnished and implemented by the applicant.

426.F. A convenience store may include the following activities, subject to any additional approvals as noted below if they are conducted as part of the convenience store:

1. Retail sales of books, magazines, videos, software, and video games, provided that adult entertainment uses are expressly prohibited;
2. Automatic bank teller machines;
3. Photomats and film development drop-off sites;
4. Lottery sales counters and machines;
5. Propane fuel sales within no larger than 20-pound tanks which must be stored outside of the building at all times;
6. Car washes, subject to the requirements of 417 of this Ordinance; and,
7. Mail parcel delivery drop-off sites.

Section 427 Convention and/or Conference Centers

427.A. Within the (BI) Zone, convention and/or conference centers are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:

427.B. Convention and/or conference centers may include any of the following uses, provided such uses

are primarily sized, located and designed as one integrated development (e.g., shared parking, signage, access, lighting, storm water management, etc.) to serve those persons or groups of persons attending the convention and/or conference center, and not the general public:

1. Offices;
2. Meeting rooms and auditoriums;
3. Banquet and social halls;
4. Indoor theaters and arenas;
5. Personal service shops (i.e., barbers, salons, dry cleaners, tailors, shoe repair, but excluding adult-related uses);
6. Commercial day care facilities;
7. Information centers and booths; and,
8. Outdoor activities provided that no such activities shall be conducted upon any area of required off-street parking or off-street loading, including, but not limited to, outdoor amusements, shows for automobiles, consumer goods, agricultural equipment, supplies and livestock, sports equipment, boats, home and building materials and landscaping, community festivals, carnivals, circuses, concerts and other similar events.

427.C. MINIMUM LOT AREA - Ten (10) acres;

427.D. The applicant must demonstrate that adequate means of sewage disposal and water supply will serve the proposed use;

427.E. The subject property shall provide a suitable means of vehicular access that conveniently connects to an arterial or collector road;

427.F. Required parking will be determined based upon a combination of the types of activities proposed, and Section 315 of this Ordinance. In addition, an unimproved, grassed, overflow parking area to be provided for peak use periods shall be required. Such overflow parking areas shall be accessible only from the interior driveways of the permanent parking lot. Overflow parking areas shall contain fencing to prevent vehicles from crossing adjoining properties or directly accessing adjoining roads. Soil erosion, sedimentation and storm water runoff shall be controlled in accordance with all applicable laws and regulations;

427.G. Any booths or other structures used for the collection of admission and/or parking fees shall be set back and arranged to prevent vehicle backups on adjoining roads during peak arrival periods. Any other collection of fees (roaming parking lot attendants) shall be conducted in a manner to prevent vehicle backups on adjoining roads. If, at any time after opening, the Township determines that traffic backups are occurring on adjoining roads, and such backups are directly related to the means of access to the subject property, the Township can require the applicant to revise means to relieve the undue congestion;

427.H. Any outside pedestrian waiting lines shall be provided with a means of shade;

427.I. The applicant shall furnish expert evidence that the proposed use will not be detrimental to the use of adjoining properties due to hours of operation, noise, light, litter, dust, and pollution. All lighting on the site must comply with Section 310 of this Ordinance;

427.J. Those uses involving extensive outdoor activities and/or display shall provide sufficient screening and/or landscaping measures to mitigate any visual and/or audible impacts on adjoining properties and roads. No outdoor storage is permitted;

427.K. A traffic impact study shall be prepared in accordance with Section 319 of this Ordinance;

- 427.L.** Any exterior public address system shall be designed and operated so that the audible levels of any messages conveyed over the system will not exceed the ambient noise levels of the use, as measured at each of the property lines. Any noise generated on the site must comply with Section 311 of this Ordinance;
- 427.M.** The convention and/or conference center is eligible to utilize planned center signage, as listed in Section 322 of this Ordinance; and,
- 427.N.** All uses within the convention and/or conference center shall be linked with sidewalks and/or pathways to facilitate safe and efficient pedestrian movements.

Section 428 Composting

- 428.A.** Within the (C, A, LDR, and MU) Zones, one compost area/pile is a permitted accessory use to a residence, subject to the following requirements:
- 428.B.** The placement of a framed enclosure for composting is subject to all residential accessory use setbacks.
- 428.C.** Only waste materials from the on-site residence shall be deposited within the compost enclosure;
- 428.D.** In no case shall meat or meat by-products be composted; and,
- 428.E.** All composting enclosures shall be maintained such that they will not create a nuisance to nearby properties.

Section 429 Restaurants.

- 429.A.** Within the (BI) Zone, restaurants are permitted by right, provided that the owner/occupier complies with all applicable regulations contained within this Ordinance including but not limited to this section, and within the (MU) Zone, restaurants are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows.
- 429.B.** Exterior trash/recycling receptacles shall be provided and routinely emptied so to prevent the scattering of litter;
- 429.C.** All drive-thru window-lanes shall be separated from the parking lot's interior driveways and shall provide at least two hundred feet (200') of on-site stacking per lane, preceding the food order location. Furthermore, each drive-thru lane shall have on-site directional signs, indicator lights or pavement markings identifying the direction of travel and lane status (ie. open vs. closed);
- 429.D.** Any exterior speaker/microphone shall be arranged, operated and/or screened to comply with Section 316 of this Ordinance, including any referenced or incorporated ordinance;
- 429.E.** Requirements for off-street parking and the design and construction of all off-street parking areas and access drives shall be in compliance with the regulations of this Ordinance.
- 429.F.** All off-street loading and service areas shall be screened from the street and adjacent properties in accordance with the regulations of this Ordinance.
- 429.G.** All exterior seating/play areas shall be completely enclosed by a minimum three foot (3') high fence;
- 429.H.** All lighting systems shall be arranged, operated and/or screened to comply with Section 310 of this Ordinance;

Section 430 Dry Cleaners, Laundries and Laundromats

- 430.A.** Within the (MI and BI) Zones, dry cleaners, laundries and laundromats are permitted by right as “personal services”, provided that the owner/occupier complies with all applicable regulations contained within this Ordinance including but not limited to the following:
- 430.B.** The applicant must demonstrate that adequate means of sewage disposal and water supply will serve the proposed use;
- 430.C.** All activities shall be conducted within a completely enclosed building;
- 430.D.** During operation or plant clean-up and maintenance, all windows and doors on walls facing adjoining residential zones shall be kept closed; and,
- 430.E.** Any exhaust ventilation equipment shall be directed away from any adjoining residential use.

Section 431 Temporary Family Housing

- 431.A.** Within the (C, A, MU, and LDR) Zones, one temporary family housing unit, as defined herein, is permitted by right as an accessory use to one principal dwelling unit subject to the following requirements:
- 431.B.** **MINIMUM LOT AREA** - One (1) acre and the temporary family housing unit shall be of portable construction and may not exceed nine hundred (900) square feet of floor area;
- 431.C.** The total building coverage for the principal dwelling, any existing accessory structures and the temporary family housing unit together shall not exceed the maximum lot coverage requirement for the respective Zone;
- 431.D.** The temporary family housing unit shall be occupied by:
 - 1. one adult individual, or a handicapped and/or a disabled person, any of which are related by blood, marriage or adoption to the occupants of the principal dwelling; or,
 - 2. the caregiver who is related by blood, marriage or adoption to the handicapped or disabled occupant(s) of the principal dwelling, or an unrelated care giver who provides for care on a full-time basis;
- 431.E.** The temporary family housing unit shall be occupied by a maximum of two (2) people;
- 431.F.** For sewage disposal and water supply and all other utilities, the temporary family housing unit shall be physically connected to those systems serving the principal dwelling; no separate utility systems or connections shall be constructed or used, unless required by the PA DEP. All connections shall meet the applicable utility company standards. If on-site sewer or water systems are to be used, the applicant shall submit evidence that the total number of occupants in both the principal dwelling and the temporary family housing unit will not exceed the maximum capacities for which the one-unit systems were designed, unless those systems are to be expanded, in which case the expansion approvals are to be submitted. Any connection to or addition to an existing on-site sewer system shall be subject to the review and approval of the sewage enforcement officer;
- 431.G.** A minimum of one (1) all-weather, off-street parking space, with unrestricted ingress and egress to the street, shall be provided for the temporary family housing unit, in addition to that required for the principal dwelling;

- 431.H.** Unless provided within an existing building, the temporary family housing unit shall be installed and located only in the side or rear yards, and shall adhere to all side and rear yard setback requirements for principal uses;
- 431.I.** The temporary family housing unit shall be removed from the property within three (3) months after it is no longer occupied by a person who qualifies for the use. The applicant shall be required to post a bond with the Township for a value equal to the cost of lawful removal of the use from the property, prior to issuance of a zoning permit for the proposed use; and,
- 431.J.** Upon the proper installation of the temporary family housing unit, the Zoning Officer shall issue a temporary zoning permit. Such temporary zoning permit shall be reviewed by the Zoning Officer every twelve (12) months for renewal, until such time as the temporary family housing unit is required to be removed. In any review for renewal the Zoning Officer finds the temporary family housing unit does not comply with all applicable Zoning regulations, including this Section 431, the Zoning Officer may revoke such temporary zoning permit, requiring immediate removal of the temporary family housing unit. A fee, in the amount to be set by the Board of Supervisors, shall be paid by the landowner upon each renewal of the temporary zoning permit. Such fee shall be based upon the cost of the annual review of the permit.

Section 432 Group Homes

432.A. Within the (MU, MI and BI) Zones, group homes are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically, as follows:

432.B. SUPERVISION.

There shall be adequate supervision as needed by an adequate number of person(s) trained in the field for which the group home is intended. Such adequacy shall be determined by the Pennsylvania Department of Public Welfare.

432.C. CERTIFICATION.

Any group home involving three (3) or more unrelated persons living in a dwelling unit or that is otherwise required to be licensed or certified under any applicable state, county or federal program shall be certified or licensed, as applicable, as a condition of Township approval. A copy of any such license or certification shall be filed with the Township and shall be required to be shown to the Zoning Officer upon request. The group home shall notify the Township, in writing, within 14 days if there is a change in the type of clients, the sponsoring agency, the maximum number of residents or if an applicable certification/license expires, is suspended or is withdrawn.

432.D. REGISTRATION.

For fire and safety purposes, the group home shall register with the Township its location, sponsoring agency, general type of treatment/care, maximum number of residents permitted and the exact location of the bedrooms of the individuals who need assistance with evacuation in the event of any actual fire. Such information shall be available for public review upon request.

432.E. PARKING.

One off-street parking space per occupant shall be provided for the dwelling unit and one off-street parking space shall be provided for each employee on duty at any one time.

432.F. The use shall not meet the definition of a "boardinghouse." A group home shall not house

persons who can reasonably be considered to be a physical threat to others, as determined by the Pennsylvania Department of Public Welfare.

- 432.G.** The number of persons who may reside in a group home shall not restrict or include bona fide employees who are needed in the group home to supervise and care for residents.
- 432.H.** Any group home shall comply with all building codes, including but not limited to the Uniform Construction Code requirements applicable to said occupancy classification prior to occupancy.

Section 433 Farm Occupations

- 433.A.** Within the (C, A and MU) Zones, farm occupations, as defined herein, if conducted as an accessory use to a principal agricultural use of the property are permitted by right subject to the following requirements:
- 433.B.** Residents and up to four (4) nonresidents may be employed by the farm occupation;
- 433.C.** The use must be conducted within one (1) completely enclosed building. Where practicable the farm occupation shall be conducted within an existing farm building. However, any new building constructed for use by the farm occupation shall be located behind the farm's principal buildings, or must be no less than one hundred feet (100') from any adjoining roads or properties;
- 433.D.** Any new building constructed for use by the farm occupation shall be of a design so that it can be readily converted to agricultural use, or removed, if the farm occupation is discontinued;
- 433.E.** No part of a farm occupation shall be located within one hundred feet (100') of any side or rear lot line, nor three hundred feet (300') of any adjoining land within an (LDR or MU) Zone. Such distances shall be measured as a straight line between the closest points of any physical improvement associated with the farm occupation and the property/zoning line;
- 433.F.** The farm occupation shall occupy no more than four thousand (4,000) square feet of gross floor area, nor more than one (1) acre of lot area. However, any access drive serving the farm occupation and the farm shall not be calculated as land serving the farm occupation;
- 433.G.** No more than fifty percent (50%) of the land devoted to a farm occupation shall be covered by buildings, structures, parking or loading areas, or any other impervious surfaces;
- 433.H.** Any sign used for a farm occupation shall not exceed eight (8) square feet in size;
- 433.I.** For farm parcels of up to fifty (50) acres in size, while the farm occupation is in operation, no non-farm subdivision of the site shall be permitted; and,
- 433.J.** The applicant is required to submit written information indicating that the disposal of all materials and wastes will be accomplished in a manner that complies with State and Federal regulations. Such evidence shall, at a minimum include, copies of contracts with waste haulers licensed to operate within Cumberland County, which have been contracted to dispose of the materials and wastes used, or generated, on-site or some other legal means of disposal. The zoning permit for this use shall remain valid, only so long as such contracts remain in effect and all materials and wastes are properly disposed of on a regular basis. Should the nature of the farm occupation change in the future, such that the materials used, or wastes generated, changes significantly, either in type or amount, the owner of the farm occupation shall so inform the Zoning Officer, and shall provide additional evidence demonstrating continued compliance with the requirements of this Section.

433.K. The applicant shall submit the following signed and notarized statement:

"I understand that this use has prescribed limitations that are imposed to protect the rural character of the Township. I also recognize that continued success of my business that requires expansion beyond such limitations at this location would constitute a zoning violation. Should expansion beyond these limitations occur, I will be required to find another, more suitable, location with the appropriate zoning."

Section 434 Farmers and/or Flea Markets

- 434.A.** Within the (BI) Zone, farmers and/or flea markets are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:
- 434.B.** The retail sales area shall be considered to be that of the smallest rectangle, or other regular geometric shape which encompasses all display stands, booths, tables, or stalls, plus any adjoining aisles and/or walkways from which consumers can inspect items for sale. The retail sales area shall include all indoor and/or outdoor areas as listed above;
- 434.C.** The retail sales area shall be set back at least fifty (50) feet from all property lines, and shall be calculated as part of the maximum permitted lot coverage, regardless of its surface treatment;
- 434.D.** Off-street parking shall be provided at the rate of one space per each two hundred (200) square feet of retail sales area and shall be designed and used in accordance with Section 315 of this Ordinance. No required off-street parking spaces shall be used for the display and/or storage of items for sale;
- 434.E.** Off-street loading shall be provided at the rate similar to that imposed on retail sales as listed in Section 314 of this Ordinance. The retail sales area, as described above, shall be used to calculate needed loading space(s);
- 434.F.** All outdoor display and sale of merchandise shall occur between official sunrise and no later than one hour prior to official sunset;
- 434.G.** Any exterior amplified public address system shall be arranged and designed so as to prevent objectionable impact on adjoining properties and the applicant shall demonstrate compliance with Section 316 of this Ordinance, including all referenced and incorporated ordinances;
- 434.H.** All lighting systems shall be arranged, operated and/or screened to comply with Section 310 of this Ordinance; and,
- 434.I.** Trash receptacles shall be provided amid any outdoor retail sales area. Such trash receptacles shall be routinely emptied so as to prevent the scattering of litter and debris. All applications shall include a description of an acceptable working plan for the clean-up of litter.

Section 435 Fences and Walls

- 435.A.** Within the (C, A, LDR and MU) Zones, fences and walls are permitted by right as accessory uses within required yard areas, provided that no fence or wall (except agricultural, required junkyard, athletic court, outdoor shooting range walls or fences, or a retaining walls as noted below) shall be erected to a height of more than:
1. three (3) feet in a front yard; except that,
 2. fences and walls erected upon reverse frontage lots may extend up to height of six (6) feet

- within those yards that do not contain vehicular access onto an adjoining road; and,
3. six (6) feet in any side or rear yard.
- 435.B.** Within the (MI and BI) Zones, fences and walls are permitted by right as accessory uses, provided that no fence or wall (except agricultural, required junkyard or tennis court walls or fences, or a retaining walls as noted below in Section 435.D.) shall be erected to a height of more than ten (10) feet in any yard.
- 435.C.** No fence or wall shall interfere with the required clear sight triangles in Sections 301, 303 and 305.C. of this Ordinance;
- 435.D.** The use of retaining walls higher than three (3) feet up to a maximum height of twelve feet (12') is permitted, subject to the following findings:
1. That the proposed height of the retaining wall is necessary to facilitate an efficient use of the site and/or protect an important or sensitive natural or cultural feature of the site;
 2. That the applicant has submitted written expert evidence from a professional engineer registered to practice within the Commonwealth of Pennsylvania that the proposed retaining wall is designed and will be constructed to assure structural integrity and will in no way adversely affect any drainage pattern and/or underground utility lines nor interfere with their rights-of-way;
 3. That the applicant has provided sufficient separation and physical barriers between the proposed retaining wall and any pedestrian and/or vehicle movement areas to ensure adequate vehicle and pedestrian safety; and,
 4. That the base of the retaining wall is setback a horizontal distance at least equal to its height from each property line.
- 435.E.** The use of barbed wire and electric fences are expressly prohibited in the (LDR) Zone.
- 435.F.** Fences and walls shall be constructed of durable materials suited for its purpose and the use of discarded materials, vehicles, and appliances is prohibited. No wall or fence shall be constructed of corrugated metal, corrugated fiberglass, or sheet metal.
- 435.G.** All fences and walls shall be erected and maintained in an upright, safe, and sound condition.

Section 436 Fish Hatcheries and/or Fish Farms

- 436.A.** Within the (C and A) Zone, fish hatcheries and/or fish farms are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:
- 436.B.** The applicant must furnish evidence of receipt of an approved artificial propagation license from the PA Department of Agriculture, Bureau of Animal Health.
- 436.C.** A written plan that describes the methods used to: (1) contain and prevent animal escape; (2) dispose of deceased animals in compliance with applicable State laws; (3) handle, and dispose of animal wastes in a manner that is compatible with surrounding uses both on and off of the site; and, (4) offer the humane treatment and care of animals at all times.

Section 437 Medical Marijuana Facilities

- 437.A.** Within the (BI) Zone, medical marijuana facilities, which include both medical marijuana dispensaries and medical marijuana grower/processor facilities, are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:
- 437.B.** Applicant shall establish that it complies with all requirements, including without limitation planning and land use requirements, as set forth in the Medical Marijuana Act, as may be amended, for either a dispensary or grower/processor, as may be applicable to the proposed use.
- 437.C.** No medical marijuana facility shall be located within 1,000 feet of any church, school, day care, or residential property.
- 437.D.** Any application for a medical marijuana facility shall be accompanied by a security plan addressing the safety and security of the physical facility, personnel, and the public.
- 437.E.** A medical marijuana dispensary may sell, along with medical marijuana, medical devices and instruments which are needed to administer medical marijuana.

Section 438 Freestanding Communication Antennas, Towers and Equipment

- 438.A.** Within the (C, A, MI and BI) Zones, freestanding communication antennas, towers and equipment are permitted as an accessory use by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:

438.B. PREREQUISITE CO-LOCATION ANALYSIS

1. Approval of a new freestanding communication antenna, tower and equipment will only be permitted after qualified expert demonstration by the applicant that no other opportunity exists within a two (2) mile radius of the proposed site to co-locate such antenna onto any of the following:
 - a. utility transmission towers;
 - b. observation towers;
 - c. communication towers;
 - d. silos;
 - e. steeples;
 - f. smokestacks;
 - g. water towers;
 - h. flagpoles; and,
 - i. other similar structures.

2. In order to demonstrate compliance with this Section, the applicant must prepare and submit an inventory map of all such co-location opportunities within a two (2) mile radius of the proposed site and list the specific reason why each co-location site is not possible, for one or more of the following reasons:
 - a. Written refusal by current tower owner to accommodate proposed antenna;
 - b. Topographic limitations that prevent adequate transmission coverage;

- c. Adjacent impediments blocking adequate transmission coverage;
 - d. Technical limitations of the system that prevent adequate transmission coverage;
 - e. Proposed antenna exceeds structural capacity of structure or tower;
 - f. Inadequate space on structure or tower;
 - g. Reserved space on existing structure or tower for other antennas; and/or,
 - h. Other specifically described limiting factors rendering existing structure or tower unusable.
3. To the extent the applicant is not the fee simple owner of the property at which the communication antenna or tower is proposed, the applicant shall submit a copy of the written agreement with the landowner upon whose property the antenna or tower is to be constructed.

438.C. SITING REQUIREMENTS

The applicant shall demonstrate, using technical evidence, that the proposed location is necessary for the efficient operation of the system. All other uses associated with the communication antenna or tower, such as a business office, maintenance depot, business sign, or vehicle storage, shall not be located on the site, unless the use is otherwise permitted in the Zone in which the site is located;

438.D. FUTURE CO-LOCATION REQUIREMENTS

In order to reduce the number of towers needed in the Township in the future, any proposed new tower or other support structure shall be designed to accommodate other co-located antennas, including, but not limited to, police, fire and emergency services;

438.E. REQUIRED ANTENNA TOWERS

Except as provided below, a monopole antenna tower shall be required when new towers are proposed, unless the applicant can conclusively demonstrate that:

1. The cost of erecting a monopole would preclude the provision of adequate service to the public;
2. The use of a monopole would produce an unsafe antenna support structure at the proposed location;
3. The proposed alternative antenna structure would have the least adverse visual impact on the environment and surroundings; and/or,
4. The proposed alternative antenna support structure is more architecturally compatible with surrounding uses and blends in better with the existing characteristics of the site and its surroundings.

438.F. PERMITTED HEIGHT

The applicant shall submit expert testimony that the communication antenna or tower is the minimum height required to function satisfactorily. In no case shall an antenna or tower exceed one hundred ninety-nine feet (199') in height;

438.G. REQUIRED SETBACKS

Any communication antenna or tower shall be set back from each property line a distance equal to its height, plus fifty feet (50'). This setback shall also be applicable to guy wire anchors for the

communication antenna or tower. No antenna or tower shall be located within five hundred horizontal feet (500') of:

1. Any land within the (LDR and MU) Zones;
2. The nearest property line of any existing residence;
3. The nearest property line of any approved lot which has been subdivided during the last five (5) years for residential purposes, which has not yet been constructed; and,
4. The nearest property line of any lot proposed for residential purposes that has been submitted for preliminary or final subdivision approval.

438.H. REQUIRED FINISHES AND LIGHTING

Communication antennas or towers shall be painted with silver or gray paint or have a galvanized finish in order to reduce visual impact. Support structures may be painted green up to the height of nearby trees, to lessen visual impact. No communication antenna or tower may be artificially lighted, except when required by the Federal Aviation Administration, State regulations or by Township requirements;

438.I. ANTI-CLIMBING REQUIREMENTS

All communication antennas or towers shall be fitted with anti-climbing devices, as approved by the manufacturers;

438.J. COMPLIANCE WITH COMMUNICATION REQUIREMENTS

The applicant shall be required to demonstrate that it is licensed by the Federal Communications Commission to operate the proposed use and that it will comply with the applicable standards governing human exposure to electromagnetic radiation by the Federal Communications Commission. The applicant shall also demonstrate compliance with guidelines recommended by the American National Standard Institute (ANSI) (ANSI/ EEEEC95-1-1992) with respect to radio frequency emissions;

438.K. COMPLIANCE WITH AVIATION REQUIREMENTS

The applicant shall demonstrate that the proposed use will comply with all applicable Federal Aviation Administration and Commonwealth Bureau of Aviation regulations;

438.L. REQUIRED HISTORIC SITE FINDINGS

In accordance with Section 106 of the National Historic Preservation Act as an undertaking requiring a Federal permit, license or approval, the applicant shall be required to obtain a Letter of Determination from the State Historic Preservation Office of the Pennsylvania Historical and Museum Commission, determining that the proposed use will not adversely affect any historic resources;

438.M. REQUIRED CONSTRUCTION CERTIFICATION

The applicant shall furnish a sealed statement from a registered engineer that the support methods employed will prevent the collapse, toppling or falling of the communication antenna or tower, or portion thereof, and will prevent the windborne scattering of ice onto adjoining properties and/or roads;

438.N. REQUIRED FENCING AND SIGNAGE

All communication antennas or towers and guy wire anchors shall be completely enclosed by a minimum eight foot (8") high non-climbable fence. All ground-mounted satellite dishes that are used to transmit video format data shall also require prominent posting on the fence of signage warning of dangerous radiation levels. Any gates within the fence shall be self-closing and shall be locked when the site is unattended;

438.O. REQUIRED PARKING

If a tower site is fully automated, two (2) off-street parking spaces shall be required. If the site is not automated, the number of required parking spaces shall equal the number of people on the largest shift, but in any event, may not be less than two (2) off-street parking spaces;

438.P. REQUIRED LANDSCAPING

The applicant shall be required to provide landscaped screening, as defined herein, around the ground-level features of the proposed use (e.g., tower base, fence, parking and loading, related buildings, guy wire anchors, etc.). In addition, existing vegetation on and around the site shall be preserved to the greatest extent possible;

438.Q. REQUIRED REMOVAL PLAN

The applicant shall submit a plan for the removal of the communication antenna when it becomes functionally obsolete or is no longer in use. The applicant shall be responsible for the removal of the antenna within three (3) months from the date it ceases operation or the antenna becomes obsolete;

438.R. REQUIRED AS-BUILT PLAN

Prior to issuance of a certificate of use and occupancy, the applicant shall be required to submit an "as-built" site plan, prepared by either a registered surveyor or a professional engineer, depicting elevations, the communication antenna or tower, buildings, fences, screening, access, and any accessory structures; and,

438.S. REQUIRED CERTIFICATE OF INSURANCE

The applicant shall submit and keep on file, with the Township, a copy of its current Federal Communications Commission license, the name, address and emergency telephone number for the operator of the communications tower and a certificate of insurance evidencing general liability coverage in the minimum amount of \$1,000,000 per occurrence and property damage coverage in the minimum amount of \$1,000,000 per occurrence covering the communications tower and communications antennas.

438.T. REQUIRED BIENNIAL INSPECTION

Beginning in December of 2018, and by December 1 of each even-numbered year thereafter, any approved communication antenna or tower shall be inspected by an expert who is regularly involved in the maintenance, inspection and/or erection of such antennas or towers. At a minimum, this inspection shall be conducted in accordance with the Tower Inspection Class Checklist provided in the Electronics Industries Association (EIA) Standard 222 "Structural Standards for Steel Antenna Towers and Antenna Support Structures." A copy of said inspection report shall be provided to the Township, along with a review fee in the amount to be determined by resolution by the Board of Supervisors. Failure to provide this inspection report and review fee shall constitute a violation of this Ordinance.

Section 439 Funeral Homes

- 439.A.** Within the (MU) Zone, funeral homes are permitted by special exception provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:
- 439.B.** One off-street parking space shall be provided for each 50 square feet of gross floor area shall be designed to prevent back-ups onto adjoining roads; the applicant shall describe what measure will be used to prevent back-ups (e.g. overflow parking, parking attendants, etc.) to prevent such back-ups;
- 439.C.** All parking areas shall be setback at least ten feet (10') from adjoining lot lines, and no joint off-street parking areas shall be permitted; and,

Section 440 Garage / Yard / Moving Sales

- 440.A.** Within the (C, A, LDR and MU) Zones, and upon properties with principal residential dwelling units, garage yard and/or moving sales are an accessory permitted use, subject to the following standards:
- 440.B.** Such sales may only be conducted by an owner or occupant of a lot;
- 440.C.** No more than three (3) total sales may be conducted during any calendar year;
- 440.D.** No garage/yard/moving sale shall be conducted for a period longer than three (3) consecutive days. No garage/yard/moving sale shall be conducted on a Sunday;
- 440.E.** Such sales may offer personal possessions for sale; no import or stocking of inventory shall be permitted.
- 440.F.** Only one (1) sign, not to exceed four (4) square feet in area, shall be permitted to advertise the garage/yard sale. Said sign shall be located on the lot where the sale occurs and shall be removed within six (6) hours of the completion of the sale;
- 440.G.** In no case shall any aspect of the garage/yard sale be conducted in the street right of way.
- 440.H.** The conduct of a garage/yard/moving sale beyond the extent described herein represents a commercial business and shall require appropriate zoning authorization.

Section 441 Golf Courses and Driving Ranges

- 441.A.** Within the (C, A and MU) Zones, golf courses and driving ranges are permitted by special exception provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically set forth below. While golf courses must comply with all of the following criteria, freestanding driving ranges (not provided as part of a golf course) must only comply with Sections 441.B., 441.C., 441.F., and 441.J:
- 441.B.** In no case shall the golf course design permit or encourage a golf ball to be driven across any building, building lot, parking lot, street, access drive, or driveway, and all driving ranges shall be designed to include fencing (with a minimum height of 50 feet) along roads and adjacent buildings within 100 ft. of any golf ball landing area on a driving range;

441.C. GOLF PATHS

Golf paths shall be graded so as to discharge storm water runoff. Surface conditions of paths shall be adequately protected from an exposed soil condition.

1. The golf course design shall minimize golf path crossings of streets, access drives and driveways. Easily identifiable golf paths must be provided for crossings of streets, access drives or driveways. The golf course design shall both discourage random crossing and require use of the golf path crossings of streets, access drives and driveways. Golf path crossings shall conform to the following:
 - a. Each crossing shall be perpendicular to the traffic movements;
 - b. Only one (1) street, access drive or driveway may be crossed at each location;
 - c. No crossing is permitted between a point fifteen feet (15') and one hundred fifty feet (150') from the cartway edge of a street, access drive or driveway intersection;
 - d. The crossing must be provided with a clear sight triangle of seventy-five feet (75'), measured along the street, access drive or driveway centerline and the golf path centerline, to a location on the centerline of the golf path, five feet (5') from the edge of the roadway. No permanent obstruction over thirty inches (30") high shall be placed within this area;
 - e. Sight Distance - Golf path intersections shall be designed to provide adequate sight distance with regard to both horizontal and vertical alignment. The required sight distance shall be governed by Section 303 of this Ordinance;
 - f. The golf cart path shall not exceed a slope of eight percent (8%) within twenty-five feet (25') of the cartway crossing;
 - g. Golf path crossings shall be signed, warning motorists and pedestrians and golfers. The surface of the golf path shall be brightly painted with angle stripes; and,
 - h. Golf path crossings of collector or arterial streets shall consist of a tunnel or bridge that is not located at street grade. The golf course design shall both prohibit on-grade crossing of collector or arterial streets and require the use of the tunnel. The construction of the collector or arterial roadway crossing of the tunnel shall comply with PennDOT standards.

441.D. All golf course buildings shall be set back seventy-five feet (75') from any adjoining roads and one hundred feet (100') from adjoining residential structures or parcels;

441.E. Golf courses may include the following accessory uses, provided such uses are reasonably sized, and located so as to provide incidental service to the golf course employees and users:

1. Clubhouse, which may consist of:
 - a. Restaurant, snack bar, lounge, and banquet facilities;
 - b. Locker and rest rooms;
 - c. Pro shop;
 - d. Administrative offices;
 - e. Golf cart and maintenance equipment storage and service facilities;
 - f. Guest lodging for those using the golf course, provided:
 - no lodging units have separate exterior means of ingress/egress;
 - all lodging units shall be contained within the main clubhouse; and,
 - such guest lodging shall have a total occupancy of no more than twenty

- (20) persons;
 - i. Fitness and health equipment, including workout machines, spas, whirlpools, saunas, and steam rooms;
 - j. Game rooms, including card tables, billiards, ping-pong, and other similar table games; and,
 - k. Baby-sitting rooms and connected fence-enclosed playlots.
2. Accessory recreation amenities located outside of a building, including:
- a. Driving range, provided that no lighting is utilized;
 - b. Practice putting greens;
 - c. Swimming pools;
 - d. Tennis, platform tennis, handball, racquetball, squash, volleyball, and badminton courts;
 - e. Bocce ball, croquet, shuffleboard, quoits, horseshoe pits, and washers' courses;
 - f. Picnic pavilions, picnic tables, park benches, and barbecue pits;
 - g. Hiking, biking, horseback riding, and cross-country ski trails; and,
 - h. Playground equipment and playlot games, including 4-square, dodgeball, tetherball, and hopscotch.
3. Freestanding maintenance equipment and supply buildings and storage yards.
- 441.F.** All outdoor storage of maintenance equipment and/or golf carts shall be set back at least one hundred feet (100') and screened from adjoining residential structures and roads;
- 441.G.** The applicant shall submit an analysis of raw water needs (groundwater or surface water) from either private or public sources, indicating quantity of water required. If the source is from a municipal system, the applicant shall submit documentation that the municipal system will supply the water needed.
- 441.H.** If the facility is to rely upon non-public sources of water, a water feasibility study will be provided to enable the municipality to evaluate the impact of the proposed development on the groundwater supply and on existing wells. The purpose of the study will be to determine if there is an adequate supply of water for the proposed development and to estimate the impact of the new development on existing wells in the vicinity. A water feasibility study shall include the following information:
- 1. calculations of the projected water needs;
 - 2. a geologic map of the area with a radius of at least one mile from the site;
 - 3. the location of all existing and proposed wells within one thousand feet (1,000') of the site, with a notation of the capacity of all high-yield wells;
 - 4. the location of all existing on-lot sewage disposal systems within one thousand feet (1,000') of the site;
 - 5. the location of all streams within one thousand feet (1,000') of the site and all known point sources of pollution;
 - 6. based on the geologic formation(s) underlying the site, the long-term safe yield shall be determined;
 - 7. a determination of the effects of the proposed water supply system on the quantity and quality of water in nearby wells, streams and the groundwater table; and,
 - 8. a statement of the qualifications and the signature(s) of the person(s) preparing the study.
- 441.I.** A water system which does not provide an adequate supply of water for the proposed development, considering both quantity and quality, or does not provide for adequate groundwater recharge, considering the water withdrawn by the proposed development, shall not be approved by the Township.

441.J. The applicant shall demonstrate that proposed lighting will comply with Section 310 of this Ordinance.

Section 442 Health, Fitness, Social, Fraternal and Other Private Clubs

442.A. Within the (MU and BI) Zones, health, fitness, social, fraternal and other private clubs are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:

442.B. The applicant must furnish evidence as to how the use will be controlled so as to not constitute a nuisance due to noise or loitering outside the building;

442.C. Off-street parking shall be provided, as required by the combination of elements comprising the use, including accessory uses in accordance with Section 315 of this Ordinance;

442.D. All outdoor recreation facilities shall be set back at least fifty feet (50') from the street right-of-way line, and twenty-five feet (25') from all other lot lines;

442.E. Any accessory eating, or retail use, shall not be directly accessible without passing through the main clubhouse building;

442.F. All lighting (including but not limited to outdoor recreation areas) shall be designed and arranged to comply with Section 310 of this Ordinance;

442.G. If an exterior amplified public address system is to be utilized, the applicant shall submit qualified expert evidence that the proposed public address system will be designed and operated in a manner to comply with Section 316 of this Ordinance, including any referenced and incorporated ordinances.

442.H. An acceptable working plan for the cleanup of litter shall be furnished and implemented by the applicant; and,

442.I. This use shall expressly exclude adult uses, casinos, nightclubs, off-track betting parlors and outdoor shooting ranges.

Section 443 Heavy Equipment and/or Commercial Truck Sales, Service and/or Repair Facilities

443.A. Within the (BI) Zone, heavy equipment and/or commercial truck sales, service and/or repair service facilities are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:

443.B. All service and/or repair activities shall be conducted within a completely enclosed building;

443.C. All uses involving drive-thru service shall provide sufficient on-site stacking lanes to prevent vehicle backups on adjoining roads;

443.D. No outdoor storage of parts, equipment, lubricants, fuel, or other materials used or discarded, as part of the service or repair operation, shall be permitted. All exterior storage and/or display areas

shall be screened from adjoining properties within the (LDR and MU) Zones. All exterior storage/display areas shall be set back at least fifty feet (50') from adjoining street lines, and shall be covered in an all-weather, dust-free surface;

- 443.E.** The demolition or junking of vehicles, boats, machinery, trucks, trailers, mobile homes, and heavy equipment vehicles, and/or parts thereof, on the property is prohibited;
- 443.F.** Any ventilation equipment outlets associated with the service/repair work area(s) shall not be directed toward any adjoining property within the (LDR and MU) Zones;
- 443.G.** All vehicles shall be repaired and removed from the premises promptly and no vehicle shall remain on the site for more than 45 days unless it is stored within a completely enclosed building; and,
- 443.H.** The applicant shall furnish evidence of how the storage and disposal of materials will be accomplished in a manner that complies with all applicable State and Federal regulations.

Section 444 Heavy Industrial Uses

444.A. Within the (MI and BI) Zones, heavy industrial uses, as defined herein, are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:

444.B. The applicant shall provide a detailed description of the proposed use in each of the following topics:

1. The nature of the on-site processing operations, the materials used in the process, the products produced, and the generation and methods for disposal of any wastes and/or by-products. In addition, the applicant shall furnish evidence that the storage and disposal of materials will be accomplished in a manner that complies with State and Federal regulations;
2. The general scale of the operation in terms of its market area, specific floor space requirements for each step of the industrial process, the total number of employees on each shift, and an overall needed site size;
3. Any environmental impacts that are likely to be generated (e.g., odor, noise, smoke, dust, litter, glare, vibration, electrical disturbance, wastewater, storm water, solid waste, etc.) and specific measures employed to mitigate or eliminate any negative impacts. The applicant shall further furnish expert evidence that the impacts generated by the proposed use fall within acceptable levels as regulated by applicable laws and ordinances, including, but not limited to, those of Sections 310, 313 and 316 (including all referenced and incorporated ordinances) of this Ordinance; and,
4. A traffic impact study prepared by a professional traffic engineer, according to Section 319. of this Ordinance.

444.C. Any use where diesel operated trucks periodically congregate will have in place an anti-idling policy, with a maximum idling time per truck of five (5) minutes.

Section 445 Helicopter Pads, Private

445.A. Within the (MI and BI) Zones, helicopter pads, private as an accessory use are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets

all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:

- 445.B.** All facilities shall be designed and operated in strict compliance with all applicable State and Federal laws and regulations;
- 445.C.** The applicant shall furnish evidence of the obtainment of a license from the Pennsylvania Department of Transportation, Bureau of Aviation, prior to the approval of the conditional use application;
- 445.D.** The applicant shall furnish evidence of the techniques that will be used to employ “fly-neighborly” guidelines to avoid adverse audio-visual impacts to nearby residents and livestock;
- 445.E.** No part of the take-off/landing pad shall be located nearer than three hundred feet (300') from any property line; and,
- 445.F.** The heliport may include auxiliary facilities, such as fueling and maintenance equipment subject to compliance with Section 514 of this Ordinance.

Section 446 Historic Structure Conversions

- 446.A.** Within the (C, A, LDR, MU and MI) Zones, historic structure conversions are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:
- 446.B.** The proposed use will enable the preservation, restoration or rehabilitation of the historic structure, as defined herein. The applicant is required to submit expert evidence that any alterations, improvements, extensions, additions or other modifications to the historic structure will be accomplished in a manner that does not jeopardize the historic status of the site and/or its structures. The applicant shall be required to participate in a meeting with the Pennsylvania Historic and Museum Commission (PHMC) or the Cumberland County Historical Society (ACHS) according to Section 518.C.2. of this Ordinance and present the PHMC's/ACHS's written findings as part of the special exception application for this use;
- 446.C.** The proposed use is compatible with the surrounding area. In determining compatibility, the likely impacts of the proposed use including but not limited to traffic, lighting, noise, litter, activity levels, buffer and screen plantings, signs, hours of operation and the number of proposed employees shall be considered. In addition, any public health and safety impacts that will be generated by the proposed use shall also be considered. All uses must demonstrate adequate means of water supply and sewage disposal. These characteristics of the proposed use will be evaluated within the context of the property considering the nature and character of the surrounding area, topography, pedestrian and vehicular access, and any other relevant factors or circumstances;
- 446.D.** The proposed use is consistent with the purpose of the underlying Zone and it satisfies all applicable requirements of the underlying Zone and any specific criteria attached to the proposed use as listed within this Article 4 of the Zoning Ordinance. Any proposed use that is incompatible with the Zone and the neighborhood in which the subject property is located shall be denied. As required, land development approvals must be obtained;
- 446.E.** All proposed off-street parking, off-street loading and waste storage containers shall be screened from adjoining roads, residences and properties within the (LDR and MU) Zones; and,
- 446.F.** Notwithstanding other regulations contained elsewhere within this Ordinance no more than one (1) sign shall be permitted containing up to a maximum eight (8) square feet and is located at

least ten (10) feet from each lot line.

Section 447 Home Improvement and Building Supply Stores

- 447.A.** Within the (BI) Zones, home improvement and building supply stores are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:
- 447.B.** All outdoor storage and display areas (exclusive of nursery and garden stock) shall be screened from adjoining roads and properties;
- 447.C.** If the subject property contains more than (2) acres, it shall front along an arterial or collector road;
- 447.D.** The retail sales area shall be all areas open for public display, including, but not limited to, shelves, racks, bins, stalls, tables, and booths, plus any adjoining aisles or walkways from which consumers can inspect items for sale. The retail sales area shall include both interior and exterior areas, as listed above;
- 447.E.** Off-street parking shall be provided at the rate of one (1) space for each two hundred fifty (250) square feet of interior retail sales area, plus one (1) space for each five hundred (500) square feet of exterior retail sales area;
- 447.F.** All exterior retail sales areas shall include a dust-free surface and a completely enclosed minimum six foot (6') high fence;
- 447.G.** The applicant shall furnish expert evidence that any exterior amplified public address system has been arranged and designed so as to comply with Section 316 of this Ordinance, including any referenced and incorporated ordinance;
- 447.H.** The applicant shall furnish expert evidence that any exterior lighting has been arranged and designed so as to comply with Section 310 of this Ordinance;
- 447.I.** Any drilling, cutting, sawing, mixing, crushing, or some other preparation of building materials, plus any testing or repair of motorized equipment, shall be conducted within a completely enclosed building;
- 447.J.** For uses upon properties greater than one (1) acre, the applicant shall submit a traffic impact study, as governed by Section 319 of this Ordinance; and,
- 447.K.** The applicant shall submit an acceptable working plan for the collection, recycling and disposal of litter and wastes.

Section 448 Home Occupations

- 448.A.** Within the (C, A, LDR and MU) Zones, home occupations, as defined herein, if conducted as an accessory use to a principal residence, are permitted by right subject to the following requirements:
- 448.B.** Up to two (2) nonresident employees shall be permitted;
- 448.C.** No more than one (1) home occupation may be located in any dwelling unit;
- 448.D.** The home occupation shall not alter the appearance of the building as a dwelling unit;
- 448.E.** No mechanical equipment shall be employed in a home occupation, other than that customarily utilized for hobby or domestic purposes;

- 448.F. No sales of any goods or merchandise shall occur on the premises that would require customer visitation to the site, other than those goods or merchandise which are produced on the premises;
- 448.G. No manufacturing shall occur on the premises other than the products of customary hobbies and fabrication of garments by a seamstress or tailor;
- 448.H. No goods shall be displayed so as to be visible from the exterior of the premises;
- 448.I. Home occupations shall be limited to not more than twenty-five percent (25%) of the floor area of the dwelling unit;
- 448.J. No accessory building or structure shall be utilized as a home occupation, except that an accessory building or structure may be used as storage area for the home occupation, provided that said area shall be included in the total area permitted for a home occupation use, and further, that no such accessory building or structure shall be accessible to the public for business purposes;
- 448.K. In addition to the required parking spaces for the dwelling unit, one (1) parking space for each nonresident employee and patron on site at one time shall be provided;
- 448.L. Only one sign advertising a home occupation shall be permitted. Such sign shall not be illuminated and shall be limited to eight (8) square feet in display area. Signs located within one hundred (100) feet of a road cartway may not be a freestanding sign as defined herein;
- 448.M. The applicant shall submit evidence of all applicable State approvals; and,
- 448.N. The applicant is required to submit written information indicating that the disposal of all materials and wastes will be accomplished in a manner that complies with State and Federal regulations. Such evidence shall, at a minimum include, copies of contracts with waste haulers licensed to operate within Cumberland County, which have been contracted to dispose of the materials and wastes used, or generated, on-site or some other legal means of disposal. The zoning permit for this use shall remain valid, only so long as such contracts remain in effect and all materials and wastes are properly disposed of on a regular basis. Should the nature of the home occupation change in the future, such that the materials used, or wastes generated, changes significantly, either in type or amount, the owner of the home occupation shall so inform the Zoning Officer, and shall provide additional evidence demonstrating continued compliance with the requirements of this Section.

Section 449 Hospitals with Related Uses

- 449.A. Within the (BI) Zone, hospitals with related uses are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:
 - 449.B. **MINIMUM LOT AREA** - Five (5) acres;
 - 449.C. The subject property shall have frontage along an arterial or collector road;
 - 449.D. Adequate provision shall be made for a system of roads sufficient to accommodate predictable vehicular traffic and to ensure safe and efficient vehicular access for emergency vehicles and equipment;
 - 449.E. Emergency entrances shall be located on a building wall which faces away from adjoining residential properties or properties within the (LDR and MU) Zones, or separated by at least three hundred feet (300') from properties within the (LDR and MU) Zones;
- 449.F. The applicant shall submit a traffic impact study, as governed by Section 319 of this Ordinance;

- 449.G.** The applicant is required to submit written information indicating that adequate provision shall be made for the collection, disposal and recycling of garbage, trash, and medical and hazardous waste;
- 449.H.** Where more than one (1) of the uses enumerated in 449.I. below are proposed, either at one time or separately over time, integrated site function and design shall be required, consistent with the creation of a campus-like environment;
- 449.I.** The following uses are expressly permitted provided they are designed, located and operated in a manner that supports the overall hospital use and campus:
1. Commercial day care facilities;
 2. Commercial schools with exclusively health care-related curricula intended to prepare enrolled students for careers in health care, nursing schools, and other allied health technology training programs;
 3. Health and fitness clubs;
 4. Hospitals and hospices;
 5. Intermediate care and skilled nursing facilities;
 6. Medical and dental offices;
 7. Outpatient health services, including, but not limited to, laboratories, radiological and diagnostic imaging services, blood banks, outpatient surgery centers, and outpatient clinics and patient-care facilities;
 8. Accessory buildings, uses and services customarily incidental to the above uses, including, but not limited to, the following:
 - a. Administrative offices;
 - b. Automobile parking lots and parking garages;
 - c. Housing for students, employees and their families in accordance with the standards of the (MU) Zone;
 - d. Helistop (see Section 449.J.1.);
 - e. Incinerators and autoclaves (see Section 449.J.2.);
 - f. Lodging facilities for patients and their families;
 - g. Public uses and essential services (e.g., private central utility plant, electrical switching facility, steam generation facility, heating facility, ventilation facility, and oxygen facility);
 - h. Retail sales of medical/health care-related supplies (e.g., durable medical equipment, prosthetics, pharmaceutical supplies) and retail sales/ service for the convenience of employees, patients and visitors (e.g., uniforms, flowers, gifts, uniform cleaning, barber/beauty salons, automatic teller banking, restaurants). All retail sales and services shall be located within buildings in which other permitted uses are located. Retail sales and services may not exceed five percent (5%) of the floor area of existing buildings; and,
 - i. Short-term, intermittent educational programs which are not intended to prepare students for careers in health care, but, rather, are intended to inform employees, patients, health care providers, or the public regarding health care issues;

449.J. SPECIFIC REQUIREMENTS FOR SELECTED ACCESSORY USES:

1. Helistops - The helistop shall only be used for the emergency transport by helicopter of patients to or from other permitted health care-related uses. The helistop shall not include auxiliary facilities, such as fueling and maintenance equipment. The helistop shall be set back a minimum of three hundred feet (300') from any adjoining property and any street. The applicant must demonstrate compliance, through a written statement, and continue to comply with applicable State and Federal standards; and,
2. Incinerators and Autoclaves - Only the processing of waste generated on-site is permitted. All processing and storage of waste shall be conducted within a completely-enclosed building. All storage of waste shall be in a manner that is leak and vector-proof. No storage of waste shall exceed seven (7) days in length. The incinerator shall be set back at least a distance equal to its height from all lot lines. The applicant must demonstrate compliance, through a written statement, and continue to comply with all applicable State and Federal standards and regulations.

Section 450 Junkyards

- 450.A.** Within the (MI) Zone, junkyards are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:
- 450.B. MINIMUM LOT AREA** - Ten (10) acres;
- 450.C.** The outdoor area devoted to the storage of junk shall be completely enclosed by a minimum eight foot (8') high, sight-tight fence or wall which shall be set back at least fifty feet (50') from all property lines;
- 450.D.** The setback area between the fence and the lot lines shall be kept free of junk storage, weeds and all scrub growth and shall be devoted to landscaping and/or screening in accordance with Section 321 of this Ordinance;
- 450.E.** All buildings used to store junk shall be completely enclosed and set back at least fifty feet (50') from all property lines;
- 450.F.** No material may be stored or stacked exceeding a height of eight (8) feet or so that it is visible from adjoining properties and roads;
- 450.G.** All additional Federal and State laws shall be satisfied;
- 450.H.** All junk shall be stored or arranged so as to permit access by firefighting equipment with vehicle access lanes of no less than twelve feet (12') in width spaced no more than five hundred feet (500') apart at the greatest separation distance. Such access lanes shall be kept free from obstruction at all times;
- 450.I.** The manner of storage and arrangement of junk, and the drainage facilities of the premises shall prevent the accumulation of stagnant water upon the premises and no inflammable liquid shall be permitted to remain in any junked container, whether the container is a separate item or is an integral part of, another item, at any time.
- 450.J.** No material shall be burned at any time;
- 450.K.** Junkyards shall be maintained in such a manner as to cause no public or private nuisance, nor to cause any offensive or noxious sounds or odors, nor to cause the breeding or harboring of rats,

flies, mosquitoes or other vectors;

450.L. No junk shall be located on land with a slope in excess of five percent (5%); and,

450.M. No junk yard shall be located within two hundred feet (200') of any land within the (LDR or MU) Zones.

Section 451 Drop Lot or Drop and Hook Lot

451.A. Within the (BI) Zone, drop lots and/or drop and hook lots are permitted by conditional use as an accessory use to a truck terminal or truck stop, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows;

451.B. Such use must be an accessory use to an approved truck terminal or truck stop principal use and must be located on the same tract and/or lot of land as such principal use which is permitted by right, by special exception or by conditional use.;

451.C. Such use must comply with all of the provisions of Section 486 (for truck or freight terminal) if the drop lot is an accessory use to a truck or freight terminal. or Section 487 (for truck stop);

451.D. Such use must comply with all of the provisions of Section 487 (for truck stop) if the drop lot is an accessory use to a truck stop;

451.E. No trailers shall be stored overnight on the drop lot and/or drop and hook lot portion of the tract.

Section 452 Kennels

452.A. Within the (A) Zone, kennels are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:

452.B. THE FOLLOWING LISTS MINIMUM REQUIRED LOT SIZES AND REQUIRED SETBACKS BASED UPON THE NUMBER OF ANIMALS KEPT:

Type and Number of Animals Kept	Minimum Required Lot Area	Minimum Required Setback of Unenclosed Animal Boarding Buildings, Pens, Stalls, Runways, and Running Areas from the Nearest Property Line
1 dog to 50 dogs	5 acres	150 feet
1 to a maximum of 200 animals, other than dogs	5 acres	150 feet
1 dog to 50 dogs, plus 1 to a maximum of 200 animals, other than dogs	5 acres	150 feet
More than 50 dogs	10 acres	300 feet
More than 51 dogs, plus more than 200 animals, other than dogs	10 acres	300 feet

- 452.C.** The applicant shall explain those measures that will ensure that the proposed use will comply with the noise regulations listed in the referenced and incorporated ordinance pursuant to Section 316 of this Ordinance;
- 452.D.** The applicant must furnish a plan for the storage and disposal of deceased animals within 24 hours of an animal's death;
- 452.E.** The applicant must demonstrate evidence of compliance with the PA Dog Law;
- 452.F.** The applicant must explain measures to be used to ensure that all animal wastes shall be regularly cleaned up and properly disposed of to prevent odors and unsanitary conditions and,
- 452.G.** The applicant is required to submit written information indicating that the disposal of all materials and wastes will be accomplished in a manner that complies with State and Federal regulations with particular attention to those pesticides, insecticides and detergents used.

453 Man-Made Lakes, Dams, Ponds, and Impoundments

- 453.A.** Within any Zone, man-made lakes, dams, ponds, and impoundments are permitted as accessory uses by right, subject to the following:
- 453.B.** All lakes, dams, ponds, and impoundments located along, and connected to, a stream that involve any of the following, shall require a permit from the PA DEP, Bureau of Dams and Waterways, Division of Dam Safety, or a letter indicating that the proposed use does not require a PA DEP permit:
 - 1. The lake, dam, pond, or impoundment contains a volume of at least fifty (50) acre feet;
 - 2. The dam reaches a height of fifteen feet (15'); and,
 - 3. The lake, dam, pond, or impoundment impounds the water from a watershed of at least one hundred (100) acres.
 - 4. Those uses that do not exceed the preceding thresholds are subject to the requirements listed in Section 464 of this Ordinance.
- 453.C.** All such lakes, dams, ponds, and impoundments shall be located seventy-five feet (75') from all adjoining lot lines, as measured from the closest point of the adjoining property line to the maximum anticipated water surface elevation;
- 453.D.** All lakes, dams, ponds, and impoundments not contiguous to a stream that have an intake, outlet, or both, and/or have an embankment within fifty feet (50') of a stream shall require the obtainment of a permit from the PA DEP Bureau of Dams and Waterways Division of Waterways and Storm Water Management;
- 453.E.** All other lakes, dams, ponds, and impoundments require the submission of a statement and seal by a qualified engineer that the proposed use is properly constructed and will not pose a threat to the public safety nor the environment during normal flow conditions and those associated with the base flood. All dams shall be constructed to a height of one and one-half feet (1.5') above the water surface elevation occurring during the base flood;
- 453.F.** All lakes, dams, ponds, and impoundments, including storm water management basins, shall be located a minimum of fifty feet (50') from any subsurface sewage disposal system or well;

453.G. FENCING

All ponds constructed within areas subject to livestock shall be enclosed by fencing that prevents livestock from trampling the pond's shores and polluting the waters; and,

453.H. MAINTENANCE

All ponds shall be regularly maintained, and floating debris shall be removed from all pipes and spillways. All ground cover shall be trimmed. Weeds, brush and trees shall not be permitted to grow on the dam or spillway.

Section 454 Mobile Home Parks

454.A. Within the (MU) Zone, mobile home parks are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:

454.B. The minimum parcel size for any mobile home park development shall be five (5) acres;

454.C. The maximum permitted density shall be limited to six (6) units per net acre;

454.D. Each single mobile home lot shall contain no less than (4,200) square feet, and be at least forty feet (40') wide;

454.E. No mobile home lot shall be within twenty-five feet (25') of a park boundary, or within fifty feet (50') of an outside street right-of-way. This area shall constitute the mobile home park boundary area;

454.F. No mobile home park office or service building shall be located within thirty feet (30') of a park boundary or an outside street right-of-way; nor within thirty feet (30') of the right-of-way of an interior park street, or the paved edge of a common parking area or common walkway; nor within thirty feet (30') of an adjacent structure or mobile home;

454.G. Each mobile home shall have a minimum front yard of twenty feet (20'), rear yard of fifteen feet (15'), and two sides of ten feet (10') each. In no case shall the distance between any two mobile homes be less than twenty feet (20');

454.H. A paved on-site walkway of a minimum width of four feet (4') shall be provided to each mobile home unit from an adjacent street;

454.I. Except as required herein, streets, curbs and sidewalks shall be constructed in accordance with the SALDO;

454.J. All roads in the park shall be private access drives and shall be paved with a bituminous or concrete surface at least twenty feet (20') wide. If on-street parking is proposed an additional width of eight feet (8') shall be required for each lane of parking;

454.K. Each mobile home lot shall abut on a park access drive with access to such access drive. No direct access to any mobile home lots shall be from public streets or highways;

454.L. Each mobile home space shall contain no more than one (1) mobile home, nor more than one (1) family;

- 454.M.** No less than ten percent (10%) of the total mobile home park area shall be set aside for recreation and open space purposes. Such area may not include any of the required mobile home park boundary area. No service buildings or offices may be constructed within the required recreation and open space area;
- 454.N.** Each mobile home stand shall have attachments for waste disposal, water supply facilities and electrical service, and such facilities shall be properly connected to an approved method of sewage disposal, and water and electrical supply;
- 454.O.** Protective skirting shall be placed around the area between the stand surface and the floor level of each mobile home so as to prevent that area from forming a harborage for rodents, creating a fire hazard, or exposing unsightly conditions;
- 454.P.** No recreation vehicle, travel or vacation trailer or other form of temporary living unit shall be placed upon any mobile home stand or used as a dwelling within the mobile home park;
- 454.Q. SERVICE AND ACCESSORY BUILDINGS:**
1. Construction - All service and accessory buildings, including management offices, storage areas, laundry buildings, and indoor recreation areas shall conform to the requirements of any applicable building code, and such shall be maintained so as to prevent deterioration caused by decay, corrosion, termites, or other destructive elements. Attachments to mobile homes in the form of sheds and lean-toos are prohibited;
 2. Mobile Home Park Office - Every mobile home park shall have an office on-site for the mobile home park manager. Every mobile home park containing fifteen (15) or more mobile home spaces shall have a structure designed and clearly identified for such office;
 3. Storage Space - Occupants of each mobile home unit shall be provided with a minimum of one hundred fifty (150) cubic feet of storage space in an individual storage building placed to the rear of each mobile home; and,
 4. Use - Service and accessory buildings located in a mobile home park shall be used only by the occupants of the same and their guests;
- 454.R.** Each mobile home shall be provided with a minimum of two (2) paved parking spaces which shall be located on the mobile home space. If on-street parking is not provided, one additional off-street parking space per unit shall be provided in a common visitor parking compound. Such visitor parking compounds shall be sized, arranged, and located so that the spaces are within three hundred feet (300') walking distance to those units served;
- 454.S.** Each mobile home shall be placed on a six-inch (6") thick poured concrete pad over a six inch (6") stone base, the length and width of which shall be at least equal to the length and width of the mobile home it is to support. Every mobile home shall be anchored to the mobile home pad where it is located, prior to the unit being occupied, and no more than seven (7) days from the arrival of the mobile home. The anchoring system shall be designed by a registered professional engineer to prevent tilting of the unit, and resist a minimum wind velocity of ninety (90) miles per hour; and,
- 454.T.** All mobile home parks shall be screened from adjoining properties and roads. Screening methods shall be described and graphically depicted as part of the special exception application.

Section 455 Manure Storage Facilities

- 455.A.** Within the (C and A) Zones manure storage facilities that are accessory to an agricultural or horticultural use are permitted by right subject to the following requirements:

- 455.B.** The applicant shall submit written evidence from a professional engineer licensed to practice within the Commonwealth of Pennsylvania, that the design and construction of the manure storage facility shall be in accordance with the Pennsylvania Department of Environmental Protection's publication *Manure Management Manual for Environmental Protection*, and any revisions, supplements, and replacements thereof, published by the Pennsylvania Department of Environmental Protection;
- 455.C.** The applicant shall furnish evidence of his/her manure management plan, as applicable under State law. All subsequent operations and activities shall be conducted in accordance with such plan;
- 455.D.** All manure storage facilities shall be operated and maintained in accordance with the Pennsylvania Department of Environmental Protection's publication *Manure Management Manual for Environmental Protection*, and any revisions, supplements, and replacements thereof, published by the Pennsylvania Department of Environmental Protection; and,
- 455.E.** Any design changes during construction or subsequent operation will require the issuance of another zoning permit subject to the applicable regulations of this Section.

Section 456 Mass Transit and/or Taxicab Terminals

- 456.A.** Within the (BI) Zone, mass transit and/or taxicab terminals are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:
- 456.B.** The applicant shall submit a traffic impact study in accordance with Section 319 of this Ordinance;
- 456.C.** The applicant shall present qualified expert evidence as to how the use will provide for the expected demand for needed, off-street parking spaces for the proposed use. In addition, the applicant shall present evidence of the ability to provide additional off-street parking spaces, if demand increases. The applicant shall also present credible evidence that the number of "oversized," off-street, parking spaces provided for public transportation vehicles will be adequate to accommodate the expected demand generated by patrons. Any gates or other barriers used at the entrance to parking areas shall be set back and arranged to prevent vehicle backups onto adjoining roads during peak arrival periods;
- 456.D.** The subject property shall have a minimum of two hundred feet (200') of contiguous road frontage along an arterial road;
- 456.E.** The subject property shall be located no closer than two hundred feet (200') from any (LDR or MU) Zones and/or property containing a school, day care facility, park, playground, library, hospital, nursing, rest or retirement home, or medical residential campus;
- 456.F.** All structures (including, but not limited to, air compressors, fuel pump islands, kiosks) shall be set back at least fifty feet (50') from any street right-of-way line;
- 456.G.** Access driveways shall be a minimum of twenty-four feet (24'), and a maximum of thirty-five feet (35') wide. All access drives onto the same road shall be set back at least one hundred fifty feet (150') from one another, as measured from closest points of cartway edges;
- 456.H.** Trash and recycling receptacles shall be provided amid off-street parking areas which shall be routinely emptied. Furthermore, an acceptable working plan for the regular cleanup of litter shall be furnished and continuously implemented by the applicant;

- 456.I.** All vehicle service and/or repair activities shall be conducted within a completely-enclosed building. No outdoor storage of parts, equipment, lubricants, fuels, or other materials used or discarded in any service or repair operations, shall be permitted;
- 456.J.** The outdoor storage of unlicensed and un-inspected vehicles is prohibited;
- 456.K.** The applicant shall submit qualified evidence that the proposed use will comply with applicable air quality standards;
- 456.L.** The demolition or junking of vehicles is prohibited. Demolished vehicles and/or parts thereof, shall be removed within thirty (30) days after arrival;
- 456.M.** Any exterior public address system shall be designed and operated so that the audible levels of any messages conveyed over the system will not exceed the noise standards of the referenced and incorporated ordinance pursuant to Section 316 of this Ordinance; and,
- 456.N.** The applicant shall furnish evidence that the storage and disposal of materials and wastes will be accomplished in a manner that complies with all applicable State and Federal regulations.

Section 457 Medical Residential Campuses

- 457.A.** Within the (MU) Zone, medical residential campuses are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:
- 457.B.** The campus shall primarily serve the needs of retirement-aged persons. At least one (1) resident of each household shall be at least fifty (50) years old, or possess some handicap that can be treated within a setting like the medical residential campus;
- 457.C.** The campus shall achieve a balanced residential/medical environment which cannot be achieved through the use of conventional zoning techniques;
- 457.D.** Residences shall be functionally, physically and architecturally integrated with medical service and recreational activity centers;
- 457.E.** Commercial, medical and recreational uses shall be grouped together and located near the populations being served;
- 457.F.** The minimum land area devoted to the campus shall be ten (10) contiguous acres;
- 457.G.** The site shall front on and have access to a collector or arterial road;
- 457.H.** All buildings or structures containing nonresidential use(s), off-street parking lots and loading areas shall be set back at least fifty feet (50') from all lot lines of the campus property;
- 457.I.** The maximum permitted overall density is ten (10) dwelling units per acre. For purposes of this Section, any two (2) care beds associated with a medical use shall constitute one (1) dwelling unit. No more than fifty percent (50%) of the total number of permitted dwelling units shall consist of care beds. For the purposes of this Section, "care beds" shall be defined as any bed where a resident of the medical residential campus may sleep that is not part of a dwelling unit upon which the maximum permitted density is computed. Examples of care beds would include, but not be limited to those associated with medical and/or nursing care, or those associated with congregate or communal living quarters;

- 457.J.** All buildings or structures used solely for residential purposes shall be set back at least fifty feet (50') from all lot lines of the campus property;
- 457.K.** The maximum permitted height is fifty feet (50'), provided that for buildings exceeding thirty-five (35) feet in height, the minimum setback from each lot line is equal to the height of the structure, with each one (1) foot above thirty-five (35) feet in height requiring two (2) feet in additional setback from each lot line;
- 457.L.** No more than sixty percent (60%) of the subject property shall be covered with buildings, parking and loading areas and/or other impervious surfaces;
- 457.M.** Each off-street parking lot shall provide at least ten percent (10%) of the total parking spaces as those designed for the physically handicapped. Furthermore, such parking spaces shall be located throughout the campus in such a manner to be conveniently accessible to the buildings/uses for which they are required;
- 457.N.** Only those uses which provide a harmonious, balanced mix of medical, residential, limited commercial and recreational uses, primarily serving campus residents, and public, quasi-public and medical services for the off-campus retirement-aged community will be permitted. Uses may include, but need not be limited to the following:
1. Dwelling, nursing homes, and congregate living facilities for the elderly or physically handicapped;
 2. Medical facilities including offices, laboratories, clinics, professional or paramedical training centers, and ambulatory care facilities;
 3. Commercial uses which are strictly related and subordinate to the residential/medical character of the campus and which directly serve the residents and employees of, or visitors to, the center. The uses should be chosen to reflect their local orientation to the immediate campus vicinity and should be of a size and scope so as not to interfere with existing or proposed retail uses located in the off-campus area; and,
 4. Recreational and social uses, such as athletic facilities, community centers, and assembly halls, limited to use only by campus residents, employees, or visitors; and,
- 457.O.** The applicant must comply with all State requirements at all times.

Section 458 Methadone Treatment Facility

- 458.A.** Within the (MI) Zone, methadone treatment facilities are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:
- 458.B.** An methadone treatment facilities shall not be permitted to be located within one thousand feet (1,000') of any other methadone treatment facilities;
- 458.C.** No methadone treatment facilities shall be located within one thousand feet (1000') of any land within the (LDR and MU) Zones;
- 458.D.** No methadone treatment facilities shall be located within one thousand feet (1000') of any parcel of land which contains any one or more of the following specified land uses:
1. Amusement park;

2. Camp (for minors' activity);
3. Child care facility;
4. Church or other similar religious facility;
5. Community center;
6. Museum;
7. Park;
8. Playground;
9. School; or
10. Other lands where minors congregate.

458.E. The distance between any two methadone treatment facilities shall be measured in a straight line, without regard to intervening structures, from the closest point on the exterior parcel line of each establishment. The distance between any methadone treatment facilities and any land use specified above shall be measured in a straight line, without regard to intervening structures, from the closest point on the exterior property line of the adult-related use to the closest point on the property line of said land use.

Section 459 Mining, Quarrying and Related Processing Operations

459.A. Within the (MI) Zone, mining, quarrying and related processing operations, including the recycling of related materials, are permitted by conditional use provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance (except as may be limited by Section 103.4. of this Ordinance) including but not limited to those general criteria contained within Section 805.B. and specifically as follows:

459.B. GENERAL

Quarries and mineral extraction-related uses including the recycling of related materials operations:

1. may not substantially injure or detract from the lawful existing or permitted use of neighboring properties;
2. may not adversely affect any public or private water supply source;
3. may not adversely affect the logical, efficient, and economical extensions of public services, facilities and utilities throughout the Township;
4. may not create any significant damage to the health, safety, welfare of the Township and its residents and property owners;
5. may not result in the land area subject to quarrying being placed in a condition which will prevent the use of that land for economically and ecologically productive uses upon completion of the quarry operation; and,
6. must demonstrate compliance with all applicable State regulations at all times.

459.C. SITE PLAN REQUIREMENTS

As a part of each application the applicant shall furnish an accurately surveyed site plan on a scale no less than 1:2400, showing the location of the tract or tracts of land to be affected by the operation. The surveyed site plan shall be certified by a registered professional engineer or a registered professional land surveyor with assistance from experts in related fields and shall include the following:

1. The boundaries of the proposed land affected, together with the drainage area above and

below the area.

2. The location and names of all streams, roads, railroads and utility lines on or immediately adjacent to the area.
3. The location of all buildings within one thousand (1,000) feet of the outer perimeter of the area affected and the names and addresses of the owners and present occupants.
4. The purpose for which each building is used.
5. The name of the owner of the affected area and the names of adjacent landowners, the municipality and the county.

459.D. MINIMUM LOT AREA - Fifty (50) acres;

459.E. FENCING

Operations that have a highwall, as defined herein, fifteen feet (15'), or higher, shall be required to enclose the actual area of mining with a minimum eight foot (8') high chain link fence and like latching gates. Operations with no highwalls, or highwalls of less than fifteen feet (15') high, shall be required to enclose the area of mining with a minimum forty-seven inches (47") high minimum 11 gauge woven wire fence that has openings no larger than six inches (6") in any direction and has posts at intervals of no more than ten feet (10'). All woven wire fences shall be equipped with latching minimum six (6) bar tube or panel gates, at vehicular access points;

All gates shall be latched at times when the site is unattended. The Township will accept departures from the above-described fence/gate specifications, only if the applicant can demonstrate that the proposed fence/gate will achieve an equal or higher level of protection;

Along all fences, the applicant will be required to post and maintain "No Trespassing" and/or "Danger" signs at intervals of no less than one (1) sign per each hundred (100) lineal feet of fence/gate. Such signs shall be no larger than two (2) square feet per sign and shall not be posted higher than five feet (5') above grade. All fences/gates shall be maintained in good condition and shall not be allowed to become deteriorated or unsightly;

There shall be no advertising placed upon the fencing/gate, except as may be permitted in Section 322 of this Ordinance;

459.F. SETBACKS

The following table identifies minimum setbacks imposed upon specific features of the quarry and other extractive-related uses from adjoining and/or nearby uses:

Quarry-Related Feature	Existing Residence	Existing Nonresidential Building	LDR or MU Zone	Adjoining Road	Public/ Nonprofit Park	Cemetery or Streambank	Adjoining Property
Stockpiles or Spoil piles	300 ft.	300 ft.	300 ft.	100 ft.	100 ft.	100 ft.	100 ft.
Mineral Processing Equipment (e.g., crushers, sorters, conveyors, dryers, etc.)	300 ft.	300 ft.	300 ft.	100 ft.	100 ft.	100 ft.	100 ft.
Quarry Pit	300 ft.	300 ft.	300 ft.	100 ft.	300 ft.	100 ft.	100 ft.
On-Site Access Roads & Off-Street Parking, Loading & Vehicle Storage and Weighing Facilities	300 ft.	300 ft.	300 ft.	100 ft.	100 ft.	100 ft.	100 ft.
Other Operational Equipment, Structures &/or Improvements	300 ft.	300 ft.	300 ft.	100 ft.	100 ft.	100 ft.	100 ft.

459.G. VEHICULAR ACCESS

Vehicular access shall be arranged as to minimize danger and congestion along adjoining roads and to avoid the creation of nuisances to nearby properties. Access drives used by trucks shall only intersect with collector or arterial roads.

1. All access drives shall be designed and located so as to permit the following minimum sight distances measured from a point at least ten (10) feet behind the curb line or edge of cartway of an intersecting public street. No sight obstructions shall be permitted which are greater than three (3) feet or less than ten (10) feet above the street surface.

Speed Limitation on Public Street (mph)	Required Sight Distance (feet)
25	240
30	275
35	315
40	350
45	426
50	475
55	550

2. All access drives serving the site shall have a paved, minimum thirty-five (35) foot wide cartway for a distance of at least two hundred (200) feet from the intersecting street right-of-way line. In addition, a fifty (50) foot long, gravel section of access drive should be placed just beyond the preceding two hundred (200) foot paved section to help collect any mud that may have attached to a vehicle's wheels;
3. In general, access drives shall intersect public streets at ninety degrees (90°) as site conditions permit, however in no case shall access drives intersect public streets at less than seventy degrees (70°). Said angle shall be measured from the centerline of the street to the centerline of the access drive.

459.H. TRAFFIC IMPACT

The applicant shall furnish a traffic impact study prepared in accordance with Section 319 of this Ordinance;

459.I. RECLAMATION

The applicant shall demonstrate compliance with Section 7.(c) of the Pennsylvania Act No. 1984-219, as may be amended. The applicant shall provide a detailed description of the proposed use of the site, once reclamation has been completed, including a description of any zoning and/or subdivision approvals or remedies that would be necessary to accommodate the proposed use. A planting plan shall also be required for areas of the reclaimed site that are not to be underwater. Such plan shall demonstrate the covering of the site with sufficient arable soil that can stabilize the site with a vegetative ground cover that prevents excessive soil erosion and will support a mix of indigenous vegetation. Finally, the applicant shall provide written notification to the Township within thirty (30) days, whenever a change in the reclamation plan is proposed to the PA DEP;

459.J. BUFFERING AND SCREENING

A minimum one hundred foot (100') wide buffer strip shall be located along all property lines. No structures, storage, parking, or any other related activity or operation shall be permitted within this buffer strip. All uses shall be screened from adjoining roads and properties. Such screening shall

be comprised of an earthen berm at least ten feet (10') in height. Such berm shall be located on the subject property and placed so as to maximize the berm's ability to absorb and/or block views of, and the noise, dust, smoke, etc. generated by, the proposed use. The berm shall be completely covered and maintained in an approved vegetative ground cover. Along any adjoining property line and road shall be located a minimum ten foot (10') wide landscape screen. Such landscape screen shall consist of evergreen shrubs and trees arranged to form both a low-level and a high-level screen. The high-level screen shall consist of deciduous and evergreen trees of not less than five feet (5') in height at the time of planting that shall be planted at intervals of not more than ten feet (10'). The low-level screen shall consist of evergreen trees and shrubs of not less than three feet (3') in height at the time of planting that shall be planted at intervals of not more than five feet (5'). The landscape screen shall be located outside of the fence required by Section 459.E. of this Ordinance and must be permanently maintained; and,

459.K. OPERATIONS PROGRESS REPORT

Within ninety (90) days after commencement of surface mining operations, and each year thereafter, the operator shall file an operations and progress report with the Zoning Officer, setting forth all of the following:

1. The name or number of the operation;
2. The location of the operation with reference to the nearest public road;
3. A description of the tract or tracts, including a site plan showing the location of all improvements, stockpile, quarry pits, etc;
4. The name and address of the landowner or his duly authorized representative;
5. An annual report of the type and quantity of mineral produced;
6. The current status of the reclamation work performed in pursuance of the approved reclamation plan;
7. A maintenance report for the site that verifies that all required fencing, berming and screening has been specifically inspected for needed repairs and/or maintenance, and that such needed repairs and/or maintenance has been performed; and,
8. Verification that the proposed use continues to comply with all applicable State regulations. The operation shall furnish copies of any approved permits and/or any notices of violation issued by the Pennsylvania Department of Environmental Protection.

459.L. WATER RESTORATION

In accordance with Section 11.(g) of the PA Noncoal Surface Mining and Conservation and Reclamation Act, any mining/processing operation that affects a public or private water supply due to contamination, interruption, or diminution shall restore or replace the affected water supply with an alternate source of water adequate in quantity and quality for the purposes served by the affected supply; and,

459.M. MAXIMUM PERMITTED HEIGHT

No piling of spoiled materials and/or waste materials shall exceed a height of fifty feet (50') above the natural unexcavated grade. Such pilings must be periodically and sufficiently covered with earth and the seed of a year-round ground cover in order to achieve a stable condition.

Section 460 Storage Unit Centers

- 460.A.** Within the (BI) Zone, storage unit centers are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:
- 460.B.** One (1) off-street parking space shall be provided for each fifty (50) storage units, plus two per any residential use associated with an on-site manager;
- 460.C.** Parking shall be provided by parking/driving lanes adjacent to the buildings. These lanes shall be at least twenty-six feet (26') wide when cubicles open onto one side of the lane only, and at least thirty feet (30') wide when cubicles open onto both sides of the lane;
- 460.D.** Required parking spaces may not be rented as, or used for, vehicular storage. However, additional external storage area may be provided for the storage of privately-owned recreation vehicles, so long as such external storage area is screened from adjoining land within the (LDR and MU) Zones and adjoining roads and is located behind the minimum front yard setback line. This provision shall not be interpreted to permit the storage of partially dismantled, wrecked, or inoperative vehicles;
- 460.E.** Except as noted above, all storage shall be kept within an enclosed building except that the storage of flammable, highly combustible, explosive or hazardous chemicals shall be prohibited. Any fuel tanks and/or machinery or other apparatuses relying upon such fuels shall be stored only in an external storage area as described above;
- 460.F.** Because of the danger from fire or explosion caused by the accumulation of vapors from gasoline, diesel fuel, paint, paint remover, and other flammable materials, the repair, construction, or reconstruction of any boat, engine, motor vehicle, or furniture is prohibited;
- 460.G.** No door openings for any storage unit shall be constructed facing any property within the (LDR and MU) Zones;
- 460.H.** Storage unit centers shall be used solely for the dead storage of property. The applicant shall adequately demonstrate that all storage unit centers rental and/or use contracts shall specifically prohibit the following examples of uses expressly prohibited upon the site:
1. Auctions, commercial wholesale or retail sales, or garage sales;
 2. The servicing, repair, or fabrication of motor vehicles, boats, trailers, lawn mowers, appliances, or other similar equipment;
 3. The operation of power tools, spray-painting equipment, table saws, lathes, compressors, welding equipment, kilns, or other similar equipment;
 4. The establishment of a transfer and storage business; and,
 5. Any use that is noxious or offensive because of odors, dust, noise, fumes, or vibrations;
- 460.I.** The storage unit centers will be surrounded by a six foot (6') to eight foot (8') high fence; and,
- 460.J.** All outdoor lights shall be shielded to direct light and glare only onto the site and may be of sufficient intensity to discourage vandalism and theft. Said lighting and glare shall be deflected, shaded and focused away from all adjoining property. The applicant shall demonstrate compliance with Section 310 of this Ordinance.

Section 461 Entertainment Facilities.

- 461.A.** Within the (MU) Zone, entertainment facilities are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:
- 461.B.** No part of the subject property shall be located within two hundred feet (200') of any land within the (LDR) Zones, and the location of the structure within which entertainment events take place shall be located at least or more than two hundred feet (200') of any property line of any residential use;
- 461.C.** All entertainment events shall be strictly confined to the interior of the facility or structure, unless applicant is granted special permission by the Board of Supervisors for any entertainment events to take place outdoors (including on any patio or deck) of the property where the entertainment facility is located.
- 461.D.** The applicant shall furnish evidence that the proposed use will not be detrimental to the use of adjoining properties due to hours of operation;
- 461.E.** The applicant shall furnish evidence as to how the use will be controlled as to comply with Sections 310 of this Ordinance;
- 461.F.** The applicant shall furnish evidence as to how the use will be controlled as to not constitute a nuisance due to loitering outside the building; and,
- 461.G.** An acceptable working plan for the cleanup and recycling of litter shall be furnished and implemented by the applicant.

Section 462 Noncommercial Keeping of Livestock

- 462.A.** Within the (C, A, LDR, and MU) Zones, the noncommercial keeping of livestock, as defined herein, is permitted by right as an accessory use to a principal residence subject to the following requirements:

462.B. MINIMUM LOT AREA

All uses shall comply with the minimum lot area requirements within each respective Zone; however, in no case shall a lot contain less than one-half (1/2) acre for group 1 animals, one (1) acre for group 2 animals, and three (3) acres for group 3 animals. Additionally, the following list specifies additional requirements by size of animals kept. [C and A only] The keeping of a combination of animal types (Group 1, 2 and 3) shall require an animal density equal to the ratio of the number of animals, by type. In no case shall a lot contain more than eighteen (18) total animals:

1. GROUP 1 - Animals whose average adult weight is less than ten (10) pounds shall be permitted at an animal density of three (3) per one-half (1/2) acre, with a maximum number of eighteen (18) animals, provided, however, that the maximum number of animals shall be four (4) within the (LDR and MU) Zones, and no roosters shall be permitted in the (LDR and MU) Zones;
2. GROUP 2 - Animals whose average adult weight is between ten (10) and one hundred (100) pounds shall be permitted at an animal density of two (2) per acre, with a maximum number of ten (10) animals; and,

3. GROUP 3 - Animals whose average adult weight is greater than one hundred (100) pounds shall be permitted at an animal density of one (1) per one (1) acre of pasture. For purposes of this Section, "pasture" shall mean grass or similar fields that are enclosed by a fence or similar enclosure. The area of the pasture shall only include such enclosed, grass areas.
- 462.C.** The following lists minimum setbacks (from all property lines) imposed upon the placement of any structure used to house noncommercial livestock; should one structure be used to house a combination of animal types, the most restrictive setback shall apply:
1. GROUP 1 Animals
The applicable setback for accessory structures in the zone, but in no event less than a twenty-five-foot (25') setback.
 2. GROUP 2 and GROUP 3 Animals
A fifty-foot (50') setback in all instances.
- 462.D.** All structures used to house noncommercial livestock shall be fitted with a durable floor surface that can withstand the wear associated with the weight and movement of livestock without failure (portable storage shed floors are generally unsuitable for such purposes) and shall be prohibited from placement in the front yard;
- 462.E.** All outdoor pasture/recreation areas shall be maintained with a vegetated and stable surface and enclosed with fencing to prevent the escape of the animals;
- 462.F.** The applicant shall furnish evidence of an effective means to dispose dead animals according to the regulations of the Pennsylvania Department of Agriculture; and,
- 462.G.** All animal wastes shall be properly stored and disposed of, so as not to be objectionable at the site's property line. All animals, their housing, and their outdoor pasture/recreation areas shall be properly maintained so as not to become a nuisance to adjoining properties.

Section 463 Nursing, Rest or Retirement Homes

- 463.A.** Within the (MU) Zone, nursing, rest or retirement homes are permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2.:
- 463.B. MINIMUM LOT AREA** - Two (2) acres;
- 463.C.** All parking areas shall be set back a minimum of twenty-five feet (25') from all property lines abutting residential dwellings or uses. All off-street parking and/or loading areas shall be screened from adjoining lots and streets;
- 463.D.** A nursing, rest or retirement home may erect one (1) sign no larger than eight (8) square feet in size, which must be set back ten feet (10') from all lot lines;
- 463.E.** Both public sewer and public water shall be utilized;
- 463.F.** At least ten percent (10%) of required parking spaces shall be designed for handicapped persons; and,
- 463.G.** No more than twenty-seven (27) care beds per acre shall be permitted.

Section 464 Ornamental Ponds and Wading Pools

- 464.A.** Within any Zone ornamental ponds and wading pools are accessory uses permitted by right, subject to the following criteria:
- 464.B.** Such uses shall comply with all side and rear yard accessory use setbacks, and principal front yard setbacks;
- 464.C.** No such impoundment shall contain more than 337.5 cubic feet of water (2,530 gallons). No such impoundment shall have a length or diameter exceeding fifteen feet (15') nor a maximum depth exceeding one and one-half (1½) feet;
- 464.D.** All ponds, pools or other impoundments exceeding the requirements of this Section shall be considered as "Man-made Lakes, Dams and Impoundments," and are subject to the criteria listed in Section 453 of this Ordinance;
- 464.E.** All such ponds or pools shall be maintained so as to not pose a nuisance by reason of odor, or the harboring of insects; and,
- 464.F.** No such pond(s) shall be used for the commercial hatching of fish or other species.

Section 465 Short-Term Rentals

- 465.A.** Within the (C and A) Zones, agricultural short-term rentals are an accessory use to a principal agricultural use permitted by right, subject to the criteria set forth in 465.C through 465.K:
- 465.B.** Within all Township Zones except the (LDR) Zone, residential short-term rentals are an accessory use to a principal residential use permitted by right, subject to the criteria set forth in 465.C through 465.K:
- 465.C.** The Applicant seeking to utilize their property as a short-term rental, whether under agricultural or residential, shall obtain a zoning permit from the Township, establishing the Applicant has complied with all zoning requirements related to the use, including those criteria contained in this Section 465. Such zoning permit shall be renewed on an annual basis.
- 465.D.** The Applicant provides proof of insurance to cover the property as a rental use, and not just as a residential use or an agricultural use. For clarification purposes, the Township shall require additional insurance, subject to the Township's discretion, to cover any damages or injuries that might be occasioned by individuals staying at short term rentals.
- 465.E.** The Applicant provides proof of adequate screening procedures to screen all individual applicants applying to rent a short-term rental, whether under residential or agricultural.
- 465.F.** The Owner of the property at which the short-term rental will be located and operated, shall use such property where short term renters will stay, as his or her primary residence.
- 465.G.** For residential short-term rentals, the Applicant shall provide one (1) off-street parking space per room rented.
- 465.H.** For any short-term rental, the Applicant shall provide or otherwise establish that any structure in which short term renters will occupy complies with the Uniform Construction Code and has an occupancy certificate. This expressly includes agricultural short-term rentals and any barn or similar outbuilding in which short term renters may sleep. Such structures shall meet all applicable

building, health, fire and related safety codes at all times, and include working smoke and carbon monoxide detectors. Emergency evacuation routes must be posted in a conspicuous location for each rented structure or room, as applicable.

- 465.I.** Any septic systems servicing a structure in which short term rentals will occur, and in which short term renters will occupy, must be up to current Township standards and be inspected by the Township SEO for compliance.
- 465.J.** Short term rentals shall only be permitted in permanent, legally established structures. Short term rentals shall not be permitted in non-habitable or temporary structures, including without limitation tents, yurts, RV's, or similar structures.
- 465.K.** Applicant shall, if awarded the right to operate a short-term rental, pay all taxes occasioned by such rental use, including all local, county, state and federal taxes.

Section 466 Outdoor Residential Athletic Courts

- 466.A.** Within the (C, A, MU and LDR) Zones, outdoor athletic residential courts are an accessory use to a residence permitted by right, subject to the following criteria:
- 466.B.** All courts shall either be setback a sufficient distance from any lot line to prevent the trespass of balls or other play objects onto adjoining properties or be equipped with fences or other barriers that will prevent such trespass; and,
- 466.C.** Any lighting fixtures shall comply with Section 310 of this Ordinance.

Section 467 Outdoor Shooting Ranges (Public and Private)

- 467.A.** Within the (C, A and MU) Zones, private outdoor shooting ranges are an accessory use to a residence permitted by right, provided that any and all discharges of firearms comply with all applicable federal, state and local laws, rules and regulations regarding the discharge of a firearm, expressly including direction of shooting and required set-backs. Firearms may only be discharged, for private outdoor shooting range purposes, between the hours of one (1) hour after official sunrise and one (1) hour preceding official sunset, except for Sunday, which shall have limited time for discharge between the hours of noon and one (1) hour preceding official sunset.
- 467.B.** Within the (C, A and MU) Zone, public outdoor shooting ranges are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows (this Section 467 shall not apply to any shooting range, or similar use, erected on private property for which the public is not freely allowed access and use, with or without a fee):
- 467.C.** The applicant shall submit a detailed written description of the methods used to ensure that outdoor shooting range operations:
 - 1. Do not substantially injure or detract from the lawful existing or permitted use of neighboring properties;
 - 2. Do not substantially damage the health, safety or welfare of the Township, or its residents and property owners;
 - 3. Comply with all applicable federal, state and local laws, rules and regulations regarding the discharge of a firearm;

4. Store ammunition only in an approved secure vault;
5. Limit the number of shooters to the number of firing points or stations identified on the development plan;
6. Require all shooters to satisfactorily complete an orientation safety program given in accordance with the PA Game Commission, or show a valid hunting permit or gun permit, before they are allowed to discharge firearms without supervision;
7. Prohibit the consumption of alcoholic beverages within the area approved as the shooting range; and,
8. Limit firing to the hours between one (1) hour after official sunrise and one (1) hour preceding official sunset, unless sufficient lighting is used, in accordance with Section 310 of this Ordinance, in which case all shooting shall cease by 9 p.m.;

467.D. A development plan shall identify the Safety Fan for each firing range. The Safety Fan shall include the area necessary to contain all projectiles, including direct fire and ricochet. The Safety Fan configuration shall be based upon qualified expert testimony regarding the trajectory of the bullet, and the design effectiveness of berms, overhead baffles, or other safety barriers to contain projectiles to the Safety Fan;

467.E. The firing range, including the entire Safety Fan, shall be enclosed with a six foot (6') high, non-climbable fence to prevent unauthorized entry into the area. Range caution signs with eight-inch (8") tall, red letters on a white background shall be posted at a maximum of one hundred-foot (100') intervals around the range perimeter. Signs shall read "**SHOOTING RANGE AREA. KEEP OUT!**";

467.F. Range flags shall be displayed during all shooting activities. Range flags shall be located in a manner visible from entrance drives, target areas, range floor, and the perimeter of the Safety Fan;

467.G. All surfaces located within the Safety Fan, including the backstop, overhead baffles, berms, and range floor, shall be free of hardened surfaces, such as rocks or other ricochet-producing materials;

467.H. All shooting range facilities, including buildings, parking, firing range, and Safety Fan shall be set back a minimum of one hundred feet (100') from the property line and street right-of-way;

467.I. The applicant shall present credible evidence that the sounds of shooting comply with Section 311 of this Ordinance;

467.J. Off-street parking facilities shall be provided with a ratio of one and one-half (1½) spaces per firing station, but not less than one (1) space for each four (4) seats; and,

467.K. No part of a shooting range property shall be located within one-quarter (¼) mile of any land within a (LDR and MU) Zones.

Section 468 Parking and/or Storage of Recreational Vehicles & Personal Cargo Trailers

468.A. The parking and/or storage of recreational vehicles, travel trailers, boats, and personal cargo trailers used solely for the transport of the residents' personal property is permitted only according to the following requirements:

1. For purposes of this section, recreational vehicles, travel trailers, boats (including trailers), and personal cargo trailers used solely for the transport of the residents' personal property are divided into two separate categories, as follows:

Class I Vehicles - Those recreational vehicles, travel trailers, boats (including trailers), and other personal cargo trailers used solely for the transport of the residents' personal property that possess no more than two hundred (200) square feet, as measured to the vehicle's outermost edges, nor exceed a height of ten (10) feet, as measured from the ground to the highest point of the main body of the vehicle. Vehicle height shall not be measured on vehicle accessories (e.g., air conditioners, vents, hatches, masts, antennas, outrigger fishing poles, etc.), but will be measured to the highest point of any flybridge or other boat console.

Class II Vehicles - Those recreational vehicles, travel trailers, boats (including trailers), and other personal cargo trailers used solely for the transport of the residents' personal property that possess more than two hundred (200) square feet, as measured to the vehicle's outermost edges, and/or exceed a height of ten (10) feet, as measured from the ground to the highest point of the main body of the vehicle. Vehicle height shall not be measured on vehicle accessories (e.g., air conditioners, vents, hatches, antennas, masts, outrigger fishing poles, etc.), but will be measured to the highest point of any flybridge or other boat console.

2. Reserved.
3. Upon any property used as a principal residence, the storage of one Class I vehicle shall be permitted per lot behind the front yard building setback line, so long as the unit is set back no less than five (5) feet from any adjoining side and rear lot line. All areas used for the storage of Class I vehicles shall be maintained so as to keep vegetation properly trimmed and debris or litter disposed of regularly. All vehicles shall maintain required licensure and prevent the leakage of fuels and/or lubricants into the ground.
4. Within the (C, A, LDR, and MU) Zones, the storage of one Class II vehicle on any property used for a principal residence, is permitted, subject to the following requirements:
 - a. In no case shall the vehicle contain more than three hundred twenty (320) square feet, as measured to the vehicle's outermost edges, nor exceed a height of thirteen (13) feet, as measured from the ground to the highest point of the vehicle's main body. Vehicle height shall not be measured on vehicle accessories (e.g., air conditioners, vents, hatches, antennas, masts, outrigger fishing poles, etc.), but will be measured to the highest point of any flybridge or other boat console.
 - b. All vehicles shall be set back a horizontal distance equal to twice the vehicle's height from every side and rear lot line.
 - c. No vehicle shall be stored in front of the building setback line. On vacant lots, the vehicle must be stored behind the required front yard setback line, as specified for principal uses.
 - d. Screening shall be provided along any side and rear lot lines. Such screening shall not extend into the required front yard. Screening shall not be required along a common side lot line when the owner resides on one (1) lot and stores the vehicle on an adjacent vacant lot that he/she owns. One ten (10) foot wide break in required screening may be provided along one (1) rear or side lot line for vehicular access onto an adjoining alley.
 - e. All areas used for the storage of Class II vehicles shall be maintained so as to keep vegetation properly trimmed and debris or litter disposed of regularly. All vehicles shall maintain required licensure and prevent the leakage of fuels and/or lubricants into the ground.

Section 469 Passenger Motor Vehicle and Recreational Vehicle Sales, Service and Repair Facilities, Including, But Not Limited To, Auto Mechanics, Drive-Thru Lubrication Services and Tires, Auto Paint, Brake, Muffler, Transmission, Windshield, Auto Body, Car Radio, and Upholstery Shop

- 469.A.** Within the (BI) Zone, passenger motor vehicle and recreational vehicle sales, service and repair facilities, including, but not limited to, auto mechanics, drive-thru lubrication services and tires, auto paint, brake, muffler, transmission, windshield, auto body, car radio, and upholstery shop are permitted by special exception provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2., and specifically as follows:
- 469.B.** All service and/or repair activities shall be conducted within a completely enclosed building;
- 469.C.** All uses involving drive-thru service shall provide sufficient on-site stacking lanes to prevent vehicle backups on adjoining roads;
- 469.D.** No outdoor storage of parts, equipment, lubricants, fuel, or other materials used or discarded, as part of the service or repair operation, shall be permitted;
- 469.E.** All exterior vehicle storage areas shall be screened from adjoining roads and any adjoining land within an (LDR and MU) Zone;
- 469.F.** The storage of vehicles to be serviced on the property without current registration is prohibited;
- 469.G.** Any ventilation equipment outlets associated with the service/repair work area(s) shall not be directed toward any adjoining property within the an (LDR or MU) Zone;
- 469.H.** All vehicles shall be repaired and removed from the premises promptly and no vehicle shall remain on the site for more than 45 days unless it is stored within a completely enclosed building;
- 469.I.** The demolition or junking of motor vehicles is prohibited; and,
- 469.J.** The applicant shall furnish evidence of how the storage and disposal of materials will be accomplished in a manner that complies with all applicable State and Federal regulations.

Section 470 Power Generation Facilities

- 470.A.** Within the (BI) Zone, power generation facilities as a principal use are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:
- 470.B.** Reserved.
- 470.C.** Any processing and/or treatment of materials (including but not limited to incineration, composting, steaming, shredding, compaction, material separation, refuse derived fuel, pyrolysis, etc.) shall be conducted within a wholly enclosed building;
- 470.D.** No materials or waste shall be deposited, stored or disposed of, and no building or structure shall be located, within two hundred feet (200') of any property line, and five hundred feet (500') of any adjoining land within the (LDR, A, C and MU) Zones;

- 470.E.** Any external area used for the unloading, transfer, storage, or deposition of material or waste must be completely screened from view at the property line. (The use of an earthen berm is encouraged where practicable.) In addition, such areas must also be completely enclosed by a minimum eight foot (8') high fence, with no openings greater than two inches (2") in any direction;
- 470.F.** The applicant must demonstrate compliance (through a written statement) and continue to comply with all applicable State and Federal standards and regulations;
- 470.G.** The use shall be screened from all adjoining land within the (LDR and MU) Zones or any adjoining land containing a residential use;
- 470.H.** All uses shall provide sufficiently long stacking lanes into the facility, so that waiting vehicles will not back-up onto public roads;
- 470.I.** All access drives onto the site shall be paved for a distance of at least two hundred feet (200') from the street right-of-way line. In addition, if portions of on-site access drives are unpaved, then a fifty foot (50') long gravel section of driveway shall be placed just beyond the preceding two hundred foot (200') paved section to help collect any mud that may have attached to a vehicle's wheels;
- 470.J.** Access to the site shall be limited to those posted times when an attendant is on duty. All areas of the site shall be protected by locked barricades, fences, gates or other positive means designed to deny access to the area at unauthorized times or locations;
- 470.K.** The unloading, processing, treatment, transfer, and disposal of material/waste shall be continuously supervised by a qualified facility operator;
- 470.L.** Any waste that is to be recycled shall be stored in leak- and vector-proof containers. Such containers shall be designed to prevent their being carried by wind or water. These containers shall be stored within a completely enclosed building;
- 470.M.** All storage of material or waste shall be indoors in a manner that is leak- and vector- proof. During normal operation, no more waste shall be stored on the property than is needed to keep the facility in constant operation; but, in no event for more than seventy-two (72) hours;
- 470.N.** A contingency plan for the disposal of waste during a facility shutdown, shall be submitted to the Township;
- 470.O.** All structures shall be set back at least a distance equal to their height;
- 470.P.** The applicant shall submit an analysis of raw water needs (groundwater or surface water) from either private or public sources, indicating quantity of water required. If the source is from a municipal system, the applicant shall submit documentation that the public authority will supply the water needed.
- 470.Q.** If the facility is to rely upon non-public sources of water, a water feasibility study will be provided to enable the municipality to evaluate the impact of the proposed development on the groundwater supply and on existing wells. The purpose of the study will be to determine if there is an adequate supply of water for the proposed development and to estimate the impact of the new development on existing wells in the vicinity. No use shall be approved without sufficient water and/or for a use that poses adverse impact on existing wells in the vicinity. A water feasibility study shall include the following minimum information:
 - 1. calculations of the projected water needs;
 - 2. a geologic map of the area with a radius of at least one mile from the site;

3. the location of all existing and proposed wells within one thousand feet (1,000') of the site, with a notation of the capacity of all high-yield wells;
4. the location of all existing on-lot sewage disposal systems within one thousand feet (1,000') of the site;
5. the location of all streams within one thousand feet (1,000') of the site and all known point sources of pollution;
6. based on the geologic formation(s) underlying the site, the long-term safe yield shall be determined;
7. a determination of the effects of the proposed water supply system on the quantity and quality of water in nearby wells, streams, and the groundwater table; and,
8. a statement of the qualifications and the signature(s) of the person(s) preparing the study;

470.R. The applicant shall provide a qualified traffic impact study in accordance with Section 319 of this Ordinance;

470.S. The applicant shall furnish expert testimony regarding emergency preparedness measures provided and/or otherwise available to respond to potential hazards regarding the spill of waste or materials during transport to and from the site, and potential hazards regarding firefighting of waste or materials upon the site.

470.T. Power generation systems may be erected as detached structures or attached to a building provided that the structural components of such systems (along with other site improvements) do not exceed the maximum permitted lot coverage requirements of the (I) Zone.

470.U. Power generation systems may be erected as detached structures or attached to a building provided that the structural components of such systems comply with all applicable setbacks of the (I) Zone.

470.V. The following provisions shall specifically apply to geothermal systems:

1. Only closed loop geothermal systems shall be permitted.
2. Prior to installation, all installation specifications and drawings for the geothermal system must be certified by a registered engineer within the Commonwealth of PA as conforming to the International Ground Source Heat Pump Association (IGSHPA) installation standards;
3. The vertical geothermal system well (or wells) installation will be made only by a Pennsylvania-licensed well driller;
4. No geothermal system sub-surface loops will be located closer than twenty feet (20') from any existing or planned drinking water wells;
5. The vertical loop in a geothermal system well (or wells) shall be pressure-grouted bottom to top with a bentonite-based or cement-based material of 0.0000001 centimeter per second or lower permeability; and
6. With respect to each geothermal system well installation, the Pennsylvania-licensed well driller and/ or system installer shall provide to the Township, before activation of the system copies of:
 - a. Accurate written records and a written geologic log;
 - b. Accurate records with respect to grouting for each such well;

- c. "As-built" plans and related documentation for each such system and well location;
 - d. Written documentation of the geothermal system testing and certification; and
 - e. A written "plan" for the operation of the geothermal system proposed by the applicant and approved by the system installer which, among other matters, provides that any geothermal system leaks or releases will be reported by the applicant (and subsequent owner) to the Township Zoning Officer within twenty-four (24) hours of the discovery of same, and the applicant (and subsequent owner) covenants and agrees to take appropriate action to minimize any fluid release to the ground and to promptly repair any system leaks; and
7. In the event of the proposed discontinuance of the use of the geothermal system, a system closure plan will be prepared and submitted to the Township for its approval by the landowner prior to the conveyance by the landowner of the land to any third party.
- 470.W.** Above-ground power generation systems shall be clear-coated, transparent, and/or be designed with a non-obtrusive color such as white, off-white or gray. All such facilities shall not be artificially lighted, except to the extent required by the Federal Aviation Administration or other applicable authority that regulates air safety.
- 470.X.** On-site electrical transmission and power lines connected to or associated with the alternate energy system that are not contained within a building shall be located underground.
- 470.Y.** Clearly visible warning signs concerning voltage must be placed at the base of all above-ground transformers and substations. Visible, reflective, colored objects, such as flags, reflectors, or tape shall be placed on the anchor points of guy wires and along the guy wires up to a height of ten (10) feet from the ground.
- 470.Z.** The applicant shall provide written evidence that the proposed power generation system shall comply with the noise standards listed in Section 313 of this Ordinance.
- 470.AA.** The applicant shall make reasonable efforts to avoid any disruption or loss of radio, telephone, television or similar signals, and shall mitigate any harm caused by the power generation system.
- 470.BB.** The applicant shall provide written evidence from the Chief of the "first-due" fire company that the proposed use can be adequately protected and that, if necessary, a suitable emergency response plan has been implemented to serve the proposed use.
- 470.CC.** The design and installation of the power generation system shall conform to applicable industry standards, including those of the American National Standards Institute and the Uniform Construction Code and be subject to all applicable permit requirements thereof as well as all other applicable laws, codes and regulations.
- 470.DD.** The applicant shall submit a written plan for the removal of the power generation system once it is no longer operational in accordance with the following:
- 1. The applicant / owner shall, at its expense, complete decommissioning of the power generation system within (12) twelve months after the end of the useful life of the system. The system will presume to be at the end of its useful life if no energy is generated for a continuous period of twelve (12) months.
 - 2. The removal of the above-ground power generation system components shall be completed within twelve (12) months of decommissioning of the system. All disturbed earth shall be re-stored, graded and re-seeded unless a zoning permit has been issued for another use to take its place.

3. The landowner or facility operator shall post and maintain decommissioning funds in an amount equal to net decommissioning costs; provided that at no point shall decommissioning funds be less than twenty five percent (25%) of decommissioning costs. The decommissioning funds shall be posted and maintained with a bonding company or a lending institution approved by the Township.
4. An independent and certified professional engineer may be retained by the Township to inspect the decommissioning of the power generation system. All such inspection fees shall be paid by the landowner.
5. Decommissioning funds may be in the form of a performance bond, surety bond, letter of credit, corporate guarantee or other form of financial assurance as may be acceptable by the Township.
6. If the applicant / owner fails to complete decommissioning during the prescribed period of twelve (12) months, the Township may take such measures as necessary to complete decommissioning in accordance with the laws of the Township and the Commonwealth of Pennsylvania.
7. The Township may release the decommissioning funds when the landowner or facility operator has satisfactorily demonstrated compliance with the removal plan.
8. The applicant shall, at all times, maintain on file with the Township Zoning Officer, the current name and contact information of the party responsible for the operation and maintenance of the power generation system.

Section 471 Principal Waste Handling, Recycling, Processing, Transfer and Disposal Facilities

- 471.A.** Within the (BI) Zone, principal waste handling, recycling, processing, transfer and disposal facilities are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:
- 471.B.** Any processing and/or treatment of waste (including but not limited to incineration, composting, steaming, shredding, compaction, material separation, refuse derived fuel, pyrolysis, etc.) shall be conducted within a wholly enclosed building;
- 471.C.** No waste shall be deposited, stored or disposed of, and no building or structure shall be located, within two hundred feet (200') of any property line, and five hundred feet (500') of any adjoining land within the (LDR, A, C and MU) Zones;
- 471.D.** Any external area used for the unloading, transfer, storage, or deposition of waste must be completely screened from view at the property line. (The use of an earthen berm is encouraged where practicable.) In addition, such areas must also be completely enclosed by a minimum eight foot (8') high fence, with no openings greater than two inches (2") in any direction;
- 471.E.** The applicant must demonstrate compliance (through a written statement) and continue to comply with all applicable State and Federal standards and regulations;
- 471.F.** The use shall be screened from all adjoining land within the (LDR and MU) Zones;
- 471.G.** All uses shall provide sufficiently long stacking lanes into the facility, so that vehicles waiting to be weighed and/or unloaded will not back-up onto public roads;

- 471.H.** All access drives onto the site shall be paved for a distance of at least two hundred feet (200') from the street right-of-way line. In addition, if portions of on-site access drives are unpaved, then a fifty foot (50') long gravel section of driveway shall be placed just beyond the preceding two hundred foot (200') paved section to help collect any mud that may have attached to a vehicle's wheels;
- 471.I.** Access to the site shall be limited to those posted times when an attendant is on duty. In order to protect against the indiscriminate and unauthorized dumping, all areas of the site shall be protected by locked barricades, fences, gates or other positive means designed to deny access to the area at unauthorized times or locations;
- 471.J.** Litter control shall be exercised to prevent the scattering of wind-borne debris, and an acceptable working plan for the cleanup of litter shall be submitted to the Township;
- 471.K.** The unloading, processing, treatment, transfer, and disposal of waste shall be continuously supervised by a qualified facility operator;
- 471.L.** Any waste that is to be recycled shall be stored in leak- and vector-proof containers. Such containers shall be designed to prevent their being carried by wind or water. These containers shall be stored within a completely enclosed building;
- 471.M.** All storage of waste shall be indoors in a manner that is leak- and vector- proof. During normal operation, no more waste shall be stored on the property than is needed to keep the facility in constant operation; but, in no event for more than seventy-two (72) hours;
- 471.N.** A contingency plan for the disposal of waste during a facility shutdown, shall be submitted to the Township;
- 471.O.** Leachate from the waste shall be disposed of in a manner in compliance with any applicable State and Federal laws or regulations. If leachate is to be discharged to a municipal sewage facility, pre-treatment shall be required, and appropriate permits shall be obtained from the applicable agencies and authorities. In no event shall leachate be disposed of in a storm sewer, to the ground, or in any other manner inconsistent with the Department of Environmental Protection's regulations;
- 471.P.** All structures shall be set back at least a distance equal to their height;
- 471.Q.** The applicant shall submit an analysis of raw water needs (groundwater or surface water) from either private or public sources, indicating quantity of water required. If the source is from a municipal system, the applicant shall submit documentation that the public authority will supply the water needed.
- 471.R.** If the facility is to rely upon non-public sources of water, a water feasibility study will be provided to enable the municipality to evaluate the impact of the proposed development on the groundwater supply and on existing wells. The purpose of the study will be to determine if there is an adequate supply of water for the proposed development and to estimate the impact of the new development on existing wells in the vicinity. No use shall be approved without sufficient water and/or for a use that poses adverse impact on existing wells in the vicinity. A water feasibility study shall include the following minimum information:
1. calculations of the projected water needs;
 2. a geologic map of the area with a radius of at least one mile from the site;
 3. the location of all existing and proposed wells within one thousand feet (1,000') of the site, with a notation of the capacity of all high-yield wells;
 4. the location of all existing on-lot sewage disposal systems within one thousand feet (1,000')

- of the site;
 - 5. the location of all streams within one thousand feet (1,000') of the site and all known point sources of pollution;
 - 6. based on the geologic formation(s) underlying the site, the long-term safe yield shall be determined;
 - 7. a determination of the effects of the proposed water supply system on the quantity and quality of water in nearby wells, streams, and the groundwater table; and,
 - 8. a statement of the qualifications and the signature(s) of the person(s) preparing the study;
- 471.S.** The applicant shall provide a qualified traffic impact study, as described in Section 319 of this Ordinance; and,
- 471.T.** Any use where diesel operated trucks periodically congregate will have in place an anti-idling policy, with a maximum idling time per truck of 5 minutes.
- 471.U.** The applicant shall furnish expert testimony regarding emergency preparedness measures provided and/or otherwise available to respond to potential hazards regarding the spill of waste materials during transport to and from the site, and potential hazards regarding firefighting of waste materials upon the site.

Section 472 Public, Private, and Commercial Schools

- 472.A.** Within the (C, A, and MU) Zones, public and private schools are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as provided below.
- 472.B.** Within the (MU) Zone, commercial schools are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as provided below.
- 472.C.** All buildings shall be set back at least one hundred (100) feet from any adjoining land within the (MI or BI) Zones;
- 472.D.** No part of a public or private school property shall be located within:
- 1. one thousand (1,000) feet of a property containing an adult-related facility, methadone treatment facility, casino, off-track betting parlor, slot machine parlors;
 - 2. five hundred (500) feet from a truck or motor freight terminal, truck stop or warehousing and wholesale trade establishments;
 - 3. three hundred (300) feet of an automobile filling station; or,
 - 4. two hundred (200) feet from a mass transit or taxicab terminal.
- 472.E.** If education is offered below the college level, an outdoor play area shall be provided, at a rate of one hundred (100) square feet per individual enrolled. Off-street parking lots shall not be used as outdoor play areas. Outdoor play areas shall not be located within the front yard and must be set back twenty-five (25) feet from all property lines. Outdoor play areas shall be completely enclosed by a six (6) foot high fence and screened from adjoining residentially zoned properties. Any vegetative materials located within the outdoor play areas shall be of a non-harmful type (poisonous, thorny, allergenic, etc.). All outdoor play areas must provide a means of shade, such as a shade tree(s) or pavilion(s);

- 472.F. Enrollment shall be defined as the largest number of students on the site at any one time during a seven-day period; and,
- 472.G. Passenger “drop-off” and “pick-up” areas shall be provided and arranged so that students do not have to cross traffic lanes on or adjacent to the site.

Section 473 Reserved

Section 474 Recycling Facilities for Paper, Plastic, Glass, and Metal Products

- 474.A. Within the (MI and BI) Zones, recycling of paper, glass and metal products is permitted by special exception, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:
- 474.B. All operations, including collection shall be conducted within a completely enclosed building;
- 474.C. There shall be no outdoor storage of materials and/or wastes processed, used or generated by the operation;
- 474.D. The applicant shall explain the scope of operation, and offer expert testimony regarding the measures used to mitigate problems associated with fumes and dust;
- 474.E. The applicant shall demonstrate compliance with Section 316 of this Ordinance, including any referenced and incorporated ordinance;
- 474.F. The applicant shall be required to submit a written working plan to assure regular maintenance of the site to immediately collect stray debris and litter.

Section 475 Residential Swimming Pools

- 475.A. Within any Zone, a swimming pool is an accessory use to a residence permitted by right, subject to the following criteria:
- 475.B. Swimming pools and any related improvements (e.g. sidewalks, decking, pumps, equipment, etc.) shall not be located within the front yard and shall be setback in accordance with the applicable zones’ accessory setback requirements, but in no event shall such setbacks be less than at least twenty-five (25) feet from any side or rear lot lines.
- 475.C. Except as noted in Section 475.F. of this Ordinance, all pools shall be entirely enclosed with a continuous, non-climbable rigid fence or wall. Such fence shall be erected before the pool is filled with water.
- 475.D. The required fence or wall shall have a minimum height of four (4) feet. No openings shall be permitted between the various fence components that would allow the passage of a four (4) inch diameter object through such opening. No openings shall be permitted between the fence or wall and the ground that would allow the passage of a two (2) inch diameter object through such opening.
- 475.E. The exterior side of the required fence or wall must rise approximately perpendicular from the ground and shall not contain steps or any protrusions or recessions which could aid in the climbing of the fence or wall.

- 475.F.** Where the swimming pool is located above ground, the sides of the pool may be considered as part of the fence required to enclose the pool, provided that the pool walls are at least four (4) feet in height and have a retractable ladder.
- 475.G.** The required fence or wall shall be equipped with a self-latching gate, which shall be locked or secured at all times when the swimming pool is unattended.
- 475.H.** All pools must use operable filtration and an effective antibacterial agent (e.g. chlorine, bromine, ozone, etc.)
- 475.I.** All pools must adhere to the strictest minimum requirements of the UCC and the Township Building Code.
- 475.J.** All pools which are no longer in service or functionally obsolete, expressly excluding non-summer periods when a pool is winterized, must be removed within three (3) months from the date the pools ceases operation.

Section 476 Riding Stables

- 476.A.** Within the (C, A and MU) Zones, riding stables are permitted by special exception provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:
- 476.B. MINIMUM LOT AREA** - Ten (10) acres.
- 476.C.** Any structure used for the boarding of horses shall be set back a minimum of one hundred (100) feet from all lot lines.
- 476.D.** All stables shall be maintained so to minimize odors perceptible at the lot line.
- 476.E.** All areas and facilities used for training shall be set back a minimum of fifty (50) feet from all lot lines.
- 476.F.** All outdoor training, show, riding, boarding, and pasture areas shall be enclosed by a fence with a minimum height of four (4) feet. Said fence shall be located a minimum of ten (10) feet from all lot lines. All outdoor pasture/recreation areas shall be maintained with a vegetated and stable surface and enclosed with fencing to prevent the escape of the animals;
- 476.G.** Required parking will be determined based upon the types of activities proposed and Section 315 of this Ordinance. Specifically with respect to parking, the applicant shall demonstrate that adequate parking facilities exist in form and number to accommodate all anticipated activities as they occur, taking into consideration the highest number of employees at a given time, the highest number of visitors at a given time, the seasonal or permanent nature of each event and the number of events which can occur simultaneously on the property. In addition, the Zoning Hearing Board may require an unimproved grassed overflow parking area to be provided for peak use periods. Such overflow parking areas shall be accessible only from the interior driveways of the permanent parking lot. Overflow parking areas shall contain fencing to prevent vehicles from crossing adjoining properties or directly accessing adjoining roads;
- 476.H.** Any booths or other structures used for the collection of admission and/or parking fees shall be set back and arranged to prevent vehicle back-ups on adjoining roads during peak arrival periods. Any other collection of fees (roaming parking lot attendants) shall be conducted in a manner to prevent vehicle back-ups on adjoining roads. If, at any time after the opening of the commercial recreation facility, the Supervisors determine that traffic back-ups are occurring on adjoining roads, and such

back-ups are directly related to the means of access to the subject property, the Supervisors can require the applicant to revise means of access to relieve the undue congestion;

- 476.I.** All parking lots and unimproved overflow parking areas shall be set back at least ten feet (10') from adjoining lot lines.
- 476.J.** All structures used to house livestock shall be fitted with a durable floor surface that can withstand the wear associated with the weight and movement of horses without failure and shall be prohibited from placement in the front yard (portable sheds are generally considered unsuitable for such purposes);
- 476.K.** The applicant shall furnish evidence of an effective means to dispose dead animals according to the regulations of the Pennsylvania Department of Agriculture;
- 476.L.** All animal wastes shall be properly stored and disposed of, so as not to be objectionable at the site's property line. All animals, their housing, and their outdoor pasture/recreation areas shall be properly maintained so as not to become a nuisance to adjoining properties; and,
- 476.M.** The applicant is required to submit written information indicating that the disposal of all materials and wastes will be accomplished in a manner that complies with State and Federal regulations with particular attention to those pesticides, insecticides and detergents used.

Section 477 Roadside Stands

- 477.A.** Within the (C and A) Zone roadside stands, as defined herein, for the seasonal sale of agricultural products are permitted by right as an accessory use to an agricultural or horticultural use, subject to the following requirements:
- 477.B.** Roadside stands shall not exceed three hundred (300) square feet of total display area;
- 477.C.** Roadside stands must be located at least twenty feet (20') from the right-of-way line and must have at least three (3) off-street parking spaces;
- 477.D.** A maximum of two (2) signs will be permitted each of which shall not exceed eight (8) square feet in total area, nor exceed a maximum height of fifteen feet (15'). Signs shall only be displayed during seasons when the roadside stand operates;
- 477.E.** Any structure must be located at least fifty feet (50') from any side or rear property line;
- 477.F.** No structures housing a roadside stand or accompanying parking area may be located within one hundred feet (100') of any intersecting street rights-of-ways; and,
- 477.G.** No more than one (1) roadside stand per property shall be permitted.

Section 478 Reserved

Section 479 Rural Occupations

- 479.A.** Within the (C, A and MU) Zones rural occupations, as defined herein, are permitted by right as an accessory use to a single family detached dwelling unit, subject to the following requirements:
- 479.B.** Only one (1) rural occupation may be conducted on the same property as the owner's principal residence and shall not exceed the area of the principal residence's ground floor or one thousand (1,000) square feet, whichever is the lesser;
- 479.C.** A rural occupation shall only be conducted within one completely enclosed outbuilding that satisfies at least one (1) of the following:
1. The building will remain the same size and in the same location as it existed on the effective date of this Ordinance; or
 2. The building is limited to one (1) story in height or twenty (20') feet, whichever is lesser, is no larger than the square footage that comprises the principal residence's main grade level, is located in the rear yard of the principal residence, and is set back at least fifty feet (50') from any side or rear lot lines. All applicants are required to design buildings that are compatible with their residential settings;
- 479.D.** In no case shall any new rural occupation building be constructed before the owner resides on the subject property. In addition, rural occupations may only be conducted so long as the sole owner of the business resides on the site;
- 479.E.** In no case shall the required maximum lot coverage be exceeded by those impervious surfaces associated with the principal residence, rural occupation and/or other accessory uses;
- 479.F.** All off-street parking and loading spaces shall be screened from adjoining roads and properties;
- 479.G.** No outdoor storage or display shall be permitted except that one (1) commercial truck of not more than eleven thousand (11,000) pounds gross vehicle weight may be parked behind the principal residence, so long as it is screened from adjoining roads and properties;
- 479.H.** One (1) non-illuminated sign not exceeding eight (8) square feet shall be permitted and must be set back at least ten feet (10') from all property lines;
- 479.I.** No rural occupation and its principal dwelling shall generate more than twenty (20) vehicle trips per day to or from the site. The applicant shall furnish a written and sworn statement regarding the expected numbers of vehicle trips associated with the proposed use;
- 479.J.** Vehicular access to the rural occupation shall be limited to the same driveway connection with the public street that serves the principal residence. No additional roadway connections shall be permitted;
- 479.K.** Only residents of the site may be employed in the rural occupation. For the purposes of this Section, "employees" shall be defined as those involved in the on-site conduct of the rural occupation;
- 479.L.** Rural occupations shall only be conducted between the hours of 6:00 a.m. and 9:00 p.m. No rural occupation shall be conducted on Sundays;
- 479.M.** No manufacturing, mechanical, or industrial use shall be permitted which causes any noise, odor, glare, fume, smoke, dust, vibration, electromagnetic interference, or other hazard that is noticeable at or beyond the line of the nearest residential lot. No use that requires application or permitting by

the PA DEP for the handling of hazardous waste or other substances, shall be permitted, except for wastewater treatment;

- 479.N.** Any area devoted to retail sales display shall be limited to twenty percent (20%) of the overall size of the rural occupation;
- 479.O.** The applicant shall furnish evidence that an approved means of sewage disposal shall be utilized, and further, that such means is part of the same system in use for the principal residence; and,
- 479.P.** The applicant is required to submit written information indicating that the disposal of all materials and wastes will be accomplished in a manner that complies with State and Federal regulations. Such evidence shall, at a minimum include, copies of contracts with waste haulers licensed to operate within Cumberland County, which have been contracted to dispose of the materials and wastes used, or generated, on-site or some other legal means of disposal. The zoning permit for this use shall remain valid, only so long as such contracts remain in effect and all materials and wastes are properly disposed of on a regular basis. Should the nature of the rural occupation change in the future, such that the materials used, or wastes generated, changes significantly, either in type or amount, the owner of the rural occupation shall so inform the Zoning Officer, and shall provide additional evidence demonstrating continued compliance with the requirements of this Section.
- 479.Q.** In any use where the public is permitted into any building pursuant to the rural occupation, such building or structure shall be outfitted in compliance with all UCC requirements, including ADA compliance and regulations for access, ramps, parking, and restrooms.

Section 480 Sales of Compost, Mulch, Woodchips and Coal

- 480.A.** Within the (A, MI and BI) Zones the sale of compost, mulch, woodchips and coal is permitted by special exception provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and specifically as follows:
- 480.B.** Reserved.
- 480.C.** The applicant must demonstrate compliance (through a written statement) and continue to comply with all applicable State and Federal standards and regulations.
- 480.D.** All loading/unloading, storage and processing of materials shall be located at least two hundred (200) feet from any property line and five hundred feet from any (LDR and MU) Zone;
- 480.E.** All uses shall provide sufficiently long stacking lanes into the facility, so that vehicles will not back-up onto public roads. In addition, the design of such use must require all vehicles to exit the site in a forward direction.
- 480.F.** All access drives onto the site must be paved for a distance of at least one hundred (100) feet from the street right-of-way line. In addition, a fifty (50) foot long gravel section shall be placed just beyond the preceding one hundred (100) foot paved section to help collect any mud that may have attached to a vehicle's wheels.
- 480.G.** All areas of the site used for the loading/unloading, storage and processing of materials shall be fitted with a durable impervious ground cover which is designed to collect and recycle any leachate.
- 480.H.** Any leachate shall be disposed of in a manner in compliance with any applicable State and Federal laws or regulations. If leachate is to be discharged to a municipal sewage facility, appropriate permits shall be obtained from the applicable agencies and authorities. In no event shall leachate

be disposed of in a storm sewer, to the ground, or in any other manner inconsistent with the PA DEP regulations. The applicant must describe leachate disposal methods to be used.

- 480.I.** All vehicle and processor repair and maintenance activities shall be conducted within a completely enclosed building.



Section 481 Satellite Dish Antennas

481.A. Within any Zone, freestanding or attached satellite dish antennas of up to one meter (39.4 inches) in diameter are permitted by right as an accessory use to a single dwelling unit, subject to the following requirements:

1. All freestanding residential installations must comply with all residential accessory use requirements specified within the Zone; and,
2. All freestanding installations shall be located (where possible) to prevent obstruction of the antenna's reception window from potential permitted development on adjoining properties;
3. All installations shall be securely anchored to prevent detachment during foul weather conditions.
4. No transmission of video format data shall be permitted;
5. Residential properties shall contain no more than two (2) such devices; and,
5. The allowance of a satellite dish antenna shall in no way place any liability upon the Township for the obstruction of the antenna's reception window due to permitted construction on adjoining or nearby properties. Any arrangements made to protect the antenna's reception window shall be between private parties, and not the Township;

481.B. In any Zone, freestanding or attached satellite dish antennas larger than one meter (39.4 inches) up to twelve feet (12') in diameter are permitted by right as an accessory use subject to the following requirements:

1. All applications must include certification by a Commonwealth registered engineer that the proposed installation complies with the Pennsylvania Uniform Construction Code, 34 Pa. Code §§403.1 – 403.142. Furthermore, written documentation of such compliance, including load distributions within the building's support structure, shall be furnished if applicable;
2. All freestanding installations must include screening treatments located along the antenna's non-reception window axes and low-level ornamental landscape treatments along the reception window axes of the antenna's base. Such treatments should completely enclose the antenna. Required screening shall consist of evergreen plantings that provide eighty percent (80%) visual blockage of the area between ground level and a height of six (6) feet along the antenna's non-reception window axes. Required low-level ornamental landscaping shall consist of vegetative materials that are planted with sufficient density to form an enclosure



with the required screening, around the base of the antenna. Ornamental landscaping height will be determined by the installation's required elevation alignments. The adjoining diagrams present illustrative examples of a required screening and landscaping treatment. All screening and landscaping requirements can be waived if the satellite dish antenna is at least one hundred (100) feet from any property line;

3. No transmission of video format data shall be permitted;
4. Freestanding installations shall be confined to the side or rear yard and the satellite dish antenna must be set back at least the horizontal distance equal to its maximum height, from all side and rear property lines; and,
5. Any granting of a special exception for a satellite dish antenna shall in no way place any liability upon the Township for the obstruction of the antenna's reception window due to permitted construction on adjoining or nearby properties. Any arrangements made to protect the antenna's reception window shall be between private parties, and not the Township.

481.C. In any (MI and BI) Zone, satellite dish antennas as principal uses are permitted by right, subject to the following criteria:

1. All installations shall comply with the area, height, bulk and setback standards imposed upon principal uses;
2. All applications must include certification by a Commonwealth registered engineer that the proposed installation complies with the Pennsylvania Uniform Construction Code, 34 Pa. Code §§403.1 – 403.142. Furthermore, written documentation of such compliance, including load distributions within the building's support structure, shall be furnished, if applicable;
3. All ground-mounted installations shall be screened from any adjoining properties. Such screening can be waived if the antenna is set back a distance at least five times its diameter from the adjoining property;
4. Those ground-mounted installations used to transmit video format data shall be completely enclosed by an eight (8) foot high fence. Such fence shall include signs warning of dangerous radiation levels, must be screened from adjoining properties, and must be locked at all times. This screening requirement can be waived if the fence is set back a distance at least five times the diameter of the satellite dish antenna, from the adjoining property; and,
5. The allowance of a satellite dish antenna(s) shall in no way place any liability upon the Township for the obstruction of the antenna's reception window due to permitted construction on adjoining or nearby properties. Any arrangements made to protect the antenna's reception window shall be between private parties, and not the Township.

Section 482 Sawmills

482.A. Within the (C, A, and MI) Zones, sawmills are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:

482.B. No material shall be deposited or stored, and no building or structure shall be located, within two hundred feet (200') of any property line and five hundred feet (500') of any land within an (LDR and MU) Zone;

- 482.C.** All uses shall provide sufficiently long stacking lanes into the facility so that vehicles waiting will not back-up onto public roads;
- 482.D.** Litter control shall be exercised to prevent the scattering of wind-borne debris, and an acceptable working plan for the cleanup of litter shall be submitted.
- 482.E.** The owner and/or operator shall be responsible for removing any mud from public roads caused by persons traveling to and from the site; and,
- 482.F.** The applicant must demonstrate compliance with Section 316 of this Ordinance, including any referenced or incorporated ordinance.
- 482.G.** Any use where diesel operated trucks periodically congregate will have in place an anti-idling policy, with a maximum idling time per truck of 5 minutes.

Section 483 Septage and Compost Processing

- 483.A.** Within the (MI) Zone, septage and compost processing are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:
- 483.B.** Any processing, loading, storage, and packaging operations, specifically excluding a Municipal composting facility, must be conducted within a completely enclosed building that is leak- and vector-proof;
- 483.C.** The applicant must demonstrate compliance (through a written statement) and continue to comply with all applicable State and Federal standards and regulations;
- 483.D.** The use shall be screened from all roads and adjoining properties;
- 483.E.** All uses shall provide sufficiently long stacking lanes into the facility, so that vehicles waiting to be weighed or loaded/unloaded will not back up onto public roads;
- 483.F.** All driveways onto the site must be paved for a distance of at least one hundred feet (100') from the street right-of-way line. In addition, a fifty foot (50') long gravel section of driveway shall be placed just beyond the preceding one hundred foot (100') paved section to help collect any mud that may have attached to a vehicle's wheels;
- 483.G.** The unloading, processing and transfer, of septage and compost shall be continuously supervised by a qualified facility operator;
- 483.H.** Any leachate shall be disposed of in a manner in compliance with any applicable State and Federal laws or regulations. If leachate is to be discharged to a municipal sewage facility, appropriate permits shall be obtained from the applicable agencies and authorities. In no event shall leachate be disposed of in a storm sewer, to the ground, or in any other manner inconsistent with the PA DEP regulations;
- 483.I.** If the facility is to rely upon non-public sources of water, a water feasibility study will be provided to enable the Township to evaluate the impact of the proposed development on the groundwater supply and on existing wells. The purpose of the study will be to determine if there is an adequate supply of water for the proposed development and to estimate the impact of the new development on existing wells in the vicinity. No use shall be approved without sufficient water and/or for a use that poses adverse impact on existing wells in the vicinity. A water feasibility study shall include the following minimum information:

1. calculations of the projected water needs;
2. a geologic map of the area with a radius of at least one mile from the site;
3. the location of all existing and proposed wells within one thousand feet (1,000') of the site, with a notation of the capacity of all high-yield wells;
4. the location of all existing on-lot sewage disposal systems within one thousand feet (1,000') of the site;
5. the location of all streams within one thousand feet (1,000') of the site and all known point sources of pollution;
6. based on the geologic formation(s) underlying the site, the long-term safe yield shall be determined;
7. a determination of the effects of the proposed water supply system on the quantity and quality of water in nearby wells, streams, and the groundwater table; and,
8. a statement of the qualifications and the signature(s) of the person(s) preparing the study;

483.J. A minimum one hundred foot (100') wide buffer strip shall be located along all property lines. No structures, storage, parking, or any other related activity or operation shall be permitted within this buffer strip. Any fences or other screening erected on the site must not be located within this buffer strip;

483.K. The applicant shall provide an analysis of the physical conditions of the primary road system serving the proposed use. The analysis shall include information on the current traffic flows on this road system, and projections of traffic generated by the proposed use. Improvements to the road shall be provided by the applicant to insure safe turning movements to and from the site and safe through-movement on the existing road; and,

483.L. Any structure used for the storage, loading, processing and/or packaging of compost shall be set back at least three hundred feet (300') from all property lines, and five hundred feet (500') from any adjoining land within the (LDR, A, C and MU) Zones. In addition, any ventilation outlets must be oriented away from any land within the (LDR, A, C and MU) Zones.

Section 484 Shopping Centers

484.A. Within the (BI) Zone, shopping centers are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:

484.B. The initial approval of the shopping center shall require conditional use review. For freestanding pad sites, the applicant may choose to identify proposed building envelopes and a list of potential uses to be applied to each pad site respectively as an alternative to the specific identification of each use; however, in reviewing such pad sites the Township will consider the worst case scenario of building site envelope and potential uses when evaluating the conditional use application. Any subsequent substitution of use within the shopping center shall be permitted by right so long as the proposed use is permitted and does not require amendment of the site plan approved by the original conditional use. Future uses to be substituted that require separate conditional use approval, shall follow such review and approval processes. Future uses that require amendment of the site plan shall require conditional use approval under Section 805.C. of this Ordinance;

484.C. Shopping centers shall front on an arterial or collector road. Drive-through lanes for any use contained within the shopping center shall connect only to internal access drives and parking lots.

Access drives serving all shopping centers shall be set back at least two hundred feet (200') from the intersection of any street right-of-way lines along the same side of the street;

- 484.D.** In addition to vehicular access to the property, the applicant shall be required to design and construct pedestrian linkages with any nearby areas, even if they are not yet developed. Such pedestrian linkages shall be located so as to provide safe and convenient access to the shopping center from the nearby areas;
- 484.E.** If bus service is available, or at any time that bus service become available to the shopping center in the future, all shopping centers must provide an improved bus stop which would be conveniently accessible for patrons who would travel to and from the site by bus. Such bus stop shall include a shelter, seating, a waste receptacle, and at least one (1) shade tree;
- 484.F.** Shopping centers with more than two hundred (200) parking spaces must integrate a designated location for a minimum of twenty (20) park and ride off-street parking spaces that is readily identifiable and conveniently accessible to passing motorists. Such park and ride spaces can include those spaces required to serve the shopping center and shall be designed, signed, lighted and maintained in accordance with Section 315 of this Ordinance;
- 484.G.** The applicant's site plan shall clearly depict the proposed locations and dimensions of all on-site circulation improvements which must demonstrate safe vehicular and pedestrian movements both upon and abutting the subject property;
- 484.H.** A traffic impact study shall be submitted by the applicant, in accordance with Section 319 of this Ordinance;
- 484.I.** The applicant shall demonstrate an adequate means of sewage disposal and water supply.
- 484.J.** Off-street parking and loading shall be provided in accordance with Sections 315 and 314, respectively, of this Ordinance.
- 484.K.** The proposed shopping center design shall comply with the applicable regulations contained within the following table:

SHOPPING CENTER DESIGN REQUIREMENTS	
↓Standard / Zone ⇒	HC
Required Lot Area	Minimum - 2 acres;
Minimum Required Lot Width	200 ft. at the building setback line & street line
Minimum Required Lot Depth	NA
Required Minimum Yard Setbacks:	The following lists required setbacks between features of the shopping center and perimeter lot lines. No specific setbacks are required between buildings located upon the shopping center site except those that may be required by the ISO (as defined herein) or by the Pennsylvania Uniform Construction Code.
Front, as Measured from Street R.O.W.	10 ft. for buildings & structures (except permitted signs) and for off-street parking; no off-street loading, or dumpsters are permitted within the front yard.
One Side	10 ft. for buildings & structures (except permitted signs), off-street parking & loading spaces & dumpsters
Both Sides	20 ft. for buildings & structures (except permitted signs) off-street parking & loading spaces & dumpsters
Rear	10 ft. for all buildings, structures, off-street parking & loading spaces & dumpsters

SHOPPING CENTER DESIGN REQUIREMENTS	
↓Standard / Zone ⇒	HC
Minimum Required Setback from (LDR and MU) Zones as measured to closest point of area devoted to the use.	200 ft.
Maximum Permitted Impervious Lot Coverage	See Section 205.E. of this Ordinance.
Maximum Permitted Building Height	See Section 205.G. of this Ordinance.

484.L. The applicant shall submit written expert evidence that demonstrates compliance with the lighting requirements of Section 310 of this Ordinance;

484.M. The applicant shall submit a landscape plan prepared by a landscape architect registered within the Commonwealth of Pennsylvania that demonstrates compliance with all applicable provisions of Section 321 of this Ordinance. Such plans shall include but not be limited to details depicting:

1. Landscape buffers and screens used to protect adjoining residential zones and residential uses, riparian and wetland buffers in accordance with Sections 511 and 512 of this Ordinance, respectively;
2. Screening used to prevent the spillage of headlights onto adjoining properties;
3. Typical interior landscape island treatments;
4. Typical landscape strip treatments; and,
5. Landscape treatments at the shopping center access drives' intersections with streets.

484.N. The applicant shall submit a sign plan that demonstrates compliance with Table 3 of Section 322 of this Ordinance regulating Planned Center Signs. Once approved as part of the conditional use review, any subsequent substitution of sign that does not increase the size and/or alter the location of signs permitted on the originally approved sign plan is permitted by right. Future signs that would alter the size and/or location of signs will require shall require conditional use approval.

Section 485 Slaughtering, Processing, Rendering, and Packaging of Food Products and Their By-Products

485.A. Within the (MI) Zone, slaughtering, processing, rendering, and packaging of food products and their by-products are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:

485.B. MINIMUM LOT AREA - Five (5) acres;

485.C. Vehicular access shall be so arranged as to minimize danger and congestion along adjoining roads and to avoid the creation of nuisances to nearby properties. Access drives used by trucks shall only intersect with collector or arterial roads;

485.D. All aspects of the slaughtering, processing, rendering, and packaging operation, excepting the unloading and holding of live animals, shall be conducted within a completely enclosed building;

- 485.E.** All live animals held outside shall be within secure holding pens or runways, sufficiently large to accommodate all animals without crowding, and not located within the front yard;
- 485.F.** The applicant shall furnish an acceptable written working plan for the recovery of escaped animals which minimizes the potential for animals to enter traffic or cross property lines, and which shall be continuously implemented;
- 485.G.** The applicant shall furnish an acceptable written working plan for the regular clean-up and disposal of all animal wastes, so as not to be objectionable at the site's property line;
- 485.H.** The unloading of live animals from trucks into holding pens and their movement into the plant shall be continuously supervised by a qualified operator, whose responsibility it shall also be to immediately identify and appropriately dispatch any obviously ill or injured animals;
- 485.I.** The unloading of live animals and their movement into the plant shall be conducted in an orderly and calm manner so as to minimize noise levels. The applicant must demonstrate those methods that will be used to comply with Section 316 of this Ordinance, including any referenced or incorporated ordinance;
- 485.J.** The loading and unloading of trucks shall be restricted to the hours between 6:00 AM and 10:00 PM;
- 485.K.** No exterior animal holding pens and/or areas devoted to loading/unloading of animals shall be located within two hundred feet (200') of any property line nor five hundred feet (500') of any land within a (LDR and MU) Zone;
- 485.L.** All animal holding pens and/or areas used for the loading/unloading of animals shall be screened from all adjoining properties and shall include a minimum fifty foot (50') wide landscape strip;
- 485.M.** The applicant shall demonstrate an adequate means of sewage disposal and water supply. Public sewer and water lines shall not meet within or beneath the plant, and shall further be designed and installed to minimize the potential for leakage and contamination by maximizing the separation distance between lines and laying sewer lines at greater depth than water lines;
- 485.N.** Wastewater shall be kept completely covered at all times to reduce the potential for release of odors. In no event shall wastewater be disposed of in a storm sewer, to the ground, or in any other manner inconsistent with PA DEP regulations;
- 485.O.** All unusable animal by-products shall be stored indoors in leak- and vector-proof containers. In the case of slaughtering or processing operations which do not do their own rendering, the applicant shall provide evidence of a written contract with a rendering operation for the daily disposal of such waste products. In no case shall any waste products remain on the site for more than twenty-four (24) hours;
- 485.P.** The applicant must demonstrate written compliance with, and continue to comply with, all applicable local, State and Federal standards and regulations;
- 485.Q.** The use shall provide sufficiently long stacking lanes and on-site loading/unloading areas, so that trucks waiting to be loaded / unloaded will not back up onto public roads. No parking or loading/unloading shall be permitted on or along any public road;
- 485.R.** The applicant shall furnish a traffic impact study prepared by a professional traffic engineer, in accordance with Section 319 of this Ordinance; and,

485.S. Any use where diesel operated trucks periodically congregate will have in place an anti-idling policy, with a maximum idling time per truck of 5 minutes.

Section 486 Truck or Motor Freight Terminals

486.A. Within the (BI) Zone, truck or motor freight terminals are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:

486.B. The applicant shall be required to submit qualified expert evidence of the methods that will be used to assure that the proposed use will not contribute materially to air pollution and will comply with all applicable Federal Environmental Protection Agency air quality standards. Test data must be furnished by applicant addressing Particulate Matter 2.5 (total weight of particles in the air that are less than 2.5 microns in size) levels taken by a certified independent air testing firm during peak use periods of the day. Upon approval of the conditional use, terminal owners must provide PM 2.5 data on a quarterly basis as sampled by a certified independent air testing firm during peak use periods of the day at locations every 200 feet around the perimeter of the property and at a distance of 75 feet from the terminal building. Terminals not in compliance with National Ambient Air Quality Standard (NAASQS) for PM 2.5, as established by EPA (15 micrograms per cubic meter averaged over an entire year and up to 66 micrograms for one 24 hour period), will furnish the Township with a plan within 60 days for reducing PM 2.5 emissions to acceptable levels. Upon approval of that plan, the terminal will have 90 days to provide evidence that satisfactory PM 2.5 levels have been reached or be subject to applicable enforcement remedies provided by this Ordinance.

486.C. The applicant shall furnish a traffic impact study, prepared by a professional traffic engineer, in accordance with Section 319 of this Ordinance;

486.D. The subject property shall have a minimum of three hundred feet (300') of contiguous road frontage along an arterial and/or collector road;

486.E. The subject property shall be located no closer than five hundred feet (500') from any (LDR and MU) Zone and/or property containing a school, day care facility, park, playground, library, hospital, nursing, rest or retirement home, or medical residential campus;

486.F. All structures (including, but not limited to, air compressors, fuel pump islands, kiosks) shall be set back at least fifty feet (50') from any street right-of-way line. Unless the fuel pump islands are set back two hundred feet (200') from the street line, they shall be designed so that, when fueling, trucks must be parallel to street;

486.G. Access driveways shall be a minimum of twenty-eight feet (28'), and a maximum of thirty-five feet (35') wide. All access drives onto the same road shall be set back at least one hundred fifty feet (150') from one another, as measured from closest points of cartway edges;

486.H. Any gates or other barriers used at the entrance to parking areas shall be set back and arranged to prevent vehicle backups onto adjoining roads during peak arrival periods;

486.I. All vehicle service and/or repair activities shall be conducted within a completely- enclosed building. Outdoor storage of parts, equipment, lubricants, fuels, or other materials used or discarded in any service or repair operations must be screened from adjoining roads and properties;

486.J. The outdoor storage of unlicensed and/or un-inspected vehicles is prohibited;

- 486.K.** The demolition or junking of vehicles and machinery is prohibited. Demolished vehicles and/or parts thereof shall be removed within thirty (30) days after arrival;
- 486.L.** Any exterior public address system shall be designed and operated so that the audible levels of any messages conveyed over the system and any other use of the property will not violate Section 313 of this Ordinance;
- 486.M.** The applicant shall demonstrate compliance with Section 310 of this Ordinance; and,
- 486.N.** The parking, storage, and/or loading of vehicles associated with the use shall be confined to the subject property; no satellite parking, storage, and/or loading lots shall be permitted;
- 486.O.** The applicant shall furnish evidence that the storage and disposal of materials and wastes will be accomplished in a manner that complies with all applicable State and Federal regulations; and,
- 486.P.** Any use where diesel operated trucks periodically congregate will have in place an anti-idling policy, with a maximum idling time per truck of five (5) minutes.

Section 487 Truck Stops

- 487.A.** Within the (BI) Zone, truck stops are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:
- 487.B.** The applicant shall be required to submit qualified expert evidence of the methods that will be used to assure that the proposed use will not contribute materially to air pollution and will comply with all applicable Federal Environmental Protection Agency air quality standards. Test data must be furnished by applicant addressing Particulate Matter 2.5 (total weight of particles in the air that are less than 2.5 microns in size) levels taken by a certified independent air testing firm during peak use periods of the day. Upon approval of the conditional use, truck stop owners must provide PM 2.5 data on a quarterly basis as sampled by a certified independent air testing firm during peak use periods of the day at locations every 200 feet around the perimeter of the property and at a distance of 75 feet from the terminal building. Truck stops not in compliance with National Ambient Air Quality Standard (NAASQS) for PM 2.5, as established by EPA (15 micrograms per cubic meter averaged over an entire year and up to 66 micrograms for one 24 hour period), will furnish the Township with a plan within 60 days for reducing PM 2.5 emissions to acceptable levels. Upon approval of that plan, the truck stop will have 90 days to provide evidence that satisfactory PM 2.5 levels have been reached or be subject to applicable enforcement remedies provided by this Ordinance.
- 487.C.** The applicant shall furnish a traffic impact study, prepared by a professional traffic engineer, in accordance with Section 319 of this Ordinance;
- 487.D.** The subject property shall have a minimum of three hundred feet (300') of contiguous road frontage along an arterial and/or collector road;
- 487.E.** The subject property shall be located no closer than five hundred feet (500') from any (LDR and MU) Zone and/or property containing a school, day care facility, park, playground, library, hospital, nursing, rest or retirement home, or medical residential campus;
- 487.F.** All structures (including, but not limited to, air compressors, fuel pump islands, kiosks) shall be set back at least fifty feet (50') from any street right-of-way line. Unless the fuel pump islands are

set back two hundred feet (200') from the street line, they shall be designed so that, when fueling, trucks must be parallel to street;

- 487.G.** Access driveways shall be a minimum of twenty-eight feet (28'), and a maximum of thirty-five feet (35') wide. All access drives onto the same road shall be set back at least one hundred fifty feet (150') from one another, as measured from closest points of cartway edges;
- 487.H.** Off-street parking shall be provided at a rate equal to that required for each of the respective uses comprising the truck stop according to Section 315 of this Ordinance. Any gates or other barriers used at the entrance to parking areas shall be set back and arranged to prevent vehicle backups onto adjoining roads during peak arrival periods;
- 487.I.** All vehicle service and/or repair activities shall be conducted within a completely- enclosed building. Outdoor storage of parts, equipment, lubricants, fuels, or other materials used or discarded in any service or repair operations must be screened from adjoining roads and properties;
- 487.J.** The outdoor storage of unlicensed and/or un-inspected vehicles is prohibited;
- 487.K.** The demolition or junking of vehicles and machinery is prohibited. Demolished vehicles and/or parts thereof shall be removed within thirty (30) days after arrival;
- 487.L.** Any exterior public address system shall be designed and operated so that the audible levels of any messages conveyed over the system and any other use of the property will not violate Section 313 of this Ordinance;
- 487.M.** The applicant shall demonstrate compliance with Section 310 of this Ordinance; and,
- 487.N.** The applicant must furnish evidence as to how the use will be controlled so as to not constitute a nuisance due to noise or loitering outside the building;
- 487.O.** An acceptable working plan for the cleanup of litter shall be furnished and implemented by the applicant and,
- 487.P.** The applicant shall furnish evidence that the storage and disposal of materials and wastes will be accomplished in a manner that complies with all applicable State and Federal regulations.
- 487.Q.** Any use where diesel operated trucks periodically congregate will have in place an anti-idling policy, with a maximum idling time per truck of five (5) minutes.

Section 488 Two-Family Conversions

- 488.A.** Within the (C, A and LDR) Zones, a detached single-family dwelling that existed on the effective date of this Ordinance, and contained (at that time) at least three thousand (3,000) square feet, may be converted by special exception into two (2) dwelling units provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 704.C.2. and within the (MU) Zones, a detached single-family dwelling that existed on the effective date of this Ordinance, and contained (at that time) at least three thousand (3,000) square feet, may be converted by right into two (2) dwelling units provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance and both as specifically as follows:
- 488.B.** The applicant shall obtain approval from the Township SEO for increased usage of septic systems, and applicant shall further furnish evidence that an approved system of water supply and sewage disposal will be utilized;

- 488.C.** No extensions or modifications to the external appearance of the building (except fire escapes) which would alter its residential character, shall be permitted;
- 488.D.** All floors above and/or below grade shall have direct means of escape to ground level;
- 488.E.** Four (4) off-street parking spaces shall be provided; however, such uses may share the same driveway provided that vehicles entering and/or exiting the property are unimpeded by a parking space; and,
- 488.F.** The applicant shall obtain any required land development approvals.

Section 489 Warehouses and Distribution centers

- 489.A.** Within the (BI) Zone, warehousing and wholesale trade establishments are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:
- 489.B.** The applicant shall provide a detailed description of the proposed use in each of the following topics:
 - 1. The nature of the on-site activities and operations, the types of materials stored, the frequency of distribution and restocking, the duration period of storage of materials, and the methods for disposal of any surplus or damaged materials. In addition, the applicant shall furnish evidence that the disposal of materials will be accomplished in a manner that complies with state and federal regulations;
 - 2. Any environmental impacts that are likely to be generated (e.g., odor, noise, smoke, dust, litter, glare, vibration, electrical disturbance, wastewater, storm water, solid waste, etc.) and specific measures employed to mitigate or eliminate any negative impacts. The applicant shall further furnish evidence that the impacts generated by the proposed use comply with applicable laws and ordinances, including but not limited to those listed in Article IV of this chapter; and
 - 3. A traffic impact study prepared by a professional traffic engineer, according to the SALDO Section 302.G.5, or successor section.
- 489.C.** The subject property shall have a minimum lot area of five acres and a minimum lot width of 300 feet. A maximum lot coverage of 70% shall be permitted if the warehouse or distribution center is served by public water and public sewer.
- 489.D.** The maximum building height may be increased by one foot for every two feet by which the building exceeds applicable minimum yard requirements, up to maximum building height of 50 feet.
- 489.E.** Any use where diesel operated trucks periodically congregate will have in place an anti-idling policy, with a maximum idling time per truck of five minutes.
- 489.F.** The use shall provide sufficiently long stacking lanes and onsite loading/unloading areas, so that trucks waiting to be loaded/ unloaded will not back up onto public roads. No parking areas or loading/unloading areas shall be permitted within 50 feet of any public street right-of-way line.
- 489.G.** Vehicular access shall be so arranged as to minimize danger and congestion along adjoining roads and to avoid the creation of nuisances to nearby properties. Access drives used by trucks

shall only intersect with arterial roads or new streets that are proposed, designed and constructed to serve the distribution center or warehouse.

- 489.H.** The subject property shall have a minimum of 300 feet of contiguous road frontage along an arterial and/or collector road.
- 489.I.** Buildings, access drives, parking areas, staging areas and loading/unloading areas on the subject property shall be located no closer than:
1. Five hundred feet from the Township's (A, LDR, and MU) Zones and/or property containing a school, day-care facility, park, playground, library, hospital, nursing, rest or retirement home, or medical residential campus; and
 2. Two hundred feet from a residential use that is located in any other zoning district.
- 489.J.** All buildings shall be set back at least 50 feet from any street right-of-way line.
- 489.K.** Access driveways shall be a minimum of 28 feet, as measured at the street right-of-way line (unless a different width is required by PADOT as part of the highway occupancy permit process), and a maximum of 35 feet wide, as measured at the throat of the access drive. All access drives onto the same road shall be set back at least 150 feet from one another, as measured from closest points of cart way edges.
- 489.L.** Any gates or other barriers used at the entrance to parking areas shall be set back and arranged to prevent vehicle backups onto adjoining roads during peak arrival periods.
- 489.M.** Vehicle service, fueling and/or repair activities shall be prohibited. Accessory forklift service and/or repair activities shall be permitted within a completely enclosed building.
- 489.N.** The outdoor storage of unlicensed and/or uninspected vehicles is prohibited.
- 489.O.** The demolition or junking of vehicles and machinery is prohibited. Demolished vehicles and/or parts thereof shall be removed within 30 days after arrival.
- 489.P.** Any exterior public address system shall be designed and operated so that the audible levels of any messages conveyed over the system and any other use of the property will not violate Section 316 of this Ordinance, including any referenced or incorporated ordinance.
- 489.Q.** The applicant shall demonstrate compliance with Section 316 of this Ordinance, including any referenced or incorporated ordinances.
- 489.R.** The parking, storage, staging and/or loading/unloading of vehicles associated with the use shall be confined to the subject property; no satellite parking, storage, staging and/or loading lots or areas shall be permitted.
- 489.S.** The applicant shall furnish evidence that the storage and disposal of materials and wastes will be accomplished in a manner that complies with all applicable state and federal regulations.
- 489.T.** Buffer yards shall comply with the provisions of Section 321 of this Ordinance, except that:
1. Buffer yards shall be increased to two hundred (200) feet along adjoining lands as follows: (i) in the (C, A, LDR, and MU) Zones, (ii) along adjoining residential uses that are located in any other zoning district, and (iii) along any land adjoining a neighboring municipality;
 2. Within the buffer yards adjoining such zones or residential uses, the screen plantings required for vegetative screens shall meet all applicable screening requirements; provided,

however, applicant shall provide for and install an earthen berm having a maximum slope of three (3) feet of run to one (1) foot of rise and a minimum height of fifteen (15) feet above grade; and

3. Stormwater management facilities may be located within buffer yards.

Section 490 Wind and/or Solar Farms

490.A. Within the (C) Zone, wind and/or solar farms (as defined herein) are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:

490.B. Within the (MU) Zone, solar farms (as defined herein) are permitted by conditional use, provided that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. and specifically as follows:

490.C. The applicant shall prepare and submit a narrative and mapping describing the proposed wind and/or solar farm including:

1. an overview of the project;
2. the project location;
3. the approximate generating capacity of the wind and/or solar farm;
4. the approximate number, representative types and height or range of heights of wind turbines and/or solar panels to be constructed, including their generating capacity, dimensions and respective manufacturers; and,
5. a description of accessory facilities.
6. an affidavit or similar evidence of agreement between the property owner(s) and the applicant demonstrating that the applicant has the permission of the property owner(s) to apply for necessary permits for construction and operation of the wind and/or solar farm.
7. a listing and map of the properties on which the proposed wind and/or solar farm will be located, and the properties adjacent to where the wind and/or solar farm will be located.
8. a site plan showing the planned location of each wind turbine, solar panel, property lines, setback lines, access road and turnout locations, substation(s), electrical cabling from the wind and/or solar farm to the substation(s), ancillary equipment, buildings, and structures, including permanent meteorological towers, associated transmission lines, and layout of all structures within the geographical boundaries of any applicable setback.

490.D. The applicant shall demonstrate with credible expert evidence that:

1. to the extent applicable, the wind and/or solar farm shall comply with the Pennsylvania Uniform Construction Code, 34 Pa. Code §§403.1 – 403.142;
2. the design of the wind and/or solar farm shall conform to applicable industry standards, including those of the American National Standards Institute. The applicant shall submit certificates of design compliance obtained by the equipment manufacturers from

Underwriters Laboratories, Det Norske Veritas, Germanischer Lloyd Wind Energies, or other similar certifying organizations;

3. each of the proposed wind turbines shall be equipped with a redundant braking system. This includes both aerodynamic overspeed controls (including variable pitch, tip, and other similar systems) and mechanical brakes. Mechanical brakes shall be operated in a fail-safe mode. Stall regulation shall not be considered a sufficient braking system for overspeed protection;
4. all electrical components of the wind and/or solar farm shall conform to relevant and applicable local, state and national codes, and relevant and applicable international standards;
5. wind turbines shall be a non-obtrusive color such as white, off-white, gray or some color similar to the background of the proposed wind turbine;
6. wind turbines shall not be artificially lighted, except to the extent required by the Federal Aviation Administration or other applicable authority that regulates air safety;
7. wind turbines and solar panels shall not display advertising, other than an incidental insignia of the turbine manufacturer;
8. on-site transmission and power lines shall, to the maximum extent practicable, be placed underground.
9. a clearly visible warning sign concerning voltage must be placed at the base of all at-grade transformers and substations.
10. visible, reflective, colored objects, such as flags, reflectors, or tape shall be placed on the anchor points of each guy wire and along each guy wire up to a height of ten feet from the ground. The applicant shall also submit an acceptable working plan for the regular inspection of such guy wires and replacement of any needed flags, reflectors, or tape;
11. wind turbines shall be designed and constructed to be non-climbable up to fifteen (15) feet above ground surface.
12. all access doors to wind turbines and electrical equipment shall be locked or fenced, as appropriate, to prevent entry by non-authorized persons.
13. wind turbines shall be setback the following distances as measured from the center of the wind turbine base to the nearest point of the respective feature listed below:

Feature	Minimum setback
Occupied building on site	Turbine height plus ten feet
Above ground utility line right-of-way	Turbine height plus ten feet
Adjoining property	1.5 times turbine height
Adjoining road right-of-way	1.5 times turbine height

<p>Ridge – the elongated crest or series of crests at the uppermost point of intersection between opposite slopes of a mountain and including all land lying between such point and an elevation 250 feet below the elevation of such point.</p>	<p>Turbine height</p>
--	-----------------------

14. The minimum height of a wind turbine shall be such that there shall be maintained a minimum of fifteen (15) feet ground clearance, as measured between the closest ground surface to the tip of the blade at its lowest turning movement.
15. The maximum height of a wind turbine shall be fifty (50) feet, as measured from the ground surface to the tip of the blade at its highest turning movement.
16. The applicant shall be responsible for the prompt repair and maintenance of all roads used to transport equipment and parts for construction, operation or maintenance of the wind and/or solar farm. The applicant shall prepare an engineering report that documents road conditions prior to construction and again within thirty (30) days after construction is complete or as weather permits. Such reports shall be reviewed by the Township engineer; any discrepancies shall be mediated by a third engineer selected by mutual acceptance by the applicant's and Township's engineers. The applicant shall demonstrate that it has appropriate financial assurance to ensure the prompt repair of damaged roads and the Township may bond the road in compliance with state regulations.
17. The applicant shall provide a copy of the project summary and site plan as required in Section 490.B. to the Township Emergency Management Coordinator. The applicant shall prepare and coordinate the implementation of an emergency response plan for the wind and/or solar farm acceptable to the Township Emergency Management Coordinator prior to the issuance of a zoning permit for the proposed use.
18. Audible sound from a wind and/or solar farm shall not exceed fifty (55) dBA, as measured at the following minimum distances. Methods for measuring and reporting acoustic emissions from the wind and/or solar farm shall be equal to or exceed the minimum standards for precision described in AWEA Standard 2.1 - 1989 titled *Procedures for the Measurement and Reporting of Acoustic Emissions from Wind turbine Generation Systems Volume I: First Tier*.
 - a. A distance of not less than fifty (50) feet or 1.1 times the wind turbine height, whichever is greater from the nearest principal building of a property owner who has agreed to locate the proposed wind and/or solar farm upon his/her property;
 - b. A distance of not less than fifty (50) feet or 1.1 times the wind turbine height, whichever is greater from the adjoining property line of property owner who has not agreed to locate the proposed wind and/or solar farm upon his/her property; and,
 - c. A distance of not less than fifty (50) feet or 1.1 times the wind turbine height, whichever is greater, from the right-of-way of any street.
19. The surface area of a ground-mounted solar energy system, regardless of the mounted angle of any solar panels, shall be considered part of and calculated in the lot coverage of the lot on which the system is located. The surface area of a ground-mounted solar energy system shall not exceed three percent (3 %) of maximum lot coverage of the lot. For panels that self-adjust, the lot coverage of each solar panel shall be calculated at that angle with the greatest horizontal exposure.

490.E. The applicant shall make reasonable efforts to minimize shadow flicker and to avoid any disruption or loss of radio, telephone, television or similar signals. The applicant shall mitigate

any such harm caused by the wind and/or solar farm on any adjoining property whose owner has not agreed to locate the proposed wind and/or solar farm upon his/her property.

490.F. The applicant shall maintain a current general liability policy covering bodily injury and property damage with limits of at least \$1 million per occurrence and \$1 million in the aggregate. Certificates of insurance coverage shall be made available to the Township each year that the wind and/or solar farm operates.

490.G. The applicant shall be responsible for the removal of the wind and/or solar farm in accordance with the following requirements:

1. The applicant shall, at his/her expense, complete removal of the wind and/or solar farm, or individual wind turbines and solar panels, within (12) twelve months after the end of the useful life of the wind and/or solar farm or individual wind turbines and solar panels. The wind and/or solar farm or individual wind turbines and solar panels will presume to be at the end of its useful life if no electricity is generated for a continuous period of twelve (12) months.
2. Removal shall include the elimination of wind turbines and solar panels, buildings, cabling, electrical components, roads, foundations to a depth of 36 inches, and any other associated facilities.
3. Disturbed earth shall be graded and re-seeded, unless the landowner requests in writing that the access roads or other land surface areas not be restored.
4. An independent and certified Professional Engineer shall be retained to estimate the total cost of removal ("Removal Costs") without regard to salvage value of the equipment, and the cost of removing net salvage value of the equipment ("Net Removal Costs"). Said estimates shall be submitted to the Township after the first year of operation and every fifth year thereafter at the applicant's and/or any successor's expense.
5. The applicant shall post and maintain removal funds in an amount equal to net removal costs; provided, that at no point shall removal funds be less than twenty five percent (25%) of removal costs. The removal funds shall be posted and maintained with a bonding company or Federal or Commonwealth chartered lending institution chosen by the Facility Owner or Operator and participating landowner posting the financial security, provided that the bonding company or lending institution is authorized to conduct such business within the Commonwealth and is approved by the Township.
6. Removal funds may be in the form of a performance bond, surety bond, letter of credit, corporate guarantee or other form of financial assurance as may be acceptable to the Township.
7. If the applicant fails to complete removal within the period prescribed by Section 490.F.1., of this Ordinance, then the landowner shall have six (6) months to complete removal.
8. If neither the applicant, nor the landowner complete removal within the periods prescribed by Sections 490.F.1., and 490.F.7. of this Ordinance, then the Township may take such measures as necessary to complete removal. The entry into and submission of evidence of a participating landowner agreement to the Township in accordance with Section 490.B.6. of this Ordinance shall constitute agreement and consent of the parties to the agreement, their respective heirs, successors and assigns that the Township may take such action as necessary to implement the removal plan.

9. The escrow agent shall release the removal funds when the applicant has demonstrated and the municipality concurs that removal has been satisfactorily completed, or upon written approval of the municipality in order to implement the removal plan.

490.H. All owners of property upon which a wind and/or solar farm is installed shall be required to acknowledge in writing to the Township that the approval of the wind and/or solar farm shall not and does not create in the property owner, its, his, her or their successors and assigns in title or, create in the property itself:

1. the right to remain free of shadows and/or obstructions to solar or wind energy caused by development of adjoining or other property or the growth of any trees or vegetation on such property; or,
2. the right to prohibit the development on, or growth of any trees or vegetation on, such property.

Article 5

Environmental Protection Regulations

Section 500 Purpose

In accordance with sound community and site planning principles, this Article provides for requirements that are imposed upon proposed uses and activities that, because of their location, pose a threat to the environmental integrity of the Township and thereby threaten public welfare. The respective sections of this Article impose necessary restrictions to ensure environmental stewardship.

Section 501 Relationship to Other Sections of This Ordinance

501.A. The provisions of this Article are designed to supplement the provisions contained elsewhere in this Ordinance and the SALDO. In those instances where design, application, review and/or performance criteria contained herein differ from those imposed elsewhere in this Ordinance or in the SALDO, the most restrictive standard shall apply. However, all other provisions of all other articles of this Zoning Ordinance and all other ordinances of the Township shall remain in full force.

501.B. This Section shall expressly not prohibit land management practices which are intended to ecologically improve any wetland, woodland, stream, lake or pond, provided that all necessary permits have been obtained from the Pennsylvania Department of Environmental Protection and all other applicable regulatory entities.

Section 502 Floodplains

502.A. All uses must comply with Chapter 92 (Floodplain Management) of the Code of Dickinson Township and floodplains shall be clearly depicted as a natural and cultural feature on site plans.

Section 503 Riparian Buffers

503.A. RIPARIAN BUFFER USE

1. PERMITTED USES - No use shall be permitted that interferes with the natural maturation of the buffer plantings required by Section 519 of the SALDO, except as follows:
 - a. Corridor crossings for farm vehicles and livestock and livestock watering facilities, all of which are accompanied by written evidence of approval of a water obstruction permit by the PA DEP;
 - b. Public roads and improvements thereto that existed on the effective date of this Ordinance;
 - c. Corridor crossings for roads and railroads provided that such crossings are accomplished upon the least possible land area and installed in such a manner that is most compatible with the required buffer plantings as described in Section 519 of the SALDO;

- d. Bridges, with the appropriate federal and/or state permits, should be used in place of culverts when crossings would require a seventy-two (72) inch or greater diameter pipe. When culverts are installed they should consist of slab, arch or box culverts and not corrugated metal pipe. Culverts should be designed to retain the natural stream channel bottom to ensure the passage of water during low flow or dry weather periods
 - e. Public sewer lines, public water lines and public utility transmission lines, provided such lines are installed in such a manner that is most compatible with the installation and ongoing maintenance of the required buffer plantings as described in Section 519 of the SALDO;
 - f. Passive recreation uses that prevent the harmful compaction of soil, tree root damage and avoid the channelization (natural or man-made) of surface water flow. Pedestrian paths can cross Zones 1, 2 and 3 provided that such paths are accomplished upon the least possible land area and disruption of the adjoining riparian buffer is minimized. Pedestrian paths can parallel through Zones 2 and 3. All pedestrian paths shall be provided with stable pervious surfaces; and,
 - g. Streambank improvement projects that have been approved by the PA DEP.
 - h. Removal of any tree that, because of its condition, location or any other factor, poses an immediate threat to the public health and safety. Examples of appropriate emergency tree cutting include, but are not limited to, partially uprooted trees that are likely to topple onto nearby structures, properties, roads and/or sidewalks, damaged trees with split trunks due to lightning strike or wind loads, trees that block emergency vehicle access during times of natural disaster, civil defense or rescue and trees that have been partially damaged or fallen that threaten to cause an immediate rise in floodwaters.
 - i. Wildlife sanctuaries, nature preserves, forest preserves and fishing areas.
 - j. Bio-retention storm water Best Management Practice (BMP) facilities planted with native plants may be installed in Zone 3 of a riparian buffer zone.
 - k. Forestry uses.
2. PROHIBITED USES – The following uses and activities are expressly prohibited within a riparian buffer. This listing of prohibited uses and activities shall not be exhaustive or interpreted to permit other activities not listed, unless they are permitted by Section 503.A.1. of this Ordinance:
- a. Except as permitted in the above Section 503.A.1., any use that interferes with the natural maturation of the buffer plantings required in Section 519 of the SALDO;
 - b. Except as permitted in the above Section 503.A.1., any use that interferes with the maintenance of the buffer plantings required in Section 519 of the SALDO;
 - c. Storage and/or disposal of any toxic, hazardous or noxious materials and substances;
 - d. Application of fertilizers, pesticides, herbicides and/or other chemicals in excess of that permitted on an approved conservation and/or nutrient management plan as approved by the CCCD, the local office of the PA Pennsylvania Natural resources and Conservation Service and/or as permitted under the Pennsylvania Conservation Reserve Enhancement Program (CREP).

- e. Areas devoted to the on-site absorption of sewage effluent and/or agricultural fertilizers including but not limited to manure.

503.B. EMERGENCY TREE CUTTING

1. At any time, a landowner may cut-down any tree within a riparian buffer that, because of its condition, location or any other factor, poses an immediate threat to the public health and safety. However, any trees removed shall be replaced in accordance with the requirements of the following Section 503.B. of this Ordinance. Examples of appropriate emergency tree cutting include, but are not limited to:
 - a. Partially uprooted trees that are likely to topple onto nearby structures, properties, roads and/or sidewalks;
 - b. Damaged trees with split trunks due to lightning strike or wind or ice loads;
 - c. Trees that block emergency vehicle access during times of natural disaster, civil defense or rescue;
 - d. Trees that have been partially damaged or fallen that threaten to cause an immediate rise in floodwaters;
 - e. Trees that have been certified by a qualified forester to be afflicted with a contagious disease, blight or infection or damage from natural causes, from which the tree is unlikely to recover;
 - f. Trees that have been certified by a qualified forester to be dead; and,
 - g. Trees that have been certified by a qualified forester to be an invasive species.

503.C. TREE REPLACEMENT STANDARDS

1. Any person who or which removes or destroys trees required by this Section 519 of the SALDO shall be subject to the penalties for violation as outlined herein and is responsible for replacement of said trees. This replacement shall be done on a tree-for-tree basis if the number of trees removed in violation of this ordinance can be identified. If the number of trees cannot be identified, then the trees shall be replaced at a rate of one tree per seven hundred fifty (750) square feet of area of tree removal as determined by the Township Zoning Officer or as suggested by a qualified forester to accomplish the purposes of this Section 503 and Section 519 of the SALDO.
2. Any person who or which removes any tree(s) in accordance with the previous Section 503.B. of this Ordinance shall be responsible for replacement of said trees. This replacement shall be done on a tree-for-tree basis or as suggested by a qualified forester.
3. Replacement trees shall be deciduous, noninvasive, native to the Township, nursery stock grown within a locale with similar climatic conditions as found within the Township, well branched, and free of disease. Replacement trees shall be selected from the selective native buffer plants list in Section 519.C. of the SALDO. Plants not included on this list may be permitted by the Township when evidence is provided from qualified sources certifying their suitability for substitution. The trees shall be balled and burlapped and not less than two (2) inches in caliper measured at breast height. The trees shall be at least ten (10) feet tall after planting and trimming. Branching shall start not less than six (6) feet from the top of the root ball.

4. Replacement trees shall be placed in accordance with the standards of Section 519 of the SALDO as long as such location does not violate any other provision of this ordinance or laws of the State.
5. Replacement trees cannot be used as credits to meet other planting requirements of this ordinance relative to street tree plantings, landscape buffer, unless the original trees would have satisfied such requirements. Any replacement trees that are to be counted as required screening shall comply with the standards listed in Section 321 of this Ordinance.
6. Replacement trees shall be planted within ninety (90) days of initial tree removal or, if because of the season, at the soonest time suggested by a qualified forester.

503.D. PENNSYLVANIA CONSERVATION RESOURCE ENHANCEMENT PROGRAM (CREP)

It is the express intent of this Section 503 and Section 519 of the SALDO to facilitate landowner participation within the Pennsylvania Conservation Resource Enhancement Program (CREP). Any requirement that is inconsistent with an approved CREP management plan shall not apply, but only to the extent that it is inconsistent with the CREP.

Section 504 Wetland and Wetland Buffers

Any wetland and/or wetland buffer (as defined in Section 108.C. of the SALDO), or portion thereof, located on any property shall be permanently protected from filling, grading, clearing, water diversion and/or development, and disturbance of any wetland and/or wetland buffer for filling, grading, clearing, water diversion and/or development is strictly prohibited unless conducted pursuant to a land development plan approved by the Township in accordance with the requisite SALDO procedures.

Section 505 Steep Slopes

505.A. APPLICABILITY & USE

Any steep slopes (as defined in Section 112) located on a property shall be permanently protected from disturbance and/or development, except as provided for by Sections 505.B. and 505.C. of this Ordinance.

505.B. ROAD IMPROVEMENT EXEMPTIONS

The disturbance of steep slopes for widening, alignment improvement or sight distance improvements of an existing street for public safety reasons or that are required by, approved by or accomplished by the Township or PennDOT, are expressly exempted from the requirements of this Section.

505.C. LIMITS ON AREA OF DISTURBANCE

The total area of disturbance that is permitted upon steep slopes shall be limited on each individual lot as follows:

1. Thirty percent (30%) of the aggregate areas of existing natural slopes of fifteen percent (15%) to twenty-five percent (25%); and/or,
2. Fifteen percent (15%) of the aggregate areas of existing natural slopes greater than twenty-five percent (25%).

3. The above limits shall not apply to contiguous areas of steep slope disturbance involving less than five hundred (500) square feet.

Section 506 Appalachian Trail Overlay Zone

506.A. PURPOSE

The purpose of this Overlay Zone is to:

1. preserve the natural, scenic, historic and aesthetic values and qualities of the Appalachian Trail (the "Trail");
2. maintain a natural resource buffer along the Trail in order to protect the Trail as an important natural and historic resource;
3. preserve the scenic and topographical conditions along the Trail that are vital to the Trail's natural and scenic quality;
4. promote connections with municipal trails, both existing and that may exist in the future, and integration with the Township's natural resource system;
5. provide health benefits through increased recreational activities; and,
6. comply With Act 24 of 2008, which amended the 1978 Pennsylvania Appalachian Trail Act, by directing governing bodies to take such action deemed appropriate to preserve the various values and qualities of the Trail as described above.

506.B. DESIGNATION OF APPALACHIAN TRAIL OVERLAY ZONE

The Appalachian Trail Overlay Zone shall consist of that area located and measured one hundred fifty (150) feet horizontally perpendicular from the centerline of the Appalachian Trail and having a uniform total width of three hundred (300) feet.

506.C. APPLICABILITY

The provisions of this Section shall apply to all lands within the Appalachian Trail Overlay Zone as that area is described in Section 506.B. of this Ordinance and as depicted on the Official Township Zoning Map. The provisions of this Section shall supersede any other conflicting or less restrictive provisions in effect in this Ordinance and in any underlying Zone and, to the extent not conflicting, shall apply in addition to the requirements of the underlying Zone and other applicable provisions of this Ordinance.

506.D. PERMITTED USES

The following uses, and no others, are permitted in the Appalachian Trail Overlay Zone:

1. Open space.
2. Passive recreational uses, such as public or private parkland, nature preserves, forest preserves and fishing areas.
3. Forestry, as that activity is defined by the Pennsylvania Municipalities Planning Code.
4. Agriculture.

5. Accessory uses, structures and buildings, excluding, however, equipment storage, free standing satellite dish antennas, parking lots, outdoor wood-fired boilers and wind turbines. Any storage of the following within the Overlay Zone must be contained inside an accessory building: vehicles, lawn and farm equipment, machinery, or parts thereof, waste or discarded material. Accessory structures shall be subject to the respective regulations contained within the underlying Zone. All accessory structures or buildings must be painted or finished in earth-tone colors.
6. Municipal uses, structures and buildings, excluding, however, equipment storage, free standing satellite dish antennas, parking lots, outdoor wood-fired boilers and wind turbines. Any storage of the following within the Overlay Zone must be contained inside an accessory building: vehicles, lawn and farm equipment, machinery, or parts thereof, waste or discarded material. All municipal structures or buildings must be painted or finished in earth-tone colors.

Section 507 Historic Site Protection

507.A. PURPOSE

1. To provide the means that the Township can protect and preserve historic sites and structures.
2. To initiate a process of public and technical review prior to the demolition of historic structures.

507.B. APPLICABILITY

1. This Section imposes a conditional use review procedure for the proposed demolition and/or conversion of historic structures, as defined herein.

507.C. DEMOLITION OF AN HISTORIC STRUCTURE

1. No historic structure shall be demolished until the applicant has obtained conditional use approval and a zoning permit for such demolition.
2. Prior to the application for conditional use approval to demolish an historic structure, the applicant shall be required to (1) request to meet with the staff of the Pennsylvania Historical and Museum Commission (PHMC) to gain their ideas about potential preservation options for the building/structure, (2) request that the PHMC provide a written review of the proposed demolition and (3) provide evidence no less than ninety (90) days has elapsed since the meeting with the PHMC if no written report has been provided by the PHMC. No conditional use approval or zoning permit for the demolition of an historic structure shall be issued unless the preceding requirements have been satisfied. To inform the staff of the PHMC about the structure, the applicant shall be required to produce all of the available following materials at the time of their meeting:
 - a. Historic deeds, surveys and site plans of the subject property;
 - b. Current and historic photos of the property; and,
 - c. A description of the specific reasons why the historic structure cannot accommodate a permitted use and the demolition is warranted.

3. In applying to the Township for conditional use approval to demolish an historic structure, the applicant is required to produce all of the available following materials and information:
 - a. Historic deeds, surveys and site plans of the subject property;
 - b. Current and historic photos of the property;
 - c. If the applicant is not the landowner, a notarized letter from the landowner requesting demolition of the historic structure;
 - d. Additional information as may be requested by the Board of Supervisors;
 - e. A review letter from the PHMC of its findings as required by Section 518.C.2. of this Ordinance; and,
 - f. A description of specific measures and/or relief that could enable the preservation of the subject historic structure or specific reasons why the historic structure cannot accommodate a permitted use and the demolition is warranted.

4. In evaluating the merits of a conditional use application for the demolition of an historic structure, the Board of Supervisors must find that the applicant has met his/her burden of proof that the proposed use meets all applicable regulations contained within this Ordinance including but not limited to those general criteria contained within Section 805.B. of this Ordinance and will consider the following:
 - a. The findings of the PHMC in its review of the proposed demolition.
 - b. Should the Board of Supervisors determine that the historic structure retains significant historic value and can be practically adapted to meet the needs of the applicant, the conditional use shall be denied.
 - c. Should the Board of Supervisors determine that the historic structure retains significant historic value and can be preserved through some other practical means, the conditional use shall be denied.
 - d. Should the Board of Supervisors determine that the historic structure fails to retain significant historic value, the conditional use shall be approved authorizing the demolition.
 - e. Should the Board of Supervisors determine that the historic structure cannot be practically adapted to meet the needs of the applicant, the conditional use shall be approved authorizing the demolition.
 - f. Should the Board of Supervisors determine that the historic structure cannot be preserved by any practical means, the conditional use shall be approved authorizing the demolition.

Article 6

Nonconformities

SECTION 600 NON-CONFORMING USES AND STRUCTURES

600.A. A non-conforming use is any use, whether of land or of structure, or both, which does not comply with the applicable use provisions in this Ordinance or subsequent amendments, where such use was lawfully in existence prior to the enactment of this Ordinance or subsequent amendments.

600.B. A non-conforming structure is any structure or part of a structure manifestly not designed to comply with the applicable use provisions of this Ordinance or subsequent amendment, where such structure lawfully existed prior to the enactment of this Ordinance or subsequent amendments.

600.C. Any such non-conforming use or structure may, subject to the standards of Section 604 of this Article, be enlarged, altered, extended, reconstructed, or restored after the effective date of this Ordinance to no more than an additional twenty-five percent (25%) of the area which was in non-conformance upon the adoption of this Ordinance.

SECTION 601 CONTINUATION OF NON-CONFORMING USES AND STRUCTURES

601.A. ANY NON-CONFORMING USE OR STRUCTURE MAY BE CONTINUED INDEFINITELY, PROVIDED SUCH USE OR STRUCTURE:

1. Shall not be moved to another location where such use or structure would be non-conforming.
2. Shall not be changed to another non-conforming use or structure without approval by the Zoning Hearing Board and then only to a use or structure which, in the opinion of the Zoning Hearing Board is of the same or of a more restricted nature in accordance with Section 604 of this Article.
3. Shall not be re-established if such use or structure has been discontinued for any reason for a period of twelve (12) months or more, or has been changed to, or replaced by, a conforming use or structure. Intent to resume a non-conforming use shall not confer the right to do so.
4. Shall not be restored for other than a conforming use after damage from any cause, unless the non-conforming use or structure is reinstated within twelve (12) months of such damage; if the restoration of such structure is not completed within the said twelve (12) month period, the non-conforming use of such structure shall be deemed to have been discontinued, unless such nonconforming use is carried on without interruption in the undamaged portion of such structure.

SECTION 602 REPAIRS AND MAINTENANCE

602.A. Notwithstanding any of the above regulations, nothing in this Article shall be deemed to prevent normal maintenance and repair of any nonconforming use or structure, or the carrying out, upon the issuance of a building permit, of major structural alterations or demolitions necessary in the interest of public safety. In granting such a building permit, the Township shall state the precise reason such alterations were deemed necessary.

602.B. Any nonconformity which is partially or totally destroyed by fire, explosion, flood or other phenomenon may be reconstructed, repaired and used for the same nonconforming use, or any permitted use under the Zone, provided that the reconstruction shall commence within 18 months from the date the nonconformity was destroyed. Date of commencement shall be the date when final plans are submitted to the Township for approval.

SECTION 603 REGISTRATION OF NON-CONFORMING USES AND STRUCTURES

All lawful uses and structures existing at the effective date of this Ordinance which do not conform to the requirements set forth in this Ordinance, or any amendments thereto, may be identified and registered by the Zoning Officer. Failure or neglect of the Zoning Officer to identify or register uses or structures which are non-conforming as defined in this Ordinance or subsequent amendments does not exempt such use or structures from the applications of this Ordinance.

SECTION 604 EXPANSION AND CHANGE OF NON-CONFORMING USES AND STRUCTURES

604.A. PROCEDURE

Any non-conforming use or structure or combination thereof may be expanded or changed only upon approval of the Zoning Hearing Board after a special exception hearing as defined elsewhere in this Ordinance.

604.B. STANDARDS

Each application for an expansion or change of a nonconforming use shall be subject to the following standards:

1. It shall be the responsibility of the applicant to sufficiently document to the Zoning Hearing Board that the proposed expansion or change will not be contrary to the purposes of this Ordinance and the public health, safety, and welfare of township residents in general and of the residents of the immediate area, in particular: (i) that such expansion or change does not exceed the twenty five percent (25%) maximum increase as set forth in Section 600.C., and (ii) that such expansion or change shall comply with the applicable yard and setback requirements of the district where located.
2. Any person seeking permission to change a non-conforming use or structure to any other non-conforming use or structure shall sufficiently document to the Zoning Hearing Board that such new non-conforming use or structure is more in compliance with the applicable provisions of this Ordinance than the present nonconforming use or structure.

3. The Zoning Hearing Board may attach additional provisions to the granting of a special exception to expand or change a nonconforming use or structure for the purpose of promoting the objectives and intent of this Ordinance.
4. The expansion of a non-conforming use or structure shall comply with the applicable yard requirements of the district where located.

SECTION 605 NON-CONFORMING LOTS

A lot owned individually and separately and separated in ownership from any adjoining tracts of land on the effective date of this Ordinance, which has a total lot area or lot width less than prescribed in this Ordinance, provided that the lot was and still is in single ownership, and no opportunity is present to consolidate two (2) or more contiguous lots into a lot conforming to the district requirement, may be used provided such lot shall be developed in conformity with all applicable district regulations other than the minimum lot area, lot width and yards. Existing small lots meeting the above stipulations shall comply with the following permitted building setback reductions: (i) Side yards may be proportionately reduced based upon the percentage that the existing small lot is not in compliance, but in no event shall the side yard be less than ten feet (10') (for example, if the existing small lot is twenty-five percent (25%) less than the minimum lot size requirement, the side yard may be reduced by twenty-five (25%)), front yard relief shall comply with the average setback of the two existing principal buildings with the greatest setbacks located within one hundred (100) feet on each side of the proposed building, provided, however that in no event shall the front yard be less than fifteen feet (15'); and (ii) rear yards may be proportionately reduced in the same manner as the foregoing, but in no event shall the rear yard be less than fifteen feet (15').

Article 7

Zoning Hearing Board

Section 700 Establishment and Membership

- 700.A.** The Board of Supervisors shall appoint a Zoning Hearing Board which shall consist of three (3) members who shall be residents of the Township. Their terms of office shall be three (3) years and shall be so fixed that the term of office of one member shall expire each year. The Zoning Hearing Board shall promptly notify the Board of Supervisors of any vacancies that occur. Appointments to fill vacancies shall be only for the unexpired portion of the term. Members of the Zoning Hearing Board shall hold no other office in the Township. Any member of the Zoning Hearing Board may be removed for malfeasance, misfeasance, or nonfeasance in office or for other just cause by a majority vote of the Board of Supervisors taken after the member has received fifteen (15) days' advance notice of the intent to take such a vote. A hearing shall be held in connection with the vote if the member shall request it in writing.
- 700.B.** The governing body may appoint by resolution at least one but no more than three residents of the municipality to serve as alternate members of the Zoning Hearing Board. The term of office of an alternate member shall be three years. When seated pursuant to the provisions of Section 701, an alternate shall be entitled to participate in all proceedings and discussions of the Zoning Hearing Board to the same and full extent as provided by law for Zoning Hearing Board members, including specifically the right to cast a vote as a voting member during the proceedings, and shall have all the powers and duties set forth in this Ordinance and as otherwise provided by law. Alternates shall hold no other office in the municipality, including membership on the planning commission and zoning officer. Any alternate may participate in any proceeding or discussion of the Zoning Hearing Board but shall not be entitled to vote as a member of the Zoning Hearing Board nor be compensated pursuant to Section 702 unless designated as a voting alternate member pursuant to Section 701 of this Ordinance.

Section 701 Organization of Zoning Hearing Board

- 701.A.** The Zoning Hearing Board shall elect from its own membership its officers, who shall serve annual terms as such and may succeed themselves. For the conduct of any hearing and the taking of any action, a quorum shall be not less than a majority of all members of the Zoning Hearing Board, but the Zoning Hearing Board may appoint a hearing officer from its own membership to conduct any hearing on its behalf and the parties may waive further action by the Zoning Hearing Board as provided in Section 703.
- 701.B.** If, by reason of absence or disqualification of a member, a quorum is not reached, the chairman of the Zoning Hearing Board shall designate as many alternate members of the Zoning Hearing Board to sit on the Zoning Hearing Board as may be needed to provide a quorum. Any alternate member of the Zoning Hearing Board shall continue to serve on the Zoning Hearing Board in all proceedings involving the matter or case for which the alternate was initially appointed until the Zoning Hearing Board has made a final determination of the matter or case. Designation of an alternate pursuant to this Section shall be made on a case-by-case basis in rotation according to declining seniority among all alternates.

701.C. The Zoning Hearing Board may make, alter, and rescind rules and forms for its procedure, consistent with Ordinances of the Township and laws of the Commonwealth. The Zoning Hearing Board shall keep full public records of its business, which records shall be the property of the Township, and shall submit a report of its activities to the Board of Supervisors upon request.

Section 702 Expenditures for Services

Within the limits of funds appropriated by the Board of Supervisors, the Zoning Hearing Board may employ or contract for secretaries, clerks, legal counsel, consultants and other technical and clerical services. Members of the Zoning Hearing Board may receive compensation for the performance of their duties, as may be fixed by the Board of Supervisors. Alternate members of the Zoning Hearing Board may receive compensation, as may be fixed by the governing body, for the performance of their duties when designated as alternate members pursuant to Section 701, but in no case shall such compensation exceed the rate of compensation authorized to be paid to the members by the governing body.

Section 703 Public Hearings

703.A. The Zoning Hearing Board shall conduct hearings and make decisions in accordance with the following requirements:

703.B. Public notice shall be given to the applicant, the zoning officer, such other persons as the Township Board of Supervisors shall designate by Ordinance and to any person who has made timely request for the same. Written notices shall be given at such time and in such manner as shall be prescribed by Ordinance or, in the absence of Ordinance provision, by rules of the Zoning Hearing Board. In addition to the written notice provided herein, public notice shall also include the posting of a sign at conspicuous locations along the perimeter of the subject property deemed sufficient by the Township to notify potentially interested citizens. This sign(s) shall be posted at least one (1) week prior to the hearing and will exhibit the nature, date, time, and location of the hearing;

703.C. The Board of Supervisors may prescribe reasonable fees with respect to hearings before the Zoning Hearing Board. Fees for said hearings may include compensation for the secretary and members of the Zoning Hearing Board, notice and advertising costs and necessary administrative overhead connected with the hearing. The costs, however, shall not include legal expenses of the Zoning Hearing Board, expenses for engineering, architectural or other technical consultants or expert witness costs;

703.D. The first hearing before the Zoning Hearing Board or hearing officer shall commence within sixty (60) days from the date of receipt of the applicant's application, unless the applicant has agreed in writing to an extension of time. Each subsequent hearing before the Zoning Hearing Board or hearing officer shall be held within forty-five (45) days of the prior hearing, unless otherwise agreed to by the applicant in writing or on the record. An applicant shall complete the presentation of his case-in-chief within one hundred (100) days of the first hearing. Upon the request of the applicant, the Zoning Hearing Board or hearing officer shall assure that the applicant receives at least seven (7) hours of hearings within the one hundred (100) days, including the first hearing. Persons opposed to the application may, upon the written consent or consent on the record by the applicant and municipality, be granted additional hearings to complete their opposition to the application provided the applicant is granted an equal number of additional hearings for rebuttal;

703.E. The hearings shall be conducted by the Zoning Hearing Board or the Zoning Hearing Board may appoint any member, or an independent attorney as a hearing officer. The decision, or, where no decision is called for, the findings shall be made by the Zoning Hearing Board however, the appellant or the applicant, as the case may be, in addition to the municipality, may, prior to the

decision of the hearing, waive decision or findings by the Zoning Hearing Board and accept the decision or findings of the hearing officer as final;

- 703.F** The parties to the hearing shall be the Township, any person affected by the application who has made timely appearance of record before the Zoning Hearing Board, and any other person including civic or community organizations permitted to appear by the Zoning Hearing Board. The Zoning Hearing Board shall have power to require that all persons who wish to be considered parties enter appearances in writing on forms provided by the Zoning Hearing Board for that purpose;
- 703.G** The chairman or acting chairman of the Zoning Hearing Board or the hearing officer presiding shall have power to administer oaths and issue subpoenas to compel the attendance of witnesses and the production of relevant documents and papers, including witnesses and documents requested by the parties;
- 703.H** The parties shall have the right to be represented by counsel and shall be afforded the opportunity to respond and present evidence and argument and cross-examine adverse witnesses on all relevant issues;
- 703.I** Formal rules of evidence shall not apply, but irrelevant, immaterial, or unduly repetitious evidence may be excluded;
- 703.J** The Zoning Hearing Board or the hearing officer, as the case may be, shall keep a stenographic record of the proceedings. The appearance fee for a stenographer shall be shared equally by the applicant and the Zoning Hearing Board. The cost of the original transcript shall be paid by the Zoning Hearing Board if the transcript is ordered by the Zoning Hearing Board or hearing officer; or shall be paid by the person appealing from the decision of the Zoning Hearing Board if such appeal is made, and in either event the cost of additional copies shall be paid by the person requesting such copy or copies. In other cases the party requesting the original transcript shall bear the cost thereof;
- 703.K** The Zoning Hearing Board or the hearing officer shall not communicate, directly or indirectly, with any party or his representatives in connection with any issue involved except upon notice and opportunity for all parties to participate, shall not take notice of any communication, reports, staff memoranda, or other materials, except advice from their solicitor, unless the parties are afforded an opportunity to contest the material so noticed and shall not inspect the site or its surroundings after the commencement of hearings with any party or his representative unless all parties are given an opportunity to be present;
- 703.L** The Zoning Hearing Board or the hearing officer, as the case may be, shall render a written decision or, when no decision is called for, make written findings on the application within forty-five (45) days after the last hearing before the Zoning Hearing Board or hearing officer. Where the application is contested or denied, each decision shall be accompanied by findings of fact and conclusions based thereon together with the reasons therefore. Conclusions based on any provisions of the Act or of this Ordinance, rule or regulation shall contain a reference to the provision relied on and the reasons why the conclusion is deemed appropriate in the light of the facts found. If the hearing is conducted by a hearing officer, and there has been no stipulation that his decision or findings are final, the Zoning Hearing Board shall make his report and recommendations available to the parties within forty-five (45) days and the parties shall be entitled to make written representations thereon to the Zoning Hearing Board prior to final decision or entry of findings, and the Zoning Hearing Board's decision shall be entered no later than thirty (30) days after the report of the hearing officer. Except for challenges filed under Section 916.1 of the Act, Where the Zoning Hearing Board fails to render the decision within the period required by this subsection, or fails to commence or complete the required hearing as provided in Section 703.D. of this Ordinance, the decision shall be deemed to have been rendered in favor of the applicant unless the applicant has agreed in writing or on the record to an extension of time. When a decision has been rendered in favor of the applicant

because of the failure of the Zoning Hearing Board to meet or render a decision as hereinabove provided, the Zoning Hearing Board shall give public notice of said decision within ten (10) days from the last day it could have met to render a decision in the same manner, as provided in this Section of this Ordinance. If the Zoning Hearing Board shall fail to provide such notice, the applicant may do so. Nothing in this subsection shall prejudice the right of any party opposing the application to appeal the decision to a court of competent jurisdiction:

703.M. A copy of the final decision or, where no decision is called for, of the findings shall be delivered to the applicant personally or mailed to him not later than the day following its date. To all other persons who have filed their name and address with the Zoning Hearing Board not later than the last day of the hearing, the Zoning Hearing Board shall provide by mail or otherwise, brief notice of the decision or findings and a statement of the place at which the full decision or findings may be examined; and,

703.N. TIME LIMITATIONS ON ZONING HEARING BOARD'S DECISION

1. For uses that do not require subsequent subdivision and/or land development approval:
 - a. If a variance or special exception is granted, or the issuance of a permit is approved, or other action by the applicant is authorized, the necessary zoning permit shall be secured and the authorized action begun within six (6) months after the date when the variance or special exception is finally granted, or the issuance of a permit is finally approved, or the other action by the applicant is authorized, and the building or alteration, as the case may be, shall be completed within two (2) years of said date. For good cause, the Zoning Hearing Board may upon application in writing or on the record, state the reasons therefore and extend either the six (6) months or two (2) year period;
 - b. Should the applicant fail to obtain the necessary zoning permit within said six (6) months period, or having obtained the permit should he fail to commence work thereunder within such six (6) months period, it shall be conclusively presumed that the applicant has waived, withdrawn, or abandoned his appeal or his application, and all provisions, variances and permits granted to him shall be deemed automatically rescinded by the Zoning Hearing Board; and,
 - c. Should the applicant commence construction or alteration within said six (6) months period, but should he fail to complete such construction or alteration within said two (2) year period, the Zoning Officer will, upon ten (10) days notice in writing, rescind or revoke the granted variance or special exception, or the issuance of the permit, or permits, or the other action authorized to the applicant, if the Zoning Officer finds that no good cause appears for the failure to complete within such two (2) year period, and if the Zoning Officer further finds that conditions have so altered or changed in the interval since the granting of the variance, permit or action, that revocation or rescission of the action is justified.
2. For uses that require subsequent subdivision and/or land development approval:
 - a. If a variance or special exception is granted, or other action by the appellant is authorized, the applicant shall be required to submit the subsequent subdivision and/or land development application within twelve (12) months after the date when the variance or special exception is finally granted, or the other action by the appellant is authorized, and the applicant shall have secured a zoning permit for such use within five (5) years of said date. For good cause, the Zoning Hearing Board may upon application in writing, state the reasons therefore and extend either the twelve (12) months or five (5) year period;

- b. Should the applicant fail to submit the subsequent subdivision and/or land development application within twelve (12) months period, it shall be conclusively presumed that the applicant has waived, withdrawn, or abandoned his appeal or his application, and all approvals granted to him shall be deemed automatically rescinded by the Zoning Hearing Board; and,
 - c. Should the applicant submit the subsequent subdivision and/or land development application within said twelve (12) months period, but should he fail to secure a zoning permit for such use within said five (5) year period, the Zoning Officer will, upon ten (10) days notice in writing, rescind or revoke the granted approvals, if the Zoning Officer finds that no good cause appears for the failure to secure a zoning permit within such five (5) year period, and if the Zoning Officer further finds that conditions have so altered or changed in the interval since the granting of the variance, permit or action, that revocation or rescission of the action is justified.
3. As an alternative to the preceding requirements of Section 703.N.1. and 703.N.2., an applicant can request, as part of the original application or by a subsequent request on the record before the Zoning Hearing Board, the granting of a timetable associated with the request which would supersede the deadlines imposed in Section 703.N.1.-2. In so doing, the applicant must demonstrate that the times requested are logically related to normal and expected progress of the project. In approving a timetable under this Section, the Zoning Hearing Board must establish and bind a definite timeframe for (1) application of for subdivision and/or land development approval if applicable, (2) issuance of a zoning permit, and (3) completion of construction of the project.

Section 704 Zoning Hearing Board's Jurisdiction

The Zoning Hearing Board shall have the exclusive jurisdiction to hear and render decisions in the following matters:

704.A. SUBSTANTIVE CHALLENGES TO THE VALIDITY OF ANY LAND USE ORDINANCE, except those brought before the governing body pursuant to Section 804.E. of this Ordinance.

- 1. If a challenge heard by a Zoning Hearing Board is found to have merit, the decision of the Zoning Hearing Board shall include recommended amendments to the challenged Ordinance that will cure the defects found. In reaching its decision, the Zoning Hearing Board shall consider the amendments, plans and explanatory material submitted by the landowner and shall also consider:
 - a. The impact of the proposal upon roads, sewer facilities, water supplies, schools and other public service facilities;
 - b. If the proposal is for a residential use, the impact of the proposal upon regional housing needs and the effectiveness of the proposal in providing housing units of a type actually available to and affordable by classes of persons otherwise unlawfully excluded by the challenged provisions of the Ordinance or map;
 - c. The suitability of the site for the intensity of use proposed by the site's soils, slopes, woodland, wetlands, floodplains, aquifers, natural resources and other natural features;
 - d. The impact of the proposed use on the site's soils, slopes, woodlands, wetlands, floodplains, natural resources and natural features, the degree to which these are

protected or destroyed, the tolerance of the resources to development and any adverse environmental impacts;

- e. The impact of the proposal on the preservation of agriculture and other land uses which are essential to public health and welfare; and,
 - f. For challenges alleging the exclusion of one or more land uses within the Township, the Zoning Hearing Board shall consider the availability of opportunity for such uses throughout the Township.
2. The Zoning Hearing Board, shall render its decision within forty-five (45) days after the conclusion of the last hearing. If the Zoning Hearing Board fails to act on the landowner's request within this time limit a denial of the request is deemed to have occurred on the 46th day after the close of the last hearing;
 3. The Zoning Hearing Board shall commence its hearings within sixty (60) days after the request is filed unless the landowner requests or consents to an extension of time; and,
 4. Public notice of the hearing shall be provided as specified in Section 804.B.2. of this Ordinance;

704.B. RESERVED;

704.C. SPECIAL EXCEPTIONS

The Zoning Hearing Board shall hear and act upon applications for special exceptions as specifically authorized by this Ordinance. The granting of a special exception shall be subject to the following standards and criteria. The applicant for a special exception shall demonstrate, by credible evidence, compliance with these criteria and those criteria specified elsewhere in this Ordinance for the use in question.

1. Filing Requirements - In addition to the required permit information (See Section 801) each special exception application shall include the following:
 - a. Ground floor plans and elevations of proposed structures;
 - b. Names and address of adjoining property owners including properties directly across a public right-of-way;
 - c. A scaled drawing (site plan) of the site, including finished topography with sufficient detail and accuracy to demonstrate compliance with all applicable provisions of this Ordinance; and,
 - d. A written description of the proposed use in sufficient detail to demonstrate compliance with all applicable provisions of this Ordinance;
2. General Criteria - Each applicant must demonstrate, by credible evidence, compliance with the following:
 - a. The proposed use shall be consistent with the purpose and intent of the Zoning Ordinance and such use is specifically authorized as a use by special exception within the Zone wherein the applicant seeks approval;
 - b. The proposed use shall not detract from the use and enjoyment of adjoining or nearby properties;

- c. The proposed use will not substantially change the character of the subject property's neighborhood nor adversely affect the character of the general neighborhood, the conservation of property values, the health and safety of residents or workers on adjacent properties and in the neighborhood, nor the reasonable use of neighboring properties. The use of adjacent properties shall be adequately safeguarded;
 - d. Adequate public facilities are available to serve the proposed use and the proposed use shall not have an adverse effect upon the logical and economic extension of such public services and facilities, (e.g., schools, parks and recreation, fire, police and ambulance protection, sewer, water and other utilities, vehicular access, etc.);
 - e. The applicant shall establish by credible evidence that the proposed special exception shall be in and of itself properly designed with regard to internal circulation, off-street parking, off-street loading, landscaping, screening, buffering, and all other elements of proper design as specified in this Ordinance and any other governing law or regulation;
 - f. The proposed use demonstrates a substantial likelihood of compliance with the requirements of Article 5 of this Ordinance;
 - g. The proposed use shall comply with those criteria specifically listed in Article 4 of this Ordinance. In addition, the proposed use must comply with all other applicable regulations contained in this Ordinance; and,
 - h. The proposed use will not substantially impair the integrity of the Comprehensive Plan;
3. Conditions - The Zoning Hearing Board in approving special exception applications may attach conditions considered necessary to protect the public welfare and the purposes listed above, including conditions which are more restrictive than those established for other uses in the same Zone. These conditions shall be enforceable by the Zoning Officer and failure to comply with such conditions shall constitute a violation of this Ordinance and be subject to the penalties described in Article 9;
 4. Site Plan Approval - Any site plan presented in support of the special exception pursuant to Section 704.C.1.C. shall become an official part of the record for said special exception;
 5. Time Limitation – An approved special exception shall be bound by the time limitations listed in Section 703.N. of this Ordinance.

704.D. VARIANCES

The Zoning Hearing Board shall hear requests for variances where it is alleged that the provisions of this Ordinance inflict unnecessary hardship upon the applicant. The Zoning Hearing Board may, by rule, prescribe the form of application to the Zoning Officer. The Zoning Hearing Board may grant a variance, provided that the applicant submits sufficient evidence for the Zoning Hearing Board to make the those findings set forth in Section 704.D.2. where relevant in a given case

1. Filing Requirements – Each Variance application shall include the following:
 - a. Ground floor plans and elevations of proposed structures;

- b. Names and address of adjoining property owners including properties directly across a public right-of-way;
 - c. A scaled drawing (site plan) of the site, including finished topography with sufficient detail and accuracy to demonstrate compliance with all applicable provisions of this Ordinance, except for the provisions for which the Variance is being sought; and,
 - d. A written description of the proposed use and Variance request in sufficient detail to demonstrate compliance with all applicable provisions of this Ordinance, except for the provisions for which the Variance is being sought, and a description of why the Variance is being sought, including the information required in Section 704.D.2 below;
2. General Criteria - Each applicant must demonstrate, by credible evidence, the following:
- a. That there are unique physical circumstances or conditions, including irregularity, narrowness, or shallowness of lot size or shape, or exceptional topographical or other physical conditions peculiar to the particular property and that the unnecessary hardship is due to such conditions, and not the circumstances or conditions generally created by the provisions of this Ordinance in the neighborhood or Zone in which the property is located;
 - b. That because of such physical circumstances or conditions, there is no possibility that the property can be developed in strict conformity with the provisions of this Ordinance and that the authorization of a variance is therefore necessary to enable reasonable use of the property;
 - c. That such unnecessary hardship has not been created by the appellant;
 - d. That the variance, if authorized, will not alter the essential character of the Zone or neighborhood in which the property is located, nor substantially or permanently impair the appropriate use or development of adjacent property, nor be detrimental to the public welfare;
 - e. That the variance, if authorized, will represent the minimum variance that will afford relief and will represent the least modification possible of the regulations in issue;
3. Floodplains. Variances regarding floodplains shall require compliance with Chapter 92 (Floodplain Management) of the Code of Dickinson Township;
4. Conditions. In granting any variance, the Zoning Hearing Board may attach such reasonable conditions and safeguards as it may deem necessary to implement the purposes of this Ordinance. These conditions shall be enforceable by the Zoning Officer and failure to comply with such conditions shall constitute a violation of this Ordinance and subject to the penalties described in Article 8; and,
5. Zoning Permits. If a Zoning Permit has been requested, the approved variance with any conditions imposed by the Zoning Hearing Board shall be attached to the application. Where the variance is approved prior to the application, then the approved variance with any conditions imposed by the Zoning Hearing Board shall be forwarded to the Zoning Officer.
6. Time Limitation – An approved special exception shall be bound by the time limitations listed in Section 703.N. of this Ordinance.

- 704.E. APPEALS FROM THE DETERMINATION OF THE ZONING OFFICER**, including, but not limited to, the granting or denial of any permit, or failure to act on the application therefore, the issuance of any cease and desist order or enforcement notice or the registration or refusal to register any nonconforming use, structure or lot;
- 704.F. APPEALS FROM A DETERMINATION BY A MUNICIPAL ENGINEER OR THE ZONING OFFICER** with reference to the administration of any provisions contained within Chapter 92 (Floodplain Management) of the Code of Dickinson Township;
- 704.G. APPEALS FROM THE DETERMINATION OF ANY OFFICER OR AGENCY** charged with the administration of any transfers of development rights or performance density provisions of the Zoning Ordinance;
- 704.H. APPEALS FROM THE ZONING OFFICER'S DETERMINATION** under Section 916.2 of the Act; and,
- 704.I. APPEALS FROM THE DETERMINATION OF THE ZONING OFFICER OR MUNICIPAL ENGINEER** in the administration of any land use Ordinance with reference to sedimentation and erosion control, and/or storm water management for applications not involving a subdivision/land development, nor a planned residential development as regulated in Articles V and VII of the Act, respectively.

Section 705 Appeals to the Zoning Hearing Board

- 705.A.** Appeals under Sections 704.E., 704.F., 704.G., 704.H., and 704.I. and proceedings to challenge this Ordinance under Sections 704.A. and 704.B. may be filed with the Zoning Hearing Board in writing by the landowner affected, any officer or agency of the Township, or any person aggrieved. Requests for a variance under Section 704.D. and for special exception under Section 704.C. may be filed with the Zoning Hearing Board by any landowner or any tenant with the permission of such landowner. Any appeal/application shall state:
1. The name and address of the appellant and applicant;
 2. The name and address of the landowner of the real estate to be affected;
 3. A brief description and location of the real estate to be affected by such proposed change together with a plot plan drawn to scale with sufficient clarity to show the nature and character of the request; and,
 4. A statement of the present zoning classification of the real estate in question, the improvements thereon, and the present use thereof.
- 705.B.** All appeals and any amendments thereto addressed to the Zoning Hearing Board shall be filed with the Township on forms prescribed by the Township and executed by the applicant(s).
- 705.C.** Every appeal form shall be completed in its entirety and shall include a reference to the specific section and, where applicable, the subsection at issue and a statement in numbered paragraphs setting forth the grounds for each form of relief sought together with each fact supporting the claim for relief.
- 705.D.** No appeal form or any amendment thereto shall be deemed filed unless and until the applicable fee is paid, the form is properly completed and all necessary signatures are applied. Any failure to comply with the requirements of this subsection may lead to the rejection of the appeal or amendment as determined by the Township Zoning Officer.

705.E. By executing the appeal form and any amendment thereto, every applicant verifies that to the best of his or her knowledge, information and belief each fact alleged is true and correct, and that there exists a good faith basis for the requested relief.

Section 706 Time Limitations

No person shall be allowed to file any proceeding with the Zoning Hearing Board later than thirty (30) days after the issuance of a notice of violation or similar determination by the Township or Zoning Officer, or later than thirty (30) days after the application for development, preliminary or final, has been approved or denied by the Zoning Officer or the agency responsible for granting such approval if such proceeding is designed to secure reversal or to limit the approval in any manner unless such person alleges and proves that he had no notice or knowledge, or reason to believe that such approval had been given. If such person has succeeded to his interest after such approval, he shall be bound by the knowledge of his predecessor in interest.

The failure of anyone other than the landowner to appeal from an adverse decision by the Zoning Officer on a challenge to the validity of this Ordinance or the Official Zoning Map pursuant to Section 916.2 of the Act, shall preclude an appeal from a final approval except in the case where the final submission substantially deviates from the approved tentative preliminary approval.

Section 707 Stay of Proceeding

Upon filing of any proceeding referred to in Section 705 and during its pendency before the Zoning Hearing Board, all land development pursuant to any challenged Ordinance, order or approval of the Zoning Officer or of any agency or body, and all official action thereunder, shall be stayed unless the Zoning Officer or any other appropriate agency or body certifies to the Zoning Hearing Board facts indicating that such stay would cause imminent peril to life or property, in which case, the development or official action shall not be stayed otherwise than by a restraining order, which may be granted by the Zoning Hearing Board or by the court having jurisdiction of zoning appeals on petition after notice to the Zoning Officer or other appropriate agency or body. When an application for development, preliminary or final, has been duly approved and proceedings designed to reverse or limit the approval are filed with the Zoning Hearing Board by persons other than the applicant, the applicant may petition the court having jurisdiction of zoning appeals to order such persons to post bond as a condition to continuing the proceedings before the Zoning Hearing Board. After the petition is presented, the court shall hold a hearing to determine if the filing of the appeal is frivolous. At the hearing evidence may be presented on the merits of the case. It shall be the burden of the applicant for a bond to prove the appeal is frivolous. After consideration of all evidence presented, if the court determines that the appeal is frivolous it shall grant the petition for a bond. The right to petition the court to order the appellants to post bond may be waived by the appellee but such waiver may be revoked by him if an appeal is taken from a final decision of the court. The question whether or not such petition should be granted and the amount of the bond shall be within the sound discretion of the court. An order denying a petition for bond shall be interlocutory. An order directing the responding party to post a bond shall be interlocutory.

If an appeal is taken by a respondent to the petition for a bond from an order of the court dismissing a zoning appeal for refusal to post a bond and the appellate court sustains the order of the court below to post a bond, the respondent to the petition for a bond, upon motion of the petitioner and after hearing in the court having jurisdiction of zoning appeals, shall be liable for all reasonable costs, expenses, and attorney fees incurred by the petitioner.

Section 708 Appeal

Any person, taxpayer, or the Township aggrieved by any decision of the Zoning Hearing Board may within thirty (30) days after such decision of the Zoning Hearing Board seek review by the Court of Common Pleas of such decision in the manner provided by the laws of the Commonwealth of Pennsylvania and Article X-A of the Act.

Section 709 Mediation Option

709.A. Parties to proceedings before the Zoning Hearing Board may utilize mediation as an aid in completing such proceedings. In no case shall the Zoning Hearing Board, initiate, mediate or participate as a mediating party. Mediation shall supplement, not replace, those procedures in this Article 7 once they have been formally initiated.

709.B. Participation in mediation shall be wholly voluntary. The appropriateness of mediation shall be determined by the particulars of each case and the willingness of the parties to negotiate. The Township shall assure that, in each case, the mediating parties, assisted by the mediator as appropriate, develop terms and conditions for:

1. Funding mediation;
2. Selecting a mediator who, at a minimum, shall have a working knowledge of municipal zoning and subdivision procedures and demonstrated skills in mediation;
3. Completing mediation, including time limits for such completion.
4. Suspending time limits otherwise authorized by the Act, provided there is written consensus by the mediating parties, and by an applicant or municipal decision-making body if either is not a party to the mediation;
5. Identifying all parties and affording them the opportunity to participate;
6. Subject to legal restraints, determining whether some or all of the mediation sessions shall be open or closed to the public;
7. Assuring that mediated solutions are in writing and signed by the parties, and become subject to review and approval by the appropriate decision-making body pursuant to the authorized procedures set forth in the Act:

709.C. No offers or statements made in the mediation sessions, excluding the final written mediated agreement, shall be admissible as evidence in any subsequent judicial or administrative proceedings.

Article 8

Administration

Section 800 Zoning Officer

The provisions of this Ordinance shall be enforced by an agent, to be appointed by the Board of Supervisors, who shall be known as the Zoning Officer. He/she shall receive such fees or compensation as approved by resolution of the Board of Supervisors. The Zoning Officer shall not hold any elective office within the Township. No zoning permit or Certificate of Zoning Compliance shall be granted by him/her for any purpose, except in compliance with the literal provisions of this Ordinance. The Zoning Officer is authorized to institute civil enforcement proceedings as a means of enforcement when acting within his/her scope of employment;

800.A. DUTIES & RESPONSIBILITIES

The duties and the responsibilities of the Zoning Officer shall be:

1. Process Applications - To receive, examine and process all Zoning Permit and Certificate of Zoning Compliance applications as provided by the terms of this Ordinance. The Zoning Officer shall also issue zoning permits for special exception and conditional uses, or for variances after the same have been approved.
2. Maintain Official Records - To maintain and be responsible for all pertinent records on zoning matters in the Township. These records shall include, but not be limited to, all applications received, copies of all Zoning Permits and Certificate of Zoning Compliance issued, copies of orders and findings of the Zoning Hearing Board, written complaints of alleged violations, records of all inspections made, a current copy of the Zoning Ordinance, and all amending ordinances, the official Zoning Map, and all other pertinent information. To the extent required by law, the records of this office shall be available for the use of the Township government and for inspection of any interested party during normal office hours. The Zoning Officer shall at least annually submit to the Board of Supervisors a written statement of all Permits and Certificate of Zoning Compliance issued and violations and stop-work orders recommended or promulgated.
3. Inspections - Before issuing any Zoning Permit or Certificate of Zoning Compliance at his/her discretion, to inspect or cause to be inspected all buildings, structures, signs, or land and portions thereof for which an application has been filed for a Zoning Permit or a Certificate of Zoning Compliance. Thereafter, he/she may make such inspections during the completion of the work for which a Zoning Permit has been issued. Upon completion of such work and before issuing a Certificate of Zoning Compliance, a final inspection shall be made and all violations of the approved plans or Zoning Permit shall be noted and the holder of the Zoning Permit shall be notified of the discrepancies.
4. Inspect and/or Register Nonconformities - Upon request by a landowner and/or the direction of the Board of Supervisors, to inspect nonconforming uses, structures and lots, and to keep a filed record of such nonconforming uses and structures, together with the reasons why the Zoning Officer identified them as nonconformities, as a public record and

to examine them periodically, with the view of eliminating the nonconforming uses under the existing laws and regulations.

5. Assist Local Officials - Upon the request of the Board of Supervisors or the Zoning Hearing Board, present to such bodies facts, records, and any similar information on specific requests, to assist such bodies in reaching their decisions.
6. Maintain Up-to-Date Ordinance - To be responsible for keeping this Ordinance and the Official Zoning Map up-to-date, including any amendments thereto;
7. Floodplain Variance Reporting - Upon the granting by the Zoning Hearing Board of a variance pertaining to Chapter 92 (Floodplain Management) of the Code of Dickinson Township, the Zoning Officer shall notify the applicant in writing within fifteen (15) days that:
 - a. The granting of the variance may result in increased premium rates for flood insurance;
 - b. Such variances may increase the risks to life and property.
8. Floodplain Report to DCED - Upon the approval by the Zoning Hearing Board of a special exception, or upon the approval of a conditional use by the Board of Supervisors for development located within a Floodplain as regulated by Chapter 92 (Floodplain Management) of the Code of Dickinson Township, to send written notice of the approval by registered mail to the Pennsylvania Department of Community and Economic Development.
9. Biannual Report to FIA - To remain eligible for the National Flood Insurance Program, the Zoning Officer shall submit a biannual report to the Federal Insurance Administration concerning the status of the Program in the Township (the report form shall be provided by the Federal Insurance Administration).
10. Preliminary Opinion - To render a preliminary opinion regarding a proposed land use in accordance with Section 916.2. of the Act.
11. Investigate Complaints - When in receipt of a written non-anonymous complaint stating fully the cause and basis thereof, to investigate alleged violations of this Ordinance. Said investigation shall be completed within thirty (30) days of said complaint. A written report of all investigations of this Ordinance shall be prepared and filed by the Zoning Officer. If after the investigation the Zoning Officer determines that a violation has occurred, he/she shall take action as provided for by this Ordinance.
12. Prosecute Violations - To institute civil enforcement proceedings as a means of enforcement when anyone undertakes deliberate actions that are contrary to the terms of the Ordinance, and any conditions placed upon the approval of special exceptions, variances and conditional uses or any other approvals authorized under this Ordinance.

800.B. VIOLATIONS

Failure to secure a zoning permit prior to a change in use of land or structure, or the erection, construction or alteration of any structure or portion thereof, shall be a violation of this Ordinance. Failure to obtain a certificate of zoning compliance in accordance with the requirements of Section 802 of this Ordinance shall be a violation of this Ordinance. It shall also be a violation of this Ordinance to undertake other deliberate actions which are contrary to the terms of the Ordinance, and any conditions placed upon the approval of special exceptions, variances and conditional uses. Each day that a violation is continued shall constitute a separate offense.

800.C. ENFORCEMENT NOTICE

If it appears to the Township that a violation of this Zoning Ordinance, has occurred, the Township shall initiate enforcement proceedings by sending an enforcement notice, as provided in the following:

1. The enforcement notice shall be sent to the owner of record of the parcel on which the violation has occurred, to any person who has filed a written request to receive enforcement notices regarding that parcel, and to any other person requested in writing by the owner of record.
2. An enforcement notice shall state at least the following:
 - a. The name of the owner of record and any other person against whom the Township intends to take action.
 - b. The location of the property in violation.
 - c. The specific violation with a description of the requirements that have not been met, citing in each instance the applicable provisions of the Ordinance.
 - d. The date before which the steps for compliance must be commenced and the date before which the steps must be completed.
 - e. That the recipient of the notice has the right to appeal to the Zoning Hearing Board within a prescribed period of time in accordance with procedures set forth under Section 704.E. of this Ordinance.
 - f. That failure to comply with the notice within the time specified, unless extended by appeal to the Zoning Hearing Board, constitutes a violation, with possible sanctions clearly described.

800.D. ENFORCEMENT REMEDIES

Any person, partnership or corporation who, or which, has violated or permitted the violation of the provisions of this Zoning Ordinance enacted under the Act, or prior enabling laws, shall, upon being found liable therefor in a civil enforcement proceeding commenced by the Township, pay a judgment of not more than \$500, plus all court costs, including reasonable attorney fees incurred by the Township as a result thereof. No judgment shall commence or be imposed, levied or be payable until the date of the determination of a violation by the district justice. If the defendant neither pays, nor timely appeals, the judgment, the Township may enforce the judgment pursuant to the applicable rules of civil procedure. Each day that a violation continues shall constitute a separate violation, unless the district justice, determining that there has been a violation, further determines that there was a good-faith basis for the person, partnership or corporation violating the Ordinance to have believed that there was no such violation, in which event there shall be deemed to have been only one such violation, until the fifth day following the date of the determination of a violation by the district justice, and thereafter each day that a violation continues shall constitute a separate violation. All judgments, costs and reasonable attorney fees collected for the violation of the Zoning Ordinance shall be paid over to the Township.

800.E. CAUSES OF ACTION

In case any building, structure, landscaping, or land is, or is proposed to be, erected, constructed, reconstructed, altered, converted, maintained, or used in violation of this Ordinance enacted under the Act, or prior enabling laws, the governing body or, with the approval of the governing body, an

officer of the municipality, or any aggrieved owner or tenant of real property who shows that his/her property or person will be substantially affected by the alleged violations, in addition to other remedies, may institute any appropriate action or proceeding to prevent, restrain, correct, or abate such building, structure, landscaping, or land, or to prevent, in or about such premises, any act, conduct, business, or use constituting a violation. When any such action is instituted by a landowner or tenant, notice of that action shall be served upon the municipality at least thirty (30) days prior to the time the action is begun, by serving a copy of the complaint on the governing body of the municipality. No such action may be maintained until such notice has been given.

Section 801 Zoning Permits

801.A. GENERAL REQUIREMENTS FOR ZONING PERMITS:

1. Actions Requiring Zoning Permits - A zoning permit shall be required prior to:
 - a. a change in use of land or structure,
 - b. the erection or construction of a structure (principal or accessory) or portion thereof, including, but not limited to, fences but excluding satellite dish antennas that are less than one (1) meter in diameter;
 - c. the improvement or alteration of any existing structure (principal or accessory) where such improvement or portion thereof increases the amount of space which the structure encloses;
 - d. the alteration or development of any improved or unimproved real estate, including, but not limited to, mining, dredging, filling, grading, paving, excavation, or drilling operations but not including the tilling of soil associated with agriculture;
 - e. the erection or alteration of any signs specified in Section 322 of this Ordinance as requiring a zoning permit;
 - f. the construction or installation of animal waste impoundments, lakes, ponds, dams, or other water retention basins; and/or,
 - g. the conduct of any forestry use;
 - h. For uses other than a single-family dwelling or agricultural:
 - i. The installation of a new outdoor lighting system;
 - ii. The alteration, rehabilitation, or renovation to an existing outdoor lighting installation, which is commenced after the effective date of this Ordinance, and involves the complete replacement of an existing lighting system with a new lighting system and,
 - iii. The replacement of an outdoor light fixture that existed on the effective date of this Ordinance.
2. Permit Exemptions - No zoning permit shall be required for repairs or maintenance of any structure or land provided such repairs do not change the use or the exterior dimensions of the structure, or otherwise violate the provisions of this Ordinance.
3. Form of Application - Application for zoning permits shall be made in writing to the Zoning Officer. Two (2) copies of the application including a plot plan for a Zoning Permit shall be submitted in such form as the Zoning Officer may prescribe.

4. Permit Review Deadline - Such zoning permits shall be issued or rejected within ninety (90) days from date of application.
5. Permit Conformity - No zoning permit shall be issued except in conformity with the regulations of this Ordinance, except after written order from the Zoning Hearing Board or the Courts.
6. Permit Burden of Proof - In all instances in which the Zoning Officer expresses a reasonable doubt as to the ability of a proposed use to meet all the requirements of this Ordinance, it will be incumbent upon the applicant to furnish adequate evidence in support of his/her application. If such evidence is not presented, the zoning permit will be denied.
7. Authorization to Apply - The parcel or parcels shall be in a single and full ownership, or proof of option shall be furnished at the time of application. The full names and addresses of the landowner or developer, and of the responsible officers, if the landowner or developer is a corporate body, shall be stated in the application.
8. Permit Referral - The Zoning Officer may call upon other Township staff and/or Township-appointed consultants in the review of submitted materials for applications.
9. Permit Revocation - The Zoning Officer may revoke a permit or approval issued under the provisions of this Ordinance in case of any false statement or misrepresentation of fact in the application, or on the plans on which the permit or approval was based, or for any other cause set forth in the Zoning Ordinance.
10. Required Permit Fees - No permit shall be issued until the fees prescribed by the Board of Township Supervisors approved by resolution shall be paid to the Zoning Officer. The payment of fees under this Section shall not relieve the applicant or holder of said permit from payment of other fees that may be required by this Ordinance or by any other ordinances or law. The fees collected for the review of a zoning permit include one inspection for Certificate of Zoning Compliance. Should an applicant fail to demonstrate compliance with an approved zoning permit at such inspection, he/she will be required to correct any noted violations and pay another final inspection fee, or submit a new zoning permit application (in compliance with all requirements listed above) along with its fee for each time the Township must inspect the site prior to its final issuance of a Certificate of Zoning Compliance.
11. Issuance / Rejection of Permits - Upon receipt, the Zoning Officer shall examine the permit application within a reasonable time after filing. If the application fails to comply with the provisions of this Ordinance and all pertinent local laws and/or any conditions of approval attached to the grant of any applicable subdivision and/or land development approval, he/she shall reject such application in writing, stating the reasons therefore. Should the Zoning Officer deny the permit, he/she shall inform the applicant of his/her right to appeal to the Zoning Hearing Board under Section 704.E. of this Ordinance. If satisfied that the proposed work and/or use conforms to the provisions of the Zoning Ordinance, and all local laws and ordinances applicable thereto and/or any conditions of approval attached to the grant of any applicable subdivision and/or land development approval,, he/she shall issue a permit therefore as soon as practical, but not later than ninety (90) days from receipt of the complete application.
12. Reconsideration of Application - An applicant whose request for a permit has been denied by the Zoning Officer may make a later application for a permit, provided all deficiencies which were the basis for the prior denial of the permit have been eliminated. The Zoning Officer shall not be required to make a new review of the application if this condition is not met.

13. Expiration of Permit - The permit shall expire after one (1) year from the date of issuance; provided, however, that the same may be extended by the Zoning Officer every six (6) months for a period not to exceed an additional year upon the request by the applicant who can demonstrate good cause for the extension.
14. Compliance with Ordinance - The permit shall be a license to proceed with the work and should not be construed as authority to violate, cancel, or set aside any of the provisions of the Zoning Ordinance, except as stipulated by the Zoning Hearing Board through the issuance of an approved variance under Section 704.D. of this Ordinance.
15. Compliance with Permit and Plot Plan - All work or uses shall conform to the approved application and plans for which the permit has been issued, as well as the approved plot plan.
16. Display of Zoning Permit - All approved zoning permits shall be prominently displayed on the subject property during construction, renovation, reconstruction, repair, remodeling or the conduct of other site improvements. Such permit displays shall occur within five (5) days of permit issuance, or prior to the commencement of actual work on the site, whichever occurs first. Such permit display shall be continuous until the site receives its Certificate of Zoning Compliance.
17. Availability of Zoning Permit - The Zoning Officer shall maintain a copy of all active Zoning Permits for inspection.
18. Compliance with Other Laws - Each application for a zoning permit shall include a written list of all county, state and federal permits and approvals that are required for the initiation of the use of land, buildings or structures. Additionally, the list shall include the following due diligence statement:

“By signature below, the applicant affirms [he/she/it] has in good faith performed a due diligence review of county, state and federal statutes, ordinances, regulations, and requirements to determine the permits and approvals that are required for the proposed use (to be inserted by applicant) of land, building or structure and that [he/she/it] has provided a complete list of such permits and approvals.”

The statement shall be followed by the applicant's signature and the date of signing. Each applicant has an affirmative and continuing duty to supplement this list, as may be necessary from time to time, until issuance of the Certificate of Zoning Compliance. Each supplement shall contain the foregoing due diligence statement, followed by the applicant's signature and date of signing.

19. Temporary Use Permits - It is recognized that it may be in accordance with the purpose of this Ordinance to permit temporary activities for a limited period of time in times of local or national emergency and/or disaster which activities may be prohibited by other provisions of this Ordinance. If such uses are of such a nature and are so located that, at the time of application, they will:
 - a. in no way exert a detrimental effect upon the uses of land and activities normally permitted in the Zone, and,
 - b. contribute materially to the welfare of the Township, particularly in a state of emergency, under conditions peculiar to the time and place involved, then, the Board of Supervisors may direct the Zoning Officer to issue a permit.

801.B. APPLICATION FOR ALL ZONING PERMITS

1. Applications shall contain a general description of the proposed work, development, use or occupancy of all parts of the structure or land, and shall be accompanied by plot plans in duplicate drawn to scale and showing the following as may be applicable to the requested permit:
 - a. The actual dimensions and shape of the lot to be built-upon;
 - b. The exact size and location on the lot of buildings, structures, fences, signs, and areas of land use, existing and/or proposed extensions thereto;
 - c. The number of dwelling units or other units of occupancy (eg. commercial, industrial, institutional, agricultural, accessory uses and etc.) if any, to be provided;
 - d. The location and proposed surfacing of driveways and access drives and copies of any highway occupancy permits as required by local, county and/or state agencies;
 - e. The height of all structures, buildings, and/or signs;
 - f. Distances of buildings and structures from lot lines and street right-of-way lines;
 - g. Off-street parking and loading areas and access thereto, including grades and proposed surfacing;
 - h. Outdoor areas devoted to storage of goods, materials and/or wastes;
 - i. Utility systems affected and proposed, including primary and back-up on-lot and/or public sewage disposal and water supply systems, including any required permits;
 - j. Alteration or development of any improved or unimproved real estate;
 - k. Lot coverage;
 - l. Site lighting plans, including lighting of signs in accordance with the requirements of Section 310 of this Ordinance;
 - m. Floor area devoted to each proposed use and unit of occupancy for both principal and accessory uses;
 - n. Recreation areas;
 - o. Screens, buffer yards, landscaping, erosion control filter strips and riparian buffers;
 - p. Means of pedestrian access;
 - q. Written approvals for needed Conservation Plans, Nutrient Management Plans and/or Erosion and Sediment Pollution Control Plans;
 - r. Information relating to any zoning approvals obtained from the Zoning Hearing Board or the Board of Supervisors;

- s. Proof of approval from the PA Department of Labor and Industry, when required by such agency;
 - t. Copies of any applicable subdivision/land development plan;
 - u. Workers Compensation Certificates;
 - v. Information relating to compliance with the Dickinson Township Stormwater Management Ordinance; and,
 - w. All other information necessary for the Zoning Officer to determine conformance with and provide for enforcement of this Ordinance.
2. If the proposed development, excavation or construction is located within a floodplain as regulated by Chapter 92 of the Code of Dickinson Township, the following information is specifically required to accompany all applications:
 - a. The accurate location of the floodplain and floodway;
 - b. The elevation, in relation to the National Geodetic Vertical Datum of 1929 (NGVD), of the lowest floor, including basements; and
 - c. The elevation, in relation to the NGVD, to which all structures and utilities will be floodproofed or elevated.
 3. Applications involving any excavation or earthmoving involving earth shall be able to demonstrate compliance with, and approval from, the Cumberland County Conservation District, as applicable.
 4. Prior to the application for a zoning permit, the applicant must verify that lot line markers have been accurately installed in accordance with Section 515 of the SALDO.

801.C. APPLICATION FOR ZONING PERMIT FOR USES IN THE MIXED USE, MINING INDUSTRIAL & BUSINESS INDUSTRIAL ZONES

In addition to the preceding requirements for all zoning permits, uses proposed within the Mixed Use, Mining Industrial and Business Industrial Zones shall provide the following information:

1. A location plan showing the tract to be developed, Zone boundaries, adjoining tracts, significant natural features, proposed topographic features, and streets for a distance of two hundred (200) feet from all tract boundaries.
2. A description of the operations proposed in sufficient detail to indicate the effects of those operations in producing traffic congestion, noise, glare, air pollution, water pollution, vibration, fire hazards, safety hazards, or the emission of any potentially harmful or obnoxious matter or radiation.
3. Engineering plans for treatment and disposal of sewage and industrial waste, tailings or unusable by-products.
4. Engineering plans for the handling of traffic, noise, light and glare, air pollution, water pollution, vibration, fire hazards, or safety hazards, smoke, or emission of any potentially harmful or obnoxious matter or radiation.
5. Designation of the manner by which sanitary sewage and storm water shall be disposed and water supply obtained.

6. The proposed number of shifts to be worked and the maximum number of employees on each shift.
7. Where use by more than one firm is anticipated, a list of firms which are likely to be located in the center, their floor area, and estimated number of employees.

Section 802 Certificate of Zoning Compliance

802.A. WHEN REQUIRED

It shall be unlawful to use and/or occupy any structure, building, sign, or land or portion thereof for which a Zoning Permit is required until a Certificate of Zoning Compliance has been issued by the Zoning Officer. The Zoning Officer shall not issue such Certificate unless he/she has inspected said structure, building, sign, or land and has determined that all provisions of the Zoning Ordinance and other laws of the Township have been satisfied and that the applicant has received a Certificate of Occupancy under the Township Building Code, if applicable.

802.B. FORM OF APPLICATION

The application for a Certificate of Zoning Compliance shall be in such form as the Zoning Officer may prescribe, and shall be made at the same time as the application for a Zoning Permit is filed with the Zoning Officer.

802.C. DESCRIPTION OF USE AND OCCUPANCY

The application shall contain a description of the intended use and occupancy of any structure, building, sign, or land or portion thereof for which a Zoning Permit is required herein.

802.D. ACTION UPON APPLICATION

The Zoning Officer shall inspect any structure, building, sign or use of land within fifteen (15) days after notification that the proposed work that was listed under the Zoning Permit has been completed. If he/she is satisfied that:

1. the work is in conformity and compliance with the work listed in the issued Zoning Permit;
2. the work is in conformity and compliance with and all other pertinent local laws; and,
3. that the applicant has received a Certificate of Occupancy under the Township Building Code, if applicable;

he/she shall issue a Certificate of Zoning Compliance for the intended use listed in the approved application. If the Zoning Officer finds that the work has not been performed in accordance with this Ordinance and/or the approved application, the Zoning Officer shall refuse to issue the Certificate of Zoning Compliance and shall give in writing the reasons for such refusal. The Zoning Officer shall inform the zoning permit holder of his/her right of appeal to the Zoning Hearing Board under Section 704.E. of this Ordinance.

The fees collected for the review of a zoning permit include one inspection for Certificate of Zoning Compliance. Should an applicant fail to demonstrate compliance with an approved zoning permit at such inspection, he/she will be required to correct any noted violations and pay another final inspection fee, or submit a new zoning permit application (in compliance with all requirements listed above) along with its fee for each time the Township must inspect the site prior to its final issuance of a Certificate of Zoning Compliance.

802.E. AVAILABILITY OF CERTIFICATE

The Zoning Officer shall maintain a Certificate of Zoning Compliance (or a true copy thereof) for all uses that shall be kept available for inspection at all times.

802.F. TEMPORARY CERTIFICATE OF ZONING COMPLIANCE

It is recognized that it may be in accordance with the purpose of this Ordinance to permit temporary activities for a limited period of time, which activities may be prohibited by other provisions of this Ordinance during times of local or national emergency and/or disaster. If such uses are of such a nature and are so located that, at the time of application, they will:

1. in no way exert a detrimental effect upon the uses of land and activities normally permitted in the Zone, and,
2. contribute materially to the welfare of the Township, particularly in a state of emergency, under conditions peculiar to the time and place involved, then, the Board of Supervisors may direct the Zoning Officer to issue a Certificate of Zoning Compliance for a period not to exceed six (6) months. Such Certificate of Zoning Compliance may be extended not more than once for an additional period of six (6) months.

802.G. PERFORMANCE STANDARDS

For uses that involve activities that are subject to operations and performance standards listed in Sections 310, 313 and 316 of this Ordinance, no Certificate of Zoning Compliance shall become permanent until thirty (30) days after the facility is fully operating and when, upon re-inspection by the Zoning Officer, it is determined that the facility is in compliance with all such standards.

802.H. COMPLIANCE WITH OTHER LAWS

No certificate of zoning compliance shall be issued until such time as the applicant provides evidence that the identified county, state and federal permits and approvals required for the initiation of use of land, building or structure have been obtained. Following the issuance of a certificate of zoning compliance, it is expected that the use of the land, building or structure that is the subject of the certificate shall be conducted in compliance with the zoning permit and all applicable Township, county, Commonwealth of Pennsylvania, and federal statutes, ordinances, regulations, requirements, permits and approvals.

Section 803 Fees

803.A. The Board of Supervisors shall establish by resolution a schedule of fees, charges, and expenses and collection procedures for applications for Zoning Permits, Certificate of Zoning Compliance, special exceptions, conditional uses, variances, appeals, amendments, and other matters pertaining to this Ordinance.

803.B. The schedule of fees shall be available for inspection in the office of the Zoning Officer and may be altered or amended by resolution of the Board of Supervisors.

803.C. Until all application fees, charges, and expenses have been paid in full, the application or appeal shall not be considered complete. Therefore, no proceedings related to any such application or appeal shall be initiated, no established time elements shall begin to accrue, and no action shall be taken on any such application or appeal.

Section 804 Amendments

804.A. POWER OF AMENDMENT

The Board of Supervisors may, from time to time, amend, supplement, change, or repeal this Ordinance, including the Official Zoning Map. Any amendment, supplement, change, or repeal may be initiated by the Township Planning Commission, the Board of Supervisors, or by a petition to the Board of Supervisors by an interested party.

804.B. HEARING AND ENACTMENT PROCEDURES FOR ZONING AMENDMENTS

1. Public Hearing - Before voting on the enactment of Zoning Ordinance and/or Zoning Map amendments, the Board of Supervisors shall conduct a public hearing to inform the general public of the nature of the amendment, and to obtain public comment. Such public hearing shall be conducted after public notice (as defined herein and listed below) has been given.
2. Public Notice - Before conducting a public hearing, the Board of Supervisors shall provide public notice as follows:
 - a. Notice shall be published once each week for two successive weeks in a newspaper of general circulation in the municipality. Such notice shall state the time and place of the hearing and the particular nature of the matter to be considered at the hearing. The first publication shall not be more than thirty (30) days, and the second publication shall not be less than seven (7) days from the date of the hearing. Publication of the proposed amendment shall include either the full text thereof or the title and brief summary, prepared by the municipal solicitor and setting forth all the provisions in reasonable detail. If the full text is not included:
 - i. A copy of the full text shall be supplied to a newspaper of general circulation in the municipality at the time the public notice is published; and,
 - ii. An attested copy of the proposed Ordinance shall be filed in the County Law Library, or other County office designated by the County Commissioners, who may impose a fee no greater than that necessary to cover the actual costs of storing said Ordinances.
 - b. For Zoning Map amendments, public notice shall also include the Township posting of a sign or signs at one or more conspicuous locations deemed sufficient by the Township. This sign(s) shall be posted at least one (1) week prior to the hearing and will exhibit the nature, date, time, and location of the hearing. The sign posting requirement shall not apply when the rezoning constitutes a comprehensive rezoning. In addition, notice of the public hearing shall be sent by first class mail by the municipality at least thirty (30) days prior to the date of the public hearing by first class mail to the addressees to which real estate tax bills are sent for all real property located within the area to be rezoned, as evidenced by the tax records within possession of the Township. Such notice shall include the location, date and time of the public hearing. The first class mail notice requirement shall not apply when the rezoning constitutes a comprehensive rezoning.
 - c. For curative amendments, public notice shall also indicate that the validity of the Ordinance and/or map is in question, and shall give the place where, and the times when, a copy of the request, including any plans, explanatory material or proposed amendments, may be examined by the public.
 - d. If, after any public hearing held upon an amendment, the proposed amendment is

changed substantially, or is revised, to include land previously not affected by it, the governing body shall hold another public hearing, pursuant to public notice, mailed notice and electronic notice before proceeding to vote on the amendment.

3. Enactment Notice - In addition to the public notice requirements defined herein, the Board of Supervisors must publish a reference to the time and place of the meeting at which passage of the Ordinance or amendment will be considered, and a reference to a place within the municipality where copies of the proposed Ordinance or amendment may be examined without charge, or obtained for a charge not greater than the cost thereof. Enactment notice shall be published at least once in one newspaper of general circulation in the municipality not more than sixty (60) days, nor less than seven (7) days, prior to passage. The published content of the enactment notice shall be the same as that required for public notice described in the preceding Section 804.B.2.
4. Township Planning Commission Referrals - For amendments proposed by parties other than the Township Planning Commission, the Board of Supervisors shall submit each amendment to the Township Planning Commission at least forty-five (45) days prior to the public hearing on such amendment. A report of the review by the Township Planning Commission, together with any recommendations, may be given to the Board of Supervisors within forty-five (45) days from the date of said referral. The recommendation of the Township Planning Commission may include a specific statement as to whether or not the proposed action is in accordance with the intent of this Ordinance and the Official Comprehensive Plan of the Township.
5. Cumberland County Planning Department Referrals - All proposed amendments shall be submitted to the Cumberland County Planning Department at least forty-five (45) days prior to the public hearing on such amendments. The Department may submit recommendations to the Board of Supervisors; however, if the Cumberland County Planning Department fails to act within forty-five (45) days, the Board of Supervisors may proceed without its recommendations.
6. Adjournment of Public Hearing – If, during the public hearing process, the Board of Supervisors needs additional time to understand the proposal, inform the public, receive public comment, and/or render a decision, it may adjourn the public hearing to a time and place certain.
7. Copies of Adopted Amendments - Within thirty (30) days after enactment, a copy of the amendment to the Zoning Ordinance and/or Zoning Map shall be forwarded to the Cumberland County Planning Commission.
8. Authentication of the Official Zoning Map - Whenever there has been a change in the boundary of a Zone or a reclassification of the Zone adopted, the change on the Official Zoning Map shall be made and shall be duly certified by the Township Secretary and shall thereafter be re-filed as part of the permanent records of the Township.

804.C. AMENDMENT INITIATED BY THE TOWNSHIP PLANNING COMMISSION

When an amendment, supplement, change, or repeal is initiated by the Township Planning Commission, the proposal shall be presented to the Board of Supervisors, which shall then proceed in the same manner as with a petition to the Board of Supervisors, which has already been reviewed by the Township Planning Commission;

804.D. AMENDMENT INITIATED BY THE BOARD OF SUPERVISORS

When an amendment, supplement, change, or repeal is initiated by the Board of Supervisors, such amendment, supplement, change or repeal shall follow the procedure prescribed for a petition under Section 804.B.;

804.E. AMENDMENT INITIATED BY A PETITION FROM AN INTERESTED PARTY

A petition for amendment, supplement, change, or repeal for a portion of this Ordinance shall include an accurate legal description and surveyed plan of any land to be rezoned, and all of the reasons supporting the petition to be considered. The petition shall also be signed by at least one record owner of the property in question whose signature shall be notarized attesting to the truth and correctness of all the facts and information presented in the petition. A fee to be established by the Board of Supervisors shall be paid upon the filing of such petition for change and for the purpose of defraying the costs of the proceedings prescribed herein. The Board of Supervisors may require duplicate sets of petition materials;

804.F. CURATIVE AMENDMENT BY A LANDOWNER

A landowner, who desires to challenge on substantive grounds the validity of the Ordinance or the Official Zoning Map, or any provision thereof, which prohibits or restricts the use or development of land in which he/she has an interest, may submit a curative amendment to the Board of Supervisors (including all of the reasons supporting the request to be considered), with a written request that his/her challenge and proposed amendment be heard and decided, as provided in Sections 609.1 and 916.1 of the Act; as amended. The Board of Supervisors shall commence a hearing thereon within sixty (60) days of the request. The curative amendment shall be referred to the Township and Cumberland County Planning Commission, as provided for in Section 804.B., and public notice of the hearing shall be provided as defined herein.

1. In reviewing the curative amendment, the Board of Supervisors may deny the request, accept the request as submitted, or may adopt an alternative amendment which will cure the challenged defects. The governing body shall consider the curative amendments, plans and explanatory material submitted by the landowner and shall also consider;
 - a. The impact of the proposal upon roads, sewer facilities, water supplies, schools, and other public service facilities;
 - b. If the proposal is for a residential use, the impact of the proposal upon regional housing needs, and the effectiveness of the proposal in providing housing units of a type actually available to, and affordable by, classes of persons otherwise unlawfully excluded by the challenged provisions of the Ordinance or Map;
 - c. The suitability of the site for the intensity of use proposed by the site's soils, slopes, woodland, wetlands, floodplains, aquifers, natural resources, and other natural features;
 - d. The impact of the proposed use on the site's soils, slopes, woodlands, wetlands, floodplains, natural resources, and natural features, the degree to which these are protected or destroyed, the tolerance of the resources to development, and any adverse environmental impacts; and,
 - e. The impact of the proposal on the preservation of agriculture and other land uses which are essential to public health and welfare.
 - f. For challenges alleging the exclusion of one or more land uses within the Township, the Board shall consider the availability of uses permitted throughout the Township.

2. The governing body shall render its decision within forty-five (45) days after the conclusion of the last hearing.
3. If the governing body fails to act on the landowner's request within the time limits referred to in Section 804.F.2., a denial of the request is deemed to have occurred on the 46th day after the close of the last hearing.
4. Public notice of the hearing shall include notice that the validity of the Ordinance or map is in question and shall give the place where, and the times when, a copy of the request, including any plans, explanatory material, or proposed amendments may be examined by the public.
5. The challenge shall be deemed denied when:
 - a. The governing body fails to commence the hearing within sixty (60) days;
 - b. The governing body notifies the landowner that it will not adopt the curative amendment;
 - c. The governing body adopts another curative amendment which is unacceptable to the landowner; or
 - d. The governing body fails to act on the request forty-five (45) days after the close of the last hearing on the request, unless the time is extended by mutual consent by the landowner and municipality.
6. Where, after the effective date of the Act, a curative amendment proposal is approved by the grant of a curative amendment application by the governing body pursuant to this Section, or a validity challenge is sustained by the Zoning Hearing Board pursuant to Section 704.A., or the court acts finally on appeal from denial of a curative amendment proposal or a validity challenge, and the proposal or challenge so approved requires a further application for subdivision or land development, the developer shall have two years from the date of such approval to file an application for preliminary or tentative approval for a subdivision, land development or planned residential development. Within the two-year period, no subsequent change or amendment in the zoning, subdivision or other governing ordinance or plan shall be applied in any manner which adversely affects the rights of the applicant, as granted in the curative amendment or the sustained validity challenge. Upon the filing of the preliminary or tentative plan, the provisions of Section 508 (4) of the Act shall apply.
7. Where the proposal appended to the curative amendment application or the validity challenge is approved but does not require further application under any subdivision or land development ordinance, the developer shall have one year within which to file for a zoning permit. Within the one-year period, no subsequent change or amendment in the zoning, subdivision or other governing ordinance or plan shall be applied in any manner which adversely affects the rights of the applicant, as granted in the curative amendment or the sustained validity challenge. During these protected periods, the court shall retain or assume jurisdiction for the purpose of awarding such supplemental relief as may be necessary;

804.G. CURATIVE AMENDMENT BY THE BOARD OF SUPERVISORS

1. The Board of Supervisors, by formal action, may declare this Ordinance, or portions thereof, substantively invalid and propose to prepare a curative amendment to overcome such invalidity. Within thirty (30) days following such declaration and proposal, the Board of

Supervisors shall:

- a. By resolution, make specific findings setting forth the declared invalidity of the Ordinance or portions thereof, which may include:
 - i. references to specific uses which are either not permitted or not permitted in sufficient quantity.
 - ii. references to a class of use or uses which require revision; or,
 - iii. references to the entire Ordinance which requires revisions.
 - b. Begin to prepare and consider a curative amendment to the Ordinance to correct the declared invalidity.
2. Within one hundred eighty (180) days from the date of the declaration and proposal, the Board of Supervisors shall enact a curative amendment to validate, or reaffirm the validity of, this Ordinance pursuant to the provisions required by Section 609 of the Act in order to cure the declared invalidity of the Ordinance.
 3. Upon the date of the declaration and proposal, the Board of Supervisors shall not be required to entertain or consider any curative amendment filed by a landowner. Nor shall the Zoning Hearing Board be required to give a report, upon request, for a challenge to the validity of the Ordinance under Section 704.A., subsequent to the declaration and proposal, based upon the grounds identical to, or substantially similar to, those specified in the resolution required by this Section. Upon the enactment of a curative amendment to, or the reaffirmation of the validity of, this Ordinance, no rights to a cure by amendment or challenge shall, from the date of the declaration and proposal, accrue to any landowner on the basis of the substantive invalidity of the unamended Zoning Ordinance for which the Board of Supervisors propose to prepare a curative amendment.
 4. The Board of Supervisors, having utilized the procedures as set forth in this Section, may not again utilize said procedures for a thirty-six (36) month period following the date of the enactment of a curative amendment, or reaffirmation of the validity of the Ordinance; provided, however, that, if after the date of declaration and proposal, there is a substantially new duty or obligation imposed upon the Township by virtue of a Pennsylvania Appellate Court decision, the Board of Supervisors may utilize the provisions of this Section to prepare a curative amendment to the Ordinance to fulfill this duty or obligation.

Section 805 Conditional Uses

805.A. FILING OF CONDITIONAL USE

For any use permitted by conditional use, a conditional use must be obtained from the Board of Supervisors. No conditional use application will be accepted which requires approval for any use or relief by the Zoning Hearing Board until such times as such approvals have been secured. If during the course of review of the conditional use it is determined that the proposed use requires approval for any use or relief by the Zoning Hearing Board, the application shall be either withdrawn by the applicant or may be denied by the Board of Supervisors. In addition to the information required on the zoning permit application, the conditional use application must show:

1. Ground floor plans and elevations of proposed structures.
2. Names and addresses of adjoining property owners, including properties directly across a public right-of-way.

3. A scaled drawing (site plan) of the site including finished topography with sufficient detail and accuracy to demonstrate compliance with all applicable provisions of this Ordinance, including competent evidence demonstrating a substantial likelihood of compliance with the requirements of Article 5 of this Ordinance; and,
4. A written description of the proposed use in sufficient detail to demonstrate compliance with all applicable provisions of this Ordinance, including competent evidence demonstrating a substantial likelihood of compliance with the requirements of Article 5 of this Ordinance.

805.B. GENERAL CRITERIA

Each applicant must demonstrate compliance with the following:

1. The proposed use shall be consistent with the purpose and intent of the Zoning Ordinance and such use is specifically authorized as a use by conditional use within the Zone wherein the applicant seeks approval;
2. The proposed use shall not detract from the use and enjoyment of adjoining or nearby properties;
3. The proposed use will not substantially change the character of the subject property's neighborhood nor adversely affect the character of the general neighborhood, the conservation of property values, the health and safety of residents or workers on adjacent properties and in the neighborhood, nor the reasonable use of neighboring properties. The use of adjacent properties shall be adequately safeguarded;
4. Adequate public facilities are available to serve the proposed use and the proposed use shall not have an adverse effect upon the logical and economic extension of such public services and facilities, (e.g., schools, parks and recreation, fire, police and ambulance protection, sewer, water and other utilities, vehicular access, etc.);
5. Such use shall be sized, located and designed so that no undue traffic congestion or safety hazards will be created. The surrounding streets shall be sufficient to accommodate any expected increase in traffic generated by the proposed use. There shall be control of development of highway frontage so as to limit the number of points for vehicular access and consideration of their location with regard to vehicular and pedestrian safety. Where appropriate and practicable, joint use of shared access drives along major highways shall be encouraged.
6. The applicant shall establish by credible evidence that the proposed conditional use shall be in and of itself properly designed with regard to internal circulation, off-street parking, off-street loading, landscaping, screening, buffering, and all other elements of proper design as specified in this Ordinance and any other governing law or regulation.
7. For development within a floodplain, that the application complies with those requirements listed in Chapter 92 of the Code of Dickinson Township;
8. The proposed use demonstrates a substantial likelihood of compliance with the requirements of Article 5 of this Ordinance.
9. The proposed use shall comply with those criteria specifically listed in Article 4 of this Ordinance. In addition, the proposed use must comply with all other applicable regulations contained in this Ordinance; and,
10. The proposed use will not substantially impair the integrity of the Comprehensive Plan.

805.C. CONDITIONS

The Board of Supervisors, in approving conditional use applications, may attach conditions considered necessary to protect the public welfare and the purposes listed above, including conditions which are more restrictive than those established for other uses in the same Zone. These conditions shall be enforceable by the Zoning Officer, and failure to comply with such conditions shall constitute a violation of this Ordinance and be subject to the penalties described in this Article.

805.D. SITE PLAN APPROVAL

Any site plan presented in support of the conditional use pursuant to Section 805.A.3. shall become an official part of the record for said conditional use. Approval of any conditional use will also bind the use in accordance with the submitted site plan; therefore, should a change in the site plan be required as part of the approval of the use, the applicant shall revise the site plan prior to the issuance of a zoning permit. Except in the case of granted minor changes in accordance with Section 805.G. of this Ordinance, any subsequent change on the subject property not reflected on the originally approved site plan, shall require the obtainment of another conditional use approval.

805.E. HEARING PROCEDURES:

1. Before voting on the approval of a conditional use, the Board of Supervisors shall hold a public hearing thereon, pursuant to public notice. If, after any public hearing held upon an application, the proposed application is revised, the Board of Supervisors or hearing officer shall hold another public hearing, pursuant to public notice, before proceeding to vote on the application. As an alternative the Board of Supervisors may appoint any one of its members or an independent attorney to act as a hearing officer. The decision, or, where no decision is called for, the findings shall be made by the Board however, the appellant or the applicant, as the case may be, in addition to the municipality, may, prior to the decision of the hearing, waive decision or findings by the Board and accept the decision or findings of the hearing officer as final;
2. The Board of Supervisors shall submit each such application to the Township Planning Commission at least thirty (30) days prior to the hearing on such application to provide the Township Planning Commission an opportunity to submit recommendations;
3. Public notice as defined herein, and written notice shall be given to the applicant, the Zoning Officer, such other persons as the Board of Supervisors shall designate by Ordinance, and to any person who has made timely request for the same. Written notices shall be given at such time and in such manner as shall be prescribed by Ordinance or, in the absence of Ordinance provision, by rules of the Board of Supervisors. In addition to the written notice provided herein, written notice of said hearing shall be conspicuously posted on the affected tract of land at least one (1) week prior to the hearing and will exhibit the nature, date, time, and location of the hearing;
4. The first hearing before the Board or hearing officer shall commence within sixty (60) days from the date of receipt of the applicant's application, unless the applicant has agreed in writing to an extension of time. Each subsequent hearing before the Board or hearing officer shall be held within forty-five (45) days of the prior hearing, unless otherwise agreed to by the applicant in writing or on the record. An applicant shall complete the presentation of his case-in-chief within one hundred (100) days of the first hearing. Upon the request of the applicant, the Board or hearing officer shall assure that the applicant receives at least seven (7) hours of hearings within the one hundred (100) days, including the first hearing. Persons opposed to the application may, upon the written consent or consent on the record by the applicant and municipality, be granted additional hearings to complete their opposition to the application provided the applicant

- is granted an equal number of additional hearings for rebuttal;
5. The Board of Supervisors may prescribe reasonable fees with respect to hearings. Fees for said hearings may include compensation for the secretary, notice and advertising costs, and necessary administrative overhead connected with the hearing. The costs, however, shall not include legal expenses, expenses for engineering, architectural, or other technical consultants, or expert witness costs;
 6. The parties to the hearing shall be the Township, any person affected by the application who has made timely appearance of record before the Board of Supervisors or hearing officer, and any other person, including civic or community organizations permitted to appear by the Board of Supervisors or hearing officer. The Board of Supervisors or hearing officer shall have power to require that all persons who wish to be considered parties enter appearances in writing on forms provided by the Board of Supervisors or hearing officer for that purpose;
 7. The Chairman or Acting Chairman of the Board of Supervisors or hearing officer shall have power to administer oaths and issue subpoenas to compel the attendance of witnesses and the production of relevant documents and papers, including witnesses and documents requested by the parties;
 8. The parties shall have the right to be represented by counsel and shall be afforded the opportunity to respond and present evidence and argument and cross-examine adverse witnesses on all relevant issues;
 9. Formal rules of evidence shall not apply, but irrelevant, immaterial, or unduly repetitious evidence may be excluded;
 10. The Board of Supervisors or hearing officer may keep a stenographic record of the proceedings. The appearance fee for a stenographer shall be shared equally by the applicant and the Board of Supervisors. The cost of the original transcript shall be paid by the Board of Supervisors if the transcript is ordered by the Board of Supervisors or hearing officer; or shall be paid by the person appealing the decision of the Board of Supervisors or hearing officer if such appeal is made, and in either event, the cost of additional copies shall be paid by the person requesting such copy or copies. In other cases, the party requesting the original transcript shall bear the cost thereof;
 11. The Board of Supervisors or hearing officer shall not communicate, directly or indirectly, with any party or his/her representative in connection with any issue involved except upon notice and opportunity for all parties to participate, shall not take notice of any communication, reports, staff memoranda, or other materials, except advice from their solicitor, unless the parties are afforded an opportunity to contest the material so noticed and shall not inspect the site or its surroundings after the commencement of hearings with any party or his/her representative unless all parties are given an opportunity to be present;
 12. The Board of Supervisors or the hearing officer, as the case may be, shall render a written decision or, when no decision is called for, make written findings on the conditional use application within forty-five (45) days after the last hearing before the Board of Supervisors. However, the applicant and the municipality, may, prior to the decision of the hearing, waive the decision or findings by the Board of Supervisors and accept the decision or findings of the hearing officer as final. Where the application is contested or denied, each decision shall be accompanied by findings of fact or conclusions based thereon, together with any reasons therefor. Conclusions based on any provisions of this act or of any ordinance, rule or regulation shall contain a reference to the provision relied on and the reasons why the conclusion is deemed appropriate in the light of the facts found. If the hearing is conducted by a hearing officer, and there has been no stipulation that his decision or findings are final, the Board shall make the hearing officer's report and recommendations available to the

parties within forty-five (45) days and the parties shall be entitled to make written representations thereon to the Board prior to final decision or entry of findings, and the Board's decision shall be entered no later than thirty (30) days after the report of the hearing officer;

13. Where the Board of Supervisors or hearing officer fails to render the decision within the period required by this subsection, or fails to commence the required hearing within sixty (60) days from the date of the applicant's request for a hearing, or fails to complete the hearing no later than one hundred (100) days after completion of the applicant's case in chief, unless extended for good cause upon application to the Court of Common Pleas, the decision shall be deemed to have been rendered in favor of the applicant, unless the applicant has agreed in writing or on the record to an extension of time. When a decision has been rendered in favor of the applicant because of the failure of the Board of Supervisors or hearing officer to meet or render a decision as hereinabove provided, the Board of Supervisors or hearing officer shall give public notice of the decision within ten (10) days from the last day it could have met to render a decision in the same manner as required by the public notice requirements of this act. If the Board of Supervisors or hearing officer shall fail to provide such notice, the applicant may do so. Nothing in this subsection shall prejudice the right of any party opposing the application to appeal the decision to a court of competent jurisdiction; and,
14. A copy of the final decision or, where no decision is called for, of the findings, shall be delivered to the applicant personally, or mailed to him/her no later than the day following its date. To all other persons who have filed their name and address with the Board not later than the last day of the hearing, the Board shall provide by mail or otherwise, brief notice of the decision or findings and a statement of the place at which the full decision or findings may be examined.

805.F. TIME LIMITATION:

1. For uses that do not require subsequent subdivision and/or land development approval:
 - a. If a conditional use is granted, the necessary zoning permit shall be secured and the authorized action begun within six (6) months after the date when the conditional use is finally granted, and the building or alteration, as the case may be, shall be completed within two (2) years of said date. For good cause, the Board of Supervisors may upon application in writing, state the reasons therefore and extend either the six (6) months or two (2) year period;
 - b. Should the appellant or applicant fail to obtain the necessary permits within said six (6) months period, or having obtained the permit should he fail to commence work thereunder within such two (2) year period, it shall be conclusively presumed that the appellant or applicant has waived, withdrawn, or abandoned his conditional use application, and all approvals granted to him shall be deemed automatically rescinded by the Board of Supervisors; and,
 - c. Should the appellant or applicant commence construction or alteration within said six (6) months period, but should he fail to complete such construction or alteration within said two (2) year period, the Board of Supervisors may, upon ten (10) days notice in writing, rescind or revoke the conditional use, if the Board of Supervisors finds that no good cause appears for the failure to complete within such two (2) year period, and if the Board of Supervisors further finds that conditions have so altered or changed in the interval since the granting of the conditional use, that revocation or rescission of the action is justified.
2. For uses that require subsequent subdivision and/or land development approval:

- a. If a conditional use is granted, the applicant shall be required to submit the subsequent subdivision and/or land development application within twelve (12) months after the date when the conditional use is finally granted, and the applicant shall have secured a zoning permit for such use within five (5) years of said date. For good cause, the Board of Supervisors may upon application in writing, state the reasons therefore and extend either the twelve (12) months or five (5) year period;
 - b. Should the appellant or applicant fail to submit the subsequent subdivision and/or land development application within twelve (12) months period, it shall be conclusively presumed that the appellant or applicant has waived, withdrawn, or abandoned his conditional use application, and all approvals granted to him shall be deemed automatically rescinded by the Board of Supervisors; and,
 - c. Should the appellant or applicant submit the subsequent subdivision and/or land development application within said twelve (12) months period, but should he fail to secure a zoning permit for such use within said five (5) year period, the Board of Supervisors may, upon ten (10) days notice in writing, rescind or revoke the granted conditional use approval, if the Board of Supervisors finds that no good cause appears for the failure to secure a zoning permit within such five (5) year period, and if the Board of Supervisors further finds that conditions have so altered or changed in the interval since the granting of the conditional use, that revocation or rescission of the action is justified.
3. As an alternative to the preceding requirements of Section 805.F.1. and 805.F.2., an applicant can request, as part of the original conditional use application before the Board of Supervisors, the granting of a timetable associated with the request which would supersede the deadlines imposed in Section 805.F.1.-2. In so doing, the applicant must demonstrate that the times requested are logically related to normal and expected progress of the project. In approving a timetable under this Section, the Board of Supervisors must establish and bind a definite time-frame for (1) application of for subdivision and/or land development approval if applicable, (2) issuance of a zoning permit, and (3) completion of construction of the project.

805.G. MINOR CHANGE TO APPROVED CONDITIONAL USE

1. A person or entity having obtained a conditional use approval may apply for a minor change to the approval. The intent of the minor change application process is to streamline the review and approval of minor changes to an approved conditional use that do not raise significant substantive concerns.
2. A change to an approved conditional use that involves one or more of the following is ineligible for application for a minor change:
 - a. Change in use.
 - b. Addition of or change to vehicular access.
 - c. Change that would require relief from a standard or requirement of the Zoning Ordinance or SALDO.
 - d. Change that would modify relief already obtained through grant of a variance, with or without a condition.
 - e. Change that would modify a condition of approval of a conditional use.

- f. Change that would increase the permitted residential density by more than ten percent (10%) or lot coverage by more than five percent (5%).
 - g. Change that would add and/or relocate non-residential off-street parking areas, off-street loading areas, outdoor waste storage, outdoor storage and/or display to yards, or portions thereof, adjoining residences and/or vacant lands within the LDR and/or MU Zones where such features had not been previously proposed.
3. An application for a minor change shall be submitted in writing to the Zoning Officer for review and approval. The application shall include such written and/or graphic information as may be necessary to fully explain the minor change. Concurrent with the submission of the application, the applicant shall mail a copy of the application notice to each person or entity recognized as a party in the initial application proceeding. The application shall include a sworn certificate of service that identifies, by name and address, each party served with the application.
 4. As the Zoning Officer deems necessary for the making of a decision on the application for minor change, the Zoning Officer may consult with the Township Engineer, Township Solicitor, and any other consultant.
 5. Within 15 days of the submission of the minor change, the Zoning Officer shall issue a written decision approving or recommending denial of the application for minor change. The written decision shall be issued to the applicant and all parties to the initial application proceeding.
 - a. In the event the Zoning Officer approves the application for minor change, the decision shall be officially noted in the Township records in a manner consistent with the initial approval. The written approval of the minor change shall be concurrently posted at the Township offices and on the Township website and shall be reported to the Board of Supervisors at its next scheduled regular meeting.
 - b. In the event the Zoning Officer recommends denial of the application for minor change, the written decision shall state the grounds for denial.
 6. In the event the Zoning Officer recommends denial of the application for minor change, the Board of Supervisors shall consider and take action on an application at its next public meeting held no less than 10 days after the date of the Zoning Officer's decision. The Township shall give written notice of the meeting date to the applicant and the identified parties in the initial application proceeding. Within 15 days of the Board of Supervisors' action on the application for minor change, the Township shall issue a written decision approving or denying the application. The written decision shall be issued to the applicant and all parties to the initial application proceeding
 - a. In the event the Board of Supervisors approves the application for minor change, the decision shall be officially noted in the Township records in a manner consistent with the initial approval. The written approval of the minor change shall be concurrently posted at the Township offices and on the Township website.
 - b. In the event the Board of Supervisors denies the application for minor change, the decision shall state the grounds for denial. The decision shall be officially noted in the Township records in a manner consistent with the initial approval.
 7. Neither the Zoning Officer's recommendation for denial nor a Board of Supervisor's decision denying the application for minor change operates to foreclose the applicant

from applying for and obtaining another conditional use approval for the proposed change.

Section 806 Mediation Option

806.A. Parties to proceedings before the governing body may utilize mediation as an aid in completing such proceedings. In no case shall the governing body, initiate, mediation or participate as a mediating party. Mediation shall supplement, not replace, those procedures in this Article 8 once they have been formally initiated.

806.B. Participation in mediation shall be wholly voluntary. The appropriateness of mediation shall be determined by the particulars of each case and the willingness of the parties to negotiate. The Township shall assure that, in each case, the mediating parties, assisted by the mediator as appropriate, develop terms and conditions for:

1. Funding mediation;
2. Selecting a mediator who, at a minimum, shall have a working knowledge of municipal zoning and subdivision procedures and demonstrated skills in mediation;
3. Completing mediation, including time limits for such completion.
4. Suspending time limits otherwise authorized by the Act, provided there is written consensus by the mediating parties, and by an applicant or municipal decision making body if either is not a party to the mediation;
5. Identifying all parties and affording them the opportunity to participate;
6. Subject to legal restraints, determining whether some or all of the mediation sessions shall be open or closed to the public;
7. Assuring that mediated solutions are in writing and signed by the parties, and become subject to review and approval by the appropriate decision making body pursuant to the authorized procedures set forth in the Act:

806.C. No offers or statements made in the mediation sessions, excluding the final written mediated agreement, shall be admissible as evidence in any subsequent judicial or administrative proceedings.

Section 807 Information Submission Requirements

807.A. SUBMISSION CONSTITUTES PUBLIC RECORD

1. By making a submission under this Ordinance, the applicant acknowledges and agrees that all documents and other information submitted to the Township pursuant to this Ordinance constitute public records within the meaning of the Pennsylvania Right to Know Law, Act 3 of 2008, as amended, and are therefore subject to review and reproduction upon request in accordance with that Law and applicable Township ordinances and resolutions.

807.B. APPLICANT'S DUTY OF GOOD FAITH

1. Upon the filing of an application for review under this Ordinance, the applicant shall exercise good faith and promptly address or otherwise respond substantively to the review comments and requirements of the Township and its staff and consultants.

2. It is the duty of the applicant to move the application to completion in a prompt, timely, and diligent manner so as to enable formal action by the respective agency or agent of the Township, as the case may be, and to comply with all conditions of approval imposed by such agencies or agents.

807.C. UNSWORN FALSIFICATION TO AUTHORITIES

All statements, whether written or oral, to the Township in the course of the review of the application under this Ordinance shall be true and correct to the best of the knowledge, information and belief of the applicant or its agents and consultants, and with the understanding that any false statement is subject to the penalties of 18 Pa. C.S.A. Section 4804, relating to "Unsworn Falsification to Authorities.

DICKINSON TOWNSHIP ZONING ORDINANCE
Principal Uses Table by Zone and Type of Use

USE / P-permitted use/ SE-special exception/ CU-conditional use	Chapter	C	A	LDR	MU	MI	BI
Adult Entertainment Uses	402					CU	
Agriculture and Horticulture		P	P	P	P	P	P
Airports and Heliports	403					CU	CU
Animal Hospitals and Veterinary Offices	407				P	P	P
Auction House, Excluding Automobile Auctions	408						SE
Automobile and/or Animal Racing Facility With or Without Related Wagering	409					CU	
Automobile Auctions and/or Storage Yards	410						SE
Bed and Breakfasts	412	SE	SE	SE	SE		
Boarding Houses	415				CU		
Campgrounds	416	SE					
Car Washes	417						SE
Cemeteries	418	P	P		P		
Child Day Care Facilities (Homes and Centers)	421				SE	P	P
Churches and Related Uses	419	P	P		P		
Commercial Greenhouses						P	P
Commercial Produce Operations	422		SE				
Commercial Recreation Facility	423						SE
Concentrated Animal and Animal Feeding Operations (CAOs and CAFOs)	424		P				
Conservation Design Developments	425	P	P	P	P		
Convenience Stores	426						P
Convention and/or Conference Centers	427						SE
Dance, Music, Art, Fashion and Photographic Studios and Galleries					P		
Drop Lot or Drop and Hook Lot	451						CU
Dry-cleaners, Laundries and Laundromats (personal services)	430					P	P
Duplex and Two-family Dwellings					P		
Entertainment Facilities	461				CU		
Farmers and/or Flea Markets	434						SE
Fish Hatcheries and/or Fish Farms	436	CU	CU				
Financial Institutions					P		P
Forestry Uses		P	P	P	P	P	P
Funeral Homes	439				SE		
Gas Stations (Including Minor Incidental Repair)	411						SE
Golf Courses and Driving Ranges	441	SE	SE		SE		
Group Homes	432				SE	SE	SE
Health, Fitness, Social, Fraternal and Other Private Clubs	442				SE		SE
Heavy Equipment and/or Commercial Truck Sales, Service and/or Repair Facilities	443						SE
Heavy Industrial Uses	444					SE	SE
Historic Structure Conversions	446	SE	SE	SE	SE	SE	
Home Improvement and Building Supply Stores	447						SE
Hospitals with Related Uses	449						CU
Hotels, Motels and Similar Lodging Facilities							P
Junkyards	450					CU	
Kennels	452		SE				
Laboratories for Medical, Scientific, or Industrial Research and Development							P
Machine, Tool and Die, and Metal Fabrication Shops						P	P
Manufacturing, Packaging, Storage and/or Wholesaling (see permitted uses)							P
Mass Transit and/or Taxicab Terminals	456						SE
Medical Marijuana Facilities	437						CU
Medical Offices					P		P
Medical Residential Campus	457				CU		
Methadone Treatment Facility	458					CU	
Mining, Quarrying and Related Processing Operations	459					CU	
Mobile Home Parks	454				CU		
Multiple-Family Dwellings					P		

DICKINSON TOWNSHIP ZONING ORDINANCE
Principal Uses Table by Zone and Type of Use
Continued

USE / P-permitted use/ SE-special exception/ CU-conditional use	Chapter	C	A	LDR	MU	MI	BI
Municipal and Governmental Uses		P	P	P	P	P	P
Nursing, Rest or Retirement Homes	463				SE		
Offices					P	P	P
Outdoor Shooting Ranges (Public)	467	CU	CU		CU		
Outdoor Shooting Range (Private)	467	P	P		P		
Parks and Playgrounds		P	P	P	P	P	P
Passenger Motor Vehicle and Recreational Vehicle Sales, Service and Repair Facilities	469						SE
Personal services (see permitted uses)					P	P	P
Power Generation Facilities	470						CU
Principal Waste Handling, Recycling, Processing, Transfer and Disposal Facilities	471						CU
Processing, Packaging, Bottling, Storage and/or Wholesaling of Food Products							P
Public and Private Schools	472	CU	CU		CU		
Commercial Schools	472				CU		
Public Utilities Structures	405				P	P	P
Recycling Facilities for Paper, Plastic, Glass and Metal Products	474					SE	SE
Repair Shops for Products Permitted to be Manufactured in the B-I Zone							P
Restaurants	429				CU		P
Retail Sales, Rental or Repair of Goods (see permitted uses)					P		
Riding Stables	476	SE	SE		SE		
Sale of Compost, Mulch, Woodchips and Coal	480		SE			SE	SE
Sales, Storage and/or Wholesaling of certain items (see permitted uses)							P
Sawmills	482	CU	CU			CU	
Septage and Compost Processing	483					CU	
Shopping Centers	484						CU
Shops, Offices and Showrooms for Contractors (see permitted uses)						P	P
Sign Makers						P	P
Single Family Detached Dwellings		P	P	P	P	P	P
Slaughtering, Processing, Rendering and Packaging of Food Products and Their By-products	485					CU	
Small engine repair shops							P
Storage Unit Centers	460						SE
Townhouse Dwellings					P		
Truck or Motor Freight Terminals	486						CU
Truck Stops	487						CU
Two-family Conversions	488	SE	SE	SE	P		
Warehouses and Distribution Centers	489						CU
Welding Shops						P	P
Wind Farms	490	CU					
Solar Farms	490	CU			CU		

DICKINSON TOWNSHIP ZONING ORDINANCE
Accessory Uses Table by Zone and Type of Use

USE / P- permitted use/ SE-special exception	Chapter	C	A	LDR	MU	MI	BI
Alternative Energy Systems	404	P	P	P	P	P	P
Athletic Fields and Courts and Recreation Facilities						P	P
Beekeeping	413	P	P				
Billboards	414	Billboard Sign Overlay Zone Only					
Communications Antennas that are Co-located Upon Existing Structures	420	P	P	P	P	P	P
Composting	428	P	P	P	P		
Domestic Pets	406	P	P	P	P	P	P
Family Day Care Facilities	421	P	P	P	P		
Farm occupations	433	P	P		P		
Fences and walls	435	P	P	P	P	P	P
Freestanding Communication Antennas, Towers and Equipment	438	SE	SE			SE	SE
Garage/Yard /Moving Sales	440	P	P	P	P		
Garages & Sheds for Personal Vehicles/Property		P	P	P	P		
Gardening and Raising of Plants for Personal Use		P	P	P	P		
Helicopter Pads, Private	445					SE	SE
Home Occupations	448	P	P	P	P		
Man-made Lakes, Dams, Ponds and Impoundments	453	P	P	P	P	P	P
Manure Storage Facilities	455	P	P				
No-impact Home-based Business		P	P	P	P		
Noncommercial Keeping of Livestock	462	P	P	P	P		
Ornamental Ponds and Wading Pools	464	P	P	P	P	P	P
Outdoor Residential Athletic Courts	466	P	P	P	P		
Outdoor Shooting Range (Private)	467	P	P		P		
Parking and/or Storage of Recreational Vehicles and Personal Cargo Trailers	468	P	P	P	P		
Play Structures		P	P	P	P		
Recycling Collection Facilities as an Accessory Use						P	P
Residential Swimming Pools	475	P	P	P	P	P	P
Roadside Stands	477	P	P				
Rural Occupations	479	P	P		P		
Satellite Dish Antennas	481	P	P	P	P	P	P
Short Term Rentals (Agricultural)	465	P	P				
Short Term Rentals (Residential)	465	P	P		P	P	P
Signs	322	P	P	P	P	P	P
Temporary Family Housing	431	P	P	P	P		




West Pennsboro
Township

Carlisle
Borough



Prepared by:
Cumberland County GIS
Drawn: August 2005
Revised: August 2020



South Middleton
Township

Mt. Holly
Springs
Borough


Penn
Township

Cooke
Township

Huntington
Township

Map Scale: 1:55,000

Miles



Dickinson Township Zoning

Note

**FP Districts: Floodplain area boundaries are shown approximately on this map. Actual accurate floodplain area boundaries must be interpolated from maps and studies prepared for Dickinson Township by the Federal Emergency Management Agency (FEMA) for the Federal Insurance Administration, as amended from time to time, and in accordance with Zoning Ordinance.

County Disclaimer

This map was digitally compiled for internal maintenance and developmental use by the Cumberland County, Pennsylvania, GIS & Planning Departments to provide an index to parcels and for other reference purposes. Parcel lines do not represent actual field surveys of premises. Cumberland County, Pennsylvania makes no claims as to the completeness, accuracy or content of any data contained hereon, and makes no representation of any kind, including, but not limited to, the warranties of merchantability or fitness for a particular use, nor are any such warranties to be implied or inferred, with respect to the information or data furnished herein.

No part of this document may be reproduced, stored in a retrieval system or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or otherwise, except as expressly permitted by the County of Cumberland and the Township of Dickinson.

Refer to the officially enacted "Township of Dickinson Zoning Ordinance" for information regarding interpretation of zoning district boundaries, floodplain area boundaries, procedures for requesting amendment to this map, etc

Reference

- Municipal Boundary
- Tax Parcels
- Interstates
- State Roads
- Local Roads
- Appalachian Trail
- Streams

Zoning & Overlay Districts

- Agricultural (A)
- Low Density Residential (LDR)
- Mixed Use (MU)
- Business Industrial (B-I)
- Mining/Industrial (M-I)
- Conservation (C)
- Floodplain Overlay (FP)
- Billboard Sign Overlay (BS)
- Appalachian Trail Overlay (ATOD)