- 4 C R FINAL REPORT ACR-69-484 Copy No. STUDY FOR CLEANLINESS LEVEL REQUIREMENTS FOR PNEUMATIC AND HYDRAULIC COMPONENTS SERVICE ARM SYSTEMS, COMPLEX 39 SEPTEMBER 1969 Contract NAS10-5935 N7j-17368 CCEBGION NUMBI THRU ICODEI ビルクマノし 1 8

1. A ... 12 10/2010

NASA Contract NAS10-5935

FINAL REPORT

CLEANLINESS LEVEL REQUIREMENTS FOR PNEUMATIC AND HYDRAULIC COMPONENTS -SERVICE ARM SYSTEMS, COMPLEX 39

September 1969

· .-.•

Prepared For

National Aeronautics and Space Administration J. F. Kennedy Space Center Kennedy Space Center, Florida

Approved By

les Lamp

Victor A. DesCamp Program Manager

Martin Marietta Corporation Denver, Colorado 80201

FOREWORD

This report was prepared by the Martin Marietta Corporation under Contract NAS10-5935 "Cleanliness Level Requirements for Pneumatic and Hydraulic Components - Service Arm System, Complex 39" for the J. F. Kennedy Space Center of the National Aeronautics and Space Administration. The work was administered under the Technical Direction of the Design Engineering Directorate, Mechanical Systems Division, of the J. F. Kennedy Space Center with Mr. James R. McBee acting as project manager.

Notice

Commercial names as used herein are for ease of identification only; their mention does not constitute endorsement by the authors or any government agency.

ABSTRACT

This report describes the effort accomplished, both analytical and experimental, under Contract NAS10-5935 to determine the minimum cleanliness levels required for the pneumatic and hydraulic systems on the Launch Complex 39 Service Arms. The study encompassed an in-depth system review, a critical analysis of components with respect to contamination, a literature/industry search to compile pertinent data and experience, and a test program to demonstrate component functional compliance versus contamination.

ľ

.....

:

. .

.....

.....

CONTENTS

| | | Page |
|--------------|--|--------------------------|
| Foreword | | 11 |
| | | 111 |
| | | 1v thru x11 |
| I. | Introduction | I - J |
| II. | Conclusions and Recommendations | 1. 1 . – 1. |
| | A. Conclusions | 10 F + 1 |
| | B. Recommendations | 11-2 thru 11-9 |
| 111. | Systems Analysis | III-l |
| 111 1 | A. Service Arm Description | I. I. I. - 1 . |
| | B. Detailed Analysis | 111-2 |
| | 1. Cleanliness Specifications | 111-6 |
| | 2. Filtration | 111-8 |
| | 3. General System Problems | III-11 |
| | 4. Sampling Procedures | 111-15 |
| | 5. System Orifices | 111-20 |
| | 6. Service Arm Cylinders | 111-22 thru 111-51 |
| 1V. | Component Analysis | IV-1 thru IV-5 |
| v. | Literature Search | V-1 |
| VI. | Cleanliness Level Recommendations for Test | VI-1 |
| | 1. NASA and Military Specifications | V1-3 |
| | 2. Technical Society Standards | VI-4 |
| | 3. Industry Specifications | VI-5 |
| | 4. Operations Experience | VI-6 |

iv

| | 5. Fluid Considerations | VI-6 |
|----------------|--|-----------------------------|
| | 6, System and Component Configuration | VI-7 |
| | 7. Vendor Recommendations and Industry Experience | VI~8 |
| | 8, Recommendations for Test , , , , , , , | VI-9 thru VI-19 |
| VII. | Establishment of Contaminant Classes | VII-l thru VII-l3 |
| VIII. | Contamination Test Program | VIII-1 |
| | A. Test Criteria | VIII+1 |
| | B. Pneumatic Contamination Tests | V111-4 |
| | C, Hydraulic Contamination Tests | V111-21 thru V111-115 |
| Appundi | x A Categorized Components List | Δ-1 thru Δ-14 |
| Append | x B Component Analysis Sheets | B-l thru B-88 |
| Append | x C Bibliography and Abstracts | C-1 thru C+33 |
| Figure | | 111 <u>-</u> 24 |
| 111-1 | Saturn V Service Arms | |
| III-2 | Service Arm Function, Extend/Retract, Control Console #1, Arms 1, 2 | 1 11- 25 |
| III-3 | Service Arm Function, Hydro-pneumatic, Arm Extend/Retract, Arms 4, 5, 6, 7, 8 | III - 27 |
| III- 4 | Service Arm Function, Control Console #1, Arm 9 Only | 111 - 29 |
| 111-5 | Service Arm Function, Cable Retract, Control Console #2, Arms 4, 5, 6, 7, 8 | 111-31 |
| 111 - 6 | Service Arm Function, Extend/Retract, Manual Console, Arm 3 Only | III-3 2 |

| · III-7 | Service Arm Function, Latchback Cylinder, Arm 3 Only | III-33 |
|-----------------|--|-----------------|
| III-8 | Service Arm Function, Water Quench Valve and Latchback Cylinder, Arms 1, 2, 3, 4, 5, 6, 7, 8 | III- 33 |
| 111-9 | Service Arm Function, Latchback Cylinder and Water Quench Valve, Arm 9 Only | 111-34 |
| [[1-]0 | Service Arm Function, Umbiliteal Reconnect Cylinder, Arm 4 Only | 1II= 35 |
| 111-13 | Service A m Function, Platform Extend/Retract, Arms 5, 6, 7 | ETT+30 |
| 111-12 | Service Arm Function, Carrier Kickoff, Arm 2 Only | 111-37 |
| [-]3 | Service Arm Function, Carrier Kickoff, Arms 4, 5, 6, 7 | 111-57 |
| 111-14 | Service Arm Function, Carrier Rickoff, Arm 8 Only | 111-38 |
| 111-15 | Service Arm Function, Carrier Withdrawal/Re- connect, Arm 1 Only | 111 - 39 |
| 111-16 | Service Arm Function, Hydraulie Carrier With- drawal Cylinder, Arms 4, 5, 6, 7 | 111-40 |
| LTI-17 | Service Arm Function, LEM Withdrawal Cylinder, Arm 7 Only | III-41 |
| 111-18 | Service Arm Function, Service Module Carrier Withdrawal, Carrier Kickoff, Arm 8 Only | TIT-4 2 |
| 111-19 | Service Arm Function, Coupling Kickoff/With- drawal, Arm 4 Only | 111-43 |
| 111-20 | Service Arm Function, Line Tray Withdrawal, Arm 2 Only | 111-44 |
| III-21 | Service Arm Function, Tray W. Arawal, Arms 6, 7 | III-4 5 |
| 111-22 | 2 Service Arm Function, Environmental Chamber, Arm 9 Only | III- 46 |
| 111 - 23 | 3 Hydraulic Charging Unit | III-47 |
| 111-24 | 4 Service Arm Filtration | 111-48 |
| III- 2 | a meta da del constituente | III-4 9 |
| 111-2 | | 111-50 |
| 111-2 | the training the framewing from | 111-51 |

vi

| /1-1 | Particle Count Analysis (31 operational aircraft and missiles) | VI- 15 |
|--------|---|-----------------|
| VI-2 | Particle Count Analysis (11 AF aircraft) | VI-16 |
| VI-3 | Particle Count Analysis (143 naval aircraft | VI-17 |
| VI-4 | Particle Count Analysis (17 AF aircraft) | VI-18 |
| VI-5 | Particle Count Analysis (service arm hydraulic systems) | VI-19 |
| VII-1 | A.C. "Gearse" Road Dust - 870X | V1.1-2 |
| VII-2 | Red Iron Oxide Particles - 350X | VII -3 |
| VII-3 | Teflon Particles - 140X | VILeá |
| VII-4 | Cotton Lintner Fibers - 140X | V11-5 |
| VII-5 | Particle Count Composition A.C. "Coarse" Road | VII8 |
| VII-6 | Particle Count Composition 0x60 Teflon | V11-9 |
| VII-7 | Contamination Level for Hydraulic Tests | VII-12 |
| VII-8 | Contamination Level for Pneumatic Tests | VII-13 |
| VIII-1 | Pneumatic Gylinder Functional Test Schematic | V111-52. |
| VIII-2 | Two-Way Solenoid Valve Functional Test Schematic | VIII-53 |
| VIII-3 | Three-Way Solenoid Valve Functional Test Schematic | VIII-54 |
| VIII-4 | Regulator Functional Test Schematic | V111- 55 |
| VIII-5 | System Test Fixture Schematic | VIII-56 |
| VIII-6 | Pneumatic Contamination Test System | VIII-57 |
| VIII-7 | Pneumatic Contamination Test Control Panel | VII1-58 |
| VIII-8 | Contaminant Injector Development Data | VIII-59 |
| VIII-9 | | VIII-60 |
| VIII-1 | O Millipore Filter Pads from Pneumatic Contamin- ation Tests | VIII-61 |
| VIII-1 | 1 Pressure Regulator (75M08831-1) | VIII-62 |
| | 2 Pressure Regulator (75M08831-1) | VIII-63 |
| | 3 Spool Piece and Filter Screen (75M08831-1) | VIII-64 |

vii

.

MCR -69 -484

5

.....

.....

Ì

:

| VIII-14 | Inlet Fitting (75M08831~1) | VIII-65 |
|------------------|--|-------------------------|
| VIII-15 | Two-Way Solenoid Valve (75M08824-1) | VIII-66 |
| VU11-16 | Two-Way Solenoid Valve (75M08824-1) | VIII-67 |
| VIII-17 | Inlet and Outlet Filter Screens (75M08824-1) | VIII-68 |
| VIII-18 | Three-Way Solonoid Valve (75M08825-1) | VIII-69 |
| VIII-19 | Three-Way Solenoid Valve (75M08825-1) | VIII-70 |
| V 3.11-20 | Spool Piece (75M08825~1) | VIII-71 |
| VIII-21 | Pressure Handlonder (75M08829) | VIII=72 |
| VELL-22 | Pressure Handloader (75M08829) | VIII.#73 |
| VIII=23 | Poppet Stem (75M08829) | V1.1.f. ~ 74 |
| VIII-24 | Eroded Poppet Seat Nitrogen Handloader (75M08829) 15X Magnification | VIII-75 |
| VIII-25 | Sensing Piston and Spool (75M08829) | VI11-76 |
| V111-26 | Three-Way Solenoid Valve (75M09285-1, S/N 280) | V I. I. I 77 |
| V111-27 | Three-Way Solenoid Valve (75M09285-1, S/N 280) | VIII-78 |
| V111-28 | Spool Piece (75M09285-1, S/N 280) | VIII- 79 |
| VIII-29 | Three-Way Solenoid Valve (75M09285-1, S/N 281) | VI11-30 |
| VIII-30 | 281) | VIII-81 |
| V111-31 | 281) | VIII-82 |
| VIII-32 | • | VIII-83 |
| VIII-33 | Two-Way Solenoid Valve (75N08823-1) | VIII-84 |
| VIII-34 | Pneumatic Cylinder (75M09014) | VIII-85 |
| VIII-35 | Pneumatic Cylinder (75M09014) | VII1-86 |
| VIII-36 |) Hydraulic Systems Test Schematic | VIII-87 |
| VIII-37 | Test System Hydraulic Contamination Tests (front view) | VIII-88 |
| VIII-38 | B Hydraulic Test System (with accumulator and cooling coils) | VIII-8 9 |

viii

:

.....

| VIII-39 | Test System Hydraulic Contamination Tests (rear view) | VI11-90 |
|------------------|--|-----------------|
| VIII-40 | Pressure Handloader (75M08830) | VIII-91 |
| | Pressure Handloader (75M08830) | VIII-92 |
| VIII-41 | Valve Body (75M08830) | VIII-93 |
| VIII-42 | | , |
| VIII-43 | O-Ring Failure, Pressure Handloader (75M08830) | VIII-94 |
| VIII#44 | Piston (75M08830) | VIII-95 |
| VIII-45 | Poppet Stem (75M08830) | VIII-96 |
| VIII-46 | Fittings and Filter Screens (75M08830) | VIII-97 |
| VIII-47 | Cheek Valves (75M05365-4) | VIII-98 |
| VIII-48 | Check Valves (75M05365-4) | V111-99 |
| VII1-49 | Two-Way Solenoid Valves (75M08823-1) | VI1I-100 |
| VIII-50 | Two-Way Solenoid Valves (75M08823-1) | V] []-[0] |
| VIII-51 | Poppet Stem (75M08823-1) | VIII-102 |
| VIII-52 | Retaining Spool (75M08823-1) | VII1-103 |
| VIII-53 | Static O-Ring and Support Seat (75M08823-1) | VIII-104 |
| V111-54 | llydraulic Cylinder (75M065067) | VIII-105 |
| VIII-55 | Hydraulic Cylinder (75M065067) | VIII-106 |
| VIII - 56 | Cylinder Chevron Packing (75M065067) | VIII-107 |
| VIII-57 | Accumulator (75M08814-1) | VIII-108 |
| VIII-58 | Accumulator (75M08814-1) | VIII-109 |
| VIII-59 | Accumulator (75M088i4-1, S/N 3300) | VIII-110 |
| VIII-60 | Static O-Rings (end caps), (75M08814-1) | V1II-111 |
| VIII-61 | Accumulator Bore (75M08814-1, S/N 3300) | VIII-112 |
| VIII-62 | Accumulator Pistons (75M08814-1) | VIII-113 |
| VIII-63 | Accumulator (end view), (75M08814-1, S/N 3299) | VIII-114 |
| VIII-64 | Accumulator Bore (75M08814-1, S/N 3299) | VIII-115 |

ix

÷

ine tenting the

· . . .

þ

ļ

ĺ

:

BUT THE PLANE AND A STATE

| Table | | | |
|-----------------|--|-----------------|---|
| 111-1 | Service Arm Retract Times | III-1 | • |
| 111-1 111-2 | Baseline Documentation | III-3 | |
| III-2 III-3 | Service Arm Functions | III-4 | |
| III-4 | Government Cleanliness Specifications | III - 7 | |
| | Potential Reservoir Fill Contamination | III-10 | |
| III - 5 | Particulate Criteria (75M09467) | III- 16 | |
| III-6 111-7 | Service Arm Hydraulic Samples | TTI-17 | : |
| | Service Arm Hydraulic Samples | 11.1 -18 | |
| III-8 | Service Arm Orifice Size Tabulation | III-20 | |
| 111 - 9 | Service Arm Cylinder Force Analysis | III-23 | |
| III - 10 | Cleaning Costs | IV-3 | |
| IV-1 | Component Cleaning Costs | IV-4 | : |
| IV -2 | Test Specimens for Contamination Test | IV-5 | |
| IV-3 | Cleanliness Specification | VI-11 | |
| VI-1 | Industry Experience and Specifications | VI-13 | |
| VI-2 | Contamination Test Levels | VII-10 | |
| VII-1 | Cleanliness Levels | VIII-3 | |
| VIII-1 | | VIII-8 | |
| VIII-2 | System Test Cycle Logic | VIII-10 | |
| VIII-3 | System Test Run Schedule | VIII-11 | |
| VIII-4 | Solenoid Valve Functional Test Data | VIII-12 | |
| VIII-5 | Regulator Functional Test Data | * | |
| VIII-6 | Pneumatic Cylinder Functional Test Data (75M09014) | VIII-12 | |
| VIII-7 | Millipore Particle Count Data | VIII-15 | |
| VIII-8 | System Test Interim Internal Leakage Test | VIII-15 | |
| VIII-9 | Test Instrumentation | VIII-23 | |
| VIII-10 | HIAC Particle Counter Data, Test System Prior to Component Installation | VIII-24 | |
| VIII-11 | HIAC Particle Counter Data, Test System After Component Installation | VIII-24 | |
| VIII-12 | HIAC Particle Counter Data, Prefiltered Test Fluid | VIII-25 | |
| | | | |

х

1 1 N

.

- ⁻ -

| VIII-13 | Hydraulic Contamination Test Levels | VIII=25 |
|-----------------|--|-----------------|
| VIII-14 | Effluent Particle Count, Hydraulic Accumulator (75MO8814-1, S/N 6K3299) | VIII-26 |
| VIII-15 | Effluent Particle Count, Hydraulic Accumulator (75M08814-1, S/N 6K3300) | VIII-27 |
| VIII- 16 | Effluent Particle Count, Hydraulic Cylinder (75M06506-7) | VIII-27 |
| VIII-17 | Effluent Particle Count, Hydraulic Cylinder (75M06506-7), Initial Fluid Sample | VIII-28 |
| VIII-18 | Cylinder Influent Particle Count, Hydraulic Bench Oil Sample | VIII-28 |
| VIII-19 | Effluent Particle Count, Two-Way Solenoid Valve (75M08823-1, S/N 398) | VIII-29 |
| VIII-20 | Effluent Particle Count, Two-Way Solenoid Valve (75M08823-1, S/N 399) | V111-29 |
| VIII-21 | Effluent Particle Count, Check Valve (75MO5365-4, S/N 9021312) | VIII-29 |
| VIII-22 | Effluent Particle Count, Check Valve (75MO5365-4, S/N 9021313) | VIII-30 |
| VIII-23 | Effluent Particle Count, Check Valve (75MO5365-4) Millipore Filter Visual Count . | VIII-30 |
| VIII-24 | Effluent Particle Count, Hydraulic Pressure Regulator (75M08830-2) | VIII-30 |
| VIII-25 | Sequence of Operation | VIII-32 |
| VIII-26 | a market by the transformed ator | VIII- 34 |
| VIII-2,7 | Functional Test Data, Hydraulic Cylinder (75M06506-7) | VIII- 34 |
| VIII-28 | Functional Test Data, Pneumatic Two-Way Solenoid Valve (75M08823-1, S/N 398) | VIII- 35 |
| VIII-29 | Functional Test Data, Pneumatic Two-Way Solenoid Valve (75M08823-1, S/N 399) | VIII-36 |
| VIII-30 |) Functional Test Data Sheet, Hydraulic Check Valve (75M05365-4) | VIII-37 |
| VIII-31 | Functional Test Data Sheet, Hydraulic Pressure Regulator (75M08830-2) | VIII-37 |

xi

t .

Ì

| /111-32 | HIAC Particle Counter Data, Test System after Checkout (O Test Cycles) | VIII-40 |
|-----------------|---|---------|
| VII1-33 | HIAC Particle Counter Data, 100 Test Cycles | VIII-40 |
| VIII-34 | HIAC Particle Counter Data, 200 Test Cycles | VIII-40 |
| VIII-35 | HIAC Particle Counter Data, 300 Test Cycles | VIII-40 |
| VIII-36 | HIAC Particle Counter Data, 400 Test Cycles | VIII-41 |
| VILI-37 | HIAC Particle Counter Data, 500 Test Cycles | VIII-41 |
| VIII-38 | HIAC Particle Counter Data, 600 Test Cycles | VIII-41 |
| VII1-39 | HIAC Particle Counter Data, 700 Test Cycles | VIII-41 |
| VI11-40 | HIAC Particle Counter Data, 800 Test Cycles | VIII-42 |
| VIII-41 | HIAC Particle Counter Data, 900 Test Cycles | VII1-42 |
| VIII-42 | HIAC Particle Counter Data, 1000 Test Cycles | VIII-42 |
| VIII-43 | HIAC Particle Counter Data, 1100 Test Cycles | VIII-42 |
| VIII-44 | HIAC Particle Counter Data, 1200 Test Cycles | VIII-43 |
| VIII-45 | HIAC Particle Counter Data, 1300 Test Cycles | VIII-43 |
| VIII-4 6 | Cycles | VIII-43 |
| VIII-47 | HIAC Particle Counter Data, 1500 Test Cycles | VIII-43 |
| VIII-48 | Hydraulic Oil Particle Count (Millipore) | VIII-44 |
| VIII-49 | System Test Interim Internal Leakage Test Data | VIII-44 |

xii

I. INTRODUCTION

The primary purpose of the study conducted under this contract was to determine, by analysis and testing, the minimum levels of cleanliness that would permit the Launch Complex 39 Service Arm Control Systems to meet all functional and reliability requirements.

The cleanliness levels specified for the service arm systems were originally based upon the best judgment of the system designers, and as a result of subsequent launch operations experience all indications were that they were unnecessarily stringent. Considerable expense is involved in cleaning system components to these levels, in addition to other indirect costs associated with logistics, inspection, maintenance, and delays in test operations. It was therefore desirable to reduce these costs if possible.

The objectives of this program were accomplished in four phases: (1) an in-depth review of the system, (2) a critical analysis of components with respect to contamination, (3) a literature/industry search to compile pertinent data and experience, and (4) a test program to demonstrate component compliance versus contamination. This final report describes the work performed in each phase of the program, together with all findings, test data, and conclusions.

The secondary purpose of the study was to derive basic data contributing to the general body of information on part cleanliness requirements. In addition to the data contained in this final report, a separate handbook was prepared as part of the contract requirements. The Contamination Control Handbook for Ground Fluid Systems, Martin Marietta report number MCR-69-485, was prepared as a guideline of contamination control practices for those persons engaged in the design of aerospace ground hydraulic and pneumatic systems. I-1

II. CONCLUSIONS AND RECOMMENDATIONS

A. CONCLUSIONS

At the completion of the study for cleanliness level requirements, the following conclusion was formulated:

- 1) Gleanliness levels on the service arm systems can be reduced with no degradation in performance. The proposed levels are described in detail in Chapter II, B, 1;
- 2) The data collected during the study was documented in the form of a contamination control handbook as a guide for future design and operation of hydraulic and pneumatic systems.

The study was conducted in three phases and the conclusion is based upon the results obtained. The primary results of each phase of the study are discussed below.

A thorough evaluation of the system and its components was conducted to determine the system criticality and component sensitivity to contamination. Although many components are critical to the service arm performance, they are relatively insensitive to contamination. Fifteen specific recommendations concerning the service arm system and components are discussed in further detail in Section B, Recommendations.

A contamination test was conducted on 17 service arm components that were determined to be sensitive to contamination. Contamination, in excess of the recommended cleanliness levels, was purposely injected into the system to measure component performance in a highly contaminated system. The test components were procured in a commercial clean condition. All of the components, except one, operated properly throughout all tests with no degradation caused by contamination. The 75M08829 pressure regulator proved to be extremely sensitive to contamination. The cleanliness levels recommended in this study have one reservation; four regulators in the service arm systems must be protected by additional filtration.

II-1

The literature search revealed that many systems, similar to the service arm systems, are being successfully operated on less stringent cleanliness levels. Less stringent cleanliness levels should produce substantial cost savings in future procurement and operation of the service arm systems. Cleaning costs for the service arm components range up to 189% of the base component costs. The relaxed cleanliness levels in Section B, 1 are less stringent than the present levels and approach commercial cleanliness levels which should offer a reduction in cleaning costs. More significant savings should be realized in procurement, logistics, quality control, and launch operations.

B. RECOMMENDATIONS

The investigation and analysis of the service arm systems revealed several areas, related to contamination control, that require specific attention. The following recommendations are related to specific problem areas on items that would enhance contamination control on the Saturn V service arm systems.

1. Relaxed Cleanliness Levels

It is recommended that the service arm component and system cleanliness levels be relaxed to the following levels. The present levels specified are also shown for comparison.

a. Hydraulic Systems

| Particle Size (Microns) | 0-5 | 5 - 15 | 15 - 25 | 25-50 | 50-100 | Over 100 |
|---|-----------|---------------|----------------|-------|--------|----------|
| *Quantity per ft ² of significant surface area | Unlimited | 48,000 | 8,500 | 1,500 | 250 | 50 |

1) Component Cleanliness Level

*Based upon a minimum of 200 milliliters of rinse fluid per square foot of significant surface area.

II-2

| Particle Size (microns) | 0~5 | 5-15 | 15-25 | 25-50 | 50-100 | Over 100 |
|---------------------------------|-----------|--------|--------|-------|--------|----------|
| Quantity per 100 ml of fluid | Unlimited | 64,000 | 11,400 | 2,025 | 360 | 64 |

| 2) | System | Cleanliness | Level | (Level | 8 | of | NAS-1638) | ł |
|----|--------|-------------|-------|--------|---|----|-----------|---|
|----|--------|-------------|-------|--------|---|----|-----------|---|

3) Existing Service Arm Criteria for Hydraulic Components (ABMA-SPEC-10425040)

| Particle Size (microns) | () - 5 | 25-50 | 50~100 | 0ver 100 | Fibers |
|-------------------------------|---------------|-------|--------|----------|--------|
| Quantity per 100 ml sample | Unlimited | 530 | 60 | 0 | 1.0 |

b. Pneumatic Systems

.

1) Component Cleanliness Levels

| Particle Size (microns) | 0-300 | 300-500 | 500-1000 | Over 1000 |
|--|-----------|---------|----------|-----------|
| *Quantity per It of significant surface area | Unlimited | 10 | 2 | None |

| Fiber Length (microns) | 0-750 | 750-2000 | 2000-6000 | Over 6000 |
|--|------------|----------|-----------|-----------|
| tQuantity per ft ²² of significant surface area | Unlimited! | 20 | 2 | None |

*Based upon a minimum of 200 milliliters of rinse fluid per square foot of significant surface area.

Total filterable solids limitation, 0.25 mg/ft".

2) System Cleanliness Level

| Particle Size (microns) | 0+300 | 300-500 | 500-1000 | Ov er 1000 |
|----------------------------------|------------|---------|----------|-------------------|
| Quantity per 100 grams of gas | Unlimited* | 10 | 2 | None |

| Fiber Length (microns) | 0-750 | 750 - 2000 | 2000-6000 | Over 6000 |
|----------------------------------|------------|-------------------|-----------|-----------|
| Quantity per 100 grams of gas | Unlimited* | 20 | 2 | None |

*Total filterable solids limitation, 0.30 mg/100 grams of gas

 Existing Service Arm Griteria for Pneumatic Components (MSFC-SPEC-10M01671, Level IV)

| Particle Size (microns) | 0-50 | 51-140 | 141-230 | 231 -3 20 | 321-410 | 411-500 | 501+ |
|---|-----------------------|--------|---------|------------------|---------|---------|------|
| Per ft [?] of significant surface area | No Limit [†] | 40 | 10 | 3 | 2 | 1 | () |

| Fiber Length (microns) | 0-50 | 51-500 | 501-1000 | 1001+ |
|--|-----------------------|--------|----------|-------|
| Per ft ² significant surface area | No Limit [†] | 10 | 1 | 0 |

†Total filterable solids limitation, 1.0 mg/ft 2

2. Filtration for Critical Components

The 75M08829 pressure regulator failed during the contamination tests. This regulator is highly sensitive to contamination due to a very small (0.161 in. diameter) poppet seat. The failure mode is erosion of the main poppet seat, as a result of the high velocities across the small seat area. This failure mode would also apply to all regulators in the service arm systems that have a similar configuration; namely, the small seat area with attendant high velocities. The problem may be solved by

II-4

eliminating those regulators or by protection by means of filtration. It is recommended that the problem be corrected by filtration. A careful analysis of the service arm systems revealed that the majority of these regulators are adequately protected by 10 micron (nominal) filtration just upstream of the regulators; however, four regulators require additional filtration. It is recommended that 10-micron dual-element filters be placed just upstream of the following components:

Specification

Location

75M08830-2 A5657-4, -5, -6, -7

3. A Closed Hydraulic Reservoir

The hydraulic charging unit (HCU) reservoir is vented to atmosphere, with no adequate means for preventing the entrance of moisture and salt-laden air. Moisture is a significant and contributing factor to problems that were identified with fungus and corrosion in the hydraulic system. It is recommended that the vent to atmosphere be eliminated and that a positive pressure nitrogen system, with relief capability, be incorporated into the HCU reservoir.

4. Further Study to Eliminate Fungus Contamination

A hydraulic sample taken from mobile launcher no. 1 HCU reservoir contained one to two handfuls of a gummy contamination best described as having the appearance of strawberry jam. A biological analysis, conducted in the Martin Marietta Space Biomedical Research Laboratory, concluded that the contamination was fungi. Two other contamination samples, taken on different mobile launchers, indicated the presence of viable organisms in other portions of the hydraulic system. Fungus in a hydraulic system can clog filters, and produce component and system failures.

A review of the literature and industry provided no indication of any effort directed towards the elimination of fungi in HIL-H-5606 hydraulic oil. Further study is recommended in this area of technology to combat fungi formations in hydraulic oil. 11-5

5. Hydraulic and Pneumatic System Protection during Inactive Periods

The service arm pneumatic systems are pressurized only during test operations and in the launch countdown. No attempt is made to maintain a positive pressure on the system during the long intervals between launches. The hydraulic system is drained back to the reservoir after each launch.

It is recommended that a small positive pressure be maintained on the service arm pneumatic systems to prevent the entrance of molsture and atmospheric contamination, with its attendant corrosion problems. It is further recommended that a blanket of oil be maintained on the hydraulic system. Elastemers in a hydraulic system will dry out, leak, and deteriorate from age if not blanketed with oil.

6. Filtration for Hydraulic Fluid Fill

The hydraulic oil used to fill or resupply the HCU reservoir is not filtered. Considering the particulate contamination allowable in the MIL-H-5606 oil specification, large quantities of particulate can be introduced into the HCU reservoir.

Filters in the hydraulic system downstream of the reservoir will remove particles larger than 25 microns, and approximately 98% of those particles in the range of 10 to 25 microns. The filters will not remove the small particles which produce silting, component wear, and erosion. It is recommended that the hydraulic oil introduced into the HCU reservoir be filtered to 3 microns absolute.

7. Change to MIL-H-6083 Hydraulic Oil

The service arm hydraulic system uses MIL-H-5606 hydraulic oil. The literature search revealed that industry experience has shown MIL-H-6083 to be superior to MIL-H-5606 hydraulic oil and that it has two distinct advantages: (1) MIL-H-6083 contains a rust preventative as an additive; (2) conglomeration of fine particles will not occur in MIL-H-6083 as they will in MIL-H-5606 hydraulic oil. The properties of MIL-H-6083 are very similar to MIL-H-5606, and no compatibility problems exist. Residual MIL-H-5606 hydraulic oil does not have to be completely drained from a system prior to adding MIL-H-6083 oil.

II-6

8. Bubble Point Test on Filters

When performing a component analysis on the filters on the system, it was found that a bubble point test is not conducted on the majority of the filter elements after the final cleaning operation. Our experience has shown that element degradation can occur during the cleaning operation. It is recommended that a bubble point test be performed after final cleaning of the element to verify the integrity of the filter element and its stated filtration level. It is also mandatory to perform a bubble point test after an element has been in service, cleaned, and is being placed back in service.

9, Additional Sampling Procedures

The service arm pneumatic systems are not normally sampled for contamination. To maintain cognizance of the system, it is recommended that the service arm pneumatic systems be sampled at periodic intervals as part of a standard procedure.

There is no procedure or requirement to take contamination samples during the long intervals between launches or during a down-mode operation. It is recommended that procedures be instituted to take samples at three- to six-month intervals.

10. Contractor Equipment Interfaces

If the cleanliness levels on the service arm systems are relaxed, it is necessary to either revise the interface specifications for contractor equipment, or to provide adequate filtration just prior to the interface.

11. Standardization of Component Specifications

A total of eight different cleanliness level specifications are identified on the service arm component specifications. Instances were found where <u>fluid</u> sampling criteria had been specified for <u>component</u> cleanliness levels. Several component specifications applied optional cleanliness levels of widely differing criteria to the same component. This situation is a contributing factor to problems in attaining and maintaining a workable cleanliness program. It is recommended that a single cleanliness specification be referenced on all component specifications, system engineering, and applicable procedures. 11-7

12. Quality Control on System Samples

During our investigation of the service arm sampling procedures, there was no evidence of quality control as applied to the results of the contamination samples. No apparent action was taken on numerous system samples that did not meet specification. Once a realistic cleanliness level has been specified for a system, it is necessary to take corrective action if the samples do not meet specification. This action is required to prevent system degradation or subsequent failure. It is recommended that quality Control monitor the results of the system samples.

13. Atmospheric Protection for Electrical Equipment

Corrosion of component electrical parts is one of the most predominant categories of failure in the service arm systems. The electrical portion of the components is not provided with positive protection against atmospheric moisture and salt. The service arm consoles do not contain an inert gaseous purge, and inspection revealed that the console doors are often left open between launches. The least expensive method of preventing corrosion, caused by atmospheric moisture, is to maintain a dry gaseous positive pressure (0.5-in. water gage) within the service arm consoles. This can be accomplished with dry nitrogen or air, but a compressor-dry air system would probably be more economical than nitrogen.

14. Consolidated NASA Cleanliness Specification

Operational personnel reported that a multitude of cleanliness specifications exists for the different systems on the Saturn V complex. Different specifications also exist for the same system because of different design responsibilities. Most companies in the aerospace industry have consolidated all of their cleaning criteria into one specification to eliminate confusion and reduce total costs. The Saturn V contamination control program would be greatly enhanced if a single consolidated cleanliness specification were prepared for all systems. An extension of this cleanliness specification would also include consolidated criteria for all of the NASA centers.

II-8

15. Consolidated Sampling Procedure

The requirement to take a system sample, and the governing criteria for each sample, are specified in each respective operational test procedure. There is no composite correlation of the samples taken on the Saturn V launch stand, and as a result there is no consistent approach to sampling or sampling criteria. A standard sampling procedure should be established to coordinate all of the samples taken on Complex 39. This procedure would combine all sampling information and criteria into one central document and would eliminate confusion among different groups. The procedure should list fluid commodity, sample port location, the procedure used when taking the sample, and the criteria for the sample.

1s

III. SYSTEMS ANALYSIS

A. SERVICE ARM DESCRIPTION

Launch Complex 39 has nine service arms on each launch umbilical tower (LUT). The primary function of the service arms is to provide personnel and astronaut access, fluid commodity loading and unloading, electrical power, environmental control, and checkout of the Saturn V vehicle. After the Saturn V vehicle arrives at the launch pad, the service arms are extended to the vehicle and various checkout functions are performed to ensure the integrity of the systems. Prior to launch, the service umbilicals are connected to the vehicle to perform loading, access, and checkout. After all functions are complete the service arms disconnect all umbilical carriers and couplings from the vehicle, withdraw the umbilical lines, and then retract the arm back to the LUT where the arm is locked into place. Four of the service arms are withdrawn prior to liftoff, and five at or directly after liftoff (Fig. ILI-1 and Table III-1).

| Arm 1 | (S-IC aft) | 0 hr 0 min 30 sec |
|-------|---------------------|--|
| Arm 2 | (S-IC forward) | 0 hr 0 min 16.2 sec |
| Arm 3 | (S-II aft) | 11 hr 30 min 0 sec |
| Arm 4 | (S-II intermediate) | <u>Lift</u> off |
| Arm 5 | (S-II forward) | Liftoff |
| Arm 6 | (S-IVB aft) | Liftoff |
| Arm 7 | (S-IVB forward) | Liftoff |
| Arm 8 | (service module) | Liftoff |
| Arm 9 | (command module) | 0 hr 43 min 0 sec |
| 1 | | the second s |

Table III-1 Service Arm Retract Times

This study concerns the hydraulic (MIL-H-5606) and pneumatic (nitrogen-helium) control systems that perform the following basic functions on the service arms:

- 1) Carrier kickoff;
- Carrier withdraw/reconnect;
- Coupling kickoff/withdraw;

ITI-1

4) Line tray withdrawal;

5) Service arm extend/retract (automatic);

Service arm extend/retract (manual);

7) Latchback mechanism;

8) Water quench system actuation;

9) Platform extend/retract;

10) Environmental chamber operation.

B. DETAILED ANALASIS

When specifying a cleanliness level for a large and complex system such as the service arms, it is not possible to merely assign a level by association to other systems. This task must first address itself to the function of the system, the criticality assigned to each function of the system, and a review of the backup or redundancy configurations. In addition, the selection of a system cleanliness level depends greatly upon orifice sizes, level and adequacy of filtration, sampling procedures, system sample results, the maintenance provisions used to prevent cleanliness degradation, and finally a careful review of each critical component in the system.

As the initial phase of this contract, a detailed analysis of all service arm fluid systems was performed with the primary objective of identifying those components, both hydraulic and pneumatic, that perform critical system functions. At the initiation of the contract, a decision was made to use the updated configuration of the service arms, effectivity AS-503. Table III-2 lists the basic documentation (and the applicable revisions) that describe the baseline for this study.

During the initial phase of the systems analysis, 47 basic operational functions were identified among the nine service arms. It also became apparent that many of these functions appeared in identical configurations on more than one service arm, including identical component item-find numbers. The logical decision was made, therefore, to consolidate the 47 functions into a set of individual or repetitive systems, resulting in a significant simplification of the analysis task. This activity was subsequently accomplished, with the result that a commonality set of 23 system functions was identified (Table III-3).

K.

•••••

•

.

:

i

.

.

:

5

| Schematic Number | Title | Revision <u>Number</u> |
|-------------------------|--------------------------------|---------------------------|
| 76K02010 | Hydraulic Charging Unit | Revision A |
| 76 K 02011 | S-IC Intertank Arm | Revision A |
| 76K02012 | S-IC Forward Arm | Revision A |
| 76K02013 | S-II Aft Arm | Revision A |
| 76K02014 | S-II Intermediate Arm | Revision A |
| 76 K 02015 | S-II Forward Arm | Revision A |
| 76 K 02016 | S-IVB Aft Arm | Revision A |
| 76K02017 | S-IVB Forward Arm | Revision A |
| 76K02018 | Service Module Arm | Revision A |
| 76 K 04767 | Apollo Access Arm | Revision B |
| 76к03445 | Environmental Chamber | New |
| 76 K 00190 | Item Find List, Arm 9 | Revision B |
| 75M06518 | Item Find List, Arms 1-8 | Revision E |
| 76 K 02001 | Service Arm Component Settings | Revision H |
| Technical Manual No. | <u>Title</u> | Publication |
| TM439 | Pressure Regulators | 11 Dec 67 |
| 'TM440 | Solenoid Valves | 13 Dec 67 |
| TM441 | Cylinders | 15 Dec 67 |
| TM442 | Pilot Operated Valves | 20 Dec 67 |
| TM443 | Miscellaneous Components | 22 Dec 67 |
| TM500 | Hydraulic Charging Unit | 30 Jun 67 |
| TM501 | S-IC Intertank Arm | 15 Jan 68 |
| TM502 | S-IC Forward Arm | 2 Feb 68 |
| TM503 | S-II Aft Arm | 3 May 68 |
| TM 504 | S-II Intermediate Arm | 30 Aug 68 |
| TM505 | S-II Forward Arm | 15 Jul 68 |
| TM 506 | S-IVB Aft Arm | 15 Feb 68 |
| ° m 507 | S-IVB Forward Arm | 26 Jul 68 |
| TM508 | Service Module Arm | 16 Aug 68 |
| TM509 | Apollo Access Arm | 10 Nov 67 |

Table III-2 Baseline Documentation

Table III-3 Service Arm Functions

| System Description | Arm Usage |
|--|--|
| Control Console #1 Control Console #1 Control Console #1 Control Console #2 Manual Console Water Quench and Latchback Latchback Cylinder Water Quench and Latchback Carrier Reconnect Platform Extend/Retract Carrier Kickoff Carrier Kickoff Carrier Kickoff Carrier Withdrawal/Reconnect Carrier Withdrawal LEM Withdrawal Cylinder Carrier Kickoff Coupling Kickoff/Withdrawal Tray Withdrawal Tray Withdrawal Environmental Chamber Hydraulic Charging Unit | 1,2 4,5,6,7,8 9 4,5,6,7,8 3 1,2,4,5,6,7,8 3 9 4 5,6,7 2 4,5,6,7 8 1 4,5,6,7 7 8 4 4 5,6,7 7 9 |

Schematics of the above fluid systems are presented in Figures III-2 through III-23. With all service arm systems now reduced to their basic elements, a detailed study of each isolated system schematic was conducted in conjunction with applicable operational data in order to gain a thorough understanding of the design philosophy and technique. This effort revealed the fact that the set of commonality systems was comprised of nearly 1100 nonduplicating item-find numbers. It was also obvious that many of these were nonfunctional, performed maintenance duties, or were otherwise not critical to a successful launch.

The major effort in the analysis of the service arm systems was an item-by-item examination of each component in each system. For this purpose, charts were prepared for each component showing the item-find number, nomenclature, all possible modes of failure, the system effect of each failure mode, and a classification breakdown of the importance of a failure to the launch. For the purposes of this study, the following failure-effect categories were considered:

- 1) Loss of life or mission failure;
- 2) Launch delay of any duration;
- System malfunction or data loss (used during countdown and launch, but not critical to launch success);
- Local information loss or maintenance function (not required during countdown and launch);
- 5) Nonfunctional (no contribution, such as test ports, interface fittings, etc.)

The above effort differed from the usual interpretation of a failure analysis in that, in line with the program objectives, only effects arising from contamination problems were considered. The following ground rules were followed when determining failure modes and establishing failure effects:

- 1) The worst possible moment of failure in point of time was considered;
- The functioning of any particular subsystem was considered to be essential, even though a redundant capability exists;
- Redundancy of components was not considered, since parallel components can be equally susceptible to contamination;
- 4) Failure by contamination only was considered -- not mechanical, electrical, structural, environmental, or operator error (Example: broken springs, incorrect procedures, etc.);
- Only one failure was assumed to occur at any given time;
- 6) Header supplies were assumed to be available at the proper pressures and flowrates at all times;
- 7) Contractor furnished equipment was not evaluated in the study.

The results of the above categorization were compared to those obtained by The Boeing Company in "Failure Effects Analysis", their document number D5-16494-7. The Boeing analysis was, of course, conducted under different ground rules; in that work, failure due to contamination was not the only failure mode considered, and failures in redundant areas were considered to have no effect. These facts resulted in our analysis showing considerably more Category A and B components than did theirs.

In addition, Martin Marietta made no attempt to differentiate between a launch delay and a launch scrub, as did Boeing. However, for the vast majority of components, our estimation of failure modes and effects was consistently in agreement with that of Boeing.

As a result of this effort, 329 individual item-find numbers out of the original total of approximately 1100 were retained for further consideration; 135 in Category A (loss of life or mission failure) and 194 in Category B (launch delay of any duration). Conversion of this total to a part number arrangement disclosed that 79 different components manufactured by 27 vendors were represented. The categorized list of these 79 components is included in this report as Appendix A. It was from this list of Category A and B components that the final selection was made of the components to be used in the test phase of this program. No further consideration was given to those components classified as Category C, D, and E since these components were not critical to the system operation and generally consisted of hand valves, fittings, and other components that were not critical from a contamination viewpoint. The criteria used for further evaluation of these components is described in chapter IV, Component Analysis.

In the course of the above system studies, several general areas arose that were felt to be deserving of discussion. These were:

- 1) Cleanliness specifications;
- 2) Filtration;
- 3) General system problems;
- 4) Sampling procedures;
- 5) System orifices; and
- 6) Service arm cylinders.

A discussion of each of these subjects follows.

1. Cleanliness Specifications

During this study it was found that there are a multitude of cleanliness specifications being used to specify fluid, component, and system cleanliness levels on the service arms. Eight different cleanliness specifications have been identified for hydraulic and gaseous nitrogen applications, generated by four different government agencies, and ranging in age from April 1960 to March 1968, a span of eight years. These specifications are listed in Table III-4.

111-6

| Table III-4 | Government | Cleanliness | Specifications |
|-------------|------------|-------------|----------------|
|-------------|------------|-------------|----------------|

| Specification Number | FluId | Issuing Agency |
|----------------------|---------------|----------------|
| 1. KSC-C-123 | Fluids | NASA Kennedy |
| 2. 10M01621 | Pneumatic | NASA Marshall |
| 3. 10425040 | Hydraulle | Army Ordinance |
| 4. MSFC-SPEC-164 | Pneumatic | NASA Marshall |
| 5. MSFC-PROC-166 | Hydraulic | NASA Marshall |
| 6. MSFC=SPEC=234 | Nitrogen | NASA Marshall |
| 7. 75M09467 | Hydraulic | NASA Marsuall |
| 8. MIL-11-5606B | Hydraulic off | NAV-WEPS |

Of this total, the KSC-C-123 and 10M01621 specifications are apparently identical in all respects, but all others specify different criteria levels. Specifications 2, 3, 6 and 8 are referenced in the scope of work for this contract; the other four are not. Instances were found where system <u>fluid</u> sampling criteria had been specified for <u>component</u> cleanliness levels. Several component specifications applied optional cleaning procedures of widely differing criteria to the same component. Detailed criteria for these specifications are contained in Table IV-1.

This situation is a significant and contributing factor to problems in attaining and maintaining a workable cleanliness program. Undoubtedly, several of these eight specifications were prepared for a specific requirement some time ago, then applied intact to the service arm systems whose functional requirements and component configurations may bear little or no resemblance to those for which the specification was originally prepared. Such a large variety of specifications must inevitably lead to confusion by compounding communications problems between those persons who are responsible for actual cleanliness determinations. The use of a single, comprehensive specification is recommended to eliminate confusion and unify the requirements for all aspects of the cleanliness program. Further, this single specification should then be referenced on all component procurement drawings and all system installation drawings and operating or maintenance procedures.

Operational personnel (The Boeing Company) were contacted during the course of this study regarding cleanliness specifications, sampling techniques, contamination control, etc. One significant area of discussion centered around cleanliness specifications. They reported that a multitude of specifications exist for the different systems on Saturn V; and that for the same piece of pipe and commodity, different specifications exist for each system on the tower. This comment would indicate the need for a single consolidated cleanliness specification for all systems on Saturn V. Most companies in the aerospace industry have consolidated all of their cleaning criteria into one specification to eliminate confusion and reduce costs. The optimum solution would be a single consolidated cleanliness specification for all NASA centers. The above recommendation presents a formidable coordination task, but it is not impossible. The net return should result in a significant cost reduction.

It should be noted that a consolidation of cleaning procedures will generally incur an initial cost to engineering and sometimes in procurement. Engineering must be revised to maintain configuration control. Manufacturers will probably request additional price increases in hardware to change their engineering and cleaning processes if the criteria is actually revised. If the criteria is less stringent, a substantial cost savings should be realized. The total impact of the change must be evaluated; but initial costs are generally offset by significant savings in operations, procurement, launch stand operation, and logistics.

2. Filtration

Adequate filtration is one of the best means of maintaining system cleanliness and protecting critical components in the system.

The method of filtration employed on the service arms is shown in Figure III-24. The hydraulic supply in the hydraulic charging unit (HCU) has a 144-micron sump filter that filters all hydraulic fluid used in the service arms. The low pressure pump just downstream of this filter is a gear-type pump and the 144-micron filter is adequate. The vendor for this pump maintains that the pump will operate satisfactorily at Level 9 of NAS 1638 (commercial cleanliness). The high pressure pump inlet, and the pump bypass back to the reservoir, are individually filtered to 10 microns nominal. The hydraulic supply to the service arm consoles is also filtered to 10 microns. The hydraulic return drain to the HCU reservoir is filtered to 10 microns by means of a large depth-type filter. Filters are located within the service arm systems to protect critical components.

Filters for the service arm pneumatic system are located at the console inlets on each level. All pneumatic supplies, with the exception of the 125 psi nitrogen system, are filtered to 10 microns nominal. The 125 psi nitrogen system does not contain any critical components and no additional filtration is recommended. Numerous samples taken in the pneumatic headers to the service arms indicate no particles over 140 microns, with only one to five particles in the range of 50 to 140 microns. Small filters are contained within the pneumatic systems to protect individual components.

The majority of the filters in the system are of the single element in-line type installed in hard piping installations. These filter elements are difficult to maintain and the system will generally receive contamination from the atmosphere unless special protection is provided during checkout. We recommend that dual-element or T-type filters be considered for future design applications.

In our experience, dual element filters have been found to offer several advantages, and the literature reviewed substantiates this position. A typical hydraulic system dual element filter consists of a 15-micron (absolute) primary element backed up by a 3-micron (absolute) secondary element that can effectively control silting contamination. Filters are proportional devices and most manufacturer's define nominal rating as the ability to trap 98% of particles of the rated size or larger. Absolute ratings are generally interpreted at 100%; however, the possibility exists of passing fiber-type contaminants longer in dimension than the absolute rating, but smaller in diameter. With a dual element device, increased turbulence and double filtration effectively increases filtration reliability. Except in extraordinary circumstances, the secondary element need never be changed; the primary element can be readily changed without mechanically disturbing the system or exposing the system to external contaminants. This is the primary advantage of the device. These advantages accrue with little additional expense.

Under circumstances where continuous high flowrates are involved, the dual element-type filter would be more effective when used for critical component protection, with a much coarser filter used off the header supply. However, in the service arm systems, supply flowrates are relatively small and infrequent, and maintenance would probably not be excessive if the device were used off the header as a blanket system protector.

Components that are particularly sensitive to contamination should be protected by filtration just upstream of the component. If the component does not see large quantities of fluid, an integral filter screen (Fig. III-25) contained within the component may be considered. Integral screens should have ample area and sufficient structural backup to prevent loading, $\angle P$ buildup, and subsequent rupture of the screen. Fitting-type screens (Figure III=25) are not recommended. During the contamination tests conducted on this contract, all of the fitting-type screens failed. These screens do not contain sufficient area and often will rupture and proceed down the system, with the possibility of a major contamination failure downstream. Another disadvantage of these screens is that in normal operations they are never maintained or cleaned.

The majority of the filters contained in the service arm systems are manufactured by Fluid Dynamics. A bubble point tost for verification of the filtration level is performed after they are manufactured. The filters are then cleaned by another vendor, but are not bubble point tested after cleaning. Our experience has shown that it is necessary to perform a bubble point test after any cleaning operation and prior to usage in order to verity the integrity of the filter and its stated filtration level. Also, it is mandatory to perform a bubble point test after an element has been in service, cleaned, and is being placed back in service. We recommend that the above practices be instituted for the service arm systems.

The HCU reservoir is filled with MIL-H-5606 hydraulic fluid trom drums by means of a hand pump. The oil is introduced into the HCU return line downstream of the filter; thus no filtration of the oil is accomplished upon resupply or initial fill of the hydraulic reservoir.

Considering the volume of the reservoir and the particulate contamination allowable in the MIL-H-5606 oil specification, the quantities of particulate that could be introduced into the reservoir in a single fill operation are given in Table III-5.

| Particle Size Range (Microns) | 0-5 | 5-15 | 15-25 | 25 - 50 | 50-100 |
|----------------------------------|-----------|------------|------------|----------------|---------|
| Number of Particles | Unlimited | 47,200,000 | 18,900,000 | 4,720,000 | 472,000 |

Table III-5 Potential Reservoir Fill Contamination

111-10

None of the particles smaller than 10 microns will be removed by the service arm hydraulic system filters. Martin Marietta recommends that all hydraulic oil introduced into the HCU reservoir be filtered to 3 microns.

Contamination tests were conducted on critical service components as the last phase in this contract. The major conclusion reached in these tests was that the 75M08829 pressure regulator is highly sensitive to contamination. The failure mode was erosion of the main poppet stem seat, as a result of the high velocities across the small seat. This conclusion would also apply to all regulators in the service arm systems that have a similar configuration, namely, the small seat area with attendant high velocities.

To alleviate this condition, these regulators may either be replaced or protected by adequate filtration just upstream of the component. We recommend that the problem be corrected by filtration. A careful analysis of the service arm systems revealed that the majority of these regulators were located in close proximity to the filters at the inlet of the consoles and were the first components downstream of these filters. These regulators will be adequately protected by the 10-micron filters. The following regulators are not protected by adequate filtration.

| Specification | Location |
|----------------------|---------------------|
| 75M08830-2 | A5657-4, -5, -6, -7 |

Martin Marietta recommends that 10-micron absolute dual-element filters be installed just prior to the above regulators. This recommendation is made even if the relaxed cleanliness levels, described in this report, are not implemented. The present cleanliness levels of the service arm system (reference Tables III-7 and III-8) are dirty enough to warrant this recommendation.

This study did not include an investigation of the contractor equipment that interfaces with the service arm systems. If the relaxed cleanliness levels described in this report are implemented, the contractor interface specifications should either be revised or adequate filtration should be required in order to protect their equipment.

3. General System Problems

The previous discussion on filtration concerned particulates as a detrimental form of contamination. Another important consideration in hydraulic and pneumatic systems is the elimination

of moisture. In the service arm system, the reservoir of the hydraulic charging unit is vented to atmosphere, with no adequate means for preventing the entrance of moisture and salt-laden air. This is felt to be a significant contributing factor to problems that were identified with fungi in the system and corrosion in accumulators and cylinders.

A contaminated hydraulic oil sample was taken from the hydraulic charging unit on mobile launcher No. 1 in January 1969. The sample contained approximately one to two handfuls of a gummy contamination best described as having the appearance of "strawberry jam" of a thick, gummy nature. A chemical analysis was conducted by NASA and the contamination was reported to be a cellulose fiber, but it was not determined whether it was organic or synthetic. There was a small trace of calcium, zinc, and iron.

Since the analysis indicated a fibrous material, the hydraulic system and reservoir mist filter were inspected to determine if any system degradation had produced a "fibrous" material. The inspection did not reveal any degradation or any other contamination in the reservoir vent system or on the hydraulic system filter.

After reviewing the results of the chemical analysis, it appeared that the chemical analysis could be supplemented by a biological analysis, and such an analysis of the contamination was conducted in the Space Biomedical Research Laboratory of Martin Marietta. The analysis concluded that:

"Microscopic examination of the contaminated hydraulic oil sample revealed the presence of branched filaments (Fig. III-26) characteristic of fungi mycelium. An attempt was made to demonstrate the presence of viable fungi. Standard bacteriological culture media (Sabouraud's dextrose agar, trypticase soy agar and nutrient agar) were inoculated with samples of contaminated oil. After 48 hours incubation at 32°C, typical fungal colonies were evident. Thus, using preliminary data as a basis, it is believed that the oil contaminant is a fungus."

Additional tests were performed on the fungi culture. We were unable to produce a culture in clean MIL-H-5606 hydraulic oil, but were able to produce a culture in plain tap water under the oil. There are four distinct classes of fungi; this particular fungi was isolated to the Fungi-Imperfectii class. Lack of information on structure and presence of fruiting bodies prevented an accurate classification within its individual class without further tests which were beyond the scope of this contract.

Two other contamination samples tenatively indicate the presence of viable organisms in other portions of the hydraulic system - on different mobile launchers. A 0.25-inch elogged hydraulic line was reported on service arm 6, mobile launcher #2 on 12 July 1968. The substance in this line was reported to be a "black gummy mass". Failure analysis conducted by the NASA Materials Analysis Branch reported that the material consisted of stainless steel corrosion products (Fe-0; and Cr_2O_2). The description of a "black gummy mass -- or sludge" related very closely to a viable bio-organism which a biological analysis may have verified. There was no indication, in this sample, of any products resulting from the degradation of elastomers.

A hydraulic oil sample was taken on 26 February 1969 from the hydraulic charging unit reservoir on LUT 2. In addition to particulate contamination found in the sample, it was reported that a "long fiber of pale green jelly" was present in the sample. No biological tests were performed on this sample. If the visual description was accurate, it may also indicate the presence of viable organisms in the hydraulic system.

Viable organisms could have been introduced into the system in a variety of ways; either by atmospheric means, by external means (components, maintenance, etc.), or transported into the system while the hydraulic oil supply was being replenished. All organisms require water to maintain their viable state; others require nitrogen or oxygen in addition to water.

Viable organisms cannot be sterilized by a normal component cleaning procedure. They can be sterilized by either applying heat-steam or by the use of biocides. The applications of heatsteam to the service arm systems is not satisfactory because of the detrimental effects to elastomers and components. Complete elimination of water vapor from the system is a very difficult task and generally can only be accomplished by a vacuum technique.

Viable organisms have caused problems in other systems such as jet fuel tanks, and the problem was solved with biocides. To our knowledge, only one study has been directed towards the use of biocides to control fungi in hydraulic oil. This study was performed in England on a hydraulic oil different than MIL-H-5606. The use of biocides is common knowledge; but its effect on the hydraulic oil, elastomers, and components in the system has not been investigated. Further study is recommended in this area of technology to combat fungi formations in hydraulic oil.

ITI-13

The mass transport of fungi from one part of a system to another can be prevented by the use of filtration techniques. Five-micron nominal (or less) filtration is required; the minimum filtration level in the service arm systems is 10-micron nominal.

It is our recommendation that the vent-to-atmosphere on the hydraulic charging unit reservoir be eliminated. This vent should be replaced with a small positive pressure nitrogen system (with pressure relief capability) to prevent water vapor from entering the hydraulic system. A closed system is recommended to prevent degradation from corrosion and to eliminate conditions conducive to the propagation of viable organisms.

Moisture will enter a hydraulic or pneumatic system by a diffusion process unless a positive pressure is maintained on the system. The service arm systems are pressurized only during test operations and in the launch countdown. No attempt is made to maintain positive pressure on the system during the long interval between launches. It is recommended that a small positive pressure be maintained on the nitrogen system to prevent migration of moisture and particulate into the system through relief ports, calibration fittings, bleed orifices, etc. It is further recommended that the hydraulic system be fully blanketed with hydraulic oil at a small positive pressure to prevent atmospheric contamination and drying out of the seals. Elastomers in a hydraulic system will dry out, leak, and deteriorate from age if not blanketed with oil.

The history of component failures on the service arms indicates that the single largest contamination failure is corrosion of electrical contacts. Most of the electrical components are located in the service arm consoles. The consoles on the service arms are not purged with nitrogen and are not adequately sealed to prevent moisture from entering the consoles. Further, inspection of the service arms revealed that the doors on the consoles are often left open between launches. Again, the least expensive method of preventing corrosion caused by atmospheric moisture is to maintain a positive pressure (0.5-inch water gage) within the service arm consoles. This can be accomplished with dry nitrogen or air. On a system as large as the service arms, a compressordry-air system would probably be more economical than the use of nitrogen.

The service arm hydraulic system is essentially a dead-ended system and cannot be thoroughly flushed in the event the system were to become heavily contaminated. On future designs, a flushthrough capability should be provided.

The hydraulic oil used in the service arm systems is MIL-H-5606. Our experience has shown that MIL-H-6083 hydraulic oil is superior to MIL-H-5606 and has two distinct advantages: (1) MIL-H-6083 contains a rust preventative as an additive; (2) conglomeration of fine particles will not occur in MIL-H-6083 as they will in MIL-H-5606 hydraulic oil. The properties of MIL-H-6083 are very similar to MIL-H-5606, and no compatibility problems exist. Residual MIL-H-5606 hydraulic oil in a system need not be completely eliminated prior to adding MIL-H-6083. Literature comparing the two is available; no unfavorable accounts were found during our review.

4. Sampling Procedures

Meetings were conducted throughout the course of the contract with those personnel in NASA, Boeir, and Bendix who were directly associated with, or responsible for, sampling procedures, analysis, and contamination control. The following samples are normally taken on the service arm systems:

- <u>Hydraulic Charging Unit</u> Two samples are taken at the HCU during validation procedures. These are dynamic samples taken while the system is running. Samples are analysed for acid base, moisture, and particulate. Critiera for moisture are taken from MIL-H-5606B and criteria for particulate are taken from both MIL-H-5606 and 75M09467;
- 2) <u>Resupply Fluid</u> Hydraulic fluid received in drums is not sampled for moisture content. Problems have arisen in meeting 75M09467 particulate criteria when sampling the drums. The HCU reservoir is filled from the drums by means of a hand pump that does not meet cleanliness criteria, and fluid is introduced into the HCU return line downstream of the filter;
- 3) Service Arm Hydraulic System The hydraulic systems on the service arms are sampled during validation procedures to level II of 75M09467. Samples are taken with pressure on the system at (a) both sides of the arm retract cylinders -- upper and lower hinges; (b) test port of the secondary retract gage; and (c) the hydraulic standby (70 psi) system on the hydraulic side;
- 4) <u>Pneumatic System</u> The service arm pneumatic systems are not normally sampled as part of any standard procedure unless "contamination is suspected" or component failures indicate contamination. When samples are taken, level IV of 10M01671 is used for criteria. The pneumatic header is sampled during the validation procedures.

Specification 75M09467 is used as criteria for all service arm hydraulic system samples. This criteria document was not referenced in the contract and was not specified in any of the engineering documentation reviewed during the contract. The cleanliness levels in this document are considerably relaxed as compared to the other existing service arm cleanliness criteria. The specification was orginated at Marshall and was reportedly used on Saturn I. Particulate criteria excerpts from 75M09467 are given in Table III-6.

| Usage Micron Range | I Servo Valves and Close Tolerances | II Actuators and Cylinders | III Accumulators and Reservoirs |
|--------------------------|---|----------------------------------|---------------------------------------|
| 10-25 | 5,360 | . 23,680 | 42,000 |
| 25-50 | 780 | 3,640 | 6,500 |
| 50-100 | 110 | 555 | 1,000 |
| 100-150 + fibers | 11 | 52 | 92 |
| 150 + | 0 | 0 | 0 |

Table III-6 Particulate Criteria (75M09467)

In meeting with the various operational groups concerned with the service arm samples, it was apparent that a group responsible for a p_{ℓ} ticular arm did not know what procedures or criteria were being used for the other arms on the tower. The requirement to take a sample, and the governing criteria for each sample, are only spelled out in each respective operational test procedure. There is no composite correlation of the samples taken on the Saturn V launch stand.

The operational groups were of the opinion that the present cleanliness levels were too stringent. No quality controls were found to exist that specified a "no-go" situation when a system did not meet specification. It was noted that up to three samples were taken on the same system before criteria would be met.

Tables III-7 and III-8 show the results of hydraulic samples taken in the HCU and on the service arms. Figure III-27 depicts these results graphically.

Fifty-six samples from the nitrogen distribution system were reviewed and each sample showed only 1 to 5 particles in the range of 50 to 140 microns, with no particles above that range. An extensive blowdown of the system is performed prior to taking the pneumatic samples in the distribution system.

| | | | | | Particle | Size | Range (Micron) | (uc | |
|----------------------------|--------|------|---------------|---------|----------------|----------|----------------|------------|--------------|
| | | | | | | | | | Maximum Size |
| | | | | 5 to 15 | 16 to 25 | 26 to 50 | 51 to 100 | 100+ | (Microns) |
| Specification Criteria Use | Used N | 1L-H | d MIL-H-5606, | 2.500 | 1,000 | 250 | 25 | 0 | |
| тт талап | | | | | | | | | |
| Samples taken at: | LUT A | Arm | Date | | | | | | |
| Bleed Riser #3 | 2 | 9 | 7-9-68 | 17,098 | 500 | 380 | 85 | 19 | |
| Valve ≓5550 | | | | 110,136 | 38,688 | 33,072 | - <u>'</u> 3 | \ † | |
| Deceleration Valve-L | | | | 6,634 | 3,658 | 1,612 | 176 | 76 | 1100 (fiber) |
| Deceleration Valve-R | | | | 3,307 | 1,934 | 1,054 | 338 | 412 | 700 (fiber) |
| Lower Hinge Rod End | | | | 10,220 | 6,494 | 239 | 25 | 19 | 200 |
| Bleed Riser #1 | | | | 275,808 | o , 739 | 4,368 | 151 | 6 | |
| Bleed Riser #2 | | | | 3,295 | 918 | 144 | 13 | 25 | 200 |
| Upper Hinge Blind End | | | | 133,229 | 42,900 | 21,060 | 12,012 | 73 | |
| Upper Cylinder Rod End | | _ | | 338,208 | 132,912 | 36,504 | 1,089 | 0′ | |
| Lower Cylinder Blind End | | | | 10,390 | 3,879 | 238 | ,† 6 | 107 | 500 |
| | | | | | | | | | |

.

Table III-7 Service Arm Hydraulic Samples

K.

•

•

.....

MCR-69-484

ITT-17

| Specification Criteria Used 75M09467 | | | | | | | | | • |
|---|--------|---------------------------|--------------|----------------|--------------|------------|------|---------------------------------|---|
| fication Criteria U 75M09467 | | | 10 to 25 | 25 to 50 | 50 to 100 | 109 to 150 | 150+ | Maximum Size | |
| | | Level (II) Level (III) | 3,68 2,00 | 3,640 6,500 | 555 1,000 | 52 92 | 00 | 1 8 | |
| Sample taken at: LUL | Arm | Date | | | • | | (| | |
| A5550-6 1 | 9 | 2-3-68 | TNTC | 2,870 | 98 | × | Ç | | |
| A5414-6 1 | 9 | | 9,204 | 476 | 30 | 'n | 0 | | |
| A5326-1 1 | HCU | | 13,790 | 81 | 2 | 0 | | 240 | |
| A5338-1 | | | 12,667 | 82 | 7 | 2 | 0 | | |
| A5375-1 | | | 12,854 | 124 | 6 | 0 | 0 | | |
| A5206-0 | | | 8,923 | 62 | 1 | 0 | Ģ | | |
| A3320-2 | | | 14,976 | 381 | 25 | £ | 0 | | |
| A5375-1 | | | 36,504 | 102 | 'n | 0 | 0 | | |
| V 1-0200 | | - | 12,602 | 140 | 6 | 0 | 0 | 007 | |
| A5450 2 | - ~ | 6-27-68 | 890 | 98 | T | 0 | 2 | - | |
| A5403 2 | 5 | 6-27-68 | TNTC | 466 | 108 | 13 | 7 | 1,200 (fiber) 210 (particle) | ~ |
| A5/15 3 | 4 | 12-31-68 | TNTC | TNTC | 187 | 13 | 80 | | |
| 2713 | 4 | | 53,040 | 10,764 | 5,304 | 109 | 78 | | |
| A 5 5 50 | 4 | | 12,792 | 102 | 23 | 2 | 0 | | |
| DECCH | وب | | 11,887 | 1,123 | 50 | 12 | 0 | | |
| | و ز | | 3,058 | 624 | 9 | 2 | 0 | | |
| | و | ->- | 7,051 | 624 | 24 | 3 | 1 | |] |

Table III-8 Service Arm Hydraulic Samples

.

;

Į.

:

III-18

MCR-69-484

TNTC - To Numerous to Count

Bendix takes samples only when a request is received from the contractor. No conclusion is made by Bendix as to whether the sample meets specification. Hydraulic samples are taken by the open-bottle technique with the volume ranging from 100 to 1000 ml depending upon the contractor's request. Gas samples are taken by the Millipore method with flow volumes of 30 to 130 SCF. A contamination precount is made on both the open bottle and Millipore pad prior to taking a sample. Bendix prefers the open-bottle technique rather than a Millipore bomb because they believe the connection that must be made with the Millipore bomb introduces more contamination. Extensive tests conducted by Martin Marietta on Titan vehicles has proven the reverse; that less external contamination is introduced in using the Millipore bomb, and results are more consistent.

Bendix was questioned as to problems encountered in cleaning components and systems to the KSC-123 specification. They stated that no problems were generally encountered in cleaning components to Level IV of KSC-123, but some problems occurred in cleaning systems to the same level. They also stated that Level I of KSC-123 presented many problems and subsequently required more effort in cleaning, particularly with more complex components.

The sampling procedures used on the service arm systems are believed to be inadequate to ensure an acceptable system cleanliness status throughout all phases of operation. The following procedures are deemed necessary to ensure good practice in this regard:

- Nitrogen samples stand be taken on the service arm systems on a regular basis and as part of a standard procedure;
- 2) Scheduled hydraulic and pneumatic samples should be taken during the long intervals between launches, or during down-mode;
- Hydraulic fluid transferred from drums to the HCU reservoir should be filtered prior to entering the HCU;
- Hydraulic fluid should be received (as validated) as meeting the MIL-H-5606B specification;
- 5) A standard sampling procedure should be initiated to coordinate all of the samples taken on Complex 39. This procedure would serve to combine all sampling information and criteria into one central document and would eliminate confusion among different groups. The procedure should list fluid commodity, sample port location, the method used for the sampling, and the criteria for the sample;

6) No quality controls were in evidence in the event a sample did not pass criteria. Sample reports should be controlled by quality control and a resolution made if the sample does not meet criteria.

5. System Orifices

Orifices are one of the more important factors to be considered in the analysis of cleanliness levels for fluid systems. An analysis was performed on all of the orifices in the service arm systems as part of this study. Table III-9 presents a compilation of all of the orifices, both hydraulic and pneumatic, that exist as individual find numbers in the service arm systems. The table presents each orifice diameter in inches, and the equivalent micron size.

| Item-Find Number | Specification Number | Service Commodity | Diameter (in.) | Diameter (microns) |
|---------------------|-------------------------|----------------------|-------------------|-----------------------|
| A-5469 | 75M04165 | Hydráulic | 0.020 | 508 |
| A-29601 | 75M04165-2 | Pneumatic | 0.030 | 762 |
| A-5872 | 75M21479-7 | Pneumatic | 0,1406 | . 3,570 |
| A-5873 | 75M21479-7 | Pneumatic | 0.1406 | 3,570 |
| A-5738 | 75M50184-1 | Hydraulic | 0.114 | 2,895 |
| A-5644 | 75M50184-6 | Hydraulic | 0.030 | 762 |
| A-5648 | 75M51695-2 | Hydraulic | 0.030 | 762 |
| A-34762 | 76K00189-1 | Pneumatic | 0.077 | 1,955 |
| A-34765 | 76K 00189-1 | Pneumatic | 0_077 | 1,955 |
| A-34815 | 76K00189-1 | Pneumatic | 0.077 | . 1,955 |
| A-35730 | 76K00189-2 | Hydraulic | 0.043 | 1,092 |
| A-35731 | 76K00189-2 | Hydraulic | 0.043 | 1,092 |
| A-34951 | 76K03578-1 | Pneumatic | 0.047 | 1,193 |
| A-34971 | 76к03578-9 | Pneumatic | 0.093 | 2,360 |
| A-34989 | 76к03578-12 | Pneumatic | 0.040 | , 1, 016 |
| A-5594 | | Hydrualic | 0 .450 | 11,430 |
| A-5865 | | Pneumatic | 0.030 | 762 |
| A-5973 | | Pneumatic | 0.030 | 762 |

Table III-9 Service Arm Orifice Size Tabulation

The smallest diameter in the service arm system is 0,020 inches, or 508 microns. This orifice was included in the contamination tests (see Chapter VII) and the orifice did not clog even though particles up to 1000+ microns and fibers (up to 2000+ microns) were injected into the test system.

Our conclusions, backed up by test, are that the orifices in the service arm systems are not too small; even with the new cleanliness level recommended by this study.

At this juncture it should be recognized that factors other than the absolute orifice diameter must be considered when evaluating the possibility of orifice clogging. Some of these factors are:

- 1) Particle shape. If all particles were of a hard spherical shape, the orifice diameter would be the limiting factor. This, however, is practically never the case; and since current measuring practice gages the longest particle dimension, the probability is quite high that a given particle would pass through an orifice even though its longest dimension is greater than the orifice diameter. In low velocity hydraulic systems, fibers will form a mat, thus acting as a screen that traps smaller particles resulting in a clogged orifice. However, this circumstance should be minimized by the application of adequate filtration techniques;
- 2) Particle composition. Ordinarily, typical contamination is composed of both hard (metallic) and soft (organic) materials. Depending on the fluid velocity within the system, softer particles larger than the orifice diameter will be extruded through an orifice. Harder particles will not pass through an equivalent orifice size;
- 3) <u>Particle Density</u>. In gaseous systems, high-density particles tend to settle out in traps inherent in the system, due to large density ratios between the particle and the gas. Fibrous-type contamination would more likely be entrained in the fluid stream. In hydraulic systems where the fluid density is more nearly the same as that of the particulate, much less settling can be expected and entrainment should be considered to be predominant.

When design requirements dictate the use of orifices that are within the size range covered by cleanliness requirements, a method that should receive consideration is the use of series orifices. This technique involves placing two or more larger orifices in series to achieve the same flow-limiting effect as would be obtained from one very small prifice. Low-flow hydraulic systems are felt to be most deserving of this approach; pneumatic systems with attendant high fluid velocities are much less prone to buildup or nesting of particulate contaminates,

6. Service Arm Cylinders

The major service arm component problems associated with contamination that were identified to us by NASA involved cylinders and accumulators. These problems were not a direct result of particulate, but rather resulted from internal corrosion products and deteriorated seals. The causes of such difficulties were:

- 1) Inadequate removal of cleaning solvents;
- 2) Lack of blanket pressurization;
- 3) Improper lubrication during reassembly;
- 4) Seal damage during assembly.

Making the assumption that these factors are controlled, the critical failure mode for cylinders and accumulators is a piston sticking due to massive amounts of particulate contamination.

The cylinder force analysis (Table III-10) was conducted to determine the probability of a piston becoming stuck in one position due to contamination. Using the appropriate inlet pressures, calculations were conducted to determine the hypothetical thickness of material that could be sheared. The numbers tabulated in the "Shear Capacity" column of Table III-10 reflect a circumferential band of metallic material, having a shear strength of 100,000 psi, that could be sheared by the forces available on the piston. This analysis is theoretical, and only presents a relative gage in evaluating the forces present in each cylinder since the shear strength of contamination is a variable and has not been determined with any degree of accuracy. As can be seen from the tabulation, significant thicknesses would represent such massive amounts of contamination that this failure mode is considered to be an extremely remote possibility. This analysis only considers the forces necessary for a piston to become stuck on one position, and does not relate to the shearing of seals due to contamination.


| 1 | Tapte TTT-TO | | | | | | 5 - F | r to a t |
|--------------------------|--|--|-----------------------------|---|------------------------------|-----------------------------|---------------------------------------|------------------|
| | Item-Find Number | Specification Number | Service Commodity | Piston Eud Pressure (psi) | Rod End Pressure (psi) | Piston End Force (1b) | Koa Enu Force (1b) | Capacity (in) |
| Cable | | 15000001 | nitrogen, hudraulic | 000£ | | 115,300 | 1 | 0.0524 |
| Retract | A-2383 | TCZOUNC/ | 11 yuuuuu | | | | | |
| Upper and Lower Hinse | A-5497 A-5492 | 75M09362 | hydraulic | 3000 | 30 00 | 150,900 21,200 | i21,800 15,900 | 0.0484 0.0169 |
| | | | | | | | | |
| Carrier | A-5702 | 75M06506 | hydraulic | 3000 | 30 00 | 21,200 | 15,900 | 0.0169 |
| WILIULAW | | | | | | | 1 | |
| LH ₂ , LOX | A-6018 A-6007 | 75M09014 | nitrogen, helium | 1 | 0071 | 1 | 8,520 | 1600.0 |
| MILIULAW | - 2222 W | | | | | | 0 | |
| Line Tray Handling | A-5811 A-5894 | 75M07998 75M07725 | nitrogen nitrogen | 1300 875 | 1300 875 | 12,500 2,750 | 10,900 2,058 | 0.0038 |
| Note: The m | The minimum shear capa | r capacity, 0.00 |)38 inches, | city, 0.0038 inches, is equivalent to 96.5 microns | ıt to 96.5 | microns | | |
| The m repre | The maximum shear represent a conti | The maximum shear capacity, 0.0524 inches, is equivalent to 1330 microns. represent a continuous band of contamination around the cylinder bore, of | 524 inches, contaminatic | 1524 inches, is equivalent to 1330 microns. contamination around the cylinder bore, of | at to 1330 s cylinder | ti ti | These capacities the thickness in- | ities s in- |
| dicated. | ed. | | | | | | | |


Table III-10 Service Arm Cylinder Force Analysis (Catejory A and B Cylinders)

į

:

MCR-69-484







ξ.

•

......

.

÷

.....

;

:




Figure III-2 Service Arm Function, Extend/Retract, Control Console #1, Arms 1, 2






Figure III-3 Service

EOLDOUT FRAME

1.1





Figure III-3 Service Arm Function, Hydro-pneumatic, Arm Extend/Retract, Arms 4, 5, 6, 7, 8

FOLDOUT FRAME 2



FOLDOUT FRAME

ME

T

ELET

t...




Figure III-4 Service Arm Function, Control Console #1, Arm 9 Only

FOLDOUT FRAME 2

Est.

PRECEDING PAGE BLANK NOT FILME

÷

÷

III-31




Figure III-5 ? rvice Arm Function, Cable Retract, Control Console #2, Arms 4, 5, 6, 7, 8

4

111-32

Ę.

:

÷

i

1

;

.

.

.

- T. - 3:

<u>MINAL MOUSTLA CALINGER</u> (AT403-D) - CALAN-D NAE AETRAC4 **—** UPPER MINSE 75MIO314 (45452-3) (4)) CALL D (44413-) LOWES HINGE (A5414- 3) SETRA' Lator-D K \mathbf{e} I 1/2" PIPE -0.2957739 (A285.839-(A79691-3) (429693-3) BANKAL CONTANL ASSEMBLY 751415898 N.C. В æĽ, A29689-3 A/1694-3)--03562PD (<u>U\$6293</u> X (2368) (Z2637-3)-ß 6 (729587-3) 400000 (Z26955) -02612-3 <u>(233)-</u>) A29682-3 3000 PEI HYDRAULIE SUPPLY 4 3/4 THO PH SIL SUPPLY 1/2 HYDRAULIC- NETURN


....

MCR-69-484

Figure 111-6 Service Arm Function, Extend/Retract, Manual Console, Arm 3 Only

ř.

. -



T.

III-33




Figure III-9 Service Arm Function, Latchback Cylinder and Water Quench Valve, Arm 9 Only




Figure III-10 Service Arm Function, Umbilical Reconnect Cylinder, Arm 4 Only

I


:

i

ł

÷

i




III-36

ļ

÷

MCR-69-484



•

1

2

۶.

1

:

.

;

į

1 3


ì

Ő.

M. R-69-484

ŧ









.

:***: *

:






Û


III-39

•

~-,. : ç

ţŻ.





" "MCR=69=484


ł


.

...

III-40

Figure III-16 Service Arm Function, Hydraulic Carrier Withdrawal Cylinder, Arms 4, 5, 6, 7








Figure III-18 Service Arm Function, Service Module Carrier Withdrawal, Carrier Kickoff, Arm 8 Only

.




Figure III-19 Service Arm Function, Coupling Kickoff/Withdrawal, Arm 4 Only

III-43


ŧ

•==== Figure III

20 5 2

•

h



III-44

"

MCR+69+484

6






Figure III-21 Service Arm Function, Tray Withdrawal, Arms 5, 7

÷

...


۰ ۱





III-46

Ì



• •

Figure III-23 Hydraulic Charging Unit

III-48


:


. . .*


:

MCR-69-484

t









Typical Pneumatic System Filtration

Figure III-24 Service Arm Filtration



Ł





١.

.

.

1

£

Figure <u>III-25</u> Integral Filter Configurations







Figure III-26 Fungus Contamination in MIL-H-5606 011

III-50

:



ŧ

į

;

III-51

Figure III-27 Particle Count Analysis Plot (service arm hydraulic systems)

,

۰.

IV. COMPONENT ANALYSIS

In any cleanliness level analysis, a detailed study of the components in the system is recognized as one of the most important functions. The purpose of this component analysis was to (1) determine the degree of complexity and sensitivity of the components; (2) determine those components deemed to be most prone to contamination failures; and (3) select critical components for test.

The categorized component list (Appendix A), developed as part of the systems analysis task, was used as the baseline list of components to be analysed in detail. The components contained therein were determined to be critical to the operation of the service arms and were possible candidates for a contamination failure.

A detailed analysis was conducted on each component to determine its sensitivity to contamination. The final product of the component analysis task is contained in the individual Component Analysis Sheets (Appendix B of this report). Each sheet lists the component specification number, vendor name, vendor part number, component location(s), possible contamination failure mode, and a detailed description of the component relative to contamination.

The following sources of information were used in the component analysis task:

- 1) Component Specifications;
- 2) Compount Engineering Documentation;
- 3) Failure Analysis Summary and Reports;
- 4) Detailed Component Drawings;
- 5) Related Experience;

1

••••

6) Contact with Vendors.

Each component specification was reviewed for materials, lubricant, pressures, flow rates, incended application, and vendor source. The failure analysis sheets were reviewed in detail to ascertain the past history of failures experienced with each particular component. Component drawings were obtained from the vendors and examined in detail. The engineers' experience played a strong role in this task. Basically, their evaluation concerned:

- 1) Past experience with the valve or the particular design;
- 2) Clearances between moving parts;
- 3) Hardness of materials in contact with each other;
- 4) Orifice diameters;
- 5) Seal location and configuration;
- 6) Flow areas and velocities;
- 7) Quantity or volume of fluid as seen by the valve;
- 8) Adaptability to cleaning, dead-legs, etc;
- 9) Actuation forces available;
- 10) Intended design application versus the actual application;_____
- 11) Relation of the component to other components in the system;
- 12) Surface finishes;
- 13) Degree to which the component would generate particulate.

The majority of the vendors of the components in question were contacted to gain specific information as to recommended cleaning levels, part failure history, cleaning procedures, part costs, and cleaning costs.

One comment was expressed by all vendors contacted; that their components used in the service arm systems could be reliably operated at less stringent cleanliness levels than are required by NASA. The Marotta Valve Corporation indicated that they felt their "commercial clean procedure" would yield components that would come very close to meeting the MSFC-164 specification, and that the Marotta components would operate satisfactorily in the service arm systems at this level of cleanliness.

Another fact revealed through vendor contact was that the costs associated with the cleanliness levels now specified for the service arm components were very high. Table IV-1 shows the approximate base cost for the component and the costs for cleaning. It should be noted that a fixed price or "set-up charge" is incurred each time a process is set up to clean a component,

IV-2

whether for one component or for many components. It is recommended that these costs be taken into account when purchasing or cleaning components; thus, it is more economical to clean several components at a time rather than just one component.

| Specification No. | Cost with No Specification Cleaning or Cleanliness Testing (com- mercial clean) | Cost with Specification Cleaning, Cleanliness Tests + Cleaning Setup Charge per Lot |
|----------------------|--|--|
| 75M06116 | \$ 397,00 | \$547.00 + \$175.00 |
| 75M08823 | 380.00 | 530.00 + 175.00 |
| 75M08824 | 265.00 | 310.00 + 175.00 |
| 75M08825 | 31.0.00 | 360.00 + 175.00 |
| 75M08826-X | 2100.00 | 2350.00 + 250.00 |
| 75M08827-X | 2650.00 | 2800.00 + 250.00 |
| 75M08829 | 330.00 | 375.00 + 175.00 |
| 75M08830 | 295,00 | 360.00 + 175.00 |
| 75M08831 | 285.00 | 355.00 + 175.00 |
| 75M08836 | 395,00 | 450.00 + 175.00 |
| 75M09285 | 348.00 | 520.00 + 175.00 |
| 75M10090 | 1350,00 | 1435.00 + 175.00 |
| 75M13255 | 285.00 | 355.00 + 175.00 |
| 75M51630-XXX | 25.00 | 30.00 + 25.00 |
| 76K00187 | 470.00 | 520.00 + 175.00 |
| B10425701-2 | 490.00 | 535.00 + 175.00 |
| Marotta P/N | | |
| 800262-19 | 115.00 | 140.00 + 150.00 |
| Marotta P/N | | |
| 204002 | 90.00 | 110.00 + 150.00 |
| Marotta P/N | | |
| MV 583 | 285,00 | 335.00 + 175.00 |

÷۲.

Table IV-1 Cleaning Costs

Another problem area that was encountered during the course of this study was component cleaning procedures. Several vendors, who were contacted during this study, did not perform their own cleaning operations, either because they did not have cleaning facilities or because their facilities did not meet the requirements of the NASA criteria. The usual case was that the vendor would build the part, assemble it, perform the necessary functional tests, and then send it to another vendor for cleaning.

The vendor performing the cleaning would then disassemble the component, perform the necessary cleaning, and reassemble the component. In the case of some components, no functional tests were performed after the component was assembled. In addition to the expense involved (Table IV-2), the final assembly may be performed by technicians who are not as familar with the component as is the manufacturer. One vendor found it necessary to send a technician along with the part to maintain component integrity on final assembly. The ideal solution would be to select vendors who perform their own cleaning operations.

| Specification No | Base Price | Single Item Clean Cost | Cleaning Costs as a Percentage of Base Price (%) |
|---------------------|------------|---------------------------|---|
| 75M06116 | \$397,00 | \$325.00 | 82 |
| 75M08823 | 380,00 | 325.00 | 86 |
| 75M08824 | 265,00 | 220.00 | 83 |
| 75M08825 | 310.00 | 225.00 | 73 |
| 75M08826 | 2100.00 | 500,00 | 24 |
| 75M08827 | 2650.00 | 400.00 | 15 |
| 75M08829 | 330.00 | 220.00 | 67 |
| 75M08830 | 295.00 | 240.00 | 81 |
| 75M08831 | 285.00 | 245.00 | 86 |
| 75M08836 | 395.00 | 230,00 | 58 |
| 75M09285 | 348.00 | · 347.00 | . 100 |
| 75M10090 | 1350.00 | 260,00 | 19 |
| 75M13255 | 285.00 | 245.00 | 86 |
| 75M51630 | 25.00 | ° - 0 | 120 |
| 76K00187 | 470.00 | 225.00 | 48 |
| B10425701-2 | 490.00 | 220,00 | 45 |
| 800262-19 | 115.00 | 175.00 | 152 |
| 204002 | 90.00 | 170.00 | 189 |
| MV583 | 285.00 | 225.00 | 79 |
| 75M 06606 | 550,00 | 723.00 | 131 |
| 75M10992-1 | 210.00 | 370.00 | 176 |
| 75M10992-2 | 279.00 | 380.00 | 136 |
| 75M08053 | 421.00 | 743.00 | 176 |
| 75M08822 | 2800.00 | 200.00 | 7 |

Table IV-2 Component Cleaning Costs

ŧ

The following 16 components (Table IV-3) were selected for the contamination tests, Task II of this program. Other components were deemed critical but were of the same configuration as those shown below. The cylinders, accumulators, and check valves were not determined to be particularly contamination critical, but did represent the remaining broad categories of components contained in the service arm systems. They were also necessary to complete the test circuits that were representative of the service arm function. The specific details of each component are noted in their respective Component Analysis Sheets, Appendix B.

| Nomenclature | Vendor | Part Number | Similar NASA Part No. | QUy |
|----------------|------------------------------|---------------------|----------------------------------|-----|
| Regulator | Marotta Valve Corporation | 227464-J11 | 75M08829 | 1 |
| Regulator | Marotta Valve Corporation | 219004-J151 | 75M03830 | |
| Regulator | Marotta Valve Corporation | 230904-12 | 75M08831-1 | 1 |
| Solenoid Valve | Marotta Valve Corporation | 806097-1 | 75M08823+1 | 3 |
| Solenoid Valve | Marotta Valve Corporation | 228154-02 | 75M08824+1 | 1 |
| Solenoid Valve | Marotta Valve Corporation | 22 5884-02 | 75M08825+1 | 1 |
| Solenoid Valve | Marotta Valve Corporation | 806098 | 75M09285-1 | 2 |
| Cylinder | Pathon Manufacturing Company | 3H1X3SU101/2 ABR | 7 5N 06506 - 7 | 1 |
| Cylinder | Pathon Manufacturing Company | QU4X3SU191/2 ABR | 75M09014 | 1 |
| Accumulator | American Bosch | ACG300281 | 75M08814 | 2 |
| Check Valve | James Pond Clark | 277-T1-8TT | 75M05365- 4 | 2 |

| Table 1 | IV-3 | Test | Specimens | for | Contamination | Test |
|---------|------|------|-----------|-----|---------------|------|
|---------|------|------|-----------|-----|---------------|------|

IV-5

ŧ.

V. LITERATURE SE RCH

As an intregal part of this study, a literature/industry search was made to obtain available information concerning contamination in hydraulic and pneumatic fluids. Particular emphasis was placed on information relating to contamination levels generally used in equipment and systems similar to those in use at Complex 39, and information concerning the relationship bertween contamination levels and equipment performance.

A computerized literature search was conducted by Martin Marietta and a listing of pertinent articles concerning contemination was obtained from NASA and the Defense Documentation Center. During the literature search 4,892 articles on contamination were surveyed. From this number, 170 articles were ordered through our Library. The abstracts for 43 of the most informative articles concerning this study are included in Appendix C.

Some general conclusions may be reached as a result of the literature search:

- The major body of the literature concerns hydraulies; in particular, servo valves. Almost no information was found on contamination in pneumatic systems. This may indicate that the majority of contamination problems were associated with servo valves and flight control feedback circuits, and that no particular problems have been experienced in pneumatic systems;
- 2) Included in the abstracts are several papers that describe the actual operating contamination levels of aircraft and ground checkout carts. The majority of these samples indicates that aircraft are operating satisfactorily with very dirty systems;
- 3) Very few controlled contamination tests were described in the literature. Many tests have been conducted on filters, but not on components or systems;
- 4) The authors of literature on contamination in hydraulic and pneumatic systems are very definitely divided into two distinct camps --- "clean-clean" and "dirty,"

VI. CLEANLINESS LEVEL RECOMMENDATIONS FOR TEST

In several of the reports and papers reviewed during our literature search, the authors either prefaced or concluded their remarks with a statement to the effect that "there are as many different cleanliness specifications in existence as there are persons writing on the subject." Everyone concerned with cleanliness problems seems to select a level that works in his own experience. All of the major technical societies are deeply involved, with numerous committees and subcommittees striving mightly with the question. Practically every major acrospec firm has its own cleaning specification; the military and the NASA each have several. Any study that undertakes to consolidate and compare this mass of requirements is immediately overwhelmed with the disparities between the various issuing organizations. Evidence of the same diversity of opinion was found during the literature search; those authors concerned with reliable component and system operation praised extraordinary cleanliness, whereas those saddled with the responsibility of attaining, maintaining, and certifying clean hardware or fluids were much less demanding. Both sides of course, can logically justify their positions; this, however, is of little consolation to the person attempting to appraise his own position.

On the following pages all of the pertinent cleanliness information applicable to this program is tabulated. Table VI-1 lists actual specification cleanliness levels from NASA and the Military, as well as recommended standards published by technical societies. Table VI-2 lists information found in the literature concerning various company specifications and successful operating experience. An examination of these tables reveals several areas of particular interest:

- 1) Many conflicting NASA specifications exist, a situation that has been discussed in Chapter III of this report;
- Many of the specifications and standards are closedended, that is, allow zero particles above some cutoff size, whereas others are open-ended, allowing a small number of particles of any size;
- 3) Virtually all of the specifications and literature are concerned with hydraulics -- in fact, during this program practically no information was found regarding cleanliness of pneumatic systems;

VI-1

- 4) All parties apparently use the longest particle dimension as criteria, except North American who uses the smallest dimension;
- 5) All parties rely on manual particle counting methods per ARP-598, except Boeing who relies solely on a mass measurement;
- 6) In general, the specifications and proposed standards contain criteria that are much more stringent than the cleanliness levels encountered in fully operational equipment as reported by several surveys in the literature.

With all of this diverse information in hand, our task was to interpret the specifications with regard to the specific Saturn V service arm systems, and supplement them with other factors that in our opinion are essential to the determination of a satisfactory cleanliness program for any system. The following specifications and factors that were investigated during this task are listed below and are discussed in detail in the following pages:

- Existing NASA and Military specification requirements as shown in Table VI-1;
- Technical Society recommended standards as shown in Table VI-1;
- Company specifications of users in similar applications, as shown in Table VI-2;
- Actual condition recommendations from similar systems as shown in Table VI-2, and actual fluid sample reports from the service arm systems;
- 5) Consideration of the fluids used in the systems, as discussed in Chapter III;
- 6) Consideration of the components and the configuration of the actual service arm systems, as discussed in Chapters III and IV;
- 7) Vendor recommendations and Martin Marietta experience;
- 8) Assessment of the component function and the criticality assigned to that function.

1. NASA and Military Specifications

Six different NASA Specifications and four Military Specifications are listed in Table VI-1.

The NASA Specifications are divided into the following categories:

1) Hydraulic -

75M09467 - Fluid, components, and assemblies, MSFC-166 - Fluid, components, and assemblies;

2) Pneumatic -

10M01671 - Components and assemblies, MSFC-164 - Components and assemblies, MSFC-234 - Liquid and gaseous nitrogen;

Fluids, liquid or gas KSC-C-123 - Components and assemblies.

Cleanliness Specification KSC-C-123 is identical to 10M01671 except that it has been rewritten to be used for either hydraulic or pneumatic applications.

The Military Specifications categories are as follows:

1) Hydraulic -

ORD 10425040 - Components and assemblies, MIL-H-5606B - Hydraulic oil, MIL-H-6083C - Hydraulic oil;

2) Pneumatic -

AFBS 61-3C - Components and systems.

Considering the hydraulic specifications first, we found that in general the component specification sheets originally referenced ORD 10425040. This was, in most cases, later amended to allow MSFC-166 or KSC-C-123 as an alternate. By referring to the tables, it can be seen that appreciable differences exist between these three specifications; the cleaning vendor thus has considerable freedom of choice. Hydraulic fluid from the service arm system samples is normally checked to 75M09467 or MIL-H-5606B which contain still different levels from the three specifications used for component verification.

The criteria for pneumatics are less complex. It was found that most component specification sheets originally called for 10M01671 and were later amended to allow KSC-C-123 as an alternate. However, these two specifications are essentially identical. One or two isolated components were found that referenced MSFC-164; this is a very loose specification and has limited usage... Nitrogen gas is procured per MSFC-234, but no evidence was found of any specifications used for pneumatic system sampling.......

Several components were found for which usage was specified for either hydraulic or pneumatic applications; these generally referenced the 10M01671 specification, later amended to allow KSC-C-123 as an alternative.

All but one of the above specifications (MSFC-166) are closedended; that is, zero particles are allowed above a certain cutoff size. In our experience the imposition of such a requirement, for a system the size and complexity of the service arm systems is very restrictive. The service arm fluid samples that we received through NASA substantiate this position. In many instances, the samples easily met the appropriate specification level, except for one or two particles above the cutoff size. We have found that this condition is virtually impossible to eliminate. An open-ended specification such as MSFC-166, with adequate filtration techniques, was recommended by many of the vendors whom we contacted during this program.

In addition, all of the above specifications except two (MSFC-164, which has very limited usage, and 10M01671/KSC-C-123) are felt to impose restrictions that are unnecessarily stringent for the service arm systems and components. Our experience with hydraulic systems associated with Titan ground support equipment, and numerous surveys on operational aircraft reported in the literature, indicate that much higher contamination levels are tolerable than present service arm specifications allow.

2. Technical Society Standards

The Society of Automotive Engineers (SAE), the American Society for Testing Materials, (ASTM) and the Aerospace Industries Association (AIA) have all been concerned with cleanliness determinations for the past several years. The approach has generally been to establish a particle size/quantity distribution curve by one of several available mathematical methods. The resulting curve, when plotted on log-log² coordinates, is essentially a straight line.

Differing levels are established by creating multiples, such as any successive level doubling the previous one. The slope of the line on a log-log² plot will vary depending on which distributtion curve formula was chosen. Several papers were found in the literature which attempted to prove that one particular curve fitted the available experimental data better than others; this appears to be a very nebulous concept to prove. The various societies have created, revised, and combined several versions, but three have been widely circulated and are constantly found referenced in the literature and in vendor catalogs. These are ARTC-28, NAS-1638, and a combined tentative standard of the SAE, ASTM, and AIA (unnumbered). All of these are hydraulic specifications and are open-ended with a cutoff level at 100 microns. Reference to Table VI-1 reveals that none of these standards agrees with the others, or with any of the Military or NASA specifications. The NAS-1638 is, however, the most widely recognized throughout the industry, and since it contains 14 levels it is also the most widely applicable. It was our decision then that in recommending a cleanliness level, we would attempt to use an ... existing class from NAS-1638 rather than add still another independent specification to the collection already in existence.

3. Industry Specifications

Industry cleanliness specifications are listed in Table VI-2. Without excepti n, the authors s ated that these levels were determined from actual test and experience with specific equipment. General Electric utilizes Levels 6 and 8 directly from NAS-1638. Perusal of this table reveals two generalizations that can be made: (1) the majority of the specifications are openended, again substantiating our position, and (2) the majority of the specifications have cutoff points in the 100 to 300 micron range. All of these companies use the ARP-598 particle counting method except Boeing who, for their GSE, relies solely on mass measurements. Also, all companies use the longest particle dimension except North American, who reportedly utilized the shortest dimension as criteria. While these specifications are quite diverse, taken together they illustrate an industry trend toward open-ended specifications with emphasis on the lower micron ranges, implying reliance on system filtration for removal of the larger size particles.

VI-5

MCR=69=484

4. Operations Experience

During the literature search, four field surveys were found of operational aircraft hydraulic systems; one included several samples from tactical missiles. We have plotted the tabular data from these surveys on log-log² coordinates and superimposed the levels from NAS-1638 (see Fig. VI-1 through VI-4). Figure VI-5 is a similar plot of hydraulic samples taken by NASA at various points in the service arm system. It is re-emphasized that all of these plots represent satisfactorily operating hydraulic systems, the majority of which contain sensitive servo valves that are not present in the service arm system.

As would be expected in such a large sample population, a 'arge variation in system cleanliness is evident. However, the agreement in slope between NAS-1638 and the Kinney, Robinson, and NASA data is quite remarkable. The Parker data, while evidencing a somewhat different slope, still falls well within the range of several levels of the NAS-1638 and could readily be controlled to that criteria.

The correlation between such a large cross section of operational data with NAS-1638 is felt to be another strong argument in favor of using this document as a cleanliness criteria for the service arm hydraulic systems, rather than creating a new specification. Without applying statistical procedures to thisdata, Level.8 is representative of the field samples, as well as an acceptable compromise of the recommendations of both Kinney and Wiley (Fig. VI-4) for avoidance of silting problems. General Electric (Table VI-2) also utilizes Level 8 as an acceptable operational level for their engine controls.

5. Fluid Considerations

Two aspects of hydraulic fluids should be noted with respect to cleanliness level determinations. First, since MIL-H-6083C is a relative newcomer to this technology, the vast bulk of experience noted in the literature is with MIL-H-5606 oil. Because of the presence of the additive methacrylate as a viscosity improver, MIL-H-5606 hydraulic oil has a proved tendency toward particle agglomeration; that is, small particles tend to stick to one another forming, in effect, large particles. Methacrylate is identified as the adhesive. It has been shown that vibration actually aggrevates this phenomenon by increasing the force with which particles strike each other. If the agglomerates are broken up by agitation and then subjected to a further inactive period, they will reform. MIL-H-6083C does not contain methacrylate, and does not exhibit this phenomenon.

VI_6

Second, the corrosion inhibitive properties of MIL-H-6083C are important to the service arm systems from three aspects: (1) the fact that adequate measures are not available for prevention of moisture entrance into the HCU, (2) the fact that thorough system flushing is not possible due to many dead-ended lines, and (3) the long inactive periods between launches. Formation of corrosion products (particulate matter) within the system due to these three factors must be considered as a potential source of contamination problems. Martin Marietta's experience with MIL-H-6083C has been very satisfactory, and literature found on the subject has all been quite favorable.

6. System and Component Configuration

During the first half of this study, the major effort involved detailed studies of the service arm systems and components. Manufacturer's drawings were obtained for many different components, and personal discussions were held with several vendors concerning the operation of their product and its susceptability to contamination. The details of these investigations are fully discussed in Chapters III and IV, but certain aspects relate directly to the determination of a cleanliness level and are reiterated here.

Table III-9 presents a compilation of all orifices, both hydraulic and pneumatic, that exist as individual find numbers in the service arm systems. Diameters are shown both in inches and in microns.. The minimum orifice diameter encountered was 500 microns, which is not too small for the cleanliness levels recommended for the service arms.

Filtration techniques have been discussed in detail in Chapter III of this report. The point to be made here is that a cleanliness level determination cannot be made purely on the basis of orifice diameters or blueprint clearances, but must consider also that adequate and sufficient filtration techniques are employed. In general, the service arm systems contain adequate system filtration. The necessity of opening any given system for component replacement or when taking system fluid samples, plus the probability of internal contamination generation by certain components, demands that filters be included as an integral part of the system design. The presence of adequate filtration is also assumed when open-ended cleanliness specifications are proposed. Other techniques that should be implemented to ensure maintenance of any given level of system cleanliness include the use of blanket pressurization throughout, particularly in the hydraulic reservoir to prevent moisture intrusion, and prefiltering fluid prior to filling or adding fluid to the reservoir.

During the detailed component investigation, only two components were found that contained internal. clearances that might be considered out of the ordinary; both of these are spool-type solenoid-valves, one from Sterer (75M08841) and the other from General Controls (75M08839). Both are used in hydraulic systems. The Sterer valve only supplies fluid to the pilot of another control_valve; thus the flow is insignificant. The General Controls valve is used only in the manual operation system and does not have a failure history. This valve is not a critical component. In spool-type valves, no seals are used on the spool; metal-temetal fit-is relied on to hold leakage to an acceptable level, and as a consequence the clearances are quite small. In such a component, it is contamination in the extremely small range (0 to 5 microns) that should be considered troublesome; the larger particles simply cannot enter the clearance space. However, for silting problems to result from the small particulate, large flows must be present if the contaminate is to build up. Neither of these components is susceptible to these conditions. All other components are compatible to an open-ended cleanliness specification as long as adequate filtration is present.

7. Vendor Recommendations and Industry Experience

During the component investigation, many vendors were contacted by telephone and several were visited in order to discuss in detail the type of construction of their product and its mode of operation. In these discussions, not one single vendor indicated that extraordinary cleanliness procedures were necessary for reliable operation of their components. Many were familiar with MSEC-SPEC-164 and felt that this was a reasonable requirement for pneumatic systems, both from the standpoint of attainability and of reliable performance. This is one of the most liberal NASA specifications, but also the one to which the fewest references are made. Many vendors quote long histories of satisfactory performance on aircraft hydraulic systems where no asprocured cleanliness requirements are imposed. In summary, no data was obtained by vendor contact which indicated a need for presently imposed levels of NASA cleanliness specifications to ensure functional adequacy ... This conclusion includes the Sterer and General Controls spogl-type solenoid valves mentioned earlier.

Martin Marietta has considerable experience with both hydraulic and pneumatic contamination control. Flight control systems for the complete family of Titan vehicles are hydraulic, and include ground charging and checkout equipment. Martin Marietta-designed

VI -8----

Titan vehicle launch stands both at Cape Kennedy and at Vandenberg AFB contain major hydraulic stand actuation systems as well as ground pressurization systems both for ground control purposes and for vehicle requirements. The level of our corporate cleanliness specifications used for the pneumatic applications is similar in content to MSFC-SFEC-164, and our level for hydraulic components is much less stringent than either MSFC-PROC-166 or 10425040 (see Table VI-1). Using these cleanliness levels we have attained an eminently successful record throughout the Titan II weapon system, the Gemini program, and the Titan IIIA, Titan IIIC, and Titan IIIB series of launches for the Air Force.

8. Recommendations for Test

Considerations of all the data and other information obtained during the analysis portion of this program, and a careful weighing of all other factors discussed herein that we feel are pertinent to this question, led us to propose the following cleanliness levels as recommendations to the test phase of this program:

1) Hydraulic Tests

NAS-1638, Level 8

| Size Range (microns) | 0 - 5 | 5-15 | 15 - 25 | 25 - 50 | 50 - 100 | Over 100 |
|--|--------------|--------|----------------|----------------|-----------------|-----------------|
| Quantity per-100 Milliliters of Fluid | . No limit_ | 64,000 | 11,400 | 2025 | 360 | 64 |

2) Pneumatic Tests

Particles

| Size Range (microns) | 0-300 | 3 00 - 500 | 500-1000 | Over 1000 |
|----------------------------------|------------|--------------------------|----------|-----------|
| Quantity per 100 Grams of Gas | Unlimited* | 10 | . 2 | None |

Fibers

| Length (microns) | 0-750 | 750 - 2000 | 2000- 6000 | Over 6000 |
|----------------------------------|------------|-------------------|-------------------|------------------|
| Quantity per 100 Grams of Gas | Unlimited* | 20 | 2 | None |

*Total filterable solids limitation, 0.3 mg/100 grams of gas.

| | | 1 μ | 1 1 | 5µ | ιoμ | | δ0μ | 100, | |
|---|----------|-------------|----------------|-------------------|-----------------------------|--|--|--|-------|
| Hydraulic Specification, NAS 1638, January 1964 | ╺╉╌┼╴ | ╉╇ | | ╉╉┠┺┺ | ┼┈┞┈┞╴ | | ┨╺┠╍┚╼┟╴╹╴┚╶┨╶╽╶╽ | + | 1 |
| Simes 00 | | 17-1 | | | | T | | - | |
| Сіаьз О | | Un1 | imited | | 125 22 | A very a contract to a contract | | 1 None | |
| Class 1 | | - | | | 250 44 | | in product in the second se | 2 None | |
| Class 2 | | | | | 500 89 | T | | 31 | |
| Class 3 | | | | | 000 178 | 37 | | 6 1 > | |
| Class 4 | | | | i | 000 356 | | | 1 2 | |
| Class 5 | ļ | | | (| 000 712 | 126 | 2 | 2 ' | |
| | | | | | 000 1425 | 253 | 4 | 5 8 | |
| | | - | | 10 | 000 2850 | 506 | , | 0 16 | |
| | | | | | 000 5700 | 1012 | 16 | 10 32 | |
| Class 8 | | | | 64 | 000 11400 | 2025 | | 0 64 | |
| Glass 9 | | | | 128 | 000 22800 | 4050 | | 0 128 | |
| Glass 10 | | | | 256 | 000 45600 | 8100 | Contraction of the second s | | |
| Glass 11 | | | | 513 | 000 91200 | 16200 | | 30 512 | |
| Class 12 | | | * | | 0001.82400 | | | 0 1024 | |
| Hydraulic Specification, Tentative Standard | | | | 1 | | | | | |
| (BAE, ASTM, AIA) | | | | | | | | | |
| Class Q | | Π. | | 2700 | 670 | 93 | | | |
| Class 1 | | | | 4600 | A REAL PROPERTY AND INCOME. | Address of the owner | · · · · · · · · · · · · · · · · · · · | | |
| C1468 2 | H. | | | 9700 | 1 | Name of the Owner of the Owne | The second s | 6 5 | |
| Clean 3 | | | - <u>F</u> | 24000 | | New York Control of the State | | 7 | |
| Class 4 | | 11- |] | 32000 | 2 | | ter and the second seco | | |
| Class 5 | -1-1- | ╈╋ | - Gi | <u> </u> | | | | | |
| Class 6 | | ++ | | | | | | - | |
| Class 7 thru 10 | | <u>+-</u> | - | 126000 Ponding | 42000 | . 6500 | 100 | 0 9 2 | |
| Hydraulic Specification, ARTC-28, December 1964 | + | ┿╹┈╸ | - | | | | | | |
| Class 1 | | Un14 | mited | | <u> </u> | | | - | |
| Class 2 | | 0.144 | | TBD | - 220 | | | 5 None +2 | Fiber |
| Class 3 | | + | | TBD | 530 | - 60 | | oli +3 | Fibo |
| Class 4 | | + | | TBD | 1530 | 150 | | 9 1 ····· +4 | Fiba |
| Class 5 | | <u> </u> | | TBD | 5530 | . 420 | | 0 3 +7 | Fiber |
| lydraulic Specification, 75209467, 7 November 1965 | <u>+</u> | ├ ── | | _ TBD | 1650 | 320 | 2 | S None +1 | ?ibos |
| Fluid - GSE | | ┼─── | 40 | | | | | | |
| Fluid Level I | <u> </u> | | Un | Limited | 1340 | 210 | | (Particion + Fibers) 3 | Nona |
| Fluid Lovel II | ┣ | | | ┝-┢────── | 5360 | 780 | | | Nono |
| Fluid Level III - | | | | | 236 90 | 3640 | 55 | | Nona |
| Components | | <u> </u> | | ┝┥──── | 42000 | 6500 | 100 | | None |
| Assemblies | | <u> </u> | | <u> </u> | 1340 | 210 | | | None |
| Assomblies lydraulic Specification, MSFC-PROC-166, 15 March | <u>k</u> | <u> </u> | | * . | 2150 | 530 | | | None |
| 1967 | 1 | 1 | | | | | | | |
| Fluid | <u> </u> | <u> </u> | | | | | | | |
| • | 1 | | Unlimit | ed | 1340 | 210 | 21 | 3 | |
| | | | | | | | | | |
| Components | | | | | 690 | - 100 | | 6 2 | |
| Assemblies | | | | | 690 2150 | <u> </u> | | 2 | |
| Assemblies Bydraulic Specification, ORD-10425041, 25 April | | | * | | | | | 4 | |
| Assemblies Nydraulic Specification, ORD-10423041, 25 April 1960 | | | | | | | | 4 | |
| Assemblies Bydraulic Specification, ORD-10425041, 25 April 1960 Subassembly | | | Unlimit | ed | | | | 4 | |
| Assemblies Bydraulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System | | | Vnlimit | eđ | 2150 | | ·6(| 10 | |
| Assemblies Mydraulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 | | | Vnlimit V. | ed | 2150 | 530 | ·6(| 10 |) Fib |
| Assemblies lydraulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 Particles | | | ŧ | | 2150 | 530 | ·6(| 10 |) Fib |
| Assemblies ydraulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 Particles Level I | | | ŧ | ed Limited | 2150 | 530 | · 60 | 2 None +10 |) Fib |
| Assemblies ydraulic Specification, ORD-10425041, 25 April 1960 Subassembly Assambly and System neumatic Specification, 10M01671, 28 April 1964 Particles Lovel I Level II | | | ŧ | | 2150 | 530 | · 60 | None +10 | |
| Assemblies ydfaulic Specification, ORD-10425041, 25 April 1960 Subassembly Assambly and System neumatic Specification, 10M01671, 28 April 1964 Particles Level I Level II Level III | | | ŧ | | 2150 | 530 | · 60 | 2 None +10 | |
| Assemblies ydfaulic Specification, ORD-10425041, 25 April 1960 Subassembly Assambly and System neumatic Specification, 10M01671, 28 April 1964 Particles Lovel I Level II | | | ŧ | | 2150 | 530 | · 60 | 10 None +10 None | |
| Assemblies ydraulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 Particles Level I Level II Level III | | | ŧ | | 2150 | 530 | · 60 | None +10 | |
| Assemblies ydfaulic Specification, ORD-10425041, 25 April 1960 Subassembly Assambly and System neumatic Specification, 10M01671, 28 April 1964 Particles Lavel I Level II Level III Level IV | | | ŧ | | 2150 | 530 | · 60 | 10 None +10 None | |
| Assemblies ydfaulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 Particles Lavel I Level I Level II Level IV Level V | | | ŧ | | 2150 | 530 | · 60 | 10 None +10 None | |
| Assemblies ydfaulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 Particles Lavel I Level I Level II Level IV Level V Level VI | | | th | limited V. | 2150 | 530 530 40 40 | · 60 | 10 None +10 None 2 1 No 3 40 | |
| Assemblies ydraulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 Particles Level I Level I Level II Level III Level VI Fibers Level I | | | th | | 2150 | 530 | · 60 | 10 None +10 None +10 None 3 | |
| Assemblies ydraulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 Particles Lavel I Lavel I Level II Level III Level IV Level V Level VI Fibers Level I | | | th | limited V. | 2150 | 530 530 40 40 | · 60 | 10 None +10 None 2 1 No 3 40 | |
| Assemblies ydraulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 Particles Level I Level I Level II Level II Level V Level V Level V Level V Level II Level II Level II Level II Level II Level II Level II Level II Level II | | | th | limited V. | 2150 | 530 530 40 40 | · 60 | 10 None +10 None +10 None 3 | |
| Assemblies ydraulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 Particles Lavel I Level I Level II Level II Level V Level V Level V Level V Level II Level IV | | | th | limited V. | 2150 | 530 530 40 40 | · 60 | 10 None +10 None +10 None 3 | |
| Assemblies ydraulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 Particles Level I Level I Level II Level II Level V Level V Level V Level V Level II Level II Level II Level II Level II Level II Level II Level II Level IV Level V Level V | | | th | limited V. | 2150 | 530 530 40 40 | · 60 | 10 None +10 None +10 None 3 | |
| Assemblies (ydfaulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 Particles Lavel I Level I Level II Level II Level VI Pibers Level II Level II Level II Level II Level II Level VI Pibers Level II Level IV Level VI Level VI Level VI | | | th | limited V. | 2150 | 530 530 40 40 | · 60 | 10 None +10 None +10 None 3 | |
| Assemblies ydraulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 Particles Level I Level I Level II Level II Level VI Fibers Level II Level IV Level VI Level VI Level VI Level VI Level VI Level VI Level VI Meumatic end Hydraulic Specification, KSC-C-123, | | | th | limited V. | 2150 | 530 530 40 40 | · 60 | 10 None +10 None +10 None 3 | |
| Assemblies ydraulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 Particles Lavel I Level I Level II Level II Level VI Fibers Level II Level VI Level V Level S Level II Level IV Level V Level V Level V Level V Level S Level IV Level V Level V Level V Level V Level V Level V Level S Level V Level V Level V Level V Level V Level V Level V Level V Level V Level S Level V Level V Level V Level V Level V Level V Level V Level S Level V Level | | | th | limited V. | 2150 | 530 530 40 40 | · 60 | 10 None +10 None +10 None | |
| Assemblies ydfaulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 Particles Level I Level I Level II Level II Level VI Fibers Level II Level II Level II Level II Level II Level II Level VI Level VI Level VI Level VI Level VI Level VI Level VI Subassembly Assembly Subassembly | | | ų. Un Un | limited | 2150 | 530 530 40 40 40 | · 60 | 10 None +10 None +10 None | |
| Assemblies lydraulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System Incumatic Specification, 10M01671, 28 April 1964 Particles Level I Level I Level II Level II Level VI Fibers Level II Level II Level II Level II Level II Level VI Level VI | | | ų. Un Un | limited V. | 2150 | 530 530 40 40 40 10 | | 10 None +10 None +10 None | |
| Assemblies ydfaulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System neumatic Specification, 10M01671, 28 April 1964 Particles Lavel I Level I Level I Level II Level VI Fibers Level II Level II Level II Level VI Fibers Level II Level VI Level V Level V | | | ų. Un Un | limited | 2150 | 530 530 40 40 40 | | 10 None +10 None 2 1 Nc 3 40 None 10 None 10 | 2 |
| Assemblies lydfaulic Specification, ORD-10425041, 25 April 1960 Subassembly Assembly and System "neumatic Specification, 10M01671, 28 April 1964 Particles Level I Level I Level II Level II Level VI Fibers Level VI Level III Level III | | | ų. Un Un | limited | 2150 | 530 530 40 40 40 10 | | 10 2 None +10 None +10 None 2 1 None 40 None 10 | 2 |
| Assemblies Sydraulic Specification, ORD-10423041, 25 April 1960 Subasembly Assembly and System Pneumatic Specification, 10M01671, 28 April 1964 Particles Lavel I Level I Level I Level II Level II Level V Level II Level II Level II Level II Level II Level II Level II Level II Level II Level V Level V Level V Level V Level V Level V Level II Level IV | | | ų. Un Un | limited | 2150 | 530 530 40 40 40 10 | · 60 | 10 2 None 10 None 2 10 None 10 None 10 None 10 None 10 None 10 | 2 |
| Assemblies Bydraulic Specification, ORD-10423041, 25 April 1960 Subassembly Assembly and System Pneumatic Specification, 10M01671, 28 April 1964 Particles Lavel I Lavel I Level I Level II Level VI Fibers Level VI Level II Level II Level II Level II Level II Level II Level VI Level VI Level VI Level VI Level VI Level VI Level II Level IV Level V | | | ų. Un Un | limited | 2150 | 530 530 40 40 40 10 | · 60 | 10 2 None 10 None 2 1 None 10 None 10 None 10 None 10 None 10 None 2 1 No 3 | 2 |
| Assemblies lydraulic Specification, ORD-10425041, 25 April 1960 Subassembly Assambly and System Incumatic Specification, 10M01671, 28 April 1964 Particles Level I Level I Level II Level II Level VI Fibers Level II Level II Level II Level VI Level VI Level VI Level VI Level VI Level VI Level VI Level II Level II Level II Level II Level II Level II Level VI Deutstie and Hydraulie Specification, KBC-C-123, 14.March 1968 Particles Level II Level II Level II Level II Level VI Level VI | | | ų. Un Un | limited | 2150 | 530 530 40 40 40 10 | · 60 | 10 2 None 10 None 2 1 None 10 None 10 None 10 None 10 None 10 None 2 1 No 3 | 2 |
| Assemblies Bydraulic Specification, ORD-10423041, 25 April 1960 Subassembly Assembly and System Pneumatic Specification, 10M01671, 28 April 1964 Particles Lavel I Lavel I Level I Level II Level VI Fibers Level VI Level II Level II Level II Level II Level II Level II Level VI Level VI Level VI Level VI Level VI Level VI Level II Level IV Level V | | | | limited | 2150 | 530 530 40 40 40 10 | · 60 | 10 2 None 10 None 2 1 None 10 None 10 None 10 None 10 None 10 None 2 1 No 3 | _2 |

ľ

- - - -

.

.....

l

MCR-69-484

-

| \$00µ | 200µ 500µ 1000µ | 2000 | |
|---|---|--|--|
| | | 2000, 4000, 5000, | Sample |
| 1 None Z Nono 3.1 | | | 100 m1 |
| 16 1 16 1 17 3 10 5 10 11 12 21 10 41 10 92 Nono +2 12 41 | | | } 100 ml |
| 1 14 Fibers 13 +7 Fibers 14 Nono +1 | | T management of the second sec | } 100 m1 |
| G PERFECTOR 3 None 0 11 None 5 52 None 9 92 None 3 None 3 0 10 None | | | }100 m1 v |
| S.3 | | | 100 m1 V Ét ⁱ Area 100 m1 V |
| None None +10 Fibers | | | 100 ml V 100 ml V |
| None 2 3 2 40 | 1 None 10 3 2 1 40 10 3 2 1 | 1 None | ft ^r Area |
| None10 | I I | 1 None 10 1 None | N/A N/A |
| None | 1 None 10 3 2 1 None 40 10 3 2 1 None 40 10 3 2 1 40 10 3 2 | L None | N/A }ft [#] Arce |

•

T

PRECEDING PAGE BLANK NOT PILME

VI-11 and VI-12

| 11 | | 2000,. 4000µ 6000µ 1 1 1 1 1 1 1 1 1 1 1 1 1 | Samplo Size | Total Filterable Solids (Max) | Application |
|---------|-------------|---|--|--|---|
| | | |) 100 ml Vol | Class 100-0.02 mg/100 ml Class 101-0.05 mg/100 ml Class 102-0.10 mg/100 ml Class 103-0.30 mg/100 ml Class 104-0.50 mg/100 ml Class 105-0.70 mg/100 ml Class 106-1.0 mg/100 ml Class 107-2.0 mg/100 ml Class 108-4.0 mg/100 ml Class 108-4.0 mg/100 ml | Hydraulic Fluid Effluent from Parts, Assemblics, Lincs and Fittings |
| | | |) } 100 m1 Vo1 | N/A L N/A | Glass O - Rarely Attained Glass O - Rarely Attained Glass I - MTG-H-5606B Oil Glass 2 - Good Missile System Glass 3 - Oritical System, in General Glass 4 - Oritical System, in General Glass 5 - Poor Missile System Glass 5 - Poor Missile System Glass 4 - Pluid as Received Glass 7 - Industrial Service |
| | | | } 100 ml Vol | Сідин 11=0,1 пд/]00 m1 Сідин 12=0,3 пд/]00 m1 Сідин 13=0,5 пд/100 m1 Сідин 14=1,0 пд/100 m1 | Glass 1 - Ground Yest Units Glass 2 - Bervo and Powor Bystoms Glass 3 - Acrospace Ground Equipment Glass 4 - Acrospace Ground Equipment Glass 5 - Rofinery Supplied Fluid |
| | | | }100 m1 Vo1 | N/A VA | Components, Assemblies, and Pluids Loval I - Serva Valves Loval II - Actustors and Cylinders Loval III - Accumulators and Reservairs |
| | | | 100 ml Vol ft ^t Area 100 ml Vol | N/A \$ N/A | Components, Assemblies and Fluid |
| | | | 100 ml Vol 100 ml Vol | N/A N/A | Systems, Assemblies and Subassemblies |
| 1d | Nonu 3 2 | 1 None | }Ft ^E Area | 1.0 mg/ft ² 1.0 mg/ft ² 1.0 mg/ft ² 2.0 mg/ft ² 3.0 mg/ft ² | FOLDOUT ERAME Parts, Assemblies, Systems and Subsystems |
| 1 | | 1 None 10 1 None | N/A | N/A N/A | |
| 1 10 | None | 1 None | $\left.\right\} ft^{\psi} Area$ | 1.0 mg/ft ² 1.0 mg/ft ² 1.0 mg/ft ² 2.0 mg/ft ² 2.0 mg/ft ² 3.0 mg/ft ² | Parts, Assemblics, Systems and Subsystems |

| | == | | | 2700 | 670 | J | 931 | 101 | | |
|---|-----------------|-----------------|-------------------------|--|--|--|---|--|------------|-----------|
| Class 1 | | <u> </u> | | 4600 | | | | | T. |] |
| Class 2 | -8- | I, | <u> </u> | 9700 | | | | 28 3 - 56 5 - | | |
| Class 3 Class 4 | | Ľ.∦ | <u>[</u>] | 24000 | TT BALL AND THE REAL | - | | <u>26</u> 5 1011 | | |
| Class 4 | | | (' | 32000 | | and the second sec | | ~ i | | |
| Class 5 | P | Τ | | 87000 | and the second of | | | | | |
| Class 6 | | L | | 128000 | and the second division of the second divisio | | 14 | | | |
| Class 7 thru 10 | | - | | Ponding | + | / | | 4º2 | | |
| Hydraulic Specification, ARTC=28, December 1964 | | • | | (| + | k | - | ŀ | | |
| Class 1 | <u> </u> | Unlimit | ted | TBD | 220 | .T | | - | · • • | |
| Class 2 | | | <u> </u> | TBD | 220 530 | | 20 | 3 None | +2 F11 | |
| Class 3 | | | | ТВР | 530 1530 | | 50 <u>1</u> (| 의 _ | +3 Pil | |
| Class 4 | | | | TBD | | | | 보· _ | | |
| Class 5 | | | + | TBD | 5530 | 1 | | | > +7 Fil | |
| Hydraulic Specification, 75009467, 7 November 1965 | | | + | 1 | 1650 | 320 | 20 25 | 25 None | +1 P11 | -pers |
| Fluid - S6E | | | Un | limited | 1340 | 1 | | + reartic | 100 | - |
| Fluid Level I | | | | | 1340 | 1 | | (Partic) + Fiber | ers) 3 Nor | NB NB |
| Fluid Lovel II | | | + | | 5160 | F | | and the state of t | 11 Nor | ne |
| Fluid Level III . | | | | ~ | 23680 | | The second se | 1 | 52 Non | ne. |
| Componente | | | + | ~~{·~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~ | 42000 | TARGET AND A DESCRIPTION OF TAXABLE PARTY. | | | 92 Non | |
| Assesmilles | | - | + | [| 1340 | The second se | | | 3 Non | ' |
| Hydraulic Specification, MSFC-PROG-166, 15 March | | | + | ····· | 2150 | 530 | 060 | | 10 Nort | |
| 1967 | | | 1 | í ⁷ | 1 | | | | | A |
| Fluid | | Un | limite | | | - | , | 1 | | I |
| Components | | 1711 v. | *188**** | / 4 / | 1340 | The second secon | 28 | 83 | -> | 1 |
| Asaemblies | | | ━┨═┥ | (| 600 | A CONTRACTOR OF A CONTRACTOR O | the second se | 6 2 | | 1 |
| Hydraulic Specification, ORD-10425041, 25 April | | | <u> </u> | + | 2150 | 530 | 0 : 60 | | | 1 |
| ayarautic apacification, unu-lu425041, 25 April 1960 | | | ļ | 1 | | Construction of the owner of the | f | <u> </u> | - <u> </u> | |
| Subasaembly | | tt _n | | 1 | 1 | | | ł | | |
| Assembly and System | | WA + | limite | /d/ | 10 | | 7 | 2 None | | : |
| | | - | | ······ | | 530 | | None | 10 97 | |
| Pneumatic Specification, 10M01671, 28 April 1964 | | | | · | | | <u>+</u> | Num | +10 P1 | .bors |
| . Paritolas Loval T | | | | · | 1 | · · · · | 1 | 1 | | ļ |
| Level I | | | Unl | limited | | 40 | (<u></u> | None | | |
| | | | | | | 40 | 10 3 | Nege | , | 1 |
| Level III | | | | | | | 40 10 | <u></u> | 1 None | 7- |
| Level IV | | | \rightarrow | | | ·, | | | 3 2 | |
| Level V Level V | -+ | | | 1 | | | · | | 40 | |
| Loval VI | \rightarrow | | | | 1 | ······ | | | | - yrand |
| Pibers . | | | | · | (| | (| | | ┹┥ |
| Level I | $ \rightarrow $ | | Unl | limitod | | 10 | , | * | | ļ |
| Level III CLOUUT FRAME | | | | . 1 | | | (| Nona | | |
| | | | | 1 | (| | ·+ | | 10 | |
| Levol IV | | | | + | · | | r+ | | | |
| Laval V | | | | + | | | r | | | |
| Loval VI | | | | • | (| | r | | | <u> </u> |
| Protunatio and Hydrauliu Specification, KSC-C-121, | | | | · | | | | | <u> </u> | لمعلم |
| 14 March 1968 | 1 | | 1 | ļ | (| 1 | 1 | | • | |
| Particlos | -+- | | | | (| | | | | |
| Lovel I | \rightarrow | | Un1/ | limited | · | 40 | 3 1,8 | None | | } |
| Lovol II | | | | 1 | | 40 | 10 3 | 2 | | |
| Level XX | | | | | | | 40 10 | - <u></u> | 1 None | ~ |
| Lovel IV | | | | † | | | | <u>`</u> | <u>/ </u> | |
| Lovel V | | | | | | | | ; | 40 | |
| Lovel VI | | | | ŧ | | | | | | -4 |
| Fibers | | | | <u> </u> | · | | | ······ | | ┻ |
| Level I | | | Un1 | imited | | 10 | | | | |
| Level II | T | | | 1 | | tv | | None | | |
| Level IL1 | 1 | | - | t | | | | <u> </u> | :0 | |
| Level IV | | | + | f | | | | | | |
| Lavel V | | | | + | | + | | | | |
| Lavel VI | | | + | 1 | | + | | | | |
| | | | -+ | 4 | | + | | | | \Box |
| Pnoumatic and Hydraulic Spacification, EPS-90405, | | | | 1 | | | | | | - |
| Martin Marietta | | | | + | | | | | | ţ |
| Martin Marietta Level A (Airborne Hydraulics) | -+- | | ******* 4.h. | | | | 250 10 | 10 | * | 1 |
| Martin Marietta | \Rightarrow | | Unfim | mited | | | | | | |
| Martin Marietta Level A (Airborne Hydraulics) | + | | Unii | m258d | | | | | | ì |
| Martin Marietta Level A (Airborne Hydraulics) Level C Perticles (Ground Pneumatics) Level C Fibers (Ground Pneumatics) | | ······ | | | | | | | | |
| Martin Marietta Level A (Airborne Hydraulics) Level C Perticles (Ground Fneumatics) | | | | | | | | | | |
| Martin Marietta Level A (Airborne Hydraulics) Level C Particles (Ground Fneumatics) Level C Fibers (Ground Pneumatics) Paneumatic, MSFC-8PEC-164, 27 July 1964 | | | | | | | | | | |
| Martin Marietta Level A (Airborne Hydraulics) Level C Particles (Ground Fneumatics) Level C Fibers (Ground Pneumatics) Fneumatic, MSFC-SPEC-164, 27 July 1964 Components Assemblies | | | | | | | | | | |
| Martin Marietta Level A (Airborne Hydraulics) Level C Particles (Ground Pneumatics) Level C Fibers (Ground Pneumatics) Pneumatic, MSFC-SPEC-164, 27 July 1964 Components Assemblies Pneumatic, AFBS Exhibit 61-3C, 5 March 1962 | | | Unlit | imited | | | | | | |
| Martin Marietta Level A (Airborne Hydraulics) Level C Particles (Ground Pneumatics) Level C Fibers (Ground Pneumatics) Pneumatic, MSFC-SPEC-164, 27 July 1964 Components Assemblies Pneumatic, AFBS Exhibit 61-3C, 5 March 1962 Components Particles | | | Unlit | | | | | | | |
| Martin Marietta Level A (Airborne Hydraulics) Level C Particles (Ground Pneumatics) Level C Fibers (Ground Pneumatics) Pneumatic, MSFC-SPEC-164, 27 July 1964 Components Assemblies Pneumatic, AFBS Exhibit 61-3C, 5 March 1962 Components Particles Components Fibers | | | Unlit | imited | | | | | | |
| Martin Marietta Level A (Airborne Hydraulics) Level C Particles (Ground Pneumatics) Level C Fibers (Ground Pneumatics) Encumatic, MSFC-SPEC-164, 27 July 1964 Components Assemblies Pneumetic, AFBS Exhibit 61-3C, 5 March 1962 Components Particles Components Fibers Systems Particles | | | Unlit | imited | | | | | | |
| Martin Marietta Level A (Airborne Hydraulics) Level C Particles (Ground Pneumatics) Level C Fibers (Ground Pneumatics) Pneumatic, MSFC-SPEC-164, 27 July 1964 Components Assemblies Pneumatic, AFBS Exhibit 61-3C, 5 March 1962 Components Particles Components Fibers Systems Particles Systems Pibers | | | Unlit | imited | | | | | | |
| Martin Marietta Level A (Airborne Hydraulics) Level C Particles (Ground Pneumatics) Level C Pibers (Ground Pneumatics) Pneumatic, MSFC-8PEC-164, 27 July 1964 Components Assemblies Pneumatic, AFBS Exhibit 61-3C, 5 March 1962 Components Particles Components Fibers Systems Particles Systems Pibers Nitrogen, MSFC-8PEC-234, 21 September 1964 | | | Unlir Unlir | inited | | | | | | |
| Martin Marietta Level A (Airborne Hydraulics) Level C Particles (Ground Pneumatics) Level C Pibers (Ground Pneumatics) Pneumatic, MSFC-8PEC-164, 27 July 1964 Components Assemblies Pneumatic, AFBS Exhibit 61-3C, 5 March 1962 Components Particles Components Fibers Systems Particles Systems Pibers Nitrogen, MSFC-8PEC-234, 21 September 1964 Type I Gaseous | | | Unlin Unlin Unlin | imited | | and Sking(| | | | |
| Martin Marietta Level A (Airborne Hydraulics) Level C Particles (Ground Pneumatics) Level C Pibers (Ground Pneumatics) Pneumatic, MSFC-8PEC-164, 27 July 1964 Components Assemblies Pneumatic, AFBS Exhibit 61-3C, 5 March 1962 Components Particles Components Fibers Systems Particles Systems Pibers Nitrogen, MSFC-8PEC-234, 21 September 1964 Type I Gaseous | | | Unlin Unlin Unlin | imited | | and Shipping | | lone | | |
| Martin Marietta Level A (Airborne Hydraulics) Level C Particles (Sround Pneumatics) Level C Pibers (Ground Pneumatics) Encumatic, MSFC-SPEC-164, 27 July 1964 Components Assemblies Pneumatic, AFBS Exhibit 61-3C, 5 March 1962 Components Particles Components Pibers Systems Pibers Nitrogen, MSFC-SPEC-234, 21 September 1964 Type I Gaseous Type II Liquid | 40µ F1 | litrátio | Unlin Unlin Unlin | inited | ting Plant | and Shipping (| | lone | | |
| Martin Marietta Level A (Airborne Hydraulics) Level C Particles (Ground Pneumatics) Level C Fibers (Ground Pneumatics) Pnoumatic, MSFC-SPEC-164, 27 July 1964 Components Assemblies Pneumatic, AFBS Exhibit 61-3C, 5 March 1962 Components Particles Components Fibers Systems Particles Systems Pitters Nitrogen, MSFC-SPEC-234, 21 September 1964 Type I Gaseous Type II Liquid | 12µ Fil | lited | Unlin Unlin Unlin | imited | iring Plant | t and Shipping (| | lone | | |

FOLDOIN Larund

:

.

| | | | | | | > 100 ml Vol |
|---|--------------------|---|-------------------|--------------------------|-----------|---|
| +2 Fibers +3 Fibers +4 Fibers +7 Fibers +1 Fibers | | | | | | } 100 m1 Vo1 |
| 128 11 None 52 None 92 None 3 None 10 None | | | | | | 700 ml Vol |
| | | | | | | 100 ml Vol ft ² Area 100 ml Vol |
| : +10 Fibers | | | | | | 100 ml Vol 100 ml Vol |
| 1 None 3 2. 40 | 40 10 | None 3. 2 1 40 10 JT_FRAME 1 None | None 3 2 1 | Nonr | |) ft ^r Area N/A |
| · | | 1 10 | None - 1 10 | Nonel N | ione | N/A |
| 1 None 3 2 40 | 40 10 | None 3 2 1 | Mone 3 2 1 | None | | }ft ² Area |
| | 1 None 10 10 | 1 None 1 1 10 | None1 10 | None 1 No | one | N/A |
| | 10 | 2 | None 20 | | 2 None | 100 ml Vol ft ^{f.} Area ft ^{f:} Area |
| | | | None | 1 None 1 None None | | ft ² Area 1 ft ² Area 2 ft ⁷ Area 2 ft ² Area 2 N/A |
| · | | | | | None None | N/A 100 Licers as Required |
| · | FOIDOR CONTRACTOR | | | | | 100 ml Vol 100 ml Vol |

| \$; ; ; | | | 100 mi Vol | N/A | Class 1 - MIL-H-5606B Oil Class 2 - Good Missile System Class 3 - Critical System, in General Class 4 - Critical System, in General Class 5 - Poor Missile System Class 6 - Fluid as Received Class 7 - Industrial Sorvico |
|---|------------------|--------|--|--|--|
| | | | } 100 ml Vol | Сlакв ll=0.1 mg/100 ml Class 12=0.3 mg/100 ml Class 13=0.5 mg/100 ml Class 14=1.0 mg/100 ml | Class 1 - Ground Test Units Class 2 - Servo and Power Systems Class 3 - Aerospace Ground Equipment Class 4 - Aerospace Ground Equipment Class 5 - Refinery Supplied Fluid |
| | | | }100 ml vol | N/A | Components, Assemblies, and Fluids Level I - Servo Valves Level II - Actuators and Cylinders Level III - Accumulators and Reservoirs |
| | | | 100 ml Vol ft [:] Area 100 ml Vol | N/A V N/A | Components, Assemblies and Fluid |
| | | | 100 ml Vol 100 ml Vol | N/A N/A | Systems, Assemblies and Subassemblies |
| 1 None 1 10 3 2 1 1 None 1 0 1 10 | None None | | ft [:] Aroa | 1.0 mg/ft ² 1.0 mg/ft ² 1.0 mg/ft ² 2.0 mg/ft ² 2.0 mg/ft ² 3.0 mg/ft ² | FOLDOUT. FRAME Parts, Assemblics, Systems and Subsystems |
| <u>1 None</u> <u>1 None</u> <u>1 None</u> <u>1 None</u> <u>1 None</u> <u>1 10</u> <u>1 10</u> | None | - |).ft ² Area N/A | N/A 1.0 mg/ft ² 1.0 mg/ft ² 1.0 mg/ft ² 2.0 mg/ft ² 3.0 mg/ft ² N/A N/A | Parts, Assemblies, Systems and Subsystems |
| 2 None 20 | | 2 None | 100 ml Vol ft ² Area ft ² Area | 2.0 mg/100 m1 2.0-mg/ft ² 2.0 mg/ft ² | Effluent Fluid and Blowdown Gas |
| | 1 None 1 None | | ft ² Area ft ² Area | 1.0 mg/ft ² 1.0 mg/ft ² | Components and Assemblies |
| Xone | None | None | ft ^P Area ft ^P Area N/A N/A | 2.0 mg/ft ² 2.0 mg/ft ² N/A 'N/A | Components and Systems |
| | | | 100 Liters as Required | N/A N/A | Liquid and Gaseous Nitrogen |
| | | | 100 m1 Vol 100 m1 Vol | N/A N/A | Hydraulic Fluid |
| | | | | Contraction Provided | |

| | • | | 1μ | •••••••••••••••••••••••••••••••••••••• | 5µ | 1.0µ | 1 | |
|--|---|--|---|--|-----------------|-----------|-----------|----------|
| F-111 Aircraft Flight Control | | | | | 1 ··· - 1 · | | + | <u> </u> |
| Servo Actuator (Appendix C, Items 42 and 43) | Opérational Le | vel | U | nlimited | | 20, | 000 4,00 | 00 |
| | | | | | | | 1 | |
| General Electric, Engine | | | Ŭ | nlimited | | 16, | 000 2,85 | 50 |
| Hydraulic Control System | System Cleaned | to | U | nlimited | | 64, | 000 11,40 | 00 |
| (Appendix C, Item 19) | Operational Le | vel | | | | | | |
| Titan II Hydraulic | Operational Le | vel Particles | Ŭ | nlimited | | | | |
| Platform Systems | | Fibers | U | nlimited | | | 1 | |
| (Appendix C, Item 5) | | | 1 | | | | <u> </u> | |
| North American | Level 1 | | U | nlimited | | | 1 | |
| (Apollo) | Level 2 | U U | nlimited | | | | | |
| Hydraulic Systems | Level 3 | Ŭ | nlimited | | | | ······ | |
| | Level 4 | | U | nlimited | | | | |
| | Fibers | | U | nlimited | | | | |
| Three Unidentified Airframe | Manufacturer A | | | | | | | |
| Manufacturers. | Manufacturer B | | | limited | _ }_ | | 4,800 | |
| Hydraulic Oil Requirements _ | Manufacturer C | | + | nlimited | | | 00 4,00 | |
| (Appendix C, Item 35) | Manufactorer C | | | limited | | 2, | 500 1,50 | 00 |
| Survey of 143 Navy Planes Hydraulic Systems | | | | ····· | | | | |
| (Appendix C, Item 38) | Personnandad Ta | | Ur | timited | | 87,000 | 21,400 | 2 |
| Contamination in Aircraft Hydraulic Systems, | Recommended Level | | | | | ·· | | |
| Wright Patterson AFB (Appendix C, Item 33) | Maximum_Sampled | | Ut | limited | | 101,300 | 47,150 | 0 |
| (Ai endix C, Item 33) | ; | | | | | | | |
| North American Nitrogen Specification | Ann an a | | | | | | | |
| | ······ | <u> </u> | | limited | | ···· | 10 | _ |
| Convair Hydraulic Specification (Appendix C, Item 45) | | | | limited | | | 9,000 | 0 |
| | Systems | Company | ╏──┤ | | | | | |
| Hydraulic Specifications . | GS E | Boeing · | No Pa | rticulat | l e Requir | ement -We | ight. 0. | .3 m |
| for Servo Systems | New Oil | No Particulate Requirement - Weight, 0.3 m Average of 4 Largest Particles 50µ, None > | | | | | | |
| | A11 | North American | | limited | | | 2,875 | |
| | Missile | Martin-Marietta | Ūn | limited | | | 4,500 | 0 |
| | A11 | ABMA | | limited | _ | | 2,150 | |
| | A11 | SAE | Un | limited | | 50,00 | | - |
| | GSE | Lockheed | فنهد والمتحد والمتك | limited | | | 0 1,25 | |
| | A11 | Westinghouse | f. | limited | | 5,00 | | |
| (Appendix C, Item 29) | Missile Fluid | BuWeps | | limited | | 10,00 | _ | |
| | Flight Control | - | | limited | | | 0 2,50 | - |
| | Missiles | | in the second | rticulat | | | | 1 |

FOLDOUT FRAME

10µ 50µ 100µ 200µ 1 50(20,000 4,000 1,000 55 16,000 2,850 506 90 16 64,000 11,400 2,025 360 64 1,050 250 70 100 10 None 100 10 None 5 1 None Particles + Fibers ,000 4,800 1,200 240 16 4 -10,000 4,000 1,000 100 503 -2,500 1,500 150 20 5 -,000 21,400 3,130 430 41 -,300 47,150 24,380 8,340 3,590 ţ 100 10 5 1 None 9,000 900 90 9 Jone + 1 Fiber - Weight, 0.3 mg/100 m1 ... les 50µ, None >150µ 2,875 1,375 350 100 None (Rated by Smallest Dimension) 4,500 700 450 + 20 Fibers 2,150 530 60 None + 10 Fibers 0,000 20,000 5,000 500 250 . 3,500 1,250 250 25 3 5,000 None 10,000 4,000 1,000 100 50 3 0,000 2,500 500 50 10 - Weight, 0.5 mg/100 ml

.....

.

ŵ

MCR-69-484

ŧ

Table VI-2 Industr




Table VI-2 Industry Experience and Specification


ŧ

VI-13 and VI-14

MCR=69=484

.....

FOLDOUT FRAME



:

:

•

-


:

æ.,

VI-15

Figure VI-1 Particle Count Analysis (31 operational aircraft and missiles)

6



t

Figure VI-2 Particle Count Analysis (11 AF aircraft)

VI-16

.....

đ

.7

1


÷

۰.


....

.

;




VI=17



VI-18

....



.

VI-19

Figure VI-5 Particle Count Analysis (Service Arm Hydraulic Systems)

Į

.....

.

VII. ESTABLISHMENT OF CONTAMINANT CLASSES

Chapter VI describes the methodology used in arriving at the contamination level to be used in the contamination tests. This chapter describes the constituents and quantity of each, used to make up the contamination that was injected into the test circuits.

The following types of contaminant were used to make up the contamination in both the hydraulic and pnoumatic tests:

- 1) A._C. "course" road dust;
- 2) Red iron oxide particles;
- 3) Toflon particles;
- 4) Cotton lintner fibers.

A photograph of each contaminant is shown in Figures VII-1 through VII-4.

The A. C. road dust (Fig. VII-1) is a composite of screened and graded dust particles, primarily quartz. It is natural road dust from Arizona. The basic composition in each size range is:

| Particle Size (microns) | Percent by Weight |
|-------------------------|-------------------|
| G- tro- 5- | 12 ± 2 |
| 5 to 10 | 12 ± 3 |
| 10-to 20- | 14 ± 3 |
| 20 to 40 | 23 ± 3 |
| 40 to 80 | 30 ± 3 |
| 80 to 200 | 9 ± 3 |

The road dust was used because it represents a hard crystalline particle of an irregular shape similar to wind blown atmospheric contamination normally found in fluid systems at Cape Kennedy. It is also comparative to lapping compounds, filter test media, and other contaminants found in hydraulic and pneumatic systems. The hardness of these dust particles will also simulate metal particles.

VII-1




Figure VII-1 A.C. "Coarse" Road Dust - 870X

VII-2

MCR-69-484




Figure VII-2 Red Iron Oxide Particles - 350X

VII-3




Figure VII-3 Teflon Particles - 140X

VIĮI-4




Figure VII-4 Cotton Lintner Fibers - 140X

VII-5

The red iron oxide particles (Fig. VII-2) are uniform spheres approximately 5 microns in diameter. These small spheres were used to evaluate the effects of silting, stiction, and wear caused by small particles. The hardness of these particles is also similar_to-metal.

The teflon particles (Fig. VII-3) are a composite of irregular_ shaped particles ranging in size from 30 to 1000 microns... The teflon represents particles that are internally generated from the many plastic and teflon parts used in the service arm systems as lubricants (base derivative), set is, seats, hose liners, and sealant tape.____

The cotton lintner fibers (Fig. VIL-4) range in size from 50 to 4000 microns and were used to simulate a soft fiber commonly found in atmospheric contamination.

In order to accurately establish the number of particles in. each size range for the total contaminant to be used in the tests, it was necessary to ascertain the number of particles for each constituent as a function of weight. With the exception of the iron oxide, none of the suppliers of contaminant were able to supply this information. The number of particles.per given weight was required in order to establish particle counts and total weight of contaminant per 100 ml of oil or 100 grams of gas. Weight conversions were also required because of the large amounts of contamination. injected in each test; thus a manual microscopic count.would be an extremely lengthy procedure and would not be as accurate.

Automatic particle counters were used to determine particle count for a given weight. The HIAC automatic particle counter was used initially but did not prove to be adaptable to our tests; the ROYCO automatic particle counter was adaptable. The ROYCO counter is based upon the principle of light refraction, and like most counters it integrates the area of each particle and categorizes it as a round sphere in each respective size range. In manual microscopic techniques, the particle is sized by its longest dimension; thus some differences exist in the criteria baseline between manual and automatic techniques.

The initial procedure used was to weigh a sample of the constituent, place this sample in 100 ml of prefiltered Freon (carrier fluid), and then introduce the contaminant to the counter.

VII-6

The initial tests, using the above procedure, produced an unacceptable amount of scatter in data. As a result the tests were inconclusive. The majority of the problems were due to operational techniques. Samples weighing 1.5 mg were first used but it was found that the particles were conglomerating. Smaller samples (0.048 to 0.3 mg) produced large errors in weighing inaccuracies which magnify themselves in terms of particle counts. A highly accurate electronic weighing device was used to weigh the samples. This device can differentiate to 1 x 10⁻⁵ grams but even this order of accuracy was not sufficient. Dilutions were tried, but the dilutions did not prove to be representative of the total mix prior to dilution. Other problems were experienced in particle settling, traps, etc.

The final series of tests was conducted using gravity flow through the top of the ROYCO counter. The flow configuration to the inlet of the counter was designed to eliminate traps and settling points, and to prevent air bubbles from entering the counter during the initial flow process. Automatic counters, which operate on a light principle, will readily interpret air bubbles as particles and will count them as such. An ultrasonic bath was used to prevent conglomeration of the particles. It was also necessary to use large quantities of flush fluid ('iltered Freon) to completely wash all of the particles from the test beaker and through the tubing to the counter. The above techniques provided highly repeatable data from sample to sample. Figure VII-5 shows the particle count for 1.0 mg of A.C. "coarse" road dust and Figure VII-6 shows the composition of the 0X60 teflon.

Table VII-1 shows the composition of the contamination level used in the contamination tests. The pneumatic and hydraulic contamination levels that are being used in the contamination tests are approximately 30% higher than those recommended for the service arm systems. Increased levels of contamination were used in the contamination tests to ensure a margin of conservatism. The composite level includes large amounts of hard abrasive contaminan.s. System contamination, as observed in the field, will not include such large amounts of these particles. The whole intent was to over-test the components to ensure a margin of reliability.





Figure VII-5 Particle Count Composition A.C. "Coarse" Road Dust

VII-8

MCR-69-484



:

. .

١,

VII-9

Figure VII-6 Particle Count Composition 0X60 Teflon

MCR=69-484

ŧ

VII-10

Ē

:

;

| | | | Size-Re | mgo | |
|---|----------------|--------------|--------------|-----------|-----------------|
| | 6 - 10µ | ·11 - 25µ | 26 - 50µ | 51 - 100µ | 100 + |
| 0X60 Teflon 0.24 mg/100 grams gas | 2670 | 1130- | 300- | 70 | 13 |
| A.C"Coarse" Road Dust 0.96 mg/100 grams gas | 1940 | 1039 | 170 | 20 | 1 |
| RedIron Oxide <0.1 mg/100 grams.gas | 3700 | 0 | 0 | 0 | 0 |
| Cotton Lintner. Fibers <0.1 mg/100 grams gas | | | | | (4000µ maximum) |
| Total Particle Count 0.30 mg/100 grams gas | 8310 | 2169 | 470 | 90 | 14 + fibers |
| Pneu | matic Cor | tamination | Test Leve | :1 | |
| | | | Size Ra | nge | |
| | 6 - 10µ. | 11 - 25µ | 26 - 50µ | 51 - 100µ | 100 + |
| 0X60 Teflon 2.9 mg/100 m1 oi1 | 22,200 | · 9·,400 | 2,500 | 564 | 108 |
| | | | | | |
| A.C. "Coarse" Road Dust 0.2 mg/100 ml oil | 6,460 | 3,420 | 565. | 67 | 3 |
| 0.2 mg/100 ml oil Red Iron Oxide | 6,460 3,710 | 3,420 : 0 | 565. · Q. | 67 0 | 3 |
| | | | | 0 | |

| Table VII-1 Contamination Test Levels | Table | a VII-1 | Contamination | Tesť | Levela |
|---------------------------------------|-------|---------|---------------|------|--------|
|---------------------------------------|-------|---------|---------------|------|--------|


ŧ

Figure VII-7 shows the composite level of contamination used in the hydraulic tests. The cleanliness level (Level 8 of NAS1638) tentatively recommended for the hydraulic systems is superimposed upon the test level. Figure VII-8 shows the contamination level used in the pneumatic tests. Both of these cleanliness levels are considerably less stringent than the levels presently specified for the service arm systems.

:

Ĥ

VII-11






j,

MCR-69-484

Figure VII-7 Contamination Level for Hydraulic Tests



:

MCR-69-484

Figure VII-8 Contamination Level for Pneumatic Tests

VII-13

VIII. CONTAMINATION TEST PROGRAM

The objective of the study was to evaluate the cleanliness requirements for the pneumatic and hydraulic components in the service arm systems at Complex 39 in an effort to relax the cleanliness levels, and their associated high cost, while maintaining service arm reliability. A test program was included to confirm the functional performance of components subjected to the final cleanliness levels to be recommended.

Tests were performed on pneumatic and hydraulic components arranged in a system typical of the service arm applications. Each component in both the pneumatic and hydraulic systems was subjected to 1500 operational cycles, a number selected after consideration of all of the scheduled tests, launches, and anticipated checkout on the service arms for the duration of the Apollo program. The 1500 operational cycles are four times the maximum cycles expected on the service arm systems.

A. TEST CRITERIA

The test criteria were established prior to procurement of components and the subsequent test effort. The criteria, which formed the basis for the contamination tests, are quoted in the following paragraphs.

1. Component Procurement

Test specimens will be procured to the vendor part number which corresponds to the similar NASA service arm specification. The test specimens will be procured commercial clean.

2. Receiving and Inspection

Components shall be inspected for general conformance. The components shall also be visually inspected, with magnification, for contamination. The valve shall not be disassembled to perform this inspection. The contamination observed shall be re-corded.

The internal flow path of the hydraulic components will be. flushed with clean hydraulic oil and sampled to determine the contamination level of the valve as procured. The component will not be cleaned in the flush mode unless the component exhibits extreme contamination.

3. Functional Test

A bench functional test will be performed on each component to ensure its integrity and also to establish baseline functional performance for comparison during the contamination test. Performance criteria shall be recorded prior to and during testing. . Fluids used in the functional test shall be filtered prior to the test specimen.

4. System Cleanliness

The test system.shall.be cleaned to test.level "A" (Table VIII-1) or better, prior to installing the test specimens. Care shall be taken to minimize exterior contamination when installing the test specimens. The effluent count of the flush fluid shall be recorded.

5. System Functional

A functional check of the system shall be performed subsequent to the test specimen installation to ensure proper system operation prior to conducting the 1500 cycle test. The fluids used during the system functional check shall be clean filtered fluids. The hydraulic loop shall be drained after the functional check. Photographs of the system shall be taken.

6. Test Fluid

<u>Hydraulic Test</u> - The test fluid shall be MIL-H-5606 hydraulic oil prefiltered to 3 microns. After filtration, a quantity of oil equal to the volume of the system shall be prepared. Contamination shall be mixed into the oil to ensure a homogeneous mixture. Precautions shall be taken to prevent further contamination of the oil by exterior contamination.

Table VIII-1 Cleanliness Levels

Level A - System Cleanliness

Particles

| Size (microns) | 0-300 | 301-500 | 501-1000 | Over 1000 |
|--|------------|---------|----------|-----------|
| Quantity per ft ² of significant surface area | Unlimited* | 10 | 2 | 0 |

Fibers

.....

;

| Length (microns) | 0-750 x 25 | 751-2000 x 25 | 2001-6000 x 40 | Over 6000 |
|--|------------|---------------|----------------|-----------|
| Quantity per ft ² of significant surface area | Unlimited* | 20 | 2 | 0 |

*Total Filterable Solids Limitation, 0.25 mg/ft²

| Level | В | - | System | Fluid | Contamination |
|-------|---|---|--------|-------|---------------|
|-------|---|---|--------|-------|---------------|

| a | | | Size Ra | nge | |
|--|---------------|----------|----------|-----------|---------------|
| Contaminant Type | 6 - 10µ | 11 - 25µ | 26 - 50µ | 51 - 100µ | 100 + |
| OX60 Teflon 0,24 mg/100 grams gas | 2670 | 1130 | 300 | 70 | 13 |
| A.C. "Coarse" Road Dust 0.06 mg/100 grams gas | 1940 | 1030 | 170 | 20 | 1 |
| Red Iron Oxide <0.1 mg/100 grams gas | 3700 | 0 | 0 | 0 | Ú |
| Cotton Lintner Fibers <0.1 mg/100 grams gas | | | | | 4000µ maximum |
| Total Particle Count 0.30 mg/100 grams gas | 0 31 0 | 2160 | 470 | 90 | 14 + fibers |

*Total Filterable Solids Limitation, 0.3 mg/100 grams of gas

7. Criteria for Success

The test system shall be cycled for 1500 cycles. At intervals of 300 cycles the leakage of each component shall be verified. Component leakage and regulator set pressure shall be the primary criteria for determining component failure. Pressure levels and component response shall also be monitored for indication of component failure. After the completion of the test each component shall be subjected to a functional test and the data recorded.

8. Component Failure

If a component shall fail prior to the end of the test, the program manager shall be notified and he shall make one of three determinations: (1) repair the value, (2) continue the test without repairing the value, or (3) discontinue the test. The main objective will be to continue the test, if possible.

9. Failure Analysis

At the conclusion of the test, and prior to repairing any internal component parts, each component shall be disassembled. Contamination shall be noted and recorded. Photographs shall be taken to note contamination, valve failure, or general condition of the component. A failure analysis shall-be conducted if the valve failure was due to contamination.

B. PNEUMATIC CONTAMINATION TESTS

The pneumatic testing effort was started on 10 March 1969 and was completed on 4 June 1969. All testing was performed at the Martin Marietta Cold Flow Laboratory at Denver, Colorado.

The functional characteristics of eight components determined to be critical to control arm operation were established by functional test. The specimens were then assembled into an operational system, and operated 1500 cycles using deliberately contaminated nitrogen gas. The functional tests were repeated to establish any functional degradation, and the specimens were disassembled for inspection.

All specimens operated properly throughout the testing, with the exception of specimen_1, Marotta Regulator 227464-J11. This regulator was found to be extremely sensitive to contamination and failed as a result of poppet seat erosion. This_regulator has a history of nine failures on the service arm systems.

Disassembly of the specimens showed a major amount of contaminant present and little component degradation.

1. Objectives

The objectives of the pneumatic contamination tests were to:

- Test selected control arm components in a typical flow system. Component selection was based upon susceptibility to contamination combined with possession of a critical function in the control arm system;
- Demonstrate the reliability of the components at an increased level of contamination by subjecting them to 1500 operational cycles;
- 3) Perform functional tests on each test component before and after the 1500 operational cycles, in order to determine component degradation;
- Maintain cleanliness of the test fluid at a prescribed level;
- 5) Disassemble and inspect the components following the test, to determine the effect of test fluid contamination.

2. Test Specimens

7.

Test specimens were procured to the vendor part number which corresponds to the similar NASA service arm specification. The test specimens were procured commercial clean.

| Specimen | Manufacturer | Part Number | NASA Equivalent Part Number | Name |
|------------|-----------------|-----------------|--------------------------------|----------------------|
| " 1 | Marotta | 227464-J11 | 75M08829 | Regulator |
| 2 | Marott <i>u</i> | 228154-02 | 75M08824-1 | 2-way solenoid valve |
| 3 | Marotta | 806098 | 75M09285-1 | 3-way solenoid valve |
| 4 | Marotta | 806098 | 75MU9285-1 | 3-way solenoid valve |
| 5 | Pathon | QU4X3SU191/2ABR | 75M09014 | Pneumatic cylinder |
| 6 | Marotia | 230904-12 | 75M08831-1 | Regulator |
| 7 | Marotta | 806097-1 | 75M08823-1 | 2-way solenoid valve |
| 8 | Marotta | 225884-02 | 75M08825-1 | 3-way solenoid valve |

3. Test Equipment

a. Instrumentation

The recorded instrumentation functions and the gages used in_the pneumatic tests are specified on the schematics given in Figures VIII-1 through VIII-5. A Consolidated Electrodynamics Corporation Type 5-124 recorder was used for all recorded data. Accuracy of all readouts was $\pm 2\%$ full scale.

b<u>Test</u> Fixture

The test fixture schematics used for functional and system testing are included as Figures VIII-1 through VIII-5. Each test installation was cleaned to the level shown in Level A in Table VIII-1. The cleanliness was verified by a nitrogen flush at a higher flowrate than anticipated during test fixture operation. Photographs of the system test installation and control panel appear as Figures VIII-6 and VIII_7, respectively.

c. Contaminant Injector

During system test operation, a known contaminant was injected into the system periodically... The device used for adding the contaminant to the flow stream consisted of an AN-827-6 cross, oriented as shown in Figure VIII-8. With the cross oriented vertically, the contaminant was loaded through the upper port into the capped lower one. The upper port was capped and the cross oriented as shown in the figure. The velocity of the nitrogen passing over the contaminant filled port caused sufficient turbulence to draw contamination into the flow stream. The angle at which the crosses were set was determined during development tests in a separate contamination injector development system.

The components in this system were sized to approximate the flow that would exist in the system test fixture during pressurization of the cylinder. The approximate injection rates, with the injector angles, are shown in Figure VIII-8. Although the majority of the contamination is consumed early in the flow, the overall injection schedule is much less severe than the "batch" technique, and more closely duplicates the contamination distribution rate that might be found in a typical system. The injection rate was sized in this manner to ensure that all of the contaminant would be removed from the injector and distributed throughout the test system in the remaining cycles.

d. Contaminant

The contaminant used was a mixture of ground teflon particles, A.C. coarse dust, red_iron oxide, and cotton lintner fibers. The particles were mixed to form a composite level equivalent to Level B of Table VIII-1... The contaminant mixture was injected at a rate of 0.3 mg per 100 grams of gaseous nitrogen.

4. Test Method and Procedure

a. Functional Test Method and Procedure

Each test specimen was subjected to a functional test to establish its operating characteristics prior to the system test.

The 2-way and 3-way solenoid values were tested for internal and external leakage and response time. Inlet pressure on all values was 2000 psig of gaseous nitrogen.

The test specimen 1 regulator was tested at an inletpressure of 4500 psig of gaseous nitrogen for internal and external_leakage, for ability to regulate pressure at a given setting, and for a pability of venting downstream pressure in excess of the set pressure.

The test specimen 6 regulator was tested for external leakage, set pressure, and ability to vent downstream pressure in excess of the set pressure. The regulator was tested with an inlet pressure of 1000 psig of gaseous nitrogen, and was purchased with a preset and lockwired outlet pressure setting of 120 psig.

The test specimen 5 pneumatic cylinder was tested at a pressure of 1000 psig of gaseous nitrogen for internal leakage, external leakage, and breakaway pressure.

b. System Test Method and Procedure

The eight test specimens were combined with a minimum of additional components to form the operating system shown schematically in Figure VILI-5. The gaseous nitrogen inlet pressure to the system was adjusted to 4500 psig, and the outlet pressure of test specimen 1 adjusted to 1000 psig. The system was operated automatically through 1500 cycles, using the logic sequence in Table VIII-2.

| ion Open ds (+28V) Close X X X | Te | Test Specimen | - | | | | |
|---|---|---------------------------------------|------------------------|----------------|-------|-----------------|-----------|
| a Open (+28V) Close X X X | | | | | | | |
| n Open (+28V) Close X X X X | 3 | | 4 | 4 | | | 8 |
| x , , , , , , , , , , , , , , , , , , , | Vent (+28V) Pressurize | ize (+28V) | : Pressurize | Open (±28V) | Close | ILFHC (+28V) | Millipore |
| x x | × | × | | | х | x | |
| × | x | | × | | x | | X |
| | x | × | | | × | | x |
| | x | × | | X | | | × |
| 1 X | x | × | | × | | x | |
| 1 X X | x | × | | | × | × | |
| Refer to Figure VIII-5 for System Test Fixture Schematic. | Test Fixture | Schematic | | | | | |
| The logic above performs the following: | owing: | | | | | | |
| Sequence 1 - extends the pneumatic cylinder. Sequence 2 - retracts the pneumatic cylinder. Sequence 3 - vents the system through the millipore filter. Sequence 4 - diverts residual N_2 three ILFHC, and exercises Sequence 5 - returns the system to its initial condition, | c cylinder. ic cylinder. uugh the mill: three ILFHC, ' | ipore fiļt and exerci condition | er. Ses specimen 8. | | | | |

Table VIII-2 System Test Cycle Logic

MCR-69-484

۲

VIII-8

Prior to each set of 50 cycles, contaminant was added to the system at the two points indicated on Figure VIII-5. For a description of the contaminant used and the contaminant injection technique, consult paragraphs VIII, B, 3, c and VIII, B, 3, d.

All effluent gaseous nitrogen from the system was passed either through a Millipore filter tool, Model XX45-047-00, or a Martin Marietta developed in-line filter holder and counter (ILFHC) tool. This tool allows examination of the filter paper without removing it from the flow system. The vent from the initial 195 cycles of each set of 200 cycles was passed through the Millipore tool. The Millipore paper was then analyzed for particle size and size distribution. The vent from the remaining 5 cycles was then passed through the ILFHC and used as a verification of particle size and size distribution.

After cycles 100, 300, 600, 900, 1200 and 1500, internal leakage tests were performed on all test specimens to establish any degradation. All of these leakage tests were performed at the system pressures used during the cycling test.

Table VIII-3 gives a summary of test operations during the 1500 cycles.

c. Final Inspection Test Method and Procedure

Following completion of the system and functional tests, each test specimen was carefully disassembled for inspection. The component parts were inspected for evidence of abrasion, contamination, lubricant deposits, etc. Photographs were taken of significant items.

5. Test Results and Discussion

a. Initial Functional Test Results and Discussion

Test data from the initial functional tests are presented in Tables VIII-4, VIII-5, and VIII-6. For discussion of the data that do not meet the test criteria, see paragraph VIII. B, 6, d.

| 141 | ole VIII-3 | System Test F | un Schedule | |
|--|------------------|----------------------|-----------------------------|---------------|
| After Cycle Number | Inspect ILFHC | Inspect Millipore | Add Contaminant | Leak Check |
| 0 50 100 150 195 200 | x | x | X X X X X | x x |
| 250 300 350 395 400 450 | x | X | X X X X X | x |
| 500 550 595 600 650 700 | х | x | X. X X X X X | x |
| 750 795 800 850 900 950 | X. | X | X X X X X X | x |
| 995 1000 1050 1100 1150 1195 1200 | x x | x x | X X X X X | X |
| 1250 1300 1350 1400 1450 1495 1500 | x | X | X X X X X X | x |

Table VIII-3 System Test Run Schedule

| | | | | | | Func | Funcțional] | Test Data | ß | | | |
|-------------------------------|------------|-------------------|--------------------------|----------------|-------------------------------------|---------------------|-------------------------------------|------------------------|--------------------------|----------------|--------------------------|----------------|
| | | | Specimen 2 (75M08824) | aen 2 1824) | Specimen 3 S/N 281 (75M09285) | en 3; 81 285) | Specimen 4 S/N 280 (75M09285) | nen 4, 280 9285) | Specimen 5 (75M08823) | ien j 1823) | Specimen 6 (75M08825) | aen 6 3825) |
| Test | Cycle | Criteria | Initial | Final | Initial | Final | Initial | Final | Initial | Final | Initial | Fínal |
| Ext Leakage | ч | No Leakage | 0 | 0 | 0 | 0 | . 0 | 0 | 0 | c | c | c |
| Int Leakage | - | No Leakage | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 00 | 0 | 0 |
| Ext Leakage | - | No Leakage | : | ; | 0 | 0 | 0 | 0 | ; | 1 | 0 | 0 |
| Int Leakage | Ч | No Leakage | ł | Ļ | 0 | 0 | 0 | 0 | ; | 1 | 0 | 0 |
| Response | ч | | 35,4 | 34,0 | 182* | 190% | 111* | 128* | 75.8 | 81.3 | 33.5 | 35.6 |
| "ime | | ŴS | 5,6 | 1.2 | 11.0 | 8.8 | 14.5 | 11.7 | 18.3 | 15.: | 7.7 | 7.0 |
| | 7 | MS Max | 33.5 | 36.6 | 159* | 138* | 105* | 125* | 73.5 | 71.3 | 32.0 | 35.8 |
| | 4 | SH | 6.1 | 2.4 | 10.9 | 7.7 | 14.0 | 12.5 | 27.6 | 12.6 | 7.4 | 8.C |
| | 6 7 | MS Max | 33.7 | 36.6 | 157* | 135* | 103* | 115* | 72.0 | 71.9 | 31.5 | 33.6 |
| | ~ | ЯŊ | 7.6 | 1.2 | 10.6 | 8.5 | 12.9 | 11.7 | 17.8 | 15.1 | 8.4 | 7.7 |
| | 4, | | 33.5 | 36.6 | 159* | 133* | 1 103* | 111.* | 71.5 | 73.2 | 32.2 | 34.0 |
| | | MS Max | 5,6 | 1.2 | 10.6 | 8,3 | 13.2 | 12.1 | 17.6 | 13.2 | 8.4 | 7.7 |
| | ŝ | MS Max | 33.6 | 36.6 | 158* | 170% | 102* | 110* | 70.9 | 71.9 | 31.8 | 33.8 |
| | | Мах | 4.5 | 2.4 | 10,6 | 8.3 | 13.9 | 12.6 | 16.8 | 12.8 | 8.5 | 7.7 |
| Operational | | ţ | 15.5 | 17.0 | 22.5* | 21,0* | 17.6 | 17.4 | 15.4 | 16.4 | 12.2 | 13.0 |
| Vol tage | | 1 to 17V Drop-Out | 2.2 | 2.2 | 3.5 | 2.0 | 2,7 | 2.0 | 2.0 | 2.0 | 3.1 | 3.2 |
| | 7 | to 18V | 15.5 | 17.3 | 22.2* | 21.2* | 17,6 | 18.0 | 16.3 | 16.2 | 12.2 | 13.2 |
| | | to 17V | 2,2 | 2.3 | 3.5 | 2.6 | 2.5 | 2.2 | 2.0 | 2.6 | 3.1 | 3.1 |
| | m | to 18V | 15.0 | 17.6 | 22.2* | 21,0% | 17,6 | 17.9 | 16.2 | 16.3 | 12.2 | 13.3 |
| | | 8 | 2.2 | 2.4 | 3.5 | : 2.8 | 2.6 | 2.6 | 2.0 | 2.4 | 3.0 | 3.2 |
| | 4 | to 18V | 15.2 | 17,6 | 22.1* | 21.0* | 17:6 | 17.8 | 16.2 | 16.1 | 12.2 | 13.3 |
| • | | to 17V | 2.0 | 2.4 | 3,4 | 2.9 | 2.5 | 2.8 | 2.0 | 2.5 | 3.1 | 3.6 |
| | ŝ | Δ. | 15.1 | 17.6 | 22.2* | 21;0* | 17.7 | 18,0 | 16.3 | 15.8 | 12.2 | 13.6 |
| | | 1 to 17V Drop-Out | 1.9 | 2.5 | 3:6 | 2.9 | 2.4 | 2.3 | 2 ₁ 0 | 2.3 | 3.1 | 3.2 |
| *Indicates a value that fails | value | | to meet criteria, | See ps | See paragraph VIII, | VIII, B, | 6, d, | | | | | |
| | | • • | | | | | • • | | | | | - |

Table VIII⁺⁴ Solenoid Valve Functional Test Data

).

.

.

÷

2

۰.**•**

•

MCR-69-484

VIII-11

ŧ

| Data |
|------------|
| Test |
| Functional |
| Regulator |
| VIII-5 |
| Table |

.

....

.

έ.,

| | | Specimen | Specimen 1 (75Å08829) | | Specimen | Specimen 6 (75M08831) | 831) |
|--------------------------------|----------|--|-----------------------|--------------|------------------------------|-----------------------|------------------|
| Test | Cycle | Criteria | Initial | Final | Criteria | 'itial | Final |
| Lockup Pressure | | 1000 ± 100 psi 1000 ± 100 psi | 1015 1020 | 1030 1030 | 120 ± 15 psi 120 ± 15 psi | 120 120 | 120 120 |
| | m | ± 100 | 1020 | 1030 | ± 15 | 120 | 120 |
| | 4 | 1000 ± 100 psi | 1020 | 1030 | ± 15 | 120 | 120 |
| | <u>ۍ</u> | 1000 ± 100 psi | 1020 | 1030 | 120 ± 15 psi | 120 | 120 |
| Venting Pressure | г | ll60 psi max | 1140 | * | 155 psi max | 130 | 130 |
| Reseat Pressure | н | 900 psi min | 1080 | * | 105 þsí mín | 125 | 125 |
| Vent Leakage | 1 | 0 | 0.2 cc/min | * | 0 | 0 | 0 |
| External Leakage | 1 | 0 | 0 | 0 | 0 | 0 | 0 |
| Internal Leakage | r-1 | 0 | 0 | * | N/A [†] | N/A [†] | N/A [†] |
| *Gross failure of | | poppet seal during system test made these items impractical to measure | tem test mad | e these | ítems impracti | ical to m | easure. |
| [†] Test specimen was | | purclased adjusted to 120 psig and lockwired | 120 psig an | d lockw: | ired. | | |
| | | | | | | | |

| Table VIII-6 Pneumatic Cylinder Functional Test Data (75M09014) | ylinder Functiona | l Test Data (; | 75M09014) |
|---|-------------------|------------------------|------------|
| Test | Criteria | Initial | Final |
| Piston Leakage-Retract | 73,600 SCCM | 3,080 SCCM | 32 SCCM |
| Piston Leakage~Extend | 73;600 SCCM | 12,141 SCCM 1,410 SCCM | 1,410 SCCM |
| External Leakage-Cylinder | 20 SCCM | 0 | 0 |
| External Leakage+Rod | 28,320 SCCM | NJJ SCCM | 137 SCCM |
| Breakaway Pressure-Extend | 30 psig max | 9 psig | 7 psig |
| Breakaway Pressure-Retract | 30 psįg max | 8 psig | 3 psįg |
| | | | |

VIII-12

MCR-69-484

VIII-13

The data shown for the internal leakage test of the cylinder were obtained after washing the hydraulic fluid from the interior of the cylinder and relubricating the seals with Atlantic 54 lubricant. It was felt that the excess hydraulic fluid present in the cylinder as received might unduly trap the contaminant present in the system nitregen, and prevent the contaminant from reaching other system components.

The following observations were made of the contamination existing in the components as received from the vendor. The components were procured in a commercial clean condition. Inspection was performed in the flow ports only, since it was a requirement that the valve was not to be disassembled for inspection prior to test.

<u>Pressure Regulator (75M08829)</u> - Upon removal of the inlet port fitting, one particle of dirt (125 microns) was attached to the fitting. Lube was found all around the diameter of the inlet port flow path. No lube or particles were observed in the outlet port.

Two-Way Solenoid Valve (75M08824) -

Inlet Port - Slight lube film and dust contamination were evident on the flare sealing surface. One particle, approximately 75 microns, was found on the end of the union (Fig. VIII-9).

Outlet Port - Lube film was found in the union flow path. Dirt was observed on the threads of the port. A 75 micron teflon particle was observed in the outlet port flow path. A large burr was attached at the bottom of the machined port. This large burr broke off and migrated to the cutlet filter screen during functional tests.

<u>Three-Way Solenoid Valve (75M09285, S/N 280)</u> - The port closure plugs were clean. No burrs were observed on the port threads. The lube used on the O-ring seating surface (common port) was slightly dark from many small particles. The normally open and normally closed ports showed no visable contamination.

Three-Way Solenoid Valve (75M09285, S/N 281) - All port closure plugs were clean. On all three ports, burrs or catches were observed at three places spaced around the lower thread. No particles were observed.

<u>Pneumatic Cylinder (75M09014)</u> - Visual examination showed a large quantity of hydraulic oil in the cylinder. Slight contamination was observed which appears to be dirt or particles from ... pipe threads.

Pressure Regulator (75M08831) -

Inlet Port - A small (50 micron) metal colored flake was observed in the port cap together with approximately 100 small particles (50 microns maximum). A large (0.040 in.) piece of lube was observed in the flow path of the fitting. The valve inlet flow path looked clean with a slight lube film on the surface.

Outlet Port - Four lint particles (0.080 in. maximum) were observed on the interior of the port cap. Excessive lube was found in the fitting flow path and in the port. No particles were observed, but may have been present in the lube film.

<u>Two-Way Solenoid Valve (75M08823)</u> - At the base of the inlet port union some black particles (100 microns) were observed. Three particles (25 microns) were observed in the inlet port. No particles were observed in the outlet port, although a burn was observed on the valve body at the bottom of the port threads. This burn appears to be firmly attached and is a result of the thread tap.

<u>Three-Way Solenoid Valve (75M18825)</u> - The valve was double-bagged but did not have plugs in the ports. The common port contained many small particles, the largest being approximately 75 microns. The normally-open port contained some very small. particles less than 25 microns in size. The normally-closed port contained many small (less than 75 microns) particles at the bottom of the port.

b. System Test Results and Discussion

The system test was performed per the schedule in Table VIII-3. The Millipore and ILFHC sample data appear in Table VIII-7. The result of the interim leakage tests appears on Table VIII-8.

.

,

:

ŧ

•

.

VIII-15

| | | ILFHC Data | | | | | Millipore Data | | | | | | |
|--------------------------------------|-----------|----------------------------------|-------------|-------------|--------------|---------|----------------|------|-------|----------|--------|-------|----------|
| | Numb | Number of Particles at Cycle No: | | | | | Nu | mber | of Pa | rticl | es at | Cycle | Not |
| Particles Micron Ranges | 200 | 400 | 600 800# | 1000 | 1200 | 1500 | 200- | 400 | 600 | 800 | 1000 | 1200 | 1500 |
| 100-200 | 15 | 3 | . 20 | 154 | 32 | | | . 13 | 1 | 23 | 75 | | |
| 200-300 | . 14 | 1 | 10 | 28 | 18 | * | ‡ | 3 | 0 | 2 | 20 | | |
| 300-500 | L | 1 | 4 | 32 | 4 | | | - 2 | 0 | . 1 | 11 | ŧ | ‡ |
| 500-1000 | 0 | 1 | 1 | . 4 | 0 | ŀ | | · 0 | 0 | 0 | 0 | ľ | |
| Gver 1900 | . 0 | 9 | 1* | 0 | 0 | | - | 0 | 0 | 0 | 0 | | |
| Fibers Mic ro n Ranges | | | | | 1 | | | | | <u> </u> | l | L | I |
| 0-750 | 0 | 0 | 0 | 0 | 1 | | | 4 | 2 | 3 | 1 | | |
| 750-2000 | 0 | 0 | 0 | 0 | 0 | # | + | 0 | 0 | 0 | 0 | * | * |
| 2000-6000 | 1† | 0 | 0 | 0 | 0 | | | 0 | o | 0 | 1 | | |
| Over 6000 | 0 | 0 | 0 | 0 | 0 | | | 0 | 0 | 0 | 0 | | |
| | 0 8 co | 0 nglom | 0 eratio | 0 n of T | 0 FE part | tieles, | | | | • | 1 0 | | |

Table VIII-7 Millipore Particle Count Data

.

| Table VIII-8 | System Test-Interim | Internal | Leakage | Test | Data |
|--------------|---------------------|----------|---------|------|------|

•

| | İnte | rnal | Leakage | (S C | CM) | | | | |
|--------------------------------|-----------------------|----------------|------------------------|-------------|---------------------|------------------------|-----------|----------|------|
| | Test Specimen | | | | | | | | |
| Cycle Number | 1 | 2 | 3 and 4 | 4 | 5 Extend | 5 Retract | 6 | 7 | 8 |
| 0 | 0 | 0 | 0 | 0 | 7250 | 565 | 0 | 0 | 0 |
| 100 | NA.* | 0 | 0 | 0 | 4200 | 4 | 0 | 0 | 0 |
| 300 | 13,500 | 0 | 0 | 0 | 3340 | 30 | 0 | 0 | 0 |
| 600 | 60,000 | 0 | 0 | 0 | 3120 | 14 | 0 | 0 | 0 |
| 900 | 60,000 | 72 | 0 | 0 | 2110 | 20 | 0 | 0 | 0 |
| 1200 | 60,000+ | 2 | O | 0 | 1800 | 250 | 0 | 0 | 0 |
| 1500 | 60,000+ | 0 | 0 | 0 | 1410 | 110 | 0 | 0 | 0 |
| *Specimen fat cycle 50, was | led at cy refurbis | cle : hed # | l, was re and repla | mov ced | ed from in the a | the syste system at | m a cy | t cle | 200. |

At the initiation of system cycling, specimen 1 failed by leakage through the seat. Results of a failure analysis showed the stainless steel poppet seat was eroded as if sandblasted. Examination of the contaminant injector upstream of this specimen showed that essentially all the contaminant was still in the injector, so the test specimen had not been "slugged" with the contaminant. While the failure analysis was being conducted, the system was run through 200 cycles. The refurbished specimen was then returned to the system, and the cycles continued. Immediately on resumption of the cycling, test specimen 1 failed again in the same manner. Since the seat leakage allowed downstream pressure to increase until the built-in relief device relieved, system pressures were still maintained near those required with external venting from specimen 1 being the only obvious system . problem. The system was allowed to continue in this manner through the duration of the 1500 cycles.

The contaminant injectors performed adequately during the 1500-cycles.

Figure VIII-10 shows the condition of the Millipore filter papers used in the contamination tests. The correlation between sample numbers and test cycles is tabulated.

| Sample No. | Test Cycle | Material |
|------------|-------------|----------|
| B2057 | 200 Cycles | Paper |
| B2058 | 600 Cycles | Teflon |
| B2059 | 800 Cycles | Teflon . |
| B2060 | 1000 Cycles | Teflon |
| B2061 | 1200 Cycles | Teflon |
| B2062 | 1400 Cycles | Paper |
| | | |

Millipore data were not obtained at 200, 1200, and 1500 cycles because the filter pads were blown out by the high velocity particle impingement. The standard filter paper was replaced with high pressure teflon filters after the first failure. These teflon filters are designed to take high pressure surges and high velocity impingement and are considered to be the strongest filter pads available... Even the teflon filters would not take the high levels of contaminant introduced into the system and resultant particle impingement.

,--- : .

Table VIII-7 lists the particle counts obtained on the Millipore samples. The data is not representative because of filter pad erosion. On samples B2058 and B2059, the center of the filter pad is badly eroded implying that many of the particles passed through the filter. The technician in the laboratory reported that sample B2060, at 1000 cycles, was highly charged with static electricity and that when he disassembled the Millipore holder, approximately 50% of the particles "jumped" off of the filter pad and thus were not counted.

The filter pads were weighed to determine the total weight of contaminant in the sample. The weights, in all cases, were less than the tare weights taken prior to test and contaminant weight was therefore not obtainable. The decrease in weight is attributed to filter pad erosion.

c. Final Functional Test Results and Discussion

Following completion of the system test, each test specim.n was subjected to a functional test identical to that performed prior to the system test. The final functional test results appear on Tables VIII-4, VIII-5, and VIII-6. The most significant result was the improvement in the pneumatic cylinder leakage rates and breakaway pressure. With the exception of specimen 1 regulator, the remaining test specimens showed very little. change in characteristics from initial to final functional tests.

d. Test Specimen Failure Discussion

During the system test, the specimen 1 regulator failed twice, the second failure occurring after a complete refurbishment. This regulator is very sensitive to contamination.

The solenoid valve specimens 3 and 4 exhibited response times that often failed to meet the criteria established for functional testing. The criteria were based on the valve manufacturer's acceptance criteria, with one major exception. The manufacturer uses the valve position indicator switch for response measurements, while for this test, the solenoid current trace with its characteristic indications of poppet motion was used. It is felt that this method, while yielding longer response times, is a more consistent and accurate measure of a valve's response.

During system interim leakage testing, specimen 2 solenoid valve exhibited internal leakage at two of the seven prescribed measurement intervals. The leakage was zero at all other measurement intervals, and was at zero at the completion of all testing. Refer to Table VIII-4 for these data.

e. Final Inspection Test Results and Discussion

Following completion of the final functional test, each test specimen was completely disassembled for inspection. Figures VIII-11 through VIII-35 are included to show the disassembled components of each specimen. Residual contaminant was present in all the test specimens. The majority of the contaminant added to the system evidently lodged in the test specimens. Relatively little contamination reached the sample tools downstream of the system, and an inspection of the system tubing did not reveal any significant quantities of contaminant adhering to the tubing walls.

A detailed description of the observations made for each component on final disassembly follows, and is in sequence with the component photographs.

<u>Pressure Regulator (75M08831-1)</u> - The interior of the regulator was completely filled with contaminant which appeared to be primarily teflon particles rather than road dust. The envelope shown in Figure VIII-12 contains the contaminant which dropped out of the component upon disassembly. The filter screen appeared to be completely clogged with large teflon particles. The poppet, spool, and inlet screen are fully coated with contaminant (Figure VIII-13).

Both the inlet and outlet fittings contained large amounts of contamination trapped in the lube on the end of the fitting (Figure VIII-14). The condition shown in the figure was also observed on many of the other components. No indication of wear on the O-rings or sliding surfaces and no erosion or wear on the poppet seat were observed.

<u>Two-Way Solenoid Valve (75M08824-1)</u> - The filter screen on the inlet fitting was pushed out of the flow path and the screen on the outlet fitting was gone (Figure VILI-17). The screen was later found in the 1/4-inch tubing downstream of injector #2. The valve was heavily loaded with contaminant. A great quantity of particles were trapped in the lube on the spool. The poppet seat and all software were in good condition.

en (m. 1

<u>Three-Way Solenoid Valve (75M08825-1)</u> - Very little contamination was trapped in this valve as compared to the other components. Both the inlet and outlet ports were relatively clean. The flow path into the "cylinder port" makes a 90-deg bend prior to entering the component. The bulkhead at this point was badly eroded indicating impingement on the 90-deg surface. Very few particles were observed on the spool but two vertical scratches were observed on each side of the spool at 180 deg (Figure VIII-20). The matching surface on the valve was not scratched. No further degradation was observed on the poppet, software, 0rings, or sliding surfaces.

<u>Pressure Handloader (75M08829)</u> - The inlet port was relatively clean. Dark colored particles (road dust and red iron oxide) were observed in the outlet port. The main seat scaling surface on the poppet stem was badly eroded (Figure VIII-23 and VIII-24). It is concluded that the eroded seat was caused by particle impingement and is the cause of the leakage past the main seat. Erosion on this valve was greater than that observed on the initial failure of this handloader. Many particles were trapped in the lube on the retaining spool and sensing piston (Figure VIII-25). No galled or worn surfaces were evident. The O-rings and software looked good. There was a considerable amount of contaminant trapped in the valve body.

Three-Way Solenoid Valve (75M09285-1, S/N 280) - Contamination was observed in all ports. A solid film of dust particles was trapped in lube around the outside diameter of the spool (Figure VIII-28). Particles were entrapped in the heavily lubricated poppet stem. Although this valve did not leak, a fine ring of erosion was found on the poppet seat due to particle impingement. Figure VIII-31 shows the contamination and eroded poppet seat on valve serial number 281, which is similar to that observed on valve serial number 280. The O-rings and seats did not show any evidence of wear or failure.

<u>Three-Way Solenoid Valve (75M09285-1, S/N 281)</u> - Many particles, observed on the normally closed inlet port, appear to be road dust; not as many particles were found in the other two ports. The valve was heavily lubricated and particles were trapped in the lubricant. Many large teflon particles were trapped in the lube on the poppet stem (Figure VIII-31). The fine line of erosion on the poppet seat was caused by particle impingement, although this valve did not leak (Figure VIII-31). No galling, wear, or degradation of software was observed.

<u>Two-Way Solenoid Valve (75MO8223-1)</u> - The inlet fitting, inlet port and outlet port were relatively clean. Many road dust particles were trapped in the lubricant on the poppet stem and spool piece. No wearing surfaces or degradation of software was evident.

<u>Pneumatic Cylinder (75M09014)</u> - The retract side of the cup scal was full of lubricant and particles. A ring of lubricant and particles existed on the barrel at the end of travel on the istract stroke. Lubricant and particles were observed on the cylinder head on the retract side. The extend side of the piston was relatively clean, although contaminated. Ne scoring, galling, or wear was visible in the barrel. The brass piston ring showed normal and even wear. The cup seals were not damaged.

C. HYDRAULIC CONTAMINATION TESTS

The testing effort was started on 4 April 1969 and was completed on 11 July 1969. The hydraulic tests were performed at the Martin Marietta Hydraulics Laboratory at Denver, Colorado.

The functional characteristics of nine components determined to be critical to control arm operation were ostablished by functional test. The specimens were then assembled into an operational system, and operated through 1500 cycles using deliberately contaminated MIL-H-5606 hydraulic of1. The functional tests were repeated to establish any functional degradation, and the specimens were disassembled for inspection.

Several O-ring failures occurred during system checkout and also during the contamination tests. None of these failures can be attributed to contamination. It is recommended that consideration be given to improving O-ring design, such as O-ring diameter clearances, groove cross-sectional areas, and assembly design, to those test components that displayed O-ring anomalies during the system contamination test.

During disassembly and inspection, contamination was found in every section of tube, fitting, and test component, particularly where hydraulic fluid residue was not completely drained from the component. This inspection showed that the injected contaminants were well distributed throughout the system.

Function tests were conducted on each component in order to accurately evaluate individual performance before and after the systems test. The test components operational characteristics, between the initial and final functional tests, for all practical purposes are the same. There was very little, if any, degradation in performance. It is therefore concluded that the service arm hydraulic components will function reliably at the contamination levels used in these tests.

1. Objectives

The purposes of the hydraulics tests were to:

1) Test selected control arm components in a typical flow system. The test specimens have been selected as being more susceptible to contamination;

MCR=69-484

- 2) Demonstrate the reliability of the test specimens at an increased level of contamination by subjecting them to 1500 operational cycles;
- 3) Functional test each test specimen before and after the 1500 operational cycles, in order to determine component degradation;
- Maintain cleanliness of the test fluid at a prescribed level;
- 5) Disassemble and inspect the test specimens following the test, to determine the effect of test fluid contamination.

2. Test Components

The test specimens, listed in the tabulation, were procured to the vendor part number which corresponds to the similar NASA service arm specification. The test specimens were procured commercial clean,

| Quantity To Be <u>Tested</u> | Test Srecimen <u>Number</u> | <u>Manufacturer</u> | Part Number | NASA Equivalent <u>Part Number</u> | <u>Name</u> |
|------------------------------------|-----------------------------------|-----------------------------------|-----------------|--|------------------|
| 2 | 6 | James Pond Clark | 277-T1-8TT | 75M05365-4 | Check valve |
| 1 | 4 | Pathon Manufac- turing Company | 3H1X3SU101/2ABR | 75 M065067 | Cylinder |
| 2 | 3 | American Bosch | ACG300281 | 75M08814-1 | Accumulator |
| 2 | 5 | Marotta Valve | 806097-1 | 75M08823-1 | Solenoid valve |
| 1 | 7 | Marotta Valve | 219004-J151 | 75M08830 | Regulator |
| 1 | 8 | Martin Marietta | None | | 0.020 Orifice |

3. Test Equipment

·. .

a. Instrumentation

The test system schematic, Figure VIII-36, shows the instrumentation functions used during the test. The instrumentation accuracies are listed in Table VIII-9.

| Armmeter | Accuracy Timer (% of Accuracy full scale) (msec) | | | | ±5 ±5 | |
|-----------------------------|--|--|--|--|--|---|
| System Fluid Temperature | Range and Thermocouple Accuracy | en Fi | Thermocouple Iemperature Range O to 250°F | Accuracy within ±13 of Full Range | Accuracy within ±1% of Full Ramee | Accuracy within ±13 wire full Zamee |
| Transducer | Accuracy (% of full range) | 17 | 14 | 11 | 1 | [] 4] |
| Tra | Range (psig) | 0 to 5000 | 0 to 5000 | 0 to 5000 | 0 to 5000 | 0 to 5000 |
| Gage | Accuracy (% of dial range) | Y4 +1 | -:~i +i | -10 +1 | ۰۶۲ ۱۲ | -44 +1 |
| | Gage Range (psig) | 0 to 5000 | 0 to 5000 | 0 to 5000 | 0 to 5000 | 0 to 5000 |
| | Test Specimen | Check Valve (NASA-75M05365-4, James Pond Clark, P/N 277-T1-8TT) | Cylinder (NASA-75M06506-7, Pathon Manufacturing Company, P/N 3H1X3SU101/2 ABR) | Accumulator (NASA-75M08814-1 American Bosch P/N-ACG300251) (hvd both ends) | Solenoid Valve (NASA-75M08823-1, Marotta Valve, P/N-806097-1) | Regulator (NASA-75M08830, Marotta Valve P/N-219004-J151) |

Table VIII-9 Test Instrumentation

ļ

١.

Ľ

....

i

.

. . . .

1

.

.

÷

•

MCR-69-484

b. Test Fixture

The test fixture schematic used for systems testing is shown in Figure VLII-36. The test installation was flushed with MIL-H-5606 hydraulic fluid to that level shown in Table VIII-10. Table VIII-11 shows the system cleanlines: level after the components were installed. The test fluid (ALL-A-5606 (Gotto)) is oil) was prefiltered to 3 microns absolute prio: to introducing the fluid into the test system. The cleanliness level of the prefiltered fluid is shown in Table VIII-12. The cleanliness data_below was obtained by means of a HIAC automatic particle counter. Photographs of the system test installation appear as Figures VIII-37, VIII-38, and VIII-39.

| Table VIII-10 | HIAC Particle Counter Data, Test System | |
|---------------|---|--|
| | prior to Component Installation | |

| Particle Range (microns) | First 100.ml. | Next 100 ml | Next 100 ml | Next 100 ml- | Next 100 ml |
|--------------------------------|------------------|----------------|----------------|-----------------|----------------|
| 5 to 15 | 133 | 1.16 | 103 | 79 | 55 |
| 15 to ² 5 | 5 | 3 | 1 | 1. | 4 |
| 25 to 50 | 0 | 0 | 0 | 0 | 0 |
| 50 to 100 | 0 | 0 | 0 | 0 | 0 |
| 100 + | 1 | 0 | 0 | 0 | 0 |

Table VIII-11 HIAC Particle Counter Data, Test System after Component Installation

| Particle Range (microns) | First 100 ml | Next 100 ml | Next 100 ml | Next 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 283 | 143 | 144 | 95 | 81 |
| 15 to 25 | 1 | 2 | 1 | 0 | 2 |
| 25 to 50 | 1 | 1 | 0 | 0 | 0 |
| 50 to 100 | 0 | 0 | 0 | 0 | 0 |
| 100 + | 0 | 0 | 0 | 0 | 0 |

MCR-69-484___

| l | 1 | I | Ť | T | 2 | 5 |
|---|---|----|---|---|-------|---|
| | | ٠. | | - | ~ | ~ |

| Particle Range (microns) | First 100 ml | Next 100 ml | Next 100 ml | Next 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 14 | 3 | 7 | 3 | 4 |
| 15 to 25 | 2 | 1 | 1 | 0 | 0 |
| 25 to 50 | 0 | 0 | 0 | 0 | 0 |
| 50 to 100 | 0 | 0 | 0 | 0 | 0 |
| 100 + | 0 | 0 | U | 0 | 0 |

Table VIII-12 HIAC Particle Counter Data, Prefiltered Test Fluid

c. Contaminant

2

The contaminant used was a composite mixture of ground teflon particles, A.C. coarse road dust, red iron oxide, and cotton_lintner fibers. The composite level is shown in Table VIII-13.

The total quantity of contamination particles was gradually added to the system to obtain equal dispersal throughout the system.

| | | - | Size Ra | inge | |
|--|----------------|-----------------------|------------------|-----------|---------------|
| | 6 - 10µ | 11 + 25 _{1x} | 26 - 5 0µ | 51 - 100µ | 100 + |
| OX60 Teflon 2.0 mg/100 ml oil | 22,200 | 9-,400 | 2,500 | 564 | 108 |
| A.C. "Coarse" Road Dust 0.2 mg/100 ml oil | 6,460 | 3,420 | 565 | 67 | 3 |
| Red Iron Oxide <0.01 mg/100 m1 oi1 | 3,710 | 0 | 0 | 0 | 0 |
| Cotton Lintner Fibers <0.1 mg/100 m1 oil | | | | ••• | 4000µ maximum |
| Total Particle Count 2.2 mg/100 ml oil | 32,370 | 12,820 | 3,065 | 631 | 111 + fibers |

Table VIII-13 Hydraulic Contamination Test Levels

4. Test Method and Procedure

a. <u>Receiving and Inspection</u>

Test components were inspected for general conformance. The component flow ports were visually inspected using 3X magnification. No evidence of contamination was observed. Test components were not disassembled to perform this inspection. The internal flow path of the hydraulic components was flushed with clean filtered hydraulic fluid. The influent fluid was prefiltered to 3 microns absolute. A sample of effluent-fluid from all test components was sampled with a HIAC automatic particle counter; the results are shown in Tables VIII=14 thru VIII-24. These samples were taken to evaluate the cleanliness level of each component as received from the manufactu price was no attempt to clean the test components during this flushing mode.

| Particle Range (microns) | First 100 ml | Next 100 ml | Next. 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|-----------------|----------------|
| · * | | | Oil Side | of Accu | mulator | | | |
| 5 to 15 | 32,196 | 29,823 | 28,244 | 24,663 | 24,673 | 24,240 | 25,163 | 29,277 |
| 15 to 25 | 819 | 947 | 715 | 594. | 615 | 587 | 473 | 538 |
| 25 to 50 | 116 | 178 | 109 | 76 | 79 | 73 | 45 | 52 |
| 50 to 100 | 3 | 0 | 1 | 0 | 0 | 1 | 1 | 0 |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | | | Gas Side | of Accu | nulator | L | L | _ |
| 5 to 15 | 13,873 | 14,733 | 14,718 | 16,387 | 15,309 | 14,232 | 15,364 | 15,471 |
| 15 to 25 | 83 | 97 | 99 | 117 | 119 | 100 | 121 | 120 |
| 25 to 50 | 5 | 6 | • · · · | 9 | 5 | 12 | 14 | |
| 50 to 100 | 0 | 0 | 0 | 0 | 1 | 1 | 0 | 0 |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

Table VIII-14 Effluent Particle Count, Hydraulic Accumulator (75M08814-1, S/N 6K3299)

MCR+69-484

٠

l

:

•

VIII-27

| Particle Range (microns) | First 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| • | | | Ø11 SId | o of Accu | mulator | · · · | | |
| 5 to 15 | 22,824 | 20,023 | 27,913 | 38,636 | 21,755 | 21,642 | 21,897 | 19,330 |
| 15 Lo 25 | 484 | 355 | 539 | 702 | 294 | 353 | 352 | 323 |
| 25 to 50 | 38 | 43 | 60 | 94 | 43 | 37 | 28 | 30 |
| 50 to 100 | 1 | 1 | 0 | 1 | 4 | 0 | 0 | 1 |
| 100 + | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | | | Gas Side | e of Accu | mulator | | · | |
| 5 to 15 | 38,389 | 26,983 | 24,601 | 31,946 | 30,968 | 24,992 | 24,397 | 25,317 |
| 15 to 25 | 341. | 215 | 177 | 280 | 332 | 199 | 171 | 210 |
| 25 to 50 | 47 | 19 | 22 | 31 | 52 | 37 | 21 | 20 |
| 50 to 100 | 1 | . 1 | 0 | 0 | 10 | 0 | 0 | 0 |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

Table VIII-15 Effluent Particle Count, Hydraulic Accumulator (75M08814-1, S/N 6K3300)

Table VIII-16 Effluent Particle Count, Hydraulic Cylinder _- (75M06506-7)

| Particle Range (microns) | First 100 ml | .Next 100 m1 | Next 100 ml | Last 53 ml* |
|--------------------------------|-----------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| - | | | Cylinc | er Extend | Mode | | | J |
| 5 to 15 | 84,004 | 60,414 | 65,333 | 69,318 | 88,664 | 126,336 | 155,922 | 203,536 |
| 15 to 25 | 2,519 | 1,724 | 1,950 | 2,069 | 3,080 | 4,926 | 7,116 | 14,268 |
| 25 to 50 | 2,007 | 242 | 261 | 305 | 425 | 541 | 718 | 1,362 |
| 50 to 100 | 3 | . 4 | 3 | 4 | 6 | 13 | . 8 | 13 |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | | | Cylinder | Retract | Mode | | | |
| 5 to 15 | 81,531† | 74,930 | 69,401 | 75,889 | 76,592 | 72,605 | 77,284 | |
| 15 to 25 | 1,747 | 1,078 | 1,094 | 1,399 | 1,192 | 947 | 1,064 | |
| 25 to 50 | 105 | 151 | 113 | 183 | 169 | 118 | 133 | |
| 50 to 100 | 12 | 4 | 1 | 1 | 4 | 6 | 4 | |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |

*Data corrected to 100 ml sample.

tThis was a 500 ml sample and was corrected to 100 ml.

÷

Table VIII-17 Effluent Particle Count, Hydraulic Cylinder (75M06506-7), Initial Fluid Sample

| Particle Range (microns) | Retract | Retract | Extend |
|--------------------------------|----------------|---------------|---------------|
| 5 to 15 | 13,400* | 9,750* | 14,300* |
| 15 to 25 | 40.0* | 150* | 318* |
| 25 to 50 | 200* | 159* | 11.2** |
| 50 to 100 | 11 | 4 | 9 |
| 100 + | 11 | 3 | 4. |
| Total Filterable Solids | 0.9 mg/100 ml. | 0.9 mg/100 ml | 0.9 mg/100 ml |

Millispore Sample Visual Count

*Data based upon statistical count of two squares.

| Table | VIII-18 | Cylinder | Influent | Pa | rticle | Count, |
|-------|---------|-----------|----------|------------|--------|--------|
| | | Hydraulic | Bench O: | i 1 | Sample | |

| Particle Range | | Sample Number | | | | | | | | | | |
|-------------------|------|---------------|-------|--------|--------|--------|-------|--|--|--|--|--|
| (microns) | 1 | N. + 1 | N + 2 | N. + 3 | N + 4. | .N- +5 | N + 6 | | | | | |
| 5 to 15 | 1818 | 129 | 70 | 83 | 76 | 40 | 52 | | | | | |
| 15 to 25 | 6 | 2 | 1 | 0 | 0 | 0 | 0 | | | | | |
| 25 to 50 | 2 | 1 | 0 | 0 | 0 | 0 | 0 | | | | | |
| 50 to 100 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | | | | |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | | | | |

VILI-28

.

.

ŧ

•

Table VIII-19 Effluent Particle Count, Two-Way Solenoid Valve (75M08823-1, S/N 398)

| Farticle Range (microns) | First 100 ml | Next 100 ml | Next 100 ml | Next 100 m1 | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 48,780 | 29,830 | 16,775 | 8,068 | 3,877 | 2,197 | 1,397 | 1,071 | 867 |
| 15 to 25 | 21 | 18 | 32 | 8 | 6 | 12 | 8 | 4 | 19 |
| 25 to 50 | 10 | 3 | 5 | 0 | 0 | 2 | 0 | . 0 | . 1 |
| 50 to 100 | 1 | 0 | 0 | 0 | 0 | | 1 | 0 | + |
| 100 + | 0 | 0 | 0 | 0 | 0 | | | 0 | |

HIAC Particle Counter Data

Table VIFI-20 Effluent Particle Count, Two-Way Solonoid Valve (75M08823-1, S/N 399)

| HIAC | Particl | e | Counter | Data |
|------|---------|---|---------|------|
| | | | | |

| Particle Range (microns) | First 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 18,006 | 6,409 | 3,739 | 4,668 | 4,236 | 3,227 | 2,803 | 1,087 | 816 |
| 15 to 25 | 243 | 112 | 41 | 15. | 12_ | 13 | | 21 | 10 |
| 25 to 50 | 50 | 23 | 3 | 3 | 3 | 5 | 3 | 8 | 2 |
| 50 to 100 | 3 | 1 | 1 | 1 | 0 | 0 | 0 | 0 | 0 |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | - 1 | 0 |

loble VIII-21-Effluent Particle Count, Gheck Valve (75M05365-4, S/N 9021312)

| HIAC Particle | Counter | Data |
|---------------|---------|------|
|---------------|---------|------|

| Particle Range (microns) | First 100 ml | Next ;30 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 20,616 | 39,816 | 51,894 | 52,073 | 66,050 | 102,069 | 102,709 | 71,162 |
| 15 to 25 | 147 | 22 | 8 | 6 | 5 | 3 | 3 | |
| 25 to 50 | 36 | 2 | 0 | 0 | 1 | 0 | 0 | |
| 50 to 100 | 5 | 0 | 0 | 0 | | 0 | 0 | |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |

| Next 100 ml | Next 100 ml | Next 100 ml | Next 100 ml | Next 100 m1 | Next 100 ml | Next 100 ml | Next 100 ml |
|----------------|----------------------|---|---|--|--|--|--|
| 49,304 | 27,859 | 12,999 | 5,129 | 2,037 | 955 | | 252 |
| 3 | 2 | 1 | 1 | 3 | 1 | | 1 |
| 0 | 0 | 0 | 0 | 0 | 1 | | 1 |
| 0 | 0 | 0 | 0 | | ^ | | 1 |
| 0 | 0 | 0 | 0 | | | | 0 |
| | 9,304 3 0 0 | 00 ml 100 ml 9,304 27,859 3 2 0 0 0 0 0 0 | 00 ml 100 ml 100 ml 9,304 27,859 12,999 3 2 1 0 0 0 0 0 0 | 00 ml 100 ml 100 ml 100 ml 9,304 27,859 12,999 5,129 3 2 1 1 0 0 0 0 0 0 0 0 | 00 ml 100 ml 100 ml 100 ml 100 ml 100 ml 9,304 27,859 12,999 5,129 2,037 3 2 1 1 3 0 0 0 0 0 0 0 0 0 0 | 00 ml 100 ml </td <td>00 ml 100 ml 9,304 27,859 12,999 5,129 2,037 955 583 3 2 1 1 3 1 6 0 0 0 0 0 1 0 0 0 0 0 0 6</td> | 00 ml 100 ml 9,304 27,859 12,999 5,129 2,037 955 583 3 2 1 1 3 1 6 0 0 0 0 0 1 0 0 0 0 0 0 6 |

۴.

Table VIII-22 Effluent Particle Count, Check Valve (75M05365-4, 8/N 9021313) HIAC Particle Counter Data

| Particle Range (microns) | First 100 ml | Next 100 m1 |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 4,147 | 1,503 | 1,300 | 1,909 | 12,342 | 30,888 | 30,609 | 19,702 |
| 15 to 25 | 90 | 20 | , 7 | 6 | 2 | - 4 | 6 | 5 |
| 25 to 50 | 20 | 0 | 2 | 2 | 2 | 0 | 1 | · 0 |
| 50 to 100 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 100 + | 0 | 0 | . 10 | . 0 | 0 | 0 | 1 | 0 |

| Particlo Rango (microns) | Next 100 ml | Next 100 ml | Next 100 ml | Next 100 ml | Next 1CO ml | Next 100 ml | Next 100 ml | Nøxt 100 ml |
|--------------------------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 9,523 | 3,415 | 1,136 | 441 | 3.44 | : 52 | 135 | 122 |
| 15 to 25 | 3 | . 2 | 1 | 4 | 3 | 2 | 1 | 0 |
| 25 to 50 | 0 | 1 | 0 | 1 | 0 | 0 | 0 | 1 |
| 50 to 100 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | . 0 |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

 Table VIII=23
 Effluent Particle Count, Check Valve (75M05365-4)

 Millipore Filter Visual Count

| Particle Range (microns) | (S/N 9021312) Number of Particles per 100 ml ^a | Particle Range (microns) | (S/N 9021313) Number of Particles per 100 ml* |
|--------------------------------|---|--------------------------------|---|
| 5 to 15 | 174 | . 0 to 50 | Too numerous to count |
| 15 to 25 | · 28 | ·50 to 100 | 5 |
| 25 to 50 | 6 | 100 + | 2 |
| 50 to 100 | 1,5 | | |
| 100 + | 0 | | |

Total Filterable

Solids

5

VIII-30

*200 ml sample taken, data corrected to 100 ml.

0.3 mig

Table VIII-24 Effluent Particle Count, Hydraulic Pressure Regulator (75M08830-2) HTAC Particle Counts

.

| | | HIAC | Particle | Counter | Data | | |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| Particle Range (microns) | First 100 ml | Next 100 m1 |
| 5 to 15 | 39,216 | 17,744 | 14,833 | 4,412 | 2,501 | 1,903 | 1,847 |
| 15 to 25 | 273 | 64 | 42 | 56 | 17 | 6 | 8 |
| 25 to 50 | 48 | 17 | 10 | 4 | 3 | 0 | 0 |
| 50 to 100 | 6 | . 1 | , O | 1 | 0 | 0 | 0 |
| 100 + | 1 | . 1 | 2 | . 0 | 0 | 1 | 0 |

0.4 mg

...

b. Functional Test Method and Procedure

An initial functional bench test was performed on each component to ensure its integrity and to establish a baseline performance criteria prior to the system contamination test. The component functional performance data were used as criteria to evaluate component degradation during system contamination tests. The test fluid was MIL-H-5606B hydraulic oil prefiltered to 3 microns absolute. Functional tests were performed on the test components using the test system identified in each NASA component specification.

The accumulators were tested for internal and external leakage for a period of five minutes with 4500 psig on one side of the piston and zero psig on the other.

The hydraulic cylinder was tested for internal and external leakage, and breakaway pressure at 4500 psig; leakage was monitored for 5 minutes at each condition.

The two-way solenoid valve was tested for internal and external leakage and for response time.

The check valves were tested for internal leakage, cracking, and reseat pressures.

The regulator was tested at an inlet pressure of 3000 psig for internal and external leakage, for ability to regulate pressure at a given setting, and for capability of venting downstream pressure in excess of the set pressure.

The flow rate of the orifice (0.20 in.) was calibrated at an inlet pressure of 3000 ± 25 psig.

c. System Test Method and Procedure

The nine test specimens were combined with a minimum of additional components to form the operating system shown schematically in Figure VIII-36.

The hydraulic test system was pressurized to 3000 psig using the fluid power of the hydraulic power supply. Flow to the test system was controlled by a hydraulic servo-selector valve. The following sequence of events describes a half cycle of the contamination test.

High pressure fluid flow was supplied to the test system by the hydraulic power unit supply. A low frequency functional generator supplied an amplitude and frequency signal to the electrical switching console. An input signal was emitted from the console to open the servo-selector valve to permit high pressure flow to accumulator 3_1 , simultaneously emitting a signal to the solenoid valves, opening valve 5_1 and-closing valve 5_2 . The flow from accumulator 3_1 was then passed through solenoid valve 5_1 and to the piston side of cylinder 4. Flow from the solenoid valve (5_1) passed through test items 7, 8, and 9_2 and combined to flow through check valve 6_2 to accumulator 3_3 . Discharge flow from the accumulator passed through the servo-selector valve into the return of the hydraulic power unit supply. The reverse sequence of events completed a full test cycles.

Component internal leakage checks were performed every 300 cycles. System effluent was sampled every 100 cycles through the HIAG automatic particle counter. Millipore samples were also taken at intervals of 300 cycles. See Table VIII-25 for a summary of test operations during the 1500 cycles.

| Cycle Number | HIAC | Millipore | Leak Check after Last Cycle |
|--------------|------|-----------|--------------------------------|
| 0 | | | X |
| 1 | x | | |
| 100 | x | X | x |
| 200 | x | | |
| 300 | X | х | X |
| 400 | x | | |
| 500 | x | | |
| 600 | х | x | X . |
| 700 | x | | |
| 800 | x | | • |
| 900 | x | X | x |
| 1000 | x | | |
| 1100 | x | | · |
| 1200 | x | x | x |
| 1300 | x | - | |
| 1400 | x | | ŀ |
| 1500 | х | х | x |

Table VIII-25 Sequence of Operation

VIII=32

d, Final Inspection Test Method and Procedure

Following completion of the system and functional tests, each test specimen was carefully disassembled for inspection. The component parts were inspected for evidence of abrasion, contamination, lubricant deposits, etc and photographs were taken of significant items (Fig. VIII-40 thru VIII-64).

5. Test Results and Discussion

a. Initial Functional Test Results and Discussion

Test data from the initial functional tests are presented in Tables VIII-26 through VIII-31. The effluent particle counts for each component are shown in Tables VIII-14 through VIII-24.

The internal leakage of accumulator S/N 6K3300, as tested prior to system test, was almost two times the specification criteria. Accumulator S/N 6K3299 exhibited zero leakage. The cracking pressure of regulator 75M08830 was 65 to 70 psig above specification in all cases. Additional tests were conducted when it was noticed that the vent cracking and reseat pressures were affected by the inlet pressure to the regulator. The test data for all remaining components was well within specification. The above anomalies did not affect the test program since the functional tests were conducted only to ensure basic component operation and to obtain baseline performance is a for comparison after the contamination tests.

The effluent particle counts, shown in Tables VIII-14 through VIII-24, are comparable to Levels 7 and 8 of NAS 1638. The variety of components represented may provide some indication of a commercial clean condition, since all of the components were procured in a commercial clean condition. The influent background particle count of the hydraulic oil was generally below 25 particles in the 5 to 10-micron range, with no particles above 15 microns.

٠

| Table V | /111-26 | Functional (75M08814-1 | Tust. | Data, | Hydraulic | Accumulator |
|---------|---------|------------------------|-------|-------|-----------|-------------|
|---------|---------|------------------------|-------|-------|-----------|-------------|

| Test | | Functional Test Data | | | | |
|-------------------------------------|---------------------------------------|----------------------|--------|------------|--------|--|
| | | S/N 6K3299 | | S/N 6K3300 | | |
| | Requirement | Initial* | Final* | Initial | Final* | |
| Internal Leakage Air to 011 Side | 10 Drops per 15 Minutes Maximum | () | 0 | 1.2 | 0,36 | |
| Internal Leakage Oll to Air Side | 10 Drops per 15 Minutes Maximum | 0 | 6.1 | 1,2 | -0 | |
| External Leakage | Bubble Tight | () | 0 | 0 | 0 | |

*Drops per minute.

Table VIII-27 Functional Test Data, Hydraulic Cylinder (75M06506-7)

| | Maximum | Test R | esults |
|-------------------------------------|----------------------------------|----------|-----------|
| Test | Allowable | Initial_ | Final |
| Piston Leakage - Extend | 5 cc/min | 4 drops | 5.6 drops |
| Piston Leakage - Retract | 5 cc/min | 8 drops | 6.2 drops |
| External Barrel Leakage | 0 | 0 | 0 |
| Rod End External Leakage | 1 drop/25 operating cycles | 0 | 0 |
| Breakaway Pressure Extend, psig | 60 | 7 | 4,5 |
| Breakaway Pressure Retract, psig | 60 | 6 | 3,5 |

VIII-34

;

ŧ

.

5

1

:

| | Specification | Test R | esults |
|---|-------------------------|------------|-------------|
| Test | Criteria | Initial | Final |
| External Leakage Solenoid Energized | Bubble light | No Leakage | No Leakage |
| Internal Leakage Solenoid De=energized | 5 cc/mfn Maximum | No Leakage | 3 drops/min |
| External Leakage Solenoid Energized | Bubble Tight | No Leokage | No Leakage |
| Internal Leakage Solenoid De-energized | 5 ce/min Maximum | No Leakag | 3 drops/min |
| Response Time | 75 msee Maximum Opening | 1,91 | 4.70 |
| Cycle No. 1 | 75 msec Maximum Closing | 2.80 | 4.32 |
| Response Time | 75 msec Maximum Opening | 2.04 | 3.90 |
| Cycle No. 2 | 75 msec Maximum Closing | 1.91 | 3.78 |
| Response Time | 75 msee Maximum Opening | 2.49 | 3,93 |
| Cycle No. 3 | 75 msee Maximum Closing | 2.17 | 3.93 |
| Response Time | 75 msec Maximum Opening | 2.02 | 4.32 |
| Cycle No. 4 | 75 msec Maximum Closing | 2.60 | 4.06 |
| Response Time | 75 msec Maximum Opening | 2.23 | 4.44 |
| Cycle No. 5 | 75 msec Maximum Closing | 2.42 | 3.81 |
| Actuation-Deactuation Voltage | 8 to 18 vde Pull-In | 17.4 | 18.60 |
| Cycle No. 1 | 1 to 17 vdc Drop-Out | 2.9 | 2.0 |

Table VIII-28 Functional Test Data, Pneumatic Two-Way Solenoid Valve (75M08823-1, S/N 398)

VIII-36

:. .,

1

;

-

MCR-69-484

| Table VIII-29 | Functional Test Data, Pneumatic Two-Way |
|---------------|---|
| | Solenoid Valve (75M08823-1, S/N 399) |

| | Specification | Test R | lesults |
|--|----------------------------|------------|---------------------|
| Test | Criteria | Initial | Final |
| External Leakage Solenoid Energized | Bubble Tight | No Leakage | No Leakage |
| Internal Leakage Solenoid De-energized | 5 cc/min Maximum | No Leakage | L drop/min |
| External Leakage Solenoid Energized | Bubble Tight | No Luakage | No Leakage |
| Internal Leakage Solenoid. De-energized | 5 cc/min Maximum | No Leakage | l dro <u>p/mi</u> n |
| Response Time | 75 msec Maximum.Opening | 1,98. | 3.77 |
| Cycle No. 1 | 75 msec Maximum Closing | 2.84 | 3.89 |
| Response Time | 7.5. msec Maximum Opening. | 1.94 | 3.89 |
| Cycle No. 2 | 75 msec Maximum Closing | 2.79 | 3.76 |
| Response Time | 75 msec Maximum Opening | 2.09 | 3_68 |
| Cycle No. 3 | 75 msec Maximum Closing | 2.84 | 3.81 |
| Response Time | 75 msec Maximum Opening | 1.88 | 3.55 |
| Cycle No. 4 | 75 msec Maximum Closing | 3.00 | 4.06 |
| Response Time | 75 msec Maximum Opening | 1.97 | 3,82 |
| Cycle No. 5 | 75 msec Maximum Closing | 2,98 | 4.08 |
| Actuation-Deactuation Voltage | 8 to 18 vdc Pull-In | 16.8 | 14.3 |
| Cycle No. 1 | 1 to 17 vdc Drop-Out | 2.8 | 1.90 |

ł

·· · ·

.

| Table VIII-30 | Functional Test Data, Hydraulic Check Val (75M05365-4) | ve |
|---------------|--|----|
| | | |

| | | | Test | Data | |
|------------------------|-------------------------|-------------------|-----------------|-------------------|-----------------|
| | | S/N 902 | 1312 | S/N 902 | 1313 |
| Test | Requirement (psig) | Initial (psig) | Final (psig) | Initial (psig) | Final (psig) |
| Internal Leakage | Zero Leakage at 4500 | . 0 | 0 | 0 | 0 |
| Cracking Pres- sure | 0.5 to 1.0 | 0.85 | 0,55 | 0.75 | 0.80 |
| Reseat Pressure | 0.5 to 1.0 | 0,60 | 0.50 | 0.70 | 0.75 |

| Table VIII-31 | Functional Test Data, Hydraulic Pressure Regulator |
|---------------|--|
| | (75M08830-2) |

| Step | Inlet | | Requirement | Test Re | esults |
|------|----------|-------------------|----------------|----------------|--------------|
| No. | Pressure | Test | (psig) | Initial (psig) | Final (psig) |
| A-1 | 3000 | Lockup Pressure | 2900 ± 50 psig | 2840 | 2840 |
| C-1 | 3000 | Lockup Pressure | 2750 ± 50 pşig | 2750 | 2760 |
| C-2 | 3000 | Cracking Pressure | 2810 Maximum | 2875 | 2800 |
| C-3 | 3000 | Reseat Pressure | 2690 Minimum | 2850 | 2755 |
| C-4 | 3000 | Vent Leakage | Bubble Tight | Zero Leakage | Zero Leakage |
| C-5 | 3000 | External Leakage | Bubble Tight | Zero Leakage | Zero Leakage |
| F-1 | 3000 | Lockup Pressure | 500 | 500 | 500 |
| F-2 | 3000 | Cracking Pressure | 550 Maximum | 615 | 520 |
| F-3 | 3000 | Reseat Pressure | 475 Minimum | 585 | 490 |
| F-4 | 2750 | Lockup Pressure | 500 | 500 | 500 |
| F-5 | 2750 | Cracking Pressure | 550 Maximum | 620 | 515 |
| F-6 | 2750 | Reseat Pressure | 475 Minimum | 585 | 505 |
| F-7 | 3000 | Lockup Pressure | 150 | 150 | 150 |
| F-8 | 3000 | Cracking Pressure | | 326 | 165 |
| F-9 | 3000 | Reseat Pressure | | 290 | 140 |
| F-10 | 2750 | Lockup Pressure | 150 | 150 | 150 |
| F-11 | 2750 | Cracking Pressure | | 340 | 160 |
| F-12 | 2750 | Reseat Pressure | | 310 | 145 |
| G-1 | 4500 | Internal Leakage | Bubble Tight | Zero Leakage | Zero Leakage |

b. System Test Results and Discussion

The system cleanliness particle count data appear in Tables VIII-32 through VIII-48. The results of the interim leakage tests are shown in Table VIII-49.

Test System Functional Checkout Test - After filling the test system with hydraulie fluid, and prior to contaminant injection, several operational problems were encountered, and as a result the system testing was delayed until the problems could be solved. The problem areas were primarily heat buildup, air entrainment, and component O-ring failures.

During system checkout tests, it was found that the energy introduced to operate the system was heating up the hydraulic oil substantially, and ice packs did not provide enough heat sink to dissipate the heat. To solve the problem it was necessary to build cooling coils into the test system and immerse the coils in a-dry ice/alcohol bath. This method stabilized the system temperature at approximately 120 to 150°F. Air jets were used to cool the solenoids on the two-way values.

Air entrainment was a problem, since the HIAC automatic particle counter will not differentiate between contaminant particles and air bubbles, and will readily count all air bubbles that pass the sensor. Air bleeds were installed at the high points of the system but this did not solve the problem completely. By cycling of the test system, in conjunction with the use of the air bleeds, it was possible to eliminate the majority of the entrained air in the system fluid. In addition to the high point bleeds, an accumulator (Fig. VIII-38) was installed in the system upstream of the automatic counter. Hydraulic oil from the system was admitted to the accumulator, and then the flow from the accumulator was directed to the counter. The purpose of the accumulator was to allow the entrained air to rise to the top of the accumulator, thus minimizing air entrainment in the first 1000 ml of the sample.

The air entrainment problem was not in evidence when performing the initial component effluent particle counts. Effluent counts were performed with an <u>open loop</u> system rather than the closed loop used in the systems contamination test.

Before starting the contamination tests and prior to introducing contaminant, 200 cycles were run on the test system in checking out the system operation. At 195 cycles, the pressure handloader (75M08830) started leaking at the top of the handloader.

VIII-38

i

;

ļ

;

VIII-39.

The handloader was disassembled and it was found that the main piston O-ring (P/N J200A16) was rolled over and chewed up on the inside diameter. The adapter pilot for this O-ring has a very sharp 90 deg edge with no chamfer. The manufacturer of this handloader stated that similar failures have been experienced in the assembly of this part. The failure analysis concluded that the O-ring failure was initiated upon assembly. Figure VIII-43 shows the main piston O-ring failure. The light colored particles on the piston in Figure VIII-44 are lubricant.

The poppet stem O-ring also failed at 195 cycles. This failure and subsequent failures were a result of excessive O-ring groove width (Fig. VIII-45).

The handloader (75M08830) was repaired and reinstalled in the test system.

Test System Component Discropancy - The pressure handloader (75M08830) leaked through the top of the handle at 935, 1113, and 1326 cycles. In each of these failures the poppet stem O-ring (P/N J200A2) was chewed up (Fig. VIII-45). New O-rings were installed after each failure and prior to continuing the test. The O-ring failures are attributed to a rolling and spiraling action in the O-ring groove with subsequent nibbling on the inside and outside diameters. The failure analysis concluded that these Oring failures were not due to contamination, but to excessive Oring groove width which permitted the O-ring to roll and spiral.

The O-ring (J20016A), in the main piston of the handloader, had two failures: (1) just prior to test, and (2) after 1326 cycles (Fig. VIII-40).

At 1113 cycles it was observed that the filter screen on the inlet fitting had been dislodged from the ficting and had migrated to the retaining spool in the handloader. The screen was removed from the component prior to continuing the test. At 1326 cycles the filter screen in the outlet fitting was laid back parallel to the flow stream. This screen was also removed. The filter screens failed as a result of contaminant loading and subsequent ΔP across the screen, even though the screen is a very coarse mesh (Fig. VIII-46).

All of the remaining components functioned in a normal manner with no anomalies for the full duration of the system test.

¢.

é.

| Particle Range (microns) | First 100 ml | Next 100 ml | Next 100 ml | Next 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 28,728 | 33,347 | 13,580 | 7,679 | 6,688 |
| 15 to 25 | 579 | 655 | 353 | 197 | 154 |
| 25 to 50 | 60 | 77 | 52 | 37 | 26 |
| 50 to 100 | 1 | <u>;</u> 1 | 1 | . 0 | 1 |
| 100 + | 0 | 0 | 0 | 0 | 0 |

Table VIII-32 HIAC Particle Counter Data, Test Hystem after Checkout (O Test Cycles)

Table VIII-33 HIAC Particle Counter Data, 100 Test Cycles

| Particle Range (microns) | First 100 ml | Next 100 ml | Next 100 ml | Next 100 m1 | Next 100 ml | Next 100 ml | Next 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 114,941 | 114,670 | 112,663 | 111,478 | 129,715 | 112,084 | 111,833 | 111,110 |
| 15 to 25 | 10,484 | 10,279 | 10,031 | 10,002 | 10,820 | 10,043 | 10,063 | 10,027 |
| 25 to 50 | 1,041 | 1,018 | 1,003 | 1,000 | 1,088 | 1,006 | 1,006 | 1,001 |
| 50 to 100 | 105 | 101 | 101 | 100 | 111 | 100 | 100 | 100 |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

Table VIII-34 HIAC Particle Counter Data, 200 Test Cycles

| Particle Range (microns) | First 100 ml | Next 100 ml | Next . 100 ml | Next 100 ml | Next 100 ml | Next 100 ml | . Next 100 m1 | Next 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|------------------|----------------|----------------|----------------|------------------|----------------|----------------|
| 5 to 15 | 216,628 | 201,454 | 176,419 | 163,576 | 168,911 | 142,177 | 123,234 | 121,724 | 120,039 |
| 15 to 25 | 14,061 | 13,495 | 12,371 | 12,224 | 12,059 | 1,732 | 9,327 | 9,109 | 8,720 |
| 25 to 50 | 1,766 | 1,670 | 1,388 | 1,422 | 1,390 | 1,186 | 1,007 | 961 | 970 |
| 50 to 100 | 47 | 53 | 57 | 41 | 57 | 34 | 23 | 22 | 23 |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

Table VIII-35 HIAC Particle Counter Data, 300 Test Cycles

| Particle Range (microns) | First 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 181,467 | 151,585 | 121,571 | 116,556 | 185,166 | 136,804 | 135,449 | 135,139 | 139,450 |
| 15 to 25 | 15,656 | 13,734 | 11,314 | 1,896 | 6,340 | 2,507 | 2,250 | 2,241 | 2,582 |
| 25 to 50 | 1,788 | 1,519 | 1,178 | 1,105 | 781 | 272 | 227 | 2 50 | 252 |
| 50 to 100 | 152 | 133 | 107 | 104 | 38 | 9 | 10 | 9 | 14 |
| 100 + | 0 | 1 | 0 | 0 | 1 | 0 | 0 | 0 | 0 |

VIII-40

1

.

•

:

1.

.

٠,

| Particle Range (microns) | First 100 ml | Next 100 -1 | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 184,036 | 195,988 | 165,303 | 164,976 | 146,524 | 144,627 | 142,370 | 141, 582 |
| 15 to 25 | 11,626 | 14,321 | 13,000 | 12,737 | 11,699 | 11,401 | 11,142 | 11,203 |
| 25 to 50 | 1,964 | 1,351 | 1,939 | 1,930 | 1,655 | 1,703 | 1,602 | 1,621 |
| 50 to 100 | 153 | 161 | 188 | 90 | 176 | 183 | 173 | · 166 |
| 100 + | 2 | 5 | 5 | 2 | 1 | 2 | 0 | 2 |

Table VIII-37 HIAC Particle Counter Data, 500 Test Cycles

| Particle Range (microns) | First 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 183,020 | 182,065 | 172,401 | 141,580 | 112,815 | 112,670 | 111,855 | 114,318 |
| 15 to 25 | 11,571 | 14,812 | 15,337 | 12,989 | 10,339 | 10,092 | 10,132 | 10,013 |
| 25 to 50 | 1,174 | 1,591 | 1,652 | 1,336 | 1,144 | 1,031 | 1,000 | 1,000 |
| 50 to 100 | 109 | 119 | 121 | 106 | 102 | 100 | 100 | 100 |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

| Particle Range (microns) | First 100 ml | Next 100 ml | · Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|------------------|
| 5 to 15 | 197,573 | 178,170 | 173,178 | 141,040 | 112,406 | 111,304 | 111,442 | 112,086 |
| 15 to 25 | 17,063 | . 16,199 | 16,045 | 13,249 | 10,422 | 10,246 | 10,223 | 10,203 |
| 25 to 50 | 1,898 | 1,713 | 1,670 | 1,325 | 1,044 | 1,013 | 1,017 | 1,021 |
| 50 to 100 | 131 | 128 | 124 | 110 | 102 | 100 | 100 | 100 |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

Table VIII-39 HIAC Particle Counter Data, 700 Test Cycles

| Particle Range (microns) | First 100 ml | Next 100 ml | Nexť 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 151,212 | 153,024 | 155,587 | 151,687 | 148,945 | 149,625 | 150,363 | 151,254 |
| 15 to 25 | 10,517 | 11,456 | 12,194 | 12,392 | 12,304 | 12,440 | 12,561 | 12,744 |
| 25 to 50 | 1,081 | 1,164 | 1,175 | 1,167 | 1,127 | 1,154 | 1,169 | 1,157 |
| 50 to 100 | 105 | 104 | 103 | 105 | 101 | 102 | 102 | 104 |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

MCX-69-484

A. 700

٠

| | | | | to connte | "" Maraj D | UU TEAL C | Actes | |
|---------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| Particle Range _(microns) | First 100 ml | Noxt 100 ml | Next 100 ml | Next 100 m1 | Next 100 ml | Next 100 ml | Next 100 ml | Next 100 ml |
| 5 to 15 | 180,308 | 167,887 | 168,091 | 166,531 | 166,667 | 166,777 | 164,899 | 165,279 |
| 15 to 25 | 13,538 | 13,577 | 13,674 | 13,856 | 13,953 | 14,092 | 13,979 | 14,062 |
| 25 to 50 | 1,227 | 1,258 | 1,264 | 1,288 | 1,312 | 1.,329 | 1,333 | 1,320 |
| 50 to 100 | 103 | 105 | · 103 | 109 | 104 | 107 | 103 | 102 |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

Table VIII-40 HIAC Particle Counter Data, 800 Test Cycles

Table VIII-41. HIAC Particle Counter Data, 900 Test Cycles

| Particle Range (microns) | First 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 69,419 | 95,140 | 100,243 | 102,458 | 98,551 | 98,084 | 98,925 | 99,597 |
| 15 to 25 | 11,058 | 12,130 | 12,846 | 13,226 | 13,425 | 13,718 | 13,724 | 13,984 |
| 25 to 50 | 1,135 | 1,221- | 1,322 | 1,325 | 1,320 | 1,366 | 1,350 | 1,395 |
| 50 to 100 | 106 | 110 | 109 | 108 | 107 | 107 | 109 | 113 |
| 100 + | 0 | 0 | 0 | 0 | . 0 | 0 | 0 | |

| Particle Range (microns) | First 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 89,865 | 95,682- | 101,769 | 87,886 | 85,688 | 84,661 | 82,926 | 74,538 |
| 15 to 25 | 1,322 | 5,144 | 7,372 | 6,669 | 6,408 | 6,340 | 6,240 | 5,573 |
| 25 to 50 | 257 | 756 | 992 | 875 | 818 | 761 | 767 | 672 |
| 50 to 100 | . 12 | 58 | 44 | 31 | 30 | 26 | . 26 | 19 |
| 100 + | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 |

Table VIII-42 HIAC Particle Counter Data, 1000 Test Cycles

Table VIII-43 HIAC Particle Counter Data, 1100 Test Cycles

| Particle Range (microns) | First 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 110,750 | 91,983 | 78,050 | 68,516 | 61,070 | 51,529 | 47,371 | 44,242 |
| 15 to 25 | 6,726 | 7,579 | 6,649 | 5,827 | 5,325 | 4,319 | 3,856 | 3,587 |
| 25 to 50 | 866 | 1,016 | 871 | 717 | 617 | 484 | 506 | 410 |
| 50 to 100 | 32 | 23 | 28 | 11 | 10 | 16 | 4 | 8 |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

VIII-42

.....

÷

٠

Particle Next 100-m1 Range First Next Next Next Next Next Next (microns) 100 ml 100 ml 100 ml 100 ml 100 m1 100 m1 100 ml 5 to 15 90,709 92,260 95,067 71,332 60,736 61,052 64,895 60,171 15 to 25 6,586 7,606 8,079 6,537 5,713 5,813 6,264 5,695 25 to 50 834 928 955 834 637 617 672 632 50 to 100 30 24 29 20 21 16 25 12 100 + 0 0 0 0 0 0 0 0

Table VIII-44 HIAC Particle Counter Data, 1200 Test Cycles

Table VIII-45 HIAC Particle Counter Data, 1300 Test Cycles

| Particle Range (microns) | First 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 90,475 | 61,371 | 57,287 | 52,639 | 33,655 | 29,278 | 31,147 | 31,002 |
| 15 to 25 | 1,811 | 3,880 | 4,693 | 4,677 | 2,862 | 2,424 | 2,826 | 2,638 |
| 25 to 50 | 235 | 461 | 581 | 535 | 332 | 270 | 314 | 263 |
| 50 Lo 100 | 13 | 11 | 10 | 10 | 5 | 3 | 3 | 8 |
| 100 + | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

| Table VIII-46 | HIAC | Particle | Counter | Data. | 1400 | Test | Gyclos |
|---------------|------|----------|---------|-------|------|------|----------|
| | | | | ~~~~ | 4400 | + | oyurus - |

| Particles Range (microns) | First 100 ml | Next 100 m1 | Next 100 ml | Next 100 ml | Next 100 ml | Next 100 ml | • Next 100 ml | Noxt 100 ml |
|---------------------------------|-----------------|----------------|----------------|----------------|-----------------------|----------------|------------------|----------------|
| 5 to 15 | 46,451 | 46,680 | 47,123 | 49,068 | 46,562 | | | · |
| 15 to 25 | 806 | 769 | 801 | 816 | 664 | ř | | |
| 25 to 50 | 108 | 136 | 135 | 147 | 87 | | | |
| 50 to 100 | 2 | 8 | 5 | 3 | 7 | | | |
| 100 + | 0 | 0 | 0 | 0 | 0 | | | |

. .

Table VIII-47 HIAC Particle Counter Data, 1500 Test Cycles

| Particle Range (microns) | First 100 ml | Next 100 m1 | Next 100 ml | Next 100 ml |
|--------------------------------|-----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| 5 to 15 | 67,781 | 48,434 | 38,426 | 33,378 | 32,678 | 32,131 | 28,888 | 26,364 |
| 15 to 25 | 5,748 | 5,179 | 4,220 | 3,713 | 3,723 | 3,658 | 3,278 | 2,966 |
| 25 to 50 | 831 | 759 | 678 | 524 | 510 | 525 | 437 | 427 |
| 50 to 100 | 32 | 30 | 17 | 15 | 15 | 7 | 11 | 4 |
| 100 + | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 |

VIII=43

| Sample Number | 69M | 3041 | 69M3042 | 69M3043 | 69M3044 | 69M3045 |
|--------------------------------|------|--------|---------|---------|--|----------|
| Volume of Sample Counted (ml) | 10 | 5 | 10 | 100 | 100 | 100 |
| Sample Takon at Test Cycle No. | 300 | 300 | 600 | 900 | 1200 | 1500 |
| Particle Range (micron) | | r | | | ************************************** | ****** |
| 6 to 10 | TNTC | TNTC | TNTC | TNTC | TNTC | TNTC |
| 11 to 25 | TNTC | 14,400 | TNTC | TNTC | TNTC | . TNTC |
| 26 to 50 | TNTC | 6,600 | 6,600 | 9,000 | 3,100 | . 17,400 |
| 51 to 100 | 930 | 600 | 1,500 | 1,240 | 650 | 1,500 |
| Over 100 | 420 | 700 | 840 | 695 | 385 | 480 |

Table VIII-48 Hydraulic Oil Particle Count (Millipore)

VIII=44

-

Note: 1) TNTC - Too Numerous To Count. 2) Sample volumes diluted from total sample taken.

| | į | Prossure | Pressure Decay After Five Minutes (psig)/Regulator Set Pressure | | | | | | | | | |
|-------------------|-----------------|---|--|------------|------------|------------|------------|------------|------------|--|--|--|
| Test | Serial | $\begin{pmatrix} \text{Applied to} \\ (3000 + 150) \\ \hline 0 \end{pmatrix}$ | Cycle Number | | | | | | | | | |
| Components Number | (3000 - 0) | 0 | 100 | 300 | 600 | 900 | 1200 | 1500 | | | | |
| Cylinder | 75M06506 | Piston Rod Side Piston Side | 0 0 | 0 | 0 | 0 | 2.0 | 3.5 | 5.0 4.6 | | | |
| Regulator | 1592 | Inlet | 0 2960 | 0 2969 | 0 2940 | 0 2920 | 0 2920 | 0 2935 | 0 2960 | | | |
| | 3300 | Oil Test Side Air Side | 6.0 6.0 | 6.0 6.0 | 6.0 6.0 | 6.0 6.0 | 5.5 5.5 | 4.5 | 3.0 3.0 | | | |
| Accumulator- | 3299 | .Oil Test Side Air Side | 0 | 0 0 | 0 | 1.0 | 2.0 | 4.0 4.0 | 6.0 6.U | | | |
| Solenoid | 399 | Inlet Outlet | ; 0 0 | 0 0 | 0 | 0 0 | 0 | · 0 0 | 0 | | | |
| Valve 398 | Inlet Outlet | 0 | 0 0 | 0 | 0 | 0 0 | 0 | 0 | | | | |
| Check | 9021312 | Outlet | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | | |
| Valves | 9021313 | Outlet | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | | |

Table VIII-49 System Test Interim Internal Leakage Test Data

MCR=69=484

c. Final Functional Test Results and Discussion

After the system contamination test was completed, functional tests were conducted for each component in order to accurately evaluate component performance after testing. Performance was measured against the initial functional test results obtained plor to the contamination tests. Tables VIII-26 through VIII-31 present the results of each component final functional test.

The test results between the prefunctional and postfunctional tests are very nearly the same in all respects. The following conclusions may be reached from the data:

- 1) The data comparison prior to and after the contamination tests are nearly the same showing very little if any, degradation in performance;
- 2) The cylinder leakage is comparable, and the breakaway force decreased;
- 3) Solenoid response time increased slightly, and internal leakage increased but is still within the service arm specification;
- 4) The check valves had zero leakage and the cracking and reseat pressures decreased;
- 5) The regulator performance improved and was within specification, whereas the initial performance prior to the contamination tests was out of specification in some instances;
- 6) The accumulator internal leakage decreased on S/N 6K3300. The leakage on S/N 6K3299 increased from zero leakage to 6.1 drops per minute. NASA criteria are 10 drops per 15 minutes for this accumulator. The leakage was due to 0-ring laminations, not contamination;
- 7) The 0.020 bleed orifice flow rate performance was identical (0.48 gpm at 3000 psig).

d, Final Component Disassembly and Inspection

Following completion of the final functional rest, each test specimen was completely disassembled for importion. Contamination was found in every component, particularly where h, draulic oil residue was not completely drained from the component. Each piece of the system test tubing was disassembled, and again contamination was found in each piece of tube where oil residue was found. The inspection showed that the contaminant was well distributed throughout the system. Figures V(1)=40 through V(1)= 46 show the hydraulic test specimens prior to disassembly, an exploded view showing the piece parts of each component, and see lected photographs exhibiting the extent of contamination and/or anomalies.

A detailed description of the observations made for each component follows and is in sequence with the component photo-graphs.

<u>Pressure Handloader (75M08830)</u> - Many fine particles of contaminant were found in all parts of the handloader, particularly where oil residue still remained. Figures VILL-42 and VIII-43 show the contaminant, which consisted of A.C. road dust, teflon, rubber particles, and fibers, remaining in the valve body and piston.

The O-ring (J200A16) in the main piston showed normal wear (Fig. VIII-44). Two previous failures of this O-ring occurred prior to and during the tests. The first O-ring failed prior to contaminant injection; the second at 1326 cycles. This O-ring failure is attributed to assembly problems and rolling and spiraling in the groove with subsequent nibbling on the inside and outside diameters. The cause of this O-ring failure is not attributed to contamination.

The sensing piston O-ring was not worn. Four longitudinal scratches were observed on the O-ring lands, but there were no scratches on the mating part. The teflon pilot on the sensing piston was burnished on one side of the outside diameter due to wear, and showed some longitudinal scratches. The corresponding inside diameter of the retaining spool showed wear marks for the full 360 deg with some longitudinal scratches. These indications of wear and scratches are attributed to contamination. The measured final clearance between these two parts is 0.001 in. (25 microns). A.C. road dust and metal particles were observed on the retaining spool.

The main seat of the poppet stem was badly eroded due to particle impingement, although this handloader did not leak. The erosion was similar to that evidenced in the pneumatic handloader which has a similar configuration. Deep scratches were observed on the mating nylon seat for the full diameter of the conical sealing surface. These scratches were caused by particles flowing over the seat of the poppet valve thus causing the gouges. The O-ring (J200A2) on the poppet stem was badly chewed up. During the contamination tests this O-ring failed four times (Fig. VIII-45). It is our conclusion that these O-ring failures are not due to contamination, but to excessive groove width which permits the O-ring to roll and spiral. It should be noted that this component, and the flow orifice, actually saw 3000 test cycles whereas the remaining components were run for 1500 test cycles.

Figure VIII-46 shows the inlet and outlet fittings and filter screens. The inlet filter screen dislodged from the fitting at 1113 cycles and had migrated to the retaining spool in the handloader. At 1326 cycles the filter screen in the outlet fitting was laid back parallel to the flow stream. This screen was removed from the system and is shown in Figure VIII-46. The filter screens failed as a result of contaminant loading and subsequent ΔP across the screen, even though the screen is a very coarse mesh. The outlet screen was loaded with a black residue that appeared to be either a rubber seal material or lubricant from the accumulators.

All of the remaining O-rings, seals, and piece parts in the handloader were in good condition.

<u>Check Valve (75M05365-4, S/N 9021312)</u> - Many small particles and long fibers were observed in the check valve body and poppet. When the valve was disassembled, it was found that the O-ring in the valve which forms one of the sealing surfaces was missing (Figure VIII-48). The valve did not leak during the contamination tests or postfunctional tests. This check valve design has a dual sealing action; it first forms a seal on the Oring, then on the metal seat. It is believed that the O-ring was never assembled into the valve, and it was received in this condition. There was no sign of seat erosion or valve degradation due to contamination.

<u>Check Valve (75M05365-4, S/N 9021313)</u> - Many small particles and long fibers were observed in the check valve body and on the poppet. There was no evidence of degradation in the valve.

<u>Two-Way Solenoid Valve (75M08823-1, S/N 399)</u> - The solenoid body was fairly clean with a few large particles of teflon and residual lubricant in evidence.

Several particles were observed in the residual lube in the V-groove between the two top O-rings (Fig. VIII-51). All three O-rings on the stem showed normal wear and were not chipped or nibbled. The backup rings were not scratched and did not show any signs of wear. Long (0.25 in.) slivers of O-ring were observed in both of the two top O-ring grooves, but were not from this valve. The main poppet seat was not eroded. The main nylon seat was not eroded or scratched, but did show some evidence of cold flow. There was no evidence of wear in the valve.

A long sliver (0.625 inch by 200 micron) of stainless steel was still attached to the O-ring pilot edge of the O-ring support seat and is a result of machining (Fig. VIII-53). This edge was very sharp. The mating static O-ring was chewed up and its condition is believed to be the result of assembly over the sharp edge or because of a "pinching effect" during assembly.

Two-Way Solenoid Valve (75M08823-1, S/N 398) - The cleanliness condition of this valve was similar to S/N 399. All three O-rings on the poppet stem were in good condition. The nylon seat was in good condition, but showed evidence of some cold flow. There was no erosion on the main poppet seat. The bottom stem pilot showed indications of wear and longitudinal scratches for approximately 0.25 in. on the diameter. The mating inside diameter on the retaining spool also showed indications of wear and longitudinal scratches (Fig. VIII-52). The measured clearance between these two parts is 0.001 in. (25 microns). The wear and scratches were not severe, but can be attributed to contamination. Figure VIII-52 also shows many particles inside the spool, the majority of which were of O-ring material. These particles had to migrate from another component because the only 0-ring failures in this valve were not in the flow path. The static O-ring that fits on the retaining spool (Fig. VIII-52) was chipped in one place for approximately 0.25 in. on the outside diameter. This failure is attributed to assembly problems.

The static O-ring on the support seat was nibbled in a manner similar to that described for valve S/N 399.

<u>Hydraulic Cylinder (75M065067)</u> - The sliding surface of the V-cup seal on the piston head was worn around the periphery of both seals. Large pieces of V-cup seal material were observed in the piston head V-groove, and large particles of metal were

imbedded in the V-cup seal. A few longitudinal scratches were observed in the brass piston head. Although the cylinder leakage did not increase as a result of the contamination tests, all of the above anomalies can be attributed to contamination.

No scratches were visable on the cylinder bore, but the entire bore was coated with many fine particles of contaminant.

Many particles that appeared to be chevron seal material, brass chips, and test contaminant were observed on the retract head.

The chevron rod seals showed normal wear except for the last seal which was badly chewed up on the outside diameter. This seal lies next to the gland nut, and it is believed that this seal would be damaged every time on assembly because of the design (Fig. VIII-52). Very slight scratches were observed on the cylin-


<u>Hydraulic Accumulator (75M08814-1, S/N 3300)</u> - Both heads of the accumulator were very heavily lubricated with a black lubricant (Fig. VLII-59) in the threads and on the static O-rings. Large slivers of O-ring material were observed in the thread relief. A large quantity of fine road dust, large teflon, brass, and metal particles was observed in the oil residue remaining in the lower head, which is the side seeing the injected contaminants.

The static O-rings on both heads were badly nibbled on the entire outside diameter (Fig. VIII-60). The O-ring failure could be due to one of two causes: (1) pressure pulsations and incorrect groove design, or (2) cutting by the threads upon assembly-disassembly.

The barrel of the accumulator contained many deep gouges, spaced at very equal intervals (0.125 in.), that could be a result of tool marks or contamination. The cylinder wear pattern is sketched on the following page and shown in Figure VIII-61. The sketch shows only the relative position and lengths rather than the exact number of gouges. The clearances are actual measurements between the piston and the barrel. The variation in clearances is due to some "egg-shape" in the barrel, as measured at 90 deg to each other. It should be noted that the leakage in this accumulator decreased during the contamination test.

VIII-50 -

MCR-69-484



Some very slight scratches that may be due to contamination were observed all around the inside diameter. The barrel walls were coated with fine particles that appear to be teflon, fine dust, and 0-ring slivers.

The top land of the piston shows some wear and approximately 15 longitudinal scratches some of which may be due to the gouges in the bore and some to the contaminant. The extent of each cause is impossible to determine (Fig. VIII-62). The top O-ring showed normal wear with some rolling action. On the side of the O-ring opposite the backup ring there were approximately 26 pits in the O-ring that appear to be caused by laminations in the molding process. The pits were not on the sealing surface, even considering the rolling action, and were not due to contamination. The top backup ring was badly scratched around the outside diameter in a longitudinal direction. The scratches are a result of contamination with some effect due to the gouges in the bore (Fig. VIII-62).

The bettom O-ring on the piston looks very good with some very slight longitudinal scratches on the wearing surface. The condition of the bottom backup ring was the same as that of the top land. The bottom land showed normal wear with some slight burnish marks but no scratches or gouges.

Many particles of teflon, road dust, metal, and rubber were observed in the O-ring grooves and on the O-rings.

<u>Hydraulic Accumulator (75M08814-1, S/N 3299)</u> - Both heads of the accumulator were heavily lubricated and contained considerable contamination similar to S/N 3300 (Fig. VIII-63). The static O-rings were nibbled similarly to S/N 3300, but the ribbling was not as severe (Fig. VIII-60).


The accumulator bore contained one deep gouge approximately 12 in, long located in the middle of the stroke. There was indication that the bore had been polished or honed in this area after machining in an attempt to eliminate the scratch. Except for this scratch the bore was perfect, without even minor scratches (Fig. VIII-64).

The top O-ring on the piston was nubbled all around the outside diameter. One area (0.625 in. long) was nubbled out badly (Fig. VIII-62). The nubbled inclusions were shiny in appearance, indicating lamination problems in the manufacturing process. The leakage on this accumulator increased during the tests, and is probably a result of the deep nubbling that occurred in one area of the O-ring. The top land had approximately nine longitudinal scratches. Both the top and bottom backup rings contained longitudinal scratches, but not as many as on S/N 3300. The bottom O-ring was spiraled but showed normal wear with no pits or nibbling. This O-ring was on the contaminant side of the accumulator. A considerable number of particles of all types were entrapped in both O-ring grooves.

The measured clearances for the piston and accumulator were:

Top Clearance = 0.0024 to 0.0029 in. Middle Clearance = 0.0024 to 0.0027 in. Bottom Clearance = 0.0021 to 0.0024 in.

<u>Orifice</u> - This orifice (0.020 in. diameter) plate was constructed of aluminum and was placed in the system to determine the effects of clogging and erosion. The contaminant injected into the system contained particles as large as 750 microns and fibers up to 4000 micron, whereas the 0.020-in. orifice represents 500 microns. The inlet edge of the orifice was rounded to a radius. The inside diameter of the orifice contained gouges that appeared to be the result of hard particles passing through the orifice. The orifice was not plugged with particles.




e

Figure VIII-1 Pneumatic Cylinder Functional Test Schematic

VI11-52

...



Ż


3


.


Figure VIII-2 Two-Way Solenoid Valve Functional Test Schematic

VIII-53

t







VIII-54

.





Figure VIII-4 Regulator Functional Test Schematic

VIII-55

۴.

1

. :




VIII-56

.

MCR-69-484


ŧ

Figure VIII-6 Pneumatic Contamination Test System



VIII-58

MCR-69-484



MCR=69=484

......

!

ł

. . .

•

•

ł

.

1


VIII-60

.

. . .


;

MCR-69-484



Solenoid Valve (75M08824-1) (Scale Division = 0.0156 in.)

Figure VIII-9 Metal Sliver





-



1

MCR-69-484





......

.

VIII-64

MCR-69-484



Figure VILI-13 Spool Piece and Filter Screen (75M08831-1)




Figure VIII-14 Inlet Fitting (75M08831-1)

MCR-69-484






Figure VIII-15 Two-Way Solenoid Valve (75M08824-1)

VIII-66



MOR-69-484

VIII-67



MCR-69-484

VIII=68

MCR-69-484

VIII-69





Figure VIII-18 Three-Way Solenoid Valve (75M08825-1)

1

MOR-69-484



٠.






Figure VIII-20 Spool Piece (75M08825-1)





Figure VIII-21 Pressure Handloader (75M08829)



:

MCR-69-484









Figure VIII-24 Eroded Poppet Seat Nitrogen Handloader (75M08829), 15X Magnification

VIII-75

MCR-69-484



MCR=69-484

VIII-77





figure VIII-26 Three-Way Solenoid Valve (75M09285-1, S/N 280)

. MCR-69-484



MCR-69-484

VIII-79





Figure VIII-28 Spool Piece (75M09285-1, S/N 280)



MCR-69-484

Figure VIII-29 Three-Way Solenoid Valve (75M09285-1, S/N 281)


VIII-80

í.

Figure VIII-30 Three-Way Solenoid Valve (75M09285-1, S/N 281)

MCR-69-484

VIII-81.....



MCR-69-484





Figure VIII-32 Two-Way Solenoid Valve (75M08823-1)


MCR-69-484...


1

;

VIIL-83







MCR +69 -484

VIII-86

Hydraulic Power Supply Hydraulic Servo Valve Selector Rot Pressure Elec Switch 0=5000 Function Generator 0-5000 paig paig \odot 0-5000 paig 0~5000 paig C 75M08814-1 75M08814-1 $\binom{3}{2}$ 31) (4) >)(¢ 7 5006 506-7 \bowtie 凶 Ţ, AP . <u>}</u> <u>7</u>. P SOL I(1). T M W SOL H(2)75M08823-1 52 75M08823-1 区 N 1 **8**.r $\mathbf{6}_{1}$ 62 8 0.020-in. Orifice 75005365-4 75105365-4 Å 5 75M08830 N. 2 T Êxb ١. t. HLAC Millipore Sampler Particle Counter J. Particle Sampling Station

.


÷,

Figure VIII-36 Hydraulic Systems Test Schematic

MCR-69-484

Hi Pressure

VIII=87



MCR-69-484...

VIII=88

.

MCR=69-484

ŧ

Figure VIII-38 Hydraulic Test System (with accumulator and cooling coils) : Cooling Bath ator . . ł * • • • • • •


.

V111-89




; =

MCR - 69-484







1

Figure VIII-40 Pressure Handloader (75M08830)




Figure VIII-41 Pressure Handloader (75M08830)

MCR-69-484

VIII-93






Figure VIII-42 Valve Body (75M08830)

MCR-69-484









Figure VIII-44 Piston (75M08830)



MCR-69-484








Figure VIII-46 Fittings and Filter Screens (75M08830)

1.1.1.1.1.1.1

MGR-69-484





MCR=69=484

VIII-99





Figure VIII-48 Check Valves (75M05365-4).



VIII-100..

MCR-69-484





Figure VIII-50 Two-Way Solenoid_Valve (75M08823-1)



VIII-102

MCR-69-484

VIII=103




Figure VIII-52 Retaining Spool (75M08823-1).

VIII=104

ŝ

.

Ŧ

.

MCR-69-484




Figure VIII-53 Static O-Ring and Support Seat (75M08823-1)

VIII-105





Figure VIII-54 Hydraulic Cylinder (75M065067)

VIII-106

۱.

MCR-69-484 ...



VIII=107







Figure VIII-56 Cylinder Chevron Packing (75M065067)








VIII-110

÷

MCR-69-484




1


VIII-111

VIII-112

MCR-69-484_.




•



ļ

: . VIII-113



VIII-114

MCR-69-484

MCR-69-484

VIII-115

Figure VIII-64 Accumulator Bore (75M08814-1, S/N 3299)

A-1

.

.

.

2

.

:

APPENDIX A

CATEGORIZED COMPONENT LIST

PRECEDING PAGE BLANK NOT FILME

.

Δ-3

| | MCR-69-4 | D4 | | |
|-------------------------|---------------------|--|--------|--|
| SPECIFICATION NUMBER | ITEM | FIND NUMBER LOCATION | CAT | EGORY |
| | 17 W F H F | | A | В |
| В75 МО5365 | Gheck Valve | 5418 (1-8) 5441 (1-8) 5484 (4-8) 5651 (4-7) 5680 (4-7) 34756 (9) 34756 (9) 34757 (9) 34760 (9) 34763 (9) 34821 (9) | x x | X X X X X X X X X X |
| 75006116 | Solonoid Valve | 34701 (9) | | x |
| 75406118 | Check Valve | 34703 (9) | | x |
| 75M06201 | Flow Control Valve | 5521 (1-8) | x | |
| 75106350 | Pump | 5306 (HCU-1-2) | | x |
| 75M06506 | Cylinder, Hydraulic | 5702 (4-7) | x | |
| 75M06597 | Pump | 5309 (HCU-1-2) | | x |
| 75 M06604 | Check Valve | 5314 (HCU-1-2) | | x |
| | | | | |

MCR-69-484

:

.

.

A-4

i,

١.

.

MCR-69-484

| SPECIFICATION NUMBER | - ITEM | FIND NUMBER LOCATION _ | CATI | CATEGORY | |
|--|---------------------|--------------------------------------|------|-------------|--|
| •••••••••••••••••••••••••••••••••••••• | | | A | B | |
| 75M06605 | Relief Valve | 5308 (HCU-1 -2) | | x | |
| 75M06606 | Filter | 5307 (HCU-1 -2) | | x | |
| 75M06607 | Filter | 5304 (HCU-1 -2) | | x | |
| 75M06660 | Relief Valve | 5316 (HCU-1 -2) | | x | |
| 75406706 | Snubber | 5341 (HCU-1 -2) | | x | |
| 75 ₩07505 | Pressure Switch | 5342 (HCU-12) | | x | |
| 75007725 | Cylinder, Pneumatic | 5894 (2) | | x | |
| 75M07998 | Cylinder, Pneumatic | 5811 (6-7) | x | | |
| 75M08053 | Filter | 5395 (1-8) 29692 (3) 34747 (9) | | X X X | |
| 75M08142 | Valve, 3 Way | 29694 (3) | | x | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

....

÷

•

٤.

| SPECIFICATION NUMBER | • | FIND NUMBER | CATEGORY | |
|-------------------------|-----------------|--|---|---|
| | ITEM | LOCATION | A | В |
| 75408231 | Cylinder | 5583 (4-8) | x | |
| 75M08323 | Pressure Switch | 5432 (1-8) 5511 (1-8) 5533 (4-8) 5691 (4-7) 5767 (6) 5795 (7) 5852 (4-8) 5883 (2) 5908 (2) 5908 (2) 5944 (1) 5991 (4) 6033 (4) 6072 (8) 6104 (8) 6132 (8) 6377 (7) 29741 (6) | | X X X X X X X X X X X X X X X X X X X |
| 75M08325 | Check Valve | 5461 (1-8) 5561 (4-8) 5687 (4-7) 5710 (6-7) 5776 (7) 5823 (4-6) 5888 (2) 5917 (2) 5953 (1) 5978 (4) 6036 (4) 6045 (4) 6045 (4) 6045 (4) 6045 (4) 6045 (4) 6042 (8) 6142 (8) 6142 (8) 6143 (8) 6143 (8) 6387 (7) 6399 (7) 6419 (7) 29606 (7) 29607 (7) 29875 (4-6) 34802 (9) | x x x x x x x x x x x x x | X X X X X X X X X X X X X X X |

۸-5

| A-6 | 5 |
|-----|---|
|-----|---|

MCR-69-484

| | FIND NUMBER | CATEGORY | |
|----------------|---|---|---|
| ITEM | LOCATION | A | В |
| Check Valve | 5782 (7) 29745 (6) | . X . X | |
| Snubbar | 5431.(1-8) 5510.(1-8) 5532.(4-8) 5690.(4-7) 5766.(6) 5849.(4-7) 5881.(2) 5907.(2) 5943.(1) 6031.(4) 6070.(8) 6131.(8) 6131.(8) 6379.(7) 29739.(6) 34693.(9) 34726.(9) | | X X X X X X X X X X X X X X X X X X X |
| Metering Valve | 5924 (2) 5957 (1) 5478 (1-8) 6251 (9) | X X X | x |
| Relief Valve | 5476 (1-8) 5486 (1-8) 5727 (1-7) 5896 (2) 29691(3) 29693 (3) | x x | X X X X |
| | 29774 (4-7) 34665 (9) 34680 (9) 34753 (9) 34754 (9) 34797 (9) | x x x | X X X |
| | Snubber Metering Valve | ITEMLOCATIONCheck Valve $5782 (7)$ $29745 (6)Snubber5431 (1-8)5510 (1-8)5552 (4-8)5690 (4-7)5763 (7)5766 (6)5849 (4-7)5881 (2)5907 (2)5943 (1)6070 (8)612 (8)6131 (8)6379 (7)29739 (6)34693 (9)34726 (9)Metering Valve5924 (2)5957 (1)5478 (1-8)6251 (9)Relief Valve5476 (1-8)5476 (1-8)5727 (1-7)5896 (2)29693 (3)29774 (4-7)34665 (9)34753 (9)34754 (9)$ | ITEM LOCATION A Check Valve 5782 (7) 29745 (6) X Snubber 5431.(1-8) 3510 (1-8) 5522 (4-8) 5690 (4-7) X Snubber 5431.(1-8) 3552 (4-8) 5690 (4-7) X Snubber 5431.(1-8) 3569 (4-7) X Snubber 5431.(1-8) 3569 (4-7) X Sold (4) 5907 (2) 5943 (1) Sold (4) 6070 (8) 6102 (8) 6102 (8) 6121 (8) Sold (4) 6070 (8) 6122 (8) 6131.(8) 6379 (7) 29739 (6) 34633 (9) 34726 (9) X Metering Valve 5924 (2) 5957 (1) 29597 (1) 29597 (1) 5476 (1-8) X X Relief Valve 5476 (1-8) 5486 (1-8) 29693 (3) 29693 (3) 29693 (3) 29774 (4-7) 34665 (9) X X Relief Valve 5476 (1-8) 5486 (1-8) 29693 (3) 29774 (4-7) 34665 (9) X X State (9) 34753 (9) X |

| SPECTFICATION NUMBER ITEM. FIND NUMBER LOGATION. CATEGORY 75M08617 Check Valve 5610 (5-7) X X 75M08617 Check Valve 5610 (5-7) X X 75M08814 Accumulator 5468 (1-8) 5503 (1-8) X X 75M08819 Counterbalance Valve 5502 (1-8) 5503 (1-8) X X 75M68820 Pilot Operated Valve 5482 (1-8) 29675 (1-2) X X 75M68820 Pilot Operated Valve 5482 (1-8) 29675 (1-2) X X 75M68820 Pilot Operated Valve 5482 (1-8) 29675 (1-2) X X 75M68820 Pilot Operated Valve 5513 (1-8) X X 75M68821 Pilot Operated Valve 5513 (1-8) X X 75M08822 Pilot Operated Valve 55537 (4-8) X X 75M08823 Solenoid Valve 5417 (1-8) 5550 (4-8) 5550 (4-8) X X 75M08823 Solenoid Valve 5417 (1-8) 5550 (4-8) X X 75M08823 Solenoid Va | | | r | | |
|---|------------------------|----------------------|---|---------------------------------|---------------------------------|
| A B 75M08617 Check Valve 5610 (5-7) X 75M08814 Accumulator 5468 (1-8) 5654 (4-7) X X 75M08819 Counterbalance Valve 5502 (1-8) 5480 (9) X X 75M08820 Pilot Operated Valve 5481 (1-8) 5482 (1-8) X X 75M08820 Pilot Operated Valve 5481 (1-8) 5482 (1-8) X X 75M08820 Pilot Operated Valve 5481 (1-8) 5486 (9) X X 75M08821 Pilot Operated Valve 5513 (1-8) X X 75M08821 Pilot Operated Valve 5513 (1-8) X X 75M08823 Solenoid Valve 5513 (1-8) X X 75M08823 Solenoid Valve 5513 (1-8) X X 75M08823 Solenoid Valve 5517 (4-8) X X 75M08824 Solenoid Valve 5517 (4-8) X X 75M08823 Solenoid Valve 5517 (4-8) X X 75M08824 Solenoid Valve | | ፐጥክን | | CATEG | ORY |
| 75M08814 Accumulator 5468 (1-8) 5694 (4-7) X X 75M08819 Counterbalance Valve 5502 (1-8) 5503 (1-8) 34808 (9) X X 75M08820 Pilot Operated Valve 5481 (1-8) 5482 (1-2) 34766 (9) X X 75M08820 Pilot Operated Valve 5481 (1-8) 5482 (1-2) X X 75M08820 Pilot Operated Valve 5481 (1-8) 5482 (1-2) X X 75M08821 Pilot Operated Valve 5513 (1-8) X X 75M08821 Pilot Operated Valve 5513 (1-8) X X 75M08823 Solenoid Valve 5417 (1-8) 5560 (4-8) 5578 (4-8) X X 75M08823 Solenoid Valve 5417 (1-8) 5560 (4-8) 5778 (4-8) X X | 140 1413 1717 | | MW 4114 & 411 - | A | В |
| 75M08819 Counterbalance Valve 5502 (1-8) 5503 (1-8) 34808 (9) X 75M08820 Pilot Operated Valve 5481 (1-8) 5482 (1-8) 29675 (1-2) X 75M08820 Pilot Operated Valve 5481 (1-8) 5482 (1-8) 29675 (1-2) X 75M08820 Pilot Operated Valve 5481 (1-8) 5482 (1-8) X 75M08820 Pilot Operated Valve 5481 (1-8) 5482 (1-2) X 75M08821 Pilot Operated Valve 5513 (1-8) X 75M08822 Pilot Operated Valve 5513 (1-8) X 75M08823 Solenoid Valve 5417 (1-8) 5560 (4-8) X 75M08823 Solenoid Valve 5417 (1-8) 5560 (4-8) X 75M08823 Solenoid Valve 5417 (1-8) 5560 (4-8) X | 75M08617 | Check Valve | 5610 (5-7) | | x |
| 75M68820 Pilot Operated Valve 5481 (1-8) 5482 (1-8) 29675 (1-2) 29676 (1-2) 34768 (9) 34768 (9) 34776 (9) X 75M68821 Pilot Operated Valve 5513 (1-8) X 75M68823 Pilot Operated Valve 5513 (1-8) X 75M68823 Solenoid Valve 5513 (1-8) X 75M68823 Solenoid Valve 5517 (4-8) X 75M68823 Solenoid Valve 5537 (4-8) X | 75M08814 | Accumulator | | x | x |
| 5482 (1-8)X $29675 (1-2)$ X $29676 (1-2)$ X $34768 (9)$ X $34768 (9)$ X $34776 (9)$ X $34776 (9)$ X $34776 (9)$ X $34776 (9)$ X $34778 (9)$ X $34783 (9)$ X $75M08821$ Pilot Operated Valve $5513 (1-8)$ $75M08823$ Solenoid Valve $5537 (4-8)$ X $75M08823$ Solenoid Valve $5420 (1-8)$ X 75808823 Solenoid Valve $5417 (1-8)$ X $5560 (4-8)$ XX $5950 (4-8)$ XX $5950 (4-8)$ XX $5950 (4-8)$ XX $5977 (4)$ XX $34814 (9)$ XX | 75m08819 | Counterbalance Valve | 5503 (1-8) | X | |
| 75M08823 Pilot Operated Valve 5537 (4-8) X 75M08823 Solenoid Valve 5417 (1-8) X 75M08823 Solenoid Valve 5417 (1-8) X 5560 (1-8) X X 5560 (4-8) X X 5578 (4-8) X X 5667 (4-7) X X 5707 (6) X X 5977 (4) X X | 75Me ⁱ 8820 | Pilot Operated Valve | 5482 (1-8) 29675 (1-2) 29676 (1-2) 34767 (9) 34768 (9) 34771 (9) 34774 (9) 34776 (9) 34778 (9) 34780 (9) | X X X X X X X | x |
| 75M08823 Solenoid Valve 5417 (1-8) 5420 (1-8) 5460 (1-8) 5560 (4-8) X X X 5578 (4-8) 5977 (4) 34814 (9) X | 75M08821 | Pilot Operated Valve | 5513 (1-8) | x | |
| $\begin{array}{c ccccccccccccccccccccccccccccccccccc$ | 75M08823 | Pilot Operated Valve | 5537 (4-8) | x | |
| | 75M08823 | Solenoid Valve | 5420 (1-8) 5460 (1-8) 5560 (4-8) 5578 (4-8) 5650 (4-8) 5667 (4-7) 5707 (6) 5977 (4) 34814 (9) | | X X X X X X X |

ŧ

.

A-7

۸-8

i

1

•

н. 2 7

. .

:1CR-69-484

ŧ.

| SPECIFICATION NUMBER | ITEM | FIND NUMBER LOCATION | CATEGORY |
|-------------------------|----------------------|---|---|
| 75m08824 | Solenoid Valve | 5787 (7) 5837 (4-7) 5887 (2) 5914 (2) 5952 (1) 6023 (4) 6058 (8) 6090 (8) 6138 (8) 6400 (7) 29731 (6) | X X X X X X X X X X X X X X X |
| 75M08825 | Solenoid Valve | 5507 (1-8) 5528 (4-8) 5688 (4-7) 5762 (4-7) 5792 (4-7) 5879 (2) 5895 (2) 5904 (2) 5904 (2) 5940 (1) 5985 (4) 6028 (4) 6028 (4) 6028 (4) 6028 (8) 6128 (8) 6382 (7) 29736 (6) | X X X X X X X X X X X X X X X X X X X |
| 7 5 M08826 | Pilot Operated Valve | 5663 (4-8) 6081 (8) 6113 (8) 6368 (7) 6405 (7) | X X X X X X |
| 7 <i>5</i> м08827 | Pilot Operated Valve | 5730 (4-7) | x |

٠

....

÷

.

| SPECIFICATION NUMBER | ITEM | FIND NUMBER LOCATION | CATEGORY | |
|-------------------------|---|--|---|--|
| • | 18 - 18 - 18 - 18 - 18 - 18 - 18 - 18 - | INCATION | A | B |
| 75M08829 | Regulator | 5785 (7) 5835 (4-7) 5886 (2) 5913 (2) 5951 (1) 5956 (1) 6022 (4) 6057 (8) 6089 (8) 6136 (8) 6401 (7) 29730 (6) 34705 (9) | X | X X X X X X X X X X X X X X X X |
| 75M08830 | Regulator | 5419 (1-8) 34734 (9) | | x x |
| 75M08831 | Regulator | 6075 (8) 6108 (8) 6373 (7) 6410 (7) | X X X X | |
| 75408836 | Automatic Valve | 6396 (7) 6374 (7) | x x | |
| 75M08839 | Solenoid Valve | 5439 (1-8) | x | |
| 75M08841 | Solenoid Valve | 5479 (1-8) 6254 (9) 6296 (9) 29677 (1-2) 34660 (9) 34661 (9) 34769 (9) 34772 (9) 34779 (9) 34784 (9) | X X X X X X X X X | X |

A-9

| A | 10 |
|---|----|
|---|----|

.

.

....

•

. 4 • 2

:

į

MCR-69-484

ŧ

| SPECIFICATION | | FIND NUMBER | CATE | GORY |
|---------------|---------------------|---|---|---------------------------------|
| NUMBER | ITEM | LOCATION | A | В |
| 75M09007 | Check Valve | 5475 (1-8) 5553 (4-8) 34698 (9) 34770 (9) 34773 (9) 34775 (9) 34777 (9) 34809 (9) | X X X X X X | x x |
| 75009014 | Cylinder | 6007 (4) 6018 (4) | x x | |
| 75M09283 | Level Switch | 5470 (1-8) 5656 (4-7) 6249 (9) 6250 (9) 6290 (9) 6292 (9) | | X X X X X X X |
| 75M09285 | Solenoid Valve | 5642 (7) 5809 (7) 5829 (4-7) 5860 (4-7) 5868 (4) 5871 (4) 5923 (2) 6040 (4) 6049 (4) 6053 (4) 6054 (4) 6150 (8) 6413 (4-7) 29753 (6) | X X X X X X X X X X X X X X X X X X X | |
| 75409362 | Cylinder, Hydraulic | 5492 (1-8) 5497 (1-8) | | x x |

| MCR - | 59 - 4 | 84 |
|-------|---------------|----|
|-------|---------------|----|

| SPECIFICATION NUMBER | ITEM | FIND NUMBER LOCATION | CATEX | DRA |
|-------------------------|---------------------|--|------------------|---------------------------------|
| e 7 tr 8 9 er 446 t | 4 5 281 | TYOATTON | A | B |
| 75M10090 | Solenoid Valve | 5770 (6) | x | |
| 75m10272 | Regulator | 5611 (5-7) | | Х |
| 75M10807 | Cylindei | 5626 (5-7) | | X |
| 75М10992 | Filter | 5388 (1-8) 5390 (1-8) 5563 (4-8) 5613 (4) 34748 (9) 34749 (9) | | X X X X X X X |
| 75M11428 | Selector Valve | 5612 (5-7) | | x |
| 7 <i>5</i> M11149 | Air Motor | 6122 (8) 6390 (7) | x x | |
| 75M11558 | Metering Valve | 6391 (7) | x | |
| 75M12157 | Cylinder, Hydraulic | 34825 (9) 34827 (9) | | X X |
| 75412560 | Rotary Actuator | 34840 (9) 34845 (9) | x x | |
| 75M12665 | Accumulator | 6244 (9) 6245 (9) 6246 (9) 6247 (9) | X X X X | |
| 75M13255 | Regulator | 34964 (9) | x | |
| | | | | |
| | | | | |

۸-11

Δ-12

ţ

.

a.

•

MCR-69-484

t

| SPECIFICATION NUMBER | ITEM | FIND NUMBER LOCATION | CATEGORY | |
|-------------------------|---------------------|--|-----------------------|---------------------------------|
| | | | A | В |
| 75M16990 | Solenoid Valve | 34755 (9) 34758 (9) 34759 (9) 34761 (9) | | X X X X |
| 75M21479 | Orifice | 5872 (4) 5873 (4) | x x | |
| 75 m51383 | Regulator | 5459 (1-8) 5559 (4-8) 5666 (4-7) 6200 (9) | | X X X X |
| 75M51630 | Check V <u>alve</u> | 34939 (9) 34944 (9) 34954 (9) 34956 (9) 34960 (9) 34963 (9) 34972 (9) 34974 (9) 34981 (9) 34984 (9) | X X X X X | X X X X |
| 75M51766 | Pressure Switch | 34699 (9) 34724 (9) | | x x |
| 76K00187 | Solenoid Valve | 34704 (9) | | x |
| 76K00188 | Filter | 34863 (9) 34864 (9) 34865 (9) 34866 (9) 34867 (9) 34868 (9) | | X X X X X X X |
| 76K00189 | Örifice | 34762 (9) 34765 (9) 35730 (9) 35731 (9) | | X X X X |

•

. ...,

њ. 2.

| SPECIFICATION NUMBER | ITEM | FIND NUMBER LOCATION | CATEGORY | |
|-------------------------|---------------------|--|---|-----------------------|
| | | | A | В |
| 7 6K 00251 | Valve, Deceleration | 34839 (9) 34849 (9) | x | x |
| 76K03230 | Cylinder | 34934 (9) 34935 (9) | | X X |
| 76k03578 | Orifice. | 34951 (9) .34971 (9) .34989 (9) | X ¥ | x |
| 7 6 K03824 | Cylinder, Pneumatic | 34952 (9) | x | |
| 76K03825 | Cylinder, Pneumatic | 34988 (9) | x | |
| B10425701 | Solenoid Valve | 34937 (9) 34938 (9) 34938 (9) 34955 (9) 34955 (9) 34959 (9) 34961 (9) 34962 (9) 34969 (9) 34973 (9) 34973 (9) 34983 (9) 34985 (9) 34986 (9) | X X X X X X X X X | X X X X X |
| 10425928 | Check Valve | 34987 (9) | | x |
| | Check Valve | 34950 (9) | x | |

A-13

A-14

....

MCR-69-484

۲.

| SPECIFICATION . NUMBER | ITEM | FIND NUMBER. LOCATION | CATEXIORY | |
|-------------------------------------|----------------|---|------------------|-----|
| | | | A | В |
| Vendor P/N 800262-19 Marotta | Check Valve | 5866 (4) 5869 (4) 597 2 (4) 5974 (4) | X X X X | - |
| Vendor P/N 204002-19 Marotta_ | Check Valvé | 5863 (9) 6153 (6) | X X | |
| Vendor P/N MV583 Marotta | Solencid Valve | 11190 (6) | x | |
| Not Known | Orifice Plate | , 5594 (7) | x | |
| 75M24511 75M24512 75M24513 | Orifice Plate | 29727 (6) | x | |
| | | TOTALS | 137 | 194 |
| | | | | 194 |
| | | | | |
| | | | | |
| | | | | |

COMPONENT ANALYSIS SHEETS

APPENDIX B

MCR-69-484

Ł

1

.

.

:

.

20

 B=1

PRECEDING PAGE BLANK NOT FILME

MCR-69-484

B-3

COMPONENT ANALYS IS

COMPONENT Check Valve

SPECIFICATION NO. 75M05365 (-4, -6)

VENDOR James Pond Clark

<u>VENDOR P/N</u> (-4) 277 T1-8NN (-6) 277 T1-12NN.

FIND NUMBERS/CATEGORY A5418(1-8)/B, A5441(1-8)/A, A5484(4-8)/A, A5651(4-7)/B, A5680(4-7)/B, A6185(9)/B, A6226(9)/A, A6230(9)/B, A6252(9)/B, A6273(9)/B

FAILURE MODES 1)

Leakage - System Malfunction
 Stuck Open - System Malfunction.
 Stuck Closed - System Malfunction

<u>ANALYSIS</u> These check values are the James Pond Clark standard 200 series check values as shown in the James Pond Clark Catalog. It is a poppet type check value constructed of 303 SS material and Buna N seals. Cracking pressure required to open is .5 to 1 psi. The value is required to have zero leakage up to maximum operating pressure. The check value has a well guided, tapered poppet with a clean flow design such that normal flow paths of contaminant particles will flow through the value without being trapped or causing damage to the seals. The James Pond Clark Engineering representative stated that these values are used in commercial cleaned system without problems, as the poppet design is tapered to make it "self-cleaning". MMC has used many of these check values in the Titan systems without any known contaminant

ACTION Recommend the check valve not be considered for test.

COMPONENT ANALYSIS

COMPONENT

Solenoid Valve

SPECIFICATION NO. 75M06116

VENDOR Marotta Valve Corp.

<u>VENDOŘ P/N</u> 225884 (MV74VE)

FIND NUMBERS/CATEGORY A34701(9)/B

FAILURE MODES

De-energized - Can't check sys. press. transducer Energized - No system readout; constant charge Leakage - Possible erroneous readout

ANALYSIS

This value for analysis purposes according to Marotta engineering is similar to 75M08825.

ACTION

Recommend that 75M08825 be tested.

B-4

......

COMPONENT ANALYS IS

COMPONENT Check Valve

SPECIFICATION NO. 75M06118

VENDOR James Pond Clark

VENDOR P/N HP279T1-8NN

FIND NUMBERS/CATEGORY A3470(9)/B, A34703(9)/B

FAILURE MODES Same as B75M05365 (Item 1)

ANALYSIS Same as B75M05365 (Item 1)

ACTION Recommend the check valve not be considered for test.

COMPONENT

Deceleration Valve

SPECIFICATION NO. 75M06201-1 Modified to 75M21842-1

VENDOR Racine

VENDOR P/N

FIND NUMBERS/CATEGORY A5521 (1-8)/A

FAILURE MODES

Blocked ---- No Arm Retraction . Erratic - Loss of Arm Speed Control (Auto)

ANALYSIS

The deceleration value is a composite of a relief value, a sequence value, a pressure compensator value and a cam operated variable orifice spool. The sequence value and pressure compensator value are to be removed after test and retained in a parts kit. This leaves the value as a mechanical variable orifice with a flow range of 60 to 120 gpm and a full flow relief value. ECP. 0258 provides for this modification.

Seal Material - Viton A

Leakage

External - None

Lubrication - Ke1-F-90 Grease

Cleaning - Racine does their own cleaning of this component. The component is checked for cleanliness to NASA Specs by sampling the effluent after the functional test.

Tolerances - All moving parts have clearances from .0006 to .0011 of an inch.

The Racine Technical Representative felt this component would function with no problem in industrial level cleaned hydraulic fluid. Stability problems were given as the reason for modification of this value.

The variable orifice spool is the only part in this valve which is chrome plated and the rest of the valve is made from hardened steel. The parts used in the valve have a rust preventitive on them and it is removed prior to assembly. Unless the valve is protected from moisture intrusion prior to installation there may be a corrosion problem.

This value is not considered contamination sensitive due to the following reasons:

- 1. The tolerance on the variable orifice spool is fairly tight but the spool is operated by a mechanicam can which should overcome any sticking due to contamination.
- 2. Previous failure history of the valve.
- 3. Recommendation of the vendor.
- 4. Valve not considered to be a contamination generator.

ACTION

This valve is not recommended for test.

COMPONENT ANALYSIS

COMPONENT

Pump

SPECIFICATION NO. 75M06350

VENDOR

Commercial Stamping & Shearing Co.

<u>VENDOR P/N</u> P 15H 300 BEYR 10-16

FIND NUMBERS/CATEGORY A 5306 (HCU 1, 2)/B

FAILURE MODES Inoperative - Possible hydraulic failure

ANALYSIS

The fixed-displacement, gear type, supercharger pump draws fluid from the reservoir through a 140 micron (nominal) filter and supplies the mainstage high pressure pump with 11 gpm at 30 psig. The excess fluid from the supercharger pump is diverted through a low pressure relief valve and back to the reservoir. The discharge fluid from the supercharger pump is filtered through a 10 micron (nominal) filter to protect the high pressure pump from contamination.

The gear type pump does not appear to be contamination sensitive and should be able to operate satisfactorily on a contamination level at least as dirty as the high pressure pump. The high pressure pump was designed to operate satisfactorily on fluid cleaned to NAS 1638 Class 9. The gear type pump does not appear to be a large contamination generator and any contamination critical to the system should be removed by the 10 micron (normal) filter just downstream from the pump.

ACTION

This fixed-displacement, supercharger pump is not considered contamination sensitive or a high contamination generator and is not recommended for test.

MCR=69=484

COMPONENT ANSLYSIS

COMPONENT Cylinder, Hydraulic

SPECIFICATION NO. 75M06506

VENDOR Pathon Mfg. Co.

VENDOR P/N C-11145

FIND NUMBERS/CATEGORY A5702(4-7)/A

FAILURE MODESStuckNo carrier withdrawalLeakagePossible withdrawal malfunction

ANALYSIS -

Seal Material - Buna-N per MIL-P-25732, Viton A per MIL-P-25897, or Polyurethane, backup ring per MIL-R-8791

Leakage - GN₂ around barrel - none Rod end 10 cc per 25 operating cycles, internal piston by-pass 5-25 cc/min

> Hyd... around barrel - none Rod end 1 drop per 25 opërating cycles, internal piston by-pass = 5 cc/min

Lubrication - The spec calls out MIL-H-5606 for hydraulic cylinders and Kel-F-90 for pneumatic cylinders, but according to the Pathon Technical Representative it was going to be changed to some other lubricant. The lubricant may be Atlantic Refining Company #54 Lubricant. A problem with "O" ring spiraling on accumulators was evidently solved by using this lubricant.

Tolerances on cylinders between piston and barrel ranged from .0025 to .0095 in. on an 8 in. bore and .003 to .009 in. on a 3 in. bore.

The hydraulic cushion which is used on some cylinders does not appear to be contamination sensitive.

Leakage at the rod end seal would probably be the most common type failure once a cylinder is installed in the system. A metal wiper is used on the rod end to prevent contamination from entering the cylinder. Teflon or some other softer material would probably be

more effective in keeping contamination out of the cylinder but temperature requirements prevents their use.

Most of the cylinders now or soon will have stainless barrels and rods and improved seals. This should reduce the problem of contamination generation and make cylinders less sensitive to contamination.

According to the Pathon Mfg. Technical Representative they clean their cylinders to an industrial level. They perform the functional and proof pressure test using hydraulic oil MIL-H-5606 and then send the cylinders with minimum seals to their cleaning vendor, TMC (Technical Micronic Control), to be disassembled, cleaned to NASA Specs., seals replaced, reassembled, and functional checked. The approximate_cost_for this cleaning was \$200.00 for a 75_MO 7362 cylinder.

The hydraulic and pneumatic cylinders built by Pathon Mfg., Co. are not considered to be contamination sensitive. The contamination generation is not believed to be high due to the smooth finish requirements and improved seals used in cylinder construction, but testing may be required for verification.

Cleaning, assembly and test procedures or methods will be further reviewed to determine if the cylinders are meeting the reliability requirements without undue effort.....

Pathon's Technical Representative said that hydraulic cylinders could stand more contamination than the pneumatic cylinders because hydraulic fluid lubricates the contaminants and allows them to "slide around" rather than causing wear which could happen in a dry pneumatic cylinder.

ACTION

This value is not particularly contamination-sensitive, but does represent a broad category of components of the Service Arms. Recommend_test.

B-LL

COMPONENT

Pump

SPECIFICATION NO. 75M06597

VENDOR

VENDOR P/N PV05-006-31R-062

FIND NUMBERS/CATEGORY G5309 (HCU-1,-2)/B

FAILURE MODES

Inoperate - Loss of Hydraulic Pressure

Erratic - Possible Hydraulic Failure

ANALYSIS

This is a piston type variable-displacement, pressure compensated pump capable of 9.5 gpm flow at 2750 psi. With no flow demand the press is 3000 ± 150 psi. The supply to the high pressure pump is received from a boost pump at 30 psi. Ten micron (nominal) filtration is used at the inlet to the high pressure pump and at the pump case drain. A differential pressure gage is used on the filter, which is at the high pressure inlet, to indicate when the filter is clogged or dirty and requires replacement of the filter element.

Deunison Division, Abex Corp.

The Dennison Division Technical Representative was contacted and the following information was obtained:

- 1. Use clean oil. Ten micron filtration which is used on the suction side of the pump is completely adequate.
- 2. Change filters regularly.
- 3. Maximum level of contamination that the pump can stand without excessive wear is NAS 1638 Class 9. The test stands used by Dennison Division are required to meet NAS 1638 Class 8. The table below was given as the level of contamination the pump could stand and still function properly without excessive wear.

| Size Range (Micron) | Number (Per 100 m1) |
|---------------------|---------------------|
| 5-15 | 128,000 |
| 15-25 | 22,800 |
| 2 5+50 | 4,050 |
| 50-100 | 720 |
| 100 + | 128 |

The pump is not considered contamination sensitive as long as the contamination level does not exceed NAS 1638 Class 9 and adequate filtration is used. Evaluation of the failure history of this pump shows that there were not any contamination problems.

ACTION

Recommend the pump (75M06597) not be considered for test.

B-12

;

COMPONENT ANALYSIS

COMPONENT

Check Valve

SPECIFICATION NO. 75M06604

VENDOR. Ropublic Mfg. Co.

<u>VENDOR P/N</u> 497-12Y-2

FIND NUMBERS/CATEGORY A5314(HCU-1, -2)/B

FAILURE MODES Open - Motorize hydraulic pump in back-up system - loss of hydraulic press Closed - No effect Leakage - Possible hydraulic malfunction

ANALYSIS

This is a standard Republic poppet type check value and is used to prevent high pressure back flow into the HEU stage not being used. The body is aluminum alloy and the poppet is stainless steel, type 440. The seating surfaces are metal to metal, and the seals are Teflon and Buna-N. Leakage requirements are: external - none, internal - 1 drop per 2 minutes. There have not been any failures reported on this value.

ACTION

:

ł

This check value is ruggedly made for high shook, continuous service in high velocity hydraulic systems. The check value is not considered contaminant sensitive and is not recommended for test.

COMPONENT ANALYSIS

Relief Valve (Hydraulic Check Valve)

COMPONENT

SPECIFICATION NO. 75M06605

VENDOR Republic Mfg. Co.

<u>VENDOR P/N</u> 446-16Y-30 ____

FIND NUMBERS/CATEGORY A5308(HCU-1, -2)/B

FAILURE MODESClosed - Possible high boost pressureOpen - Loss of hydraulic pressureLeakage - Possible hydraulic failure

ANALYS IS

This is a standard Republic poppet type check valve with a cracking pressure of 35 psi \pm 6. The excess fluid from the low pressure boost pump is diverted through the relief valve and back to the reservoir. The body is aluminum alloy and the poppet is hardened stainless steel, type 440. The seating surfaces are metal to metal and seals used are teflon and Buna-N. Leakage requirements are: external - none, internal - 1 drop in 2 minutes. There are no reported failures on this relief valve.

ACTION

:

This relief valve (check valve) is ruggedly made for high shock, continuous service in high velocity hydraulic systems. The relief valve is not considered contaminent sensitive and is not recommended for test.

B-15

COMPONENT ANALYSIS

COMPONENT Filter

SPECIFICATION NO. 75M06606 (Rev. C)

<u>VENDOR</u> Fluid Dynamics

<u>VENDOR P/N</u> 002922

FIND NUMBERS/CATEGORY A5307(HCU-1, -2)/B.

FAILURE MODES

Clogged - Loss of Hydraulic Supply

ANALYSIS

This filter is a Fluid Dynamics 10. micron. nominal T-type filter with 304 SS element. The unit is cleaned to NASA specification by an outside cleaning facility. The element has 230 square inches of effective filter area with a specified flow capacity of 20 GPM. A Fluid Dynamics representative indicated that all units they supply are tested to verify bubble point, full flow, proof pressure, and leakage requirements. He also indicated that the same unit can be modified with a finer or coarser micron, rated element, if required. It was indicated that the only problems to date with the subject filters were incorrect handling procedures by some of the outside cleaning facilities during cleaning operations. The absolute rating of this unit is 25 micron and has a 1500 psi differential collapse pressure. The Fluid Dynamics representative also stated he has seen some of these elements completely collapsed without allowing any contaminants to escape into the system.

- ACTION 1) Recommend bubble point test on element after cleaning.
 - Specification does not call out a bubble point test. 2) Investigate use of a finer micron rating element
 - Investigate use of a finer micron rating element.
 Investigate use of a AP indicator on the unit to
 - i) Investigate use of a AP indicator on the unit to provide indication when the element requires replacement.

COMPONENT ANALYS IS

Filter

COMPONENT

SPECIFICATION NO. 75M06607

VENDORMarvelVENDOR P/NM2449FIND NUMBERS/CATEGORYA5304 (HCU -1, -2)/BFAILURE MODESClogged - Loss of hydraulic pressure

ANALYSIS

This filter is a 100 mesh (144 micron) sump type filter with a flow capacity of 10 GPM and filter area of 100 square inches. The material construction is 303 stainless steel with a monel wire mesh screen. The suction from the 30 psi low pressure pump will not collapse the filter. The filter is recleanable.

The purpose of this filter is to protect the low pressure boost pump from contamination and remove the large contaminant particles which would clog the 10 micron filter just downstream from the low pressure boost pump.

The chances of the filter becoming clogged are very remote because once the hydraulic fluid has been cleaned by recirculation, the contamination level in the reservoir should be low. Good maintenance policy, such as changing the filter at regular intervals and preventing contamination from entering the reservoir would help to insure the filter does not become clogged.

ACTION

The sump suction filter is considered adequate for the system and is not considered contaminant sensitive.

.

COMPONENT

VENDOR

Relief Valve

COMPONENT ANALYS IS

SPECIFICATION NO. 75M06660

Denison Division, Abex Corp.

<u>VENDOR P/N</u> RIV 12-S45-S6

FIND NUMBERS/CATEGORY A5316 (HCU-1, -2)/B

| FAILURE MODES | Open - Loss of Hydraulic Pressure |
|---|--------------------------------------|
| and the second se | Closed - No Effect |
| | Leakage - Possible Hydraulic Failure |

ANALYSIS

The system relief value is a variable pressure, spring loaded poppet-sect type value. It has a flow capacity greater than the maximum flow of the main stage high pressure pump. The relief value provides the system with a fluid unloading capability to prevent over pressure from the main stage pump during a malfunction of the pressure comepnsator.

```
Seal Material - Buna-N
Lubrication - Kel-F-90
Leakage Allowed
External - None
Internal - 100 cc/minute
Flow Capacity - 30 gpm
```

The Denison Technical Representative said they had no contamination problems with this value and that it would operate properly in industrial cleaned hydraulic systems. He felt this value was less sensitive to contamination than the mainstage pump, which is designed to operate on fluid cleaned to NAS 1638 Class 9. Failure analysis has revealed no failures due to contamination.

ACTION

This relief valve (75M06660) is not considered contamination sensitive and is not recommended for test.

COMPONENT ANALYSIS

COMPONENT Snubber

SPECIFICATION NO. 75M06706

VENDOR Operating & Maintenance Specialty Go.

VENDOR P/N 11316-2-1-F

FIND NUMBERS/CATEGORY A5341(HCU-1, -2)/B

FAILURE MODES

Blocked - No System Pressure Indication Vented - Possible Erroneous Indication

ANALYSIS

Catalog information supplied on these specific snubbers stresses the point that these snubbers are designed to be "self-cleaning" to the point of operating in systems with dirt and pipe scale. The vendor states that the unit contains no filters, porous metal discs, rubber or plastic parts to replace or clean. The above specifications along with the use of these snubbers in low flow requirements systems indicate these parts will not be considered as a contaminant sensitive part in_the system.

ACTION

Recommend the snubber not be considered for test.

B-19

COMPONENT ANALYSIS

COMPONENT Pressure Switch

SPECIFICATION NO. 75M07505

VENDOR Custom Components Switch

VENDOR P/N 603G-C9-7S

FIND NUMBERS/CATEGORY A5342(HCU-1, -2)/B

FAILURE MODES

Open - No System Pressure Indication Closed - Constant Indication

..

ANALYSIS

٨

This switch is actuated by a Belleville disc spring. The Belleville disc is the only portion of the unit contacted by the fluid media and there are no other moving parts. Therefore, this unit will not be considered as a contaminant sensitive part of the system.

ACTION

Recommend the pressure switch not be considered for test.

COMPONENT ANALYSIS

Cylinder, Pneumatic

COMPONENT

SPECIFICATION NO. 75M07725

VENDOR Pathon Mfg. Co.

VENDOR P/N C-11147

 FIND NUMBERS/CATEGORY
 A5894(2)/B

 FAILURE MODES
 Stuck - No. tray withdrawal

 Leakage - Possible withdrawal malfunction

ANALYS IS

The pneumatic withdrawal cylinder contains a cylinder body, two heads, a piston, a rod, seals, two adjustable cushions, and a wiper ring. The bore diameter is 2 inches, stroke 20 inches and rod diameter 1 inch.

This cylinder is similar to 75M06506-1 and reference is to be made to that analysis.

ACTION

This cylinder is not recommended for test.

B-21

COMPONENT ANALYSIS.

75M07998

COMPONENT

Cylinder, Pneumatic

SPECIFICATION NO.

VENDOR Pathon Mfg. Co.

VENDOR P/N

FIND NUMBERS/CATEGORY A5811(6-7)/A

FAILURE MODES Stuck - No tray withdrawal Leakage - Possible retraction malfunction

ANALYSIS

The pneumatic cylinder contains a cylinder body, piston, rod, seals and two end heads.

This cylinder is similar to 75M06506 and reference is to be made to that analysis.

ACTION

7.

.

This cylinder is not recommended for test.

COMPONENT ANALYSIS

<u>COMPONENT</u> Filter (10 Micron Nominal)

SPECIFICATION NO. 75M08053 (Rev. E)

VENDOR Fluid Dynamics

VENDOR P/N FR1802

FIND NUMBERS/CATEGORY A5395(1-8)/B, A34747(9)/B

FAILURE MODES

Clogged - Loss of 3000 psi Hydraulic Supply

ANALYSIS

This filter is a Fluid Dynamics 10 micron nominal filter similar to 75M06606 (Item 10), the only difference being operating pressures, 3000 psi differential collapse pressure, 150 square inches of effective filter area and has 316 SS housing rather than aluminum housing. The element is the same 304 SS wire mesh with the same flow capacity of 20 GPM of hydraulic oil.

ACTION

- 1) Recommend bubble point test when elements are cleaned.
- 2) Consider smaller micron rating element.
- 3) Similar to 75M06606

ŧ

B-23

COMPONENT ANALYSIS

COMPONENT

VENDOR

Cylinder, Pneumatic

SPECIFICATION NO. 75M08231

Pathon Mfg. Co.

VENDOR P/N

FIND NUMBERS/CATEGORY A5583(4-8)/A

| FAILURE MUDES | Stuck - No arm retraction | |
|---------------|--|--|
| | Leakage - Possible retract malfunction | |

ANALYSIS

The hydraulic-pneumatic cylinder contains a cylinder body, piston, rod, seals, and two heads. The bore diameter is 7 inches, stroke 52 inches, and rod diameter 3.25 inches.

This cylinder is similar to 75M06506~1 and reference is to be made to that analysis.

ACTION

This cylinder is not recommended for test.

COMPONENT ANALYSIS

COMPONENT Pressure Switch

SPECIFICATION NO. 75M08323 (-2, -3, -4)

VENDOR Meletron Corp.

<u>VENDOR P/N</u> 372-95-252, 372-135-246, 372-215

FIND NUMBERS/CATEGORY A5432(1-9)/B, A5511(1-8)/B, A5533(4-8)/B, A5691(4-7)/B, A5767(6)/B, A5795(7)/B, A5852(4-8)/B, A5883(2)/B, A5908(2)/B, A5944(1)/B, A5991(4)/B, A6033(4)/B, A6072(8)/B, A6104(8)/B, A6132(8)/B, A6377(7)/B, A29741(6)/B

FAILURE MODES

Open - No Recharge Capability Closed - Constant Recharge Attempt

ANALYSIS

This pressure switch is a bourdon tube actuated switch. As the only portion of this unit that will be contacted by the fluid media is the bourdon tube, there is no moving parts within the unit to be contaminant sensitive and, therefore, will not be considered as a contaminant sensitive part of the system.

ACTION

Recommend the pressure switch not be considered for test.

MCR=69=484

COMPONENT ANALYSIS.

COMPONENT Check Valve

SPECIFICATION NO. 75M08325 (-1, -2, -3, -5, -6)

VENDOR James Pond Clark

<u>VENDOR P/N</u> 279T1-4NN, -6NN, -8NN, -12NN, -4WW

FAILURE MODES Same as 75M05365 (Item 1)

ANALYSIS Same as 75M05365 (Item 1)

ACTION Recommend the check valve not be considered for test.

COMPONENT ANALYS IS

COMPONENT Check Valve

SPECIFICATION NO. 75M08326 (-1, -2)

VENDOR James Pond Clark

VENDOR P/N 279 T1-4NV, -6TB-1

FIND NUMBERS/CATEGORY A5782(7)/A, A29745(6)/A

FAILURE MODES Same as 75M05365 (Item 1)

ANALYSIS Same as B75M05365 (Item 1)

ACTION Recommend the check valve not be considered for test.

B-26

B-27

COMPONENT ANALYSIS

COMPONENT Snubber

SPECIFICATION NO. 75M08409

VENDOR Operating & Maintenance Specialty Co.

VENDOR P/N 11316-2-1-F and 75316-2-1-F

FIND NUMBERS/CATEGORY A5431(1-8)/B, A5510(1-8)/B, A55324-8/B, A5690(4-7)/B, A5763(7)/B, A5766(6)/B, A5849(4-7)/B, A5881(2)/B, A5907(2)/B, A5943(1)/B, A6031(4)/B, A6070(8)/B, A6102(8)/B, A6131(8)/B, A6379(7)/B, A29739(6)/B, A34693(9)/B, A34726(9)/B.

FAILURE MODES

Same as 75M06706

ANALYSIS

Same as 75M06706

ACTION

5

Recommend the snubber not be considered for the-test.

COMPONENT ANALYS IS

Metering Valve

75M08414 (-2, -3)

COMPONENT

VENDOR P/N

SPECIFICATION NO.

VENDOR

DR Robbins Aviation

SSKG-375A-6C-768, SSKG-375A-8C-768

FIND NUMBERS/CATEGORY A5924(2)/B, A5957(1)/A, A5478(1-8)/A A6251(9)/A

FAILURE MODES

Plugged - Possible retraction malfunction

#____

ANALYSIS

Metering valve is a Robbins catalog standard metering valve described as follows:_____

Operating pressure vacuum to 6000 psi, safety factor 4:1, Cv = 0.90, zero external and internal leakage, orifice diameter 0.312 in., body material 303 stainless steel, Buna-N seals, approximately 6 turns to full open position. Robbins valves have been widely used in industrial type applications. They are not considered as a contaminant sensitive component for this analysis providing it is opened sufficiently to allow... contaminants to pass through the valve. Open condition of the valve at time of this analysis has not been determined. Galling problem of threads has been attributed to improper choice of materials for bonnet and stem.

ACTION

This value is always fully open or fully closed, and is not recommended for test.

COMPONENT ANALYSIS

| COMPONENT | Relief Valve (Hydraulic and Pneumatic) |
|-----------------------|---|
| SPECIFICATION NO. | 75M08415 (-1, -2, -3, -5H, -10H) |
| <u>VENDOR</u> | Anderson Greenwood |
| VENDOR P/N | 28038 (-1, -2, -3, -5H etc.) |
| FIND NUMBERS/CATEGORY | A5476(1-8)/A, A5486(1-8)/A, A5727(1-7)/B, A5896(2)/B, A29693(3)/B, 29774(4-7)/B, A34665(9)/A, A34680(9)/A, A34753(9)/B, A34754(9)/B, A34797(9)/A |
| FAILURE MODES | Open - No arm retraction Closed - No effect Leakage - Possible retraction malfunction |
| ANALYSIS | |

The relief value consists of a stainless steel body (30388), teflon and buna-N seals and a Delrin seat. There have been 19 reported failures on this value and many of the failures due to a Ke1-F seat which was changed to Delrin by ECF0070. One failure was noted as being caused by a contaminant impinging on the seat.

ACTION

The relief value is not considered contaniant sensitive and is not recommended for test.

.

COMPONENT_ANALYS IS

COMFONENT Check Valve

SFECIFICATION NO. 75M08617 (-3)

VENDOR James Pond Clark

VENDOR E/N 559T1-8D-4

.

FIND NUMBERS/CATEGORY A5610(5-7)/B

FAILURE MODES Similar to Item 1 75M05365

ANALYSIS Valve design not considered to be contaminant sensitive. This item similar to 75M05365 (Item 1) and vendor representative classed this design as non-contaminant sensitive same as the 200 series type check valves.

ACTION Recommend the check valve not be considered for test.

B=30

ω.

COMPONENT ANALYSIS

| | COMPONENT | Accumulator |
|---|-------------------------|------------------------------------|
| | SPECIFICATION NO. | 75M08814 (-2) |
| | VENDOR | American Bosch Arma Corp. |
| | <u>vendor p/n</u> | ENS 41-414 |
| | FIND NUMBERS / CATEGORY | A5468(1-8)/A, A5654(4-7)/B |
| • | FAILURE MODES | Stuck Piston - No hydraulic supply |

ANALYS 19

)) { The accumulator contains a piston, cylinder, and two end caps, one for GN_2 input and the other for hydraulic fluid input. The GN_2 input forces the piston downward, exerting pressure against the hydraulic fluid. The piston moves up or down according to the pressure relationship between the hydraulic fluid and GN_2 . Attached to the accumulator, at the GN_2 end, is a level switch which indicates the position of the piston, and when to recharge the hydraulic end.

Seal Material - Buna-N per MIL-P-25732 or equal

Lubrication -- The Spec calls out Kel-f-90 grease or MIL-H-5606 hydraulic fluid. Atlantic Refining Co. #54 lubricant will be used and the Spec changed.

Leakage - Possible hydraulic failure

Leakage Allowed:

External - Bubble tight Internal - 10 drops per 15 minutes (hyd) 5 cc per minute (GN₂)

Clearances - 3 to 6 thousandths between piston and barrel

Finish - 10-14 micron-inch_RMS-

According to the American Bosch Arma Corp. Technical Representative, their normal cleaning process was to mechanically brush the components using a soft bristled brush and flush using a compatible solvent. They perform the functional, leak, and proof pressure test on all assembled accumulators. The accumulators which are required to meet NASA cleaning specs are then sent to the cleaning

vendor (ConTec or Wiley Lab) before being installed in the Service Arm System. The accumulators are disassembled and cleaned according to specification control drawing cleanliness requirements. Then they are reassembled using new seals, leak checked and functionally tested.

There have been several failures of accumulators after only a few cycles of operation and it was apparently due to the cleaning process used by the cleaning vendor. The main failures were due to O-ring spiraling, here surface deterioration, and O-ring damage upon installation. There were several recommended changes to be made to the Specification Control Drawings according to NASA internal report number 5-6250-H-614 Dated 17 September 1968.

It was the opinion of the Bosch Technical Representative that the accumulators were being "cleaned to death". Changing the cleaning methods may well improve the overall system cleanliness and reliability, in addition to decreasing the accumulator failure rate.

An unsatisfactory condition report (KSC400720 dated 9-24-68) was just received and indicated an accumulator had O-ring damage and scored inner walls, which was evidently caused by an eccentric loading from the level switch to the piston. Also, upon replacement of the soft goods on all of the accumulators from mobile launcher 1, due to internal damage and leakage problems, an accumulator was found that had approximately 90 percent of the plating gone from inside the cylinder and the O-ring sealing surface was scored.

Due to the above analysis the accumulator is not considered contamination sensitive. Contamination generation may be a problem unless the recommendations in report 5-6250-H-614 are approved and solve the problem of cleaning the accumulators.

ACTION

Although not considered to be contamination-sensitive, failure history would indicate the need for test. This component also represents a major category of components on the Service Arms. Recommend this accumulator be considered for test.

B-33

COMPONENT ANALYSIS

COMPONENT

Backpressure Valve

SPECIFICATION NO. 75M08819-1

VENDOR Rivett

VENDOR P/N 2276A

| FIND NUMBERS/CATEGORY | A5502(1-8)/A, A 5503(1-8)/A, A34808(9)/A |
|-----------------------|---|
| FAILURE MODES | Closed - Arm will not retract Leakage - Possible soft hydraulic system |

ANALYS IS

÷

The backpressure valve consists of two bodies mounted on a subplate assembly. Each body contains an adjusting screw, spring, spool, and a seat. The valve maintains a constant backpressure in the hydraulic return line.

Seal Material - Buna-N per MIL-P-25732 Lubrication - MIL-H-5606 Hydraulic Fluid or Kel-F-90 Grease Leakage - Internal - 5 cc/minute External - None Flow Capacity - 120 gpm at 60 spi pressure drop Set Pressure - 80 ± 5 psi

The only moving part in this value is the spool, which moves off the seat to allow fluid flow. The radial clearance between the spool and value body is .003 to .006 of an inch. Failure due to the spool sticking open or closed is considered very unlikely. Also failure due to leakage caused by contamination is unlikely because the seat area is large and the seat is made of Buna-N, which is a good, soft sealing material.

One failure was reported on this valve, which indicated internal leakage was caused by deformation and contamination of the soft seat sealing surfaces. This type of failure is not considered critical to the system because the fluid lost would be replaced by the backpressure system and a positive pressure maintained. Also, the chances of this failure happening are rather remote.

.

ACTION

.

This backpressure value is not considered contamination sensitive and is not recommended for test,

3. 34

.

ł

MGR-69-484

.

COMPONENT ANALYSIS

建铬铁铁铁铁石 化二乙二乙二乙二 网络花叶 化非正元

un CO TCATION DA CONSTA-

VEBOR PTO DOGLO

kijiD_20_00_00_70A11_007
A3431(1_4)/A, A5482(1_3)/A, A7472(1_07/A, A29676(1-2)/A, A34767(9)/A, A34768(9)/B, A34771(9)/A, A34774(9)/A, A34776(9)/A, A34780(9)/B, A34783(9)/B

FALLURE MODES Open - No Effect Closed - No arm retraction Leakage - Possible retraction malfunction

ANALYTES - The pilot operated valve is a two-way, two-position valve which is externally operated by a hydraulic pilot which opens or closer is stive. A mechanical detent locks the valve in either of its even a two tions. The valve consists of an actuator assembly which a success rack which operates a ball of the.

Secie St. claim Bood-N por MIL-P-25732

Bubrication - Kel F90 grease

Beakage allowed - External - none Internal - none

Critical Toterances -

- 1. .070 in. orifice which allows hyd fluid to actuate piston at a controlled rate.
- 2. .060 in between piston and bore of pilot valve.
- 3. Detent force of 35-40 in-1b to hold value in its last energized position.
- 4. Displacement per stroke of piston 0.6 in³

Plodyae does their own cleaning to MFSC Process 166D.

МСК-69-484

à

ないたので、「「ない」」

The Flodyne Representative said they had no contamination problems with this value and that it would function property if the system was considerably dirtier than present spec requirements.

Analysis of this component has found it to be considered not concamination sensitive. Below are some reasons:

- 1. Loose tolerances involved
- 2. Clean design of the ball valve
- 3. Low volume of flow in the pilot operated portion of the value
- 4. Low contamination generation
- 5. Recommendation of the vendor
- 6. History of failures

ACTION - Testing of this valve is determined to be not necessary.

Pilot Operated Valve

B-37

COMPONENT

· ...

SPECIFICATION NO.

VENDOR

rid ne Soptiols

"5M08821

<u>VENDOR P/N</u> 15G150

FIND NUMBERS/CATEGORY A5513(1-8)/A

FAILURE MODES

| #1 or #2 #1 or #2 #1 or #2 #1 or #2 #1 or #2 | Energized Open Closed | No Arm Retraction Possible Semi Extension Malfunction Possible Extension Malfunction No Arm Retraction Possible Retract Malfunction |
|--|-----------------------------|---|
|--|-----------------------------|---|

ANALYSIS

•

The pilot operated value is a two-way, two-position value which is externally operated by solenoids. A detent mechanism locks the ball in the full open or closed position. The value consists of solenoids, piston, rack and ball. The solenoid values consist of a poppet and seat assembly. When the solenoid is energized the inlet is open to outlet and de-energized the inlet is blocked and the outlet is vented.

Seal_Material - Buna-N per MIL-P-25732

Lubrication - Ke1-F-90 Grease

Leakage Allowed

External - None Internal - None

Cleaning - Flodyne does their own cleaning to MFSC-PROC-166D

Solenoid Valve Specs

Solenoid Pull - 25 1b Spring Return - 8 1b Solenoid Stroke - 0.005 in. Orifice to Piston - 0.060 in.

٠

Piston to bore clearance 0.060 in. Displacement per Stroke 0.6 in.

The Flodyne Technical Representative said they had no contamination problem with this component. He said the solenoid valve portion of this component would be the most sensitive to contamination. An inlet filter is not used on the pneumaticsolenoid valve used on this component, but Flodyne does use inlet filters on other solenoid valves which they build.

This value is the same as the hydraulic pilot operated value (P/N 15C160) except that this one has two solenoids. The value is considered not to be contamination sensitive except for the solenoid portion. The flow through the solenoid in one cycle is very small and tends to reduce its contamination sensitivity. Further study will be conducted to determine if the solenoid portion should be considered for test.

ACTION

The solenoid is used in a low flow application. This value is not recommended for test.

B-38

:

i

B-35

COMPONENT ANALYSIS

COMPONENT

Pilot Operated Valve SPECIFICATION NO. 75M08822(-1, -3) VENDOR Kemp Aero Products. VENDOR: P-/N K 402016 (-1, -3). FIND NUMBERS / CATEGORY A5537 (4-8) /A FAILURE MODES Leakage - Possible premature retraction . Closed - No arm retraction Open - No effect

ANALYSIS

The value is a pilot operated value supplied by Kemp Industries to meet the 75M08822 specification. The valve is operated by two solenoid valves, one to open the valve and the other to release the locking fingers which hold the valve and allow it to close by spring forces which allow pilot pressure to vent and the main poppet to close. The valve is designed for operating pressure of 3000 psig gaseous nitrogen with a flow factor of 2.0 SUFM/PSIA. The body material is 2024-T4. aluminum alloy (anodized) and trim materials also are 2024-T4 aluminum. Elastomers are Delvin or Buna-N. (both shown in Kemp drawing). The valve has no failure history connected with contaminant problems. The valve will remain in its last energized position with a power loss to both solenoids. This valve contains no small orifices or exceptional tight tolerances as it is all standard "O" ring design with Kel-F. 90 grease for lubrication. The pilot vent is screened for protection from external contaminants. Kemp representatives consider the valve is not contaminant sensitive and would prefer to supply the valve commercially clean ... such that they could clean and test the value in their own facility. For this analysis, the value is not considered to be contaminant sensitive and will not be considered a candidate for test.

ACTION

Recommend the valve not be considered for test.

COMPONENT ANALYSIS.

COMPONENT Solenoid Valve SPECIFICATION NO. 75M08823 VENDOR. Marotta Valve Corp. VENDOR. P/N. 806097 +1 (510H- 2A) FIND NUMBERS/CATEGORY A5417(1-8)/B, A5420(1-8)/B, A5460(1-8)/B, A5560(4-8)/B, A5578(4-8)/A, A5650(4-8)/B, A5707(6)/B, A5977(4)/B, A34814(9)/A, A34822(9)/B FAILURE MODES De-energized - No precharge, no retraction, system malfunction . Energized - System malfunction. - Possible system malfunction. Leakage

ANALYSIS

This value is a Marotta solenoid value, 2-way, 2 position, normally closed, with 1/2 inch male fittings. The value is designed for 3000 psi gaseous nitrogen or hydraulic fluid operating pressure with a 0.20 inch ESEOD ($C_D = 0.6$). Response time is 75 milli-seconds maximum. Materials in the value are 300 series. stainless steel, nylon seat, and Buna-N seals, and Kel-F grease for lubrication. The operation of the value is very similar to the 75M08825 except it is a two-way value and is 1/2 inch tube size rather than 1/4 inch tube size. Therefore, this value is further considered not to be contaminant sensitive but will be given to value used by Martin in gaseous nitrogen system cleaned to

ACTION

Valve was used in tests to complete the system circuit.

No. Ale

COMPONENT ANALYSIS

COMPONENT

<u>SPECIFICATION NO.</u> 75M08824(-1, -2)

VENDOR Marotta Valve Corp.

Solenoid Valve

<u>VENDOR P/N</u> 228154 -02, -05

| FIND NUMBERS/CATEGORY | A5787(7)/B, A5837(4-7)/B, A5887(2)/B, A5914(2)/B, A5952(1)/B, A6023(4)/B, A6058(8)/B, A6090(8)/B, A6138(8)/B, A6400(7)/B, A29731(6)/B |
|-----------------------|--|
| FAILURE MODES | De-energized - No bottle recharge Energized - Constant recharge attempt Leakage - Constant recharge attempt |
| 1.441.0.000.0 | |

ANALYSIS

This value for analysis purposes according to Marotta engineering is similar to 75M08825. The value is a two-way, two position, normally closed value for use with 3000 psi gaseous nit ogen. The value has a 0.11 inch ESEOD, 1/4 inch port. The remainder of the analysis will be the same as for 75M08825.

ACTION

This valve was used in tests to complete the system circuit.

COMPONENT ANALYSIS

| COMPONENT | Solenoid-Valve |
|-----------------------|---|
| SPECIFICATION NO. | 75M08825(-2) |
| VENDOR | Marotta Valve Corp. |
| VENDOR P/N | 225884(-02, -05) |
| FIND NUMBERS/CATEGORY | A5762(4-7)/B, A5792(4-7)/B, A5844(4-7)/B, A5879(2)/B, A5895(2)/A A5904(2)/B, A5940(1)/B, A5985(4)/B A6028(4)/B, A6066(8)/B A6099(8)/B A6128(8)/B, A6382(7)/B, A29736(6)/B |
| FAILURE MODES | De-energized - Can't check transducer Energized - No system readout, constant charge Leakage - Possible erroneous readout |

ANALYSIS

This is a Marotta solenoid valve, 3 way, 2 position, 2 inlets and 1 outlet with 1 port (closest to solenoid) normally spring closed. The unit is designed for 3000 psi operating pressure with gaseous nitrogen and bubble tight leakage. The valve has aluminum body (anodized), 303 SS stem, nylon seat and Buna-N seals. The unit has 1/4 inch tube size male fittings. The stroke on the Marotta solenoid valves is approximately .020 inch. The valve is standard "0" ring type design with balanced poppet configuration. The valve has no small orifices or pilot ports, etc., which might become clogged from normal system contaminants. The valve for this analysis is considered not to be contaminant sensitive. Marotta project engineer indicated they feel their solenoid valves would operate satisfactorily under their commercial clean conditions which they estimate to approach the MSFC 164 specification level. These valves will be given further consideration as test candidates.

ACTION

Valve was used in test circuit.

B-43

COMPONENT ANALYSIS

| Solenoid Valve (Pilot Operated) |
|---|
| 75M08826 |
| Marotta-Valve Corp. |
| 227154 -2, -4 |
| A5663(4-8)/A, A6081(8)/A, A6113(8)/A, A6368(7)/A, A6405(7)/A |
| De-energized - System Malfunction Leakage H H- GN ₂ Closed - H H |
| |

ANALYSIS

This valve is a Marotta three way, two position valve with two pilot valves. The pilot valves are solenoid valves, two way, two position, normally closed valves. The valve is designed for gaseous nitrogen or hydraulic fluid usage. Design operating pressure is 3000 psig inlet, atmospheric vent, and 600-to 1500 psig actuating port. The valve has 3/4 inch fittings with a 0.500 inch ESEOD. The valve materials are 300 series stainless steel, nylon seats, Buna-N seals and Dow Corning FS1281 lubrication. The valve has a screened port and check valve in actuation pressure inlet. There is an approximate .020 inch diameter port in the bleed side to the vent solenoid. This solenoid has been replaced with an orifice in the -4 configuration. Stroke on both poppets is approximately .100 inch. Although this valve is more complex with two solenoids, two main seats, etc., the valve is still considered by Marotta not to be contaminant sensitive and indicate they could operate the valve satisfactorily at their commercial clean level.

ACTION

This valve is not recommended for tests.

COMPONENT ANALYSIS

COMPONENT Selenoid Valve (Pilot Operated) SPECIFICATION NO. 75M08827 VENDOR. Marotta Valve Corp. VENDOR P/N 227404-2 FIND NUMBERS/CATEGORY A5730(4-7)/A FAILURE MODES De-energized - System Malfunction Energized н Ħ -Leakage 64 41 Neutral Pos. u н. н Normal Pos 11

ANALYSIS

For analysis purposes this value is similar to 75M08826. This value is a four-way, three position value and contains two pilot values, indicating switch, two stems, two poppet assemblies, two springs and a piston. The value is designed for use with gaseous nitrogen and hydraulic fluid. Operating pressures of the value are 750 psig low pressure inlet, 3000 psig high pressure inlet, and 600 to 1500 psig actuation pressure. The value has 3/4 inch fittings and 0.500 inch ESEOD. Actuation port is 1/4 inch. Materials are 316 stainless steel body, 304 stainless steel poppet, nylon seats, and Buna-N seals. Kel-F 90 grease is used for lubrication. The actuation port contains a screen and a check value same as the 75M08826 value. The remainder of the analysis for this value will be the same as for 75M08826. ____

ACTION

This valve is not recommended for test.

B-45

COMPONENT ANALYSIS

COMPONENT Regulator

SPECIFICATION NO. 75M08829

VENDOR Marotta Valve Corp.

<u>VENDOR P/N</u> 227464-J11

FIND NUMBERS/CATEGROY A5785(7)/B, A5835(4-7)/B, A5886(2)/B, A5913(2)/B, A5951(1)/B, A5956(1)/A, A6022(4)/B, A6057(8)/B, A6089(8)/B, A6136(8)/B, A6401(7)/B, A29730(6)/B, A34705(9)/B

FAILURE MODES

Closed - No Kecharge; No Withdraw, Reconnect. Erratic - Possible Low Charge

ANALYSIS

This Marotta hand operated regulator is for GN2 usage. According to Moratta's representatives the design is similar to a unit used by MMC (MMC part No. PD48\$0124-109). The unit is assembled with fitting filters in the inlet, outlet, and vent ports. The most significant de the ence between the MMC unit and this unit is the MMC unit uses omniseals rather than "O" rings and has a large sensing piston for tighter accuracy requirements. There has been no failure history of these parts in the MMC level "C" clean system. Tolerances and clearances of the MMC and subject part are essentially the same according to Marotta's engineering representatives. This is not a high flow device as its normal use is to pressurize the dome of a higher flow dome regulator. The flow past the poppet and seat would be the critical area for contaminants to cause leakage problems which is protected against by use of the fitting filters described above. As these parts are required to perform with a certain accuracy in the system they will be considered as a possible test candidate to be tested during the new proposed cleanliness level test program.

ACTION

Recommend that this regulator be considered for test.

COMPONENT ANALYSIS

COMPONENTRegulatorSPECIFICATION NO.75M08830 (-1, -2)VENDORMarotta Valve Corp.VENDOR P/N219004 (-B155, -J151)FIND NUMBERS/CATEGORYA5419(1-8)/B, A34734(9)/BFATLURE MODESClosed - Loss of hyd.sys.back pressure, standby hyd.press.
Erratic- No effect. Could cause hold early in count; soft standby sys.

ANALYSIS

This regulator is similar to 75M08829 except for lower operating pressures. The 75M08829 was designed for 10,000 psi inlet and 3000 psi outlet. This regulator is designed for 3000 psi inlet and 0-150 psi out and with a factor of .05 SCFM/PSIA. The unit is designed for use with gaseous nitrogen or hydraulic fluid. Materials used in construction of the regulator are 2024-T4 aluminum tody, 300 series stainless steel poppet, nylon seats and Buna-N seals. Kel-F 90 grease is used as lubricant. As these parts, like the 75M08829, are required to operate automatically with a certain accuracy, these parts will be considered as possible test candidates. Marotta engineering has indicated they can operate these regulators satisfactorily at their commercial clean level which approaches the MSFC 164 level. Martin has used similar regulators in ground pneumatic systems for a number of years with EPS 50405 level C cleaning with no contamination problems.

ACTION

Recommend that this valve be considered for test.

COMPONENT ANALYSIS

CORPORT -

SPECIFICATION 20.72M08831 (-2)[9.5000]Maratta Valve Corp.VENDOR P/H230904(-11) RV78PENDOR P/H230904(-11) RV78PENDOR P/HAco75(B)/A, Acio8(B)/A, Acio75(7)/A, Acide (Corp.)PENDOR P/HClosed - No withdrawal malfunction

Regulator

ANALYSIS

This regulator is a three way, spring referenced, preset pressure regulator. The regulator is designed for use with gaseous nitrogen. The unit is designed to maintain the outlet pressure either by flow from inlet to outlet to increase pressure or by flow from outlet to vent to reduce pressure to the preser pressure level within a certain accuracy. 'The unit is designed for an inlet pressure of 4500 psi maximum and an outlet pressure range of 50-190 psi. The valve has a flow factor of 0.5 scfm/psi. The inlet port is 3/8 inch and the outlet port is 1/2 inch. The unit does have a screen around the inlet port of the poppet to protect against contaminants (approx. 16? micron). As the unit is not subject to contaminant damage under normal operation, it is not considered contaminant sensitive. Marotta engineering indicates the unit should work satisfactorily in their commercial clean condition. This regulator is a standard Marotta regulator design and similar to Martin part number PD48S0124-179.

ACTION

Recommend that this valve be considered for test.

ŧ

COMPONENT ANALYSIS

| | Open - No withdrawal Leakage - Withdrawal malfunction | |
|------------------------|--|--|
| FAILURE MODES | Closed - No effect | |
| FIND NUMBERS /CATEGORY | A6374(7)/A, A6396(7)/A | |
| VENDOR P/N | 232744-3 (FVA 12) | |
| VENDOR | Marotta Valve Corp. | |
| SPECIFICATION NO. | 75M08836(=1) | |
| COMPONENT | Automatic Shutoff Valve | |

ANALYSIS

This value is an automatic shutoff value which operates with 4500 psi nitrogen gas. The value remains open until pressure drop across value increases to 40 psi. The materials are 303 CRES, mylon seat, Buna-N seals and Kel-F 90 grease for lubrication. The value has 3/4 inch ports. As the value is only for flow control and flow is such that particles should flow through value easily, it is not considered as contaminant sensitive and will not be considered as a test_candidate.

ACTION

Recommend this valve not be considered for test.

COMPONENT ANALYSIS

Solenoid Valve

AV. 14J1163____

COMPONENT

75m08839

VENDOR ITT Aerospace Controls (Formerly General Controls)

VENDOR P/N

SPECIFICATION NO.

FIND NUMBERS/CATEGORY A5439(1-8)/A

| FAILURE MODES | #1 or #2 Deenergize | ed - No Sémi-Auto | Retraction |
|---------------|---------------------|-------------------|------------|
| | #1 or #2 Energized | - No Semi-Auto | Retraction |
| | Leakage | - No Effect | |

ANALYSIS

The solenoid value is a hydraulic, pilot operated, 4 way, 3 position.cylinder lock value. It contains 2 end caps, a retainer and piston assembly, spool assembly, two solenoids, seat and ball assembly and filter assembly. Upon energizing solenoid No. 1 or No. 2, hydraulic fluid flows through the ball and seat assembly to the piston assembly which causes the spool to shift and direct hydraulic pressure to Port No. 1 or No. 2. All ports are blocked when the solenoid is not energized.

Seal Material - Buna-N per MIL-P-25732 and MIL-P-5510

Leakage - External - Bubble tight Internal - 5 cc per minute

Lubrication - Kel-F-90 grease

Clearances - Spool to sleeve clearance .00005 to .0001 of an inch based upon leakage allowance

Filter Assembly - 50 micron

The solenoid is protected against contamination in the ball and seat assembly by 50 micron filtration and the forces on the spool are sufficient to prevent sticking. There have been no reported failures due to contaminatination and only one failure due to internal leakage. This value is very similar to the Sterer 75M08841 solenoid value but the forces to operate the spool are much greater.

١.

÷.,

ACTION

This value is not considered contaminant sensitive and is not recommended for test.

1

1

COMPONENT ANALYSIS

COMPONENT Solenoid Valve

SPECIFICATION NO. 75M08841 (-1, -3)

VENDOR Sterer Engineering Company

VENDOR P/N 26370-2 (37890 - new part per Sterer Eng Rep)

FIND NUMBERS/CATEGORY A5479(1-8)/A, A29677(1-2)/A A34660(9)/A, A34661(9)/A, A34769(9)/A, A34772(9)/A, A34779(9)/A, A34784(9)/A

| FAILURE MODES | Stuck Straight | No arm retract |
|--|----------------|--------------------------------|
| المتلا فباعديا الباغا عاطيا والمتعادية بينابيه ويبعه | Stuck crossed | No effect |
| | Leakage | Possible retract malfunction . |

ANALYSIS - The solenoid valve is a four-way, two-position, double solenoid, hydraulic selector valve. The solenoid contains a spool and sleeve assembly that is operated by energizing the solenoids The movemovement of the spool and sleeve assembly allows hydraulic fluid to flow through the ports. The valve has a mechanical latch which allows the valve to remain in its last energized position.

Seal Material Bung-N per MIL-P-25732 or equal

Lubrication - Kel-f-90 grease or MIL-H-5606 hydraulic fluid

Leakage allowed - External - No leakage Internal - 10 cc per minute

Critical tolerances - Spool to sleeve clearance .00005 to .0001 of an inch based upon leakage allowance.

Solenoid Pull - 12 lb. (50% greater for new P/N)

Solenoid Travel - .065 of an inch

4

The Sterer Technical Representative said that 75M08841-1 (P/N26370-2) was changed to 75M08841-3 (P/N 37890). The basic change was in the switching mechanism and addition of a solenoid with approximately 50% greater pull. The Sterer Technical Representative also felt this valve was not contamination sensitive and similar spool type valves are used widely in aircraft systems which allow much more contamination than the NASA Specs. now imposed on this valve. He also said

a statistical analysis as to this value sticking or malfunctioning due to contamination would be enough to scare a person-but that the values do-work.

Many reports have been written on servo valves, which have a spool, which have clearances as tight and tighter than this valve and in order to fail the spool by sticking the contamination levels had to be extremely high. Levels higher than NAS 1638 class 108, which is the dirtiest level in this spec, were required in order to cause the spool to stick. The contamination was actually so high that conventional methods could not be used for checking contamination levels. Time was a factor and spools would wear at much cleaner levels. Sticking was caused by silting of small particles which get in_between the spool and sleeve assembly.

This particular value is used for supplying pilot pressure to the Flodyne pilot operated ball shut-off value and the volume of flow is very low (approximately 6/10 of a cubic inch). This low flow will reduce the chances of the spool sticking due to silting if the oil contains high contamination levels.

ACTION

Vendor experience and very low flow does not indicate the need for tests.

B-53

COMPONENT ANALYSIS COMPONENT Check Valve SPECIFICATION NO. 75M00007 VENDOR Republic Mfg. Co. VENDOR P/N 458-3288 & 9-663-1 FIND NUMBERS/CATEGORY A5475(1-8)/A, A5553(4-8)/A, A34698(9)/A, A34770(9)/A, A34773(9)/A, A34775(9)/B, A34777(9)/B, A34809(9)/A FAILURE MODES Open - No retraction Closed - No effect, possible extend malfunction, no arm extend or retract Leakage - Possible retract malfunction, extend malfunction

ANALYSIS

This is a standard Republic poppet type check valve, except for the grayloc fittings. The check valve has a 1 1/2 diameter and a flow capacity of 120 gpm at 28 psi pressure drop. The body is stainless steel, type 303, and the poppet is hardened stainless steel, type 440. The seating surfaces are metal to metal and seals used are Teflon and Buna-N. Leakage requirements are: external - zero and internal - 1 drop in 2 minutes. Two failures were reported on this check valve; both were external leakage and were not_caused by contamination.

ACTION

This check value is ruggedly made for high shock, continuous service in high velocity hydraulic systems. The check value is not considered contaminant sensitive and is not recommended for test.

Ł

COMPONENT ANALYSIS

COMPONENT

Cylinder

SPECIFICATION NO. 75M09014

VENDOR Pathon Mfg. Co.

VENDOR P/N

FIND NUMBERS / CATEGORY A6007 (4) /A, A6018 (4) /A

FAILURE MODES Stuck - No LOX cylinder withdrawal Leakage - Possible withdrawal malfunction

ANALYSIS

The 75M09014 becomes the 76K00084 by replacement of u-cup seals with "o" ring seals.

The withdrawal cylinder contains a body cylinder, piston, rod, wiper ring, seals, two heads, and an adjustable cushion. The bore diameter is 3 inches and rod diameter 1.125 inches.

The cylinder is similar to 75M06506-1 and reference is to be made to that analysis.

ACTION

See 75M06505 for action analysis.

₿**-**55

COMPONENT ANALYSIS

Level Control Switch Assembly

COMPONENT

SPECIFICATION NO. 75M09283

VENDOR Hayes Aircraft Corp.

VENDOR P/N

FIND NUMBERS/CATEGORY A5470(1-8)/B, A6249(9)/B, A6250(9)/B, A6290(9)/B, A6292(9)/B

FAILURE MODES

Open - No accumulator recharge Clogged - Constant recharge attempt Leakage - Possible hydraulic malfunction

The level control switch assembly is a single pole, double-throw, mechanically operated switch assembly. The level switch contains a harness assembly with a switch, a piston which actuates the switch, a vent valve, and sintered restrictor. The level control switch indicates the position of the accumulator piston and activates the hydraulic charging solenoid valve to maintain the proper hydraulic level in the accumulator.

Lubrication - Dow-Corning DC-55 Silicone Grease on packing and sliding surfaces.

Seal Material - Buna-N per MIL-P-25732

Leakage - External None

Stroke - 2.06 inches

The level switch has a sintered restrictor which regulates nitrogen to purge the switch and protect against explosion and fire hazards.

The only moving part of the level switch assembly exposed to the pneumatic/hydraulic system is the piston, which protrudes into the pneumatic end of the accumulator. There has been a failure of a level switch when it required 750 pounds to actuate, but it does not appear to have been caused by contamination.

ACTION

The level control switch is not considered to be contaminant sensitive and is not recommended for test.

۵

COMPONENT ANALYSIS

Marotta Valve Corp.

Solenoid Valve

COMPONENT

SPECIFICATION NO. 75M09285

VENDOR

<u>VENDOR P/N</u> 806098 (MV 583H-2A)

FIND NUMBERS/CATEGORYA5642(7)/A, A5809(7)/A, A5829(4-7)/A,
A5860(4-7)/A, A5868(4)/A, A5871(4)/A,
A5923(2)/A, A6040(4)/A, A6049(4)/A,
A6053(4)/A, A6054(4)/A, A6147(8)/A,
A6150(8)/A, A6413(4-7)/A, A6420(4-7)/A,
A29753(6)/A, 11190(6)/A (by vendor P/N_____
MV583)FAILURE MODESDe-energized - No kickoff or no withdrawal
Energized - Possible premature kickoff
or withdrawal
LeakagePossible premature kickoff
or______

ANALYSIS

This value for analysis purposes according to Marotta engineering is similar to 75M08825. The value is designed for use with 3000 psig gaseous nitrogen or hydraulic fluid. The value is a three-way, two position, normally closed value. Materials of construction are 300 series stainless steel with nylon seats.... The value has 1/2 inch ports with a 0.190 inch ESEOD. The remainder of this analysis will be considered the same as for 75M08825.

ACTION

Recommend that this valve configuration be considered for test.

MCR-69+484

B~57

COMPONENT ANALYSIS

Cylinder, Hydraulic

COMPONENT

SPECIFICATION NO. 75M09362

VENDOR Pathon Mfg. Co.

VENDOR P/N C11152

FIND NUMBERS / CATEGORY A5492 (1-8) /A, A5497 (1-8) /A

FAILURE MODES

Stuck: Possible extend/retract malfunction Leakage: Same as stuck

ANALYS IS

The hydraulic cylinder contains a cylinder body, piston, rod, seals, cartridge assembly, spare port plug assembly, needle and ball check assembly and two end heads. This cylinder has a bore diameter of 8 inches, rod diameter of 3.5 inches and stroke of 14.875 inches.

This cylinder is similar to 75M06506-1 and reference is to be made to that analysis.

ACTION

Refer to-75M06506.

MCR=69-484

COMPONENT ANALYSIS

COMPONENTRegulator, Solenoid OperatedSPECIFICATION NO.75M10090VENDORMarotta Valve Corp.VENDOR P/N230864 (RV52CC)FIND NUMBERS/CATEGORYA5770(6)/AFATLURE MODESClosed - No tray withdrawal
Open - Possible premature withdrawal
Leakage - Possible premature withdrawal

ANALYSIS

This regulator is a dome referenced regulator with a pilot valve and a pilot regulator. The pilot valve is three way, two position, solenoid valve with indicater switch. The pilot regulator is pressure regulating valve with a downstream relief designed for dome loading. The dome is loaded through the pilot valve by the pilot regulator. The valve is designed for use with gaseous nitrogen. The operating pressure is 3000 psig. The ports are 3/4 inch with a flow factor of 1.6 SCFM/PSIA in to out and 2.4 SCFM/PSIA outlet to vent. The outlet of the pilot regulator has a .020 inch orifice, but the inlet to the pilot regulator has 28 x 500 mesh stainless steel screen to protect it. The sensing passage from the outlet to the piston has .060 inch orifice. The poppet is nylon coated which could be a contaminant gener. for if it could peel off. This is a very complex assembly although it is made up of more or less standard Marotta components.

ACTION

ŧ

COMPONENT ANALYSIS

| <u>COMPONEN'</u> P | Regulator |
|-------------------------|---|
| SPECIFICATION NO. | 75 M10272 |
| VENDOR | Hannifin Go Division of Parker Hannifin Go. |
| VENDOR 1./W | H2550 |
| FIND NUMBERS / CATEGORY | A5611(5~7)/B |
| FATLAIRE MOLES | Closed - No cylinder actuation Erratic - Possible platform malfunction |

ANALYSIS

Regulator is a spring loaded diaphragm to reduce gaseous nitrogen supply pressure from 250 psi to an outlet pressure from 3-125 pai. The unit is designed for a proof pressure of 375 psi and a burst pressure of 625 psi. Materials used are corrosion resistant steel, Buna N seals, and Kel F 90 grease. Flow capacity of the unit is specified as 197 SCFM gaseous nitrogen at set pressure of 90 psi and flowing to atmosphere. The designed flow path is described by the vendor catalog as self cleaning as all flow is in a direction away from the seat. This regulator is not considered to be contaminant sensitive to normal gaseous nitrogen system usage.

ACTION

Recommend the regulator not be considered for test.

ŧ

COMPONENT ANALYSIS .

| Cylinder, Pneumatic |
|--|
| 75M10807 (-1, -3) |
| Pathon_Mfg. Co. |
| B10481, B10480 |
| A5626(5-7)/B |
| Stuck - Can't couple/uncouple vehicle Leakage - Possible coupling_malfumction |
| |

ANALYSIS

The phiumatic cylinder contains a cylinder body, piston, rod, seals and two end heads. The bore diameter is 2.0 inches, rod diameter -- 1.0 inch and stroke 5.0 inches.

This cylinder is similar to 75M06506 and reference is to be made to that analysis.

ACTION

.

Refer to 75M06506.

B-61

COMPONENT ANALYSIS

COMPONENT Filter

SPECIFICATION NO. 75M10992 (Rev. C)

VENDOR Fluid Dynamics

VENDOR P/N (-1) FL1329-1 and (-2) FL1329-2

FIND NUMBERS/CATEGORY A5388(1-8)/B, A5390(1-8)/B, A5563(4-8)B, A5613(4)/B, A34748(9)/B, A34749(9)/B

FAILURE MODES

Clogged - Loss of 750 PSI GN₂ Supply

ANALYSIS

This filter is a Fluid Dynamics 10 micron nominal filter similar to 75M06606 (Item 10). The differences being it is an in-line type, 1200 psi differential collapse pressure, 150 square inches of effective filter area for the -2, and 45 square inches after the -1. This unit is used in gaseous nitrogen system rather than hydraulic oil. The -1 is a 1/2" line size and the -2 is a 3/4" line size. It has 316 SS housing with a 304 SS wire mesh element with teflon seals.

ACTION

- 1) Recommend bubble point test on element after cleaning.
- 2) Investigate using smaller micron rating elements. Elements of various micron ratings are available for use in this housing.

COMPONENT ANALYSIS

Air Motor

COMPONENT

SPECIFICATION NO. 75M11149

VENDOR Gardner Denver

VENDOR P/N MR50C1

FIND NUMBERS / CATEGORY A6122 (8) /A, A6390 (7) /A

FAILURE MODES Inoperative - (stalled) - No LEM or service module carrier withdrawal

ANALYSIS

The air motor is a rotary vane motor with a 4-bladed rotor. The air motor is fully reversible with equal power in either direction.

Operating Pressure - 125 psi (GN₂) Max. Output at 90 psi - 5.5 hp at 247 rpm Lubrication - Kel-E=90 and SAE 30 motor oil Cleaning - KSC-C-123, Level_IV, Test Method A

There have not been any reported failures on this air motor. This type of air motor has widely been used in industrial applications and has performed well operating on industrial cleaned air systems. This air motor is not considered contaminant sensitive and any contamination generated would be vented through a check valve.

ACTION

It is recommended that the air motor not be considered for test.

COMPONENT ANALYSIS

Selector Valve

COMPONENT :

SPECIFICATION NO. 75M11428

VENDOR Republic Mfg. Co.

VENDOR P/N N8043B-8AY2LCO

FIND NUMBERS/CATEGORY A5612(5~7)/B

Straight - All cylinders will not extend Crossed - All.cylinders will not retract Leakage - Possible <u>platform malfunction</u>

ŧ.

ANALYS IS

FAILURE MODES

This is a 4-way, 2-position, manually operated selector valve. It is a Standard Republic Catalog design of their 8000 Series. The valve operates on GN, at 85-100 psi.

Seal Material - Buna-N per MIL-P-25732 or equal

Lubrication - Kel-F-90 Grease

Leakage:

Internal - None External - 30 cc per minute at 2000 psi

Cleaning - Clean, protect and inspect to MSFC Spec A10M01671, Level IV, Test Method A, Certification required.

ACTION

This is a very simple and reliable selector value and is not considered contaminant sensitive. It is recommended that this value not be considered for test.

ŧ

COMPONENT ANALYSIS

COMPONENT

Metering Valve SPECIFICATION NO. 75M11558 -VEND-OR Robbins. Aviation VENDOR P/N C427A-16C-768 FIND NUMBERS / CATEGORY A6391(7)/A FAILURE MODES Plugged - No LEM carrier withdrawal

ANALYS IS

This is a Robbins metering valve with similar design features as the 75M08414 metering valve.

ACTION

Investigation similar to action for 75M08414.

B-64

1

•••••

a

COMPONENT ANALYSIS

Cylinder, Hydraulic

COMPONENT

SPECIFICATION NO. 75M12157

VENDOR Pathon Mfg. Co.

VENDOR P/N

FIND NUMBERS/CATEGORY A34825(9)/B, A34827(9)/B

FAILURE MODESStuck - Can't lock arm extendedLeakage - Possible lock malfunction

ANALYSIS

The hydraulic cylinder contains a cylinder body, piston, rod, adjustable cushion, seals and two end heads. The bore diameter is 4 inches, rod diameter 1.75 inches and stroke 5 inches.

This cylinder is similar to 75M06506-1 and reference is to be made to that analysis.

ACTION

Refer to 75M06506.

MCR=69-484

COMPONENT ANALYSIS

COMPONENT

Rotary Actuator

SPECIFICATION NO. 75M12560-1

VENDOR Flo-Tork Corporation

VENDOR P/N

FIND NUMBERS/CATEGORY 34840(9)/A, 34845(9)/A

<u>FAILURE MODES</u> Stuck - No arm retract/extend Leakage - Possible retract/extend malfunction

ANALYSIS

The actuator contains 4 head parts, a pinion, 2 pistons with integral pinion racks, 4 cylinder sleeves and a dual cylinder body. When hydraulic pressure is applied against the pistons, the pinion racks move in opposite directions. The teeth on the rack mesh with the pinion, turning the pinion either clockwise or counter-clockwise.

Seal Material - Buna-N____

Lubrication - Mil-H-5606 Hydraulic Fluid

Leakage - Internal: .5cc/min. at 3000 psi (max.) Past actuating mechanism in locked position External: 1 drop per 25 operating cycles

Cleaning - Complete assembly shall be flushed to contain contaminants not in excess of that specified in par. 2.6.0 of 10425040 or KSC-C-123 Level IV, Method A

The cylinder sleeve material is manganese bronze (SAE 43) and has a 16 RMS finish. The piston and pinion gear are made from hardened steel. The Flo-Tork technical representative said... they just had refurbished several actuators, and there was some scoring of the cylinder walls but it was easily removed by polishing. Also, slight corrosion was found on the piston that was not submerged in hydraulic fluid. The bronze cylinder may be

۴.

a contaminant generator because it is a relatively soft material. and hard contaminant particles could score the cylinder finish. The problem of piston seizure is reduced by using the bronze cylinder which would tend to offset the bad effects of contamination generation.

ACTION

έ,

The problem of contamination generation is believed to be small -- especially due to the few cycles the actuator will see. Also, there are only a few components downstream from the actuator, and they are not regarded as being contamination sensitive. The actuator is not considered contamination sensitive and is not recommended for test.

ŧ

COMPONENT ANALYS IS

| <u>COMPONENT</u> | Accumulator |
|-----------------------|--|
| SPECIFICATION NO. | 75M12665 |
| vendor | American Bosch Arma_Corp. |
| vendor P/N | EH5 41-591 |
| FIND NUMBERS/CATEGORY | A6244(9)/A, A6245(9)/A, A6246(9)/A, A6247(9)/A_ |
| FAILURE MODES | Stuck Piston - No hydraulic supply Leakage - Possible hydraulic failure |

ANALYSIS

The accumulator is similar to 75M08814 and reference is to . be made to that analysis.

ACTION

.

,

Refer to 7.5M08814.

B-68

.

È

B-69

COMPONENT ANALYSIS

COMPONENT -RegulatorSPECIFICATION NO.75M13255VENDORMarotta Valve Corp.VENDOR226154 (RV74A)FIND NUMBERS/CATEGORYA34964 (9) /A.

<u>FAILURE MODES</u> Closed - Can't extend platform cylindor Erratic - Possible <u>platform malfunction</u>

ANALYSIS

Similar to Martin part no. PD48S0124-179 and to part no. 75M08831. For analysis of this part see analysis for 75M08831.

ACTION

This regulator is of the same configuration as 75M08831. Recommend that_either of these valves be included in the tests.

COMPONENT ANALYSIS

Solenoid Valve

COMPONENT

SPECIFICATION NO. 75M16990

VENDOR

VENDOR P/N 32310

FIND NUMBERS/CATEGORY A34755(9)/B, A34758(9)/B, A34759(9)/B, A34761(9)/B

Steror Engineering & Mfg. Co.

FAILURE MODES

#1 deenergized - Can't unlock arm -extend cylinders #2 deenergized - Can't lock arm-extend cylinders #1 energized - Can't lock arm-extend cylinders #2 energized - Can't unlock arm-extend cylinders Leakage - Possible locking malfunction

ANALYSIS

The solenoid value is a four-way, three-position double solenoid, hydraulic selector value. The solenoid contains a spool and sleeve assembly that is operated by energizing the solenoids. The movement of the spool allows hydraulic fluid to flow through the ports. The value is spring loaded so the spool returns to the center closed position when the value is not energized.

This value is the similar to 75M08841-3 and reference should be made to that analysis. The major difference is that this value is a three position spring centered closed and 75M08841-3 is a 2 position value mechanically latched in each position to protect against solenoid failure. MCR=69-484

B-71

COMPONENT ANALYSIS

75M21479

COMPONENT

SPECTFICATION NO.

A. U. Stone Co. (AUSCO)

٩

Orifice, Flow Restricting

VENDOR P/N

VENDOR

FIND NUMBERS / CATEGORY

5872(4)/A 5873(4)/A

FAILURE MODES

Clogged No LH, Line Secondary Withdrawal No LOX Line Secondary Withdrawal

ANALYS IS

The orifice has a sharp edge diameter of .1406 inch (3570 micron) and GHe is the fluid media. The orifice acts as a secondary supply in case of a primary failure.

ACTION

Because of the size of the orifice, secondary function, and fluid media used, the orifice is not considered contaminantsensitive and is not recommended for test.

COMPONENT ANALYSIS

COMPONENT - Regulator

SPECIFICATION NO. 75M51383

VENDOR Tescom

VENDOR P/N 26-1062-56-043, 26-1063-56-043

<u>FIND NUMBERS/CATEGORY</u> A5459(1-8)/B, A5559(4-8)/B, A5666(4-7)/B, A6200(9)/B

FAILURE MODES

Closed - No accumulator recharge. Erratic - Possible low accumulator, charge.

ANALYSIS

This regulator is a Tescom 1000 series hand operated regulator as described in the Tescom catalog. It is a spring loaded piston type constructed of 316 SS materials with Kel-F seats. The outlet pressure range is 50 to 6000 psig with inlet pressure to 10,000 paig. The unit assembly consists of a filter in the inlet portion constituted of bronze or stainless steel, which protects itself from partial contaminates in the flow stream. Tescom specifies in their catalog all regulators are cleaned for "gaseous oxygen service". Where special cleaning is required other than their own commercial, the parts are cleaned and tested by an approved outside facility. MMC has had very good service out of similar Tescom regulators in the Titan Systems. This part will not be considered as a contaminant sensitive. item as it does have its own filter for added protection.

ACTION

Recommend the regulator not be considered for test.

ŧ

B-73

COMPONENT ANALYSIS

Vent Check Valve

COMPONENT

SPECIFICATION NO. 75M51630

VENDOR Marotta Valve Corp.

<u>VENDOR P/N</u> 232783-634

....

. .

FIND NUMBERS/CATEGORYA34939(9)/A, A34944(9)/A, A34954(9)/A,
A34956(9)/A, A34960(9)/B, A34963(9)/B,
A34972(9)/B, A34974(9)/B, A34981(9)/AFAILURE MODESOpen - No erfect.
Closed - Lose mech.latch ability;
can't extend, retract
Leakage - No effect, APD malfunction

ANALYSIS

This check value consists only of a modified fitting with vent holes drilled into the bottom of an "O" ring groove. Pressure can flow out by pushing "O" ring out but "O" ring prevents anything from flowing into the fitting. This part is not considered contaminant sensitive and will not be considered for test.

ACTION

Recommend this part not be considered for test.

COMPONENT ANALYSIS

| COMPONENT | Pressure Switch |
|-----------------------|---|
| SPECIFICATION NO. | 75M51766 (-2, -6) |
| VENDOR | Sigma-Netics Inc. |
| VENDOR P/N | 704021(-2), (Hyd) 704026(6), (Pneu.) |
| FIND NUMBERS/CATEGORY | A34699(9)/B, A34724(9)/B |
| FAILURE MODES | Open. – No Hyd Accumulator Recharge Closed – Constant Recharge Attempt |
| | – …t – |

ANALYSIS

Pressure switch to control recharge of hydraulic accumulator. The switch is actuated by a piston which is moved by the pressure against a preset spring load. In addition to the piston seal, the switch is protected from the fluid media by a diaphragm (teflon or mylar). The -6 is set to deactivate at 2000 ± 20 psig and the -2 is set to deactivate at 50 psig. As these are a non flow device they are not considered as a contaminant sensitive

ACTION

į

Recommend the pressure switch not be considered for test.

в-75

COMPONENT ANALYSIS

Solenoid Valve

COMPONENT

SPECIFICATION NO. 76K00187

VENDOR _____ Marotta Valve Corp.

VENDOR P/N

MV509

FIND NUMBERS/CATEGORY A34704(9)/B

FAILURE MODES

De-energized - No effect Energized ----- No accumulator pressurization Leakage - No effect

ANALYSIS

This value for analysis purposes according to Marotta engineering is similar to 75M08825 and 75M08823. It is designed for 3000 psig nigrogen gas with 1/2" ports and 0.20 inch ESEOD. Materials are 300 series stainless steel, nylon seal and Buna-N seals. Remainder of the analysis will be same as for the 75M08825 value.

ACTION

Refer to 75M08825.

COMPONENT ANALYS IS

| COMPONENT | Filter, 200 Micron, In-Line |
|-----------------------|---|
| SPECIFICATION NO. | 76K00188 (-1, -2) |
| VENDOR. | Circle Seal Development Corp. |
| VENDOR P/N | 4313G-200 CK, 4343G-200 CK |
| FIND NUMBERS/CATEGORY | A34863(9)/B, A34864(9)/B, A34865(9)/B, A34866(9)/B, A34867(9)/B, A34868(9)/B |
| FAILURE MODES | Clogged - No Semi-Auto Extend/Retract |

ANALYSIS

This filter is a 200 micron rated in-line filter used in hydraulic system. Materials in contact with the fluid media are the 304 SS element, 303 or 304 SS body, and Buna N seals. The unit is designed for 3000 psig operating pressure, 4500 psig proof pressure, minimum collapse differential pressure of 3250 psi, flow capacity of 6.0 GPM with max pressure drop of 10 psid, bubble tight leakage, and has 25 square inches of effective filter area.

ACTION.

.

Investigate use of smaller micron rating and also use of T-type filter to eliminate requirements to break into system_ to change element. 200 micron rating doesn't appear to be applicable to present cleanliness level requirements.

COMPONENT ANALYS IS

COMPONENTOrifice, Flow Restricting (Hydraulic)SPECIFICATION NO.76K00189 (-1, -2)VENDORA. U. Stone Co. (Ausco)VENDOR P/NFIND NUMBERS/CATEGORYFIND NUMBERS/CATEGORYA34762 (9)/B, A34765 (9) B,
A35730 (9)/B, A35731 (9) BFAILURE MODESClogged: No Auto Retract (For -2)
No Semi-Auto Extend or Retract (For -1)

ANALYSIS

The -1 orifice has a .077 inch (1955 micron) sharp edge diameter_and is used to control the rate arm 9 will extend or retract. The -1 orifice is protected by a 200 micron in-line filter on both sides. The -2 orifice has a .043 inch (1092 micron) sharp edge diameter. The orifice controls the rate which the pilot operated ball shut-off valve (75M08820) opens and closes. The volume of flow through the -2 orifice to open or close the ball shut-off valve is less than one cubic inch.

It is considered very unlikely that the -1 orifice would become clogged because of the 200 micron filter that is used in the system. The -2 orifice does not have a filter just upstream, but the volume_of_flow is very low which reduces chances of clogging.

ACTION

ς.

. .

Both the -1 and -2 orifices are not considered contaminant sensitive; the -1 because of final filtration and -2 because of low volume of flow. It is recommended that the orifice (76K00189-1,-2) not be considered for test.

COMPONENT ANALYSIS

COMPONENT

Valve,Deceleration

SPECIFICATION NO. 76K00251 Make from 75M12561-1

VENDOR

Racine Hydraulics

VENDOR P/N

FIND NUMBERS/CATEGORY A34839(9)/A, A34849(9)/B

| FATURE MODES | Stuck - Can't retract arm Erratic - Possible retract malfunction |
|--------------|---|
| | Techact mailunction |

ANALYSIS

Drawing defines rework of 75M12561-1 valve to new . configuration. Drawing does not specify any test requirements. Valve similar to 75M06201-1 which was modified to 75M21842-1. The only difference between 76K00251 and 75M21842-1 is that 76K00251 has the relief valve blocked.

Refer to 75M06201-1_for analysis.

ACTION

Refer to 75M06201 for resultant action.

<u>B-78</u>

B-79

COMPONENT ANALYSIS

Orifice, Flow Restricting

76K03578-1, -9, -12

A. U. Stone Co. (AUSCO)

H92C-047, H92C-093, H92C-040

COMPONENT

SPECIFICATION NO.

VENDOR

VENDOR P/N

FAILURE MODES

FIND NUMBERS / CATEGORY

ANALYSIS

The orifice sizes for the 3 dash numbers are; -1, .047 inch; -9, .093 inch; -12,.040 inch. The system is operated on GN₂ and the flow velocity is very high through the orifice and nesting of fibers, which would tend to clog the orifice, is very unlikely. Also pneumatic flow is bi-directional which will tend to prevent contamination from clogging an orifice. The volume flow rate is also low, which reduces the chances for contaminants to clog an orifice.

ACTION

Because of the orifice sizes, fluid media, bi-directional flow and low volume of flow the orifice is not considered contaminant sensitive and is not recommended for test.

COMPONENT ANALYSIS

COMPONENT Cylinder, Pneumatic

SPECIFICATION NO. 76K03824

VENDOR Miller Fluid Power

VENDOR P/N .

FIND NUMBERS/CATEGORY A34952(9)/A

FAILURE MODES Stuck Piston - No platform cyl extend or retract Leakage - Possible platform malfunction

ANALYSIS

The pneumatic platform extend/retract cylinder contains a cylinder body, 2 heads, a piston, a rod and a wiper ring. The bore diameter is 2.5 inches, stroke 80.0 inches and rod diameter 1.75 inches.

Seal Material -_Buna N Per_Mil=P-5315 or Mil=P-5516

Lubrication - Type Kel-F=10_or DC 55 (Dow Corning)

Leakage - 5 SCIM Max. (internal)

Cleaning - KSC-C-123 Level VI, Test Method 4, certification required

The cylinder uses HYCAR piston cups and HYCAR rod seals. The piston rod is hardened to 50-54 Rockwell "C" and chrome plated. The cylinder has a Teflon piston rod dirt wiper and corrosion resistant surfaces. The operating pressure for the cylinder is 750 PSI.

ACTION

The pneumatic cylinder is not considered contaminant sensitive or a contaminant generator and is not recommended for test.

11

B=81

COMPONENT ANALYSIS .

COMPONENT.

MENT Cylinder, Pneumatic

SPECIFICATION NO. 76K03825

VENDOR Lionel Pacific, Inc., Aero-Space Div.

VENDOR P/N

FIND NUMBERS/CATEGORY A34988(9)/A

FAILURE MODES Stuck Piston - No Adapter Positioning Device (APD) extend or retract Leakage - Possible APD malfunction

ANALYSIS

The pneumatic APD extend/retract.cylinder.contains a_ cylinder body, 2 heads, a piston, a rod and a rod wiper. The bore diameter is 2.5 inches, stroke - 21.5 inches and rod diameter is 1 inch.

Seal Material -- Buna-N per Mil-P-5315 or Mil-P-5516

Lubrication - Type Kel-F-10 or DC 55

Léakage - 5 SCIM Max. (internal)

Cleaning - KSC-C-123 Level VI, Test Method A, certification required

The cylinder heads are made from 2024-T6 aluminum and the cylinder body, piston and rod are 17-4PH CRES Per AMS 5643, COND.H.

ACTION

The cylinder is not considered contaminant sensitive or a contaminant generator and is not recommended for test.

COMPONENT ANALYSIS

Solenoid Valve

COMPONENT

SPECIFICATION NO. 10425701

VENDOR Marotta Valve Corp

<u>VENDOR P/N</u> 229604(MV123K)

| FIND NUMBERS/CATEGORY | A34937(9)/A, A34938(9)/A, A34949(9)/B, A34953(9)/B, A34955(9)/B, A34959(9)/A, A34961(9)/A, A34962(9)/A, A34969(9)/A, A34970(9)/A, A34973(9)/A, A34983(9)/B, A34985(9)/B, A34986(9)/B |
|-----------------------|--|
| FAILURE MODES | De-energized - No cylinder retract or_extend Energized - No cylinder retract or extend Leakage - Possible malfunction |

ANALYSIS

This value is a 3-way, 2 position solenoid value similar to 75M08825 except the ports are $3/8^{ii}$ size and the body is 316 stainless steel. Designed for 3000 psig nitrogen gas with a .189 inch ESEOD. The remainder of the analysis will be considered the same as for 75M08825.

ACTION

• • Much diverse & Address Concernment

See 75M08825 for resultant action.

B-83

COMPONENT ANALYS IS

COMPONENT Check Valve

SPECIFICATION NO. 10425928

VENDOR James Pond Clark

VENDOR P/N P279T1-4TT

.

FIND NUMBERS/CATEGORY A34987(9)/B

FAILURE MODES Same as 75M05365 (Item 1)

ANALYSIS Same as 75M05365 (Item 1)

ACTION Recommend the check valve not be considered for test.

COMPONENT ANALYSIS

ŧ

COMPONENT Check Valve

SPECIFICATION NO. 10426693

VENDOR James Pond Clark

VENDOR P/N P279T1-4TT

FIND NUMBERS/CATEGORY 34950(9)/A

FAILURE MODES Same as 75M05365 (Item 1)

ANALYSIS Same as 75M05365 (Item 1)

ACTION Recommend valve not be considered for test.

B-84

B.,85

COMPONENT ANALYSIS

COMPONENT

i

ì

Check Valve

 SPECIFICATION NO.
 -

 VENDOR
 Marotta Valve Corp.

 VENDOR P/N
 800262-19(CVM 508)

 FIND NUMBERS/CATEGORY
 A5972(4)/A

 FAILURE MODES
 Closed - No LH₂ Cyl.withdrawal

 Open
 - No effect

 Leakage - No effect

ANALYSIS

This check value is poppet design check value similar to check values of same design used by Martin. The poppet is well guided and the flow path is such that any particles should tend to flow right on through the value. This item is not considered to be a contaminant sensitive part and will not be considered for test.

ACTION

Recommend this part not be considered for test.

...

COMPONENT ANALYSIS

COMPONENT

Check Valve

SPECIFICATION NO.

VENDOR Marotta V-lve Corp.

<u>VENDOR P/N</u> 204002-19(CVM-8)

FIND NUMBERS/CATEGORY A5863(8)/A, A6153(6)/A

FAILURE MODES Closed - No secondary system withdrawal, valve actuation Open ... - No effect Leakage - No effect

ANALYSIS

Poppet type check valve similar to Marotta part_number 800262. Not considered to be a contaminant_sensitive part and will not be considered for test.

ACTION

Recommend this part not be considered for test.

B-87

COMPONENT ANALYSIS

| COMPONENT | Solenoid_Valve _ |
|-----------------------|---|
| SPECIFICATION NO. | |
| VENDOR | Marotta Valve Corp |
| VENDOR P/N | MV583 |
| FIND NUMBERS/CATEGORY | <u>1</u> 1190(6)/A |
| FAILURE MODES | De-energized - No effect EnergizedNo effect Leakage - Possible premature withdrawal |
| ANAT VETE | |

ANALYSIS

This value for analysis purposes according to Marotta engineering is similar to 75M08823. MV583 is the same model series as the 75M08823 which is MV583-H2A.

ACTION

See 75M08823_for resultant action_____

COMPONENT ANALYS IS

| COMPONENT | Orifice, Flow Restricting |
|-----------------------|---------------------------------|
| SPECIFICATION NO. | Not Known |
| VENDOR | A. U. Stone Co. (AUSCO) |
| VENDOR P/N | |
| FIND NUMBERS/CATEGORY | 5594 (7)/A |
| FAILURE MODES | Clogged No hydraulic withdrawal |
| ANALYSIS | |

The orifice has a sharp edge diameter of .45 inch (11,430. micron) and is used to control the rate of hydraulic withdrawal.

ACTION

The orifice is too large to be considered contaminant sensitive and is not recommended for test.

B-88

1

.....

V

. حق

....'

ŧ

ĺ

• •

.

APPENDIX C

BIBLIOGRAPHY WITH ABSTRACTS

PRECEDING PAGE BLANK NOT FILME

MCR-69-484

C-3

 Abshire, R. W.: "Technical Considerations in Designing a Hydraulic System for the SST." <u>SAE Conference Proceedings: Aerospace</u> <u>Fluid Power Systems and Equipment Conference</u>. pp 57-62, Los Angeles, California, May 18-20, 1965. 650341.

This paper discusses the high reliability required for commercial, supersonic aircraft hydraulic systems. Contamination control influences design considerations to the extent that the systems are designed to eliminate any chance of introducing foreign contaminants after equipment installation. In this design the fluid is filtered upon introduction to the system at all fluid filling points. Fluids were selected for their resistance to creating contaminants through chemical reaction with system components.

2. Anthony, H. V., et al.: "Contamination Sensors," AEC/NASA Symposium on Contamination Control, September 1967.

This paper presents in detail a discussion of various particle counting devices such as in-place counters and automatic counters, as well as sampling techniques, including isokinetic, Wyle wedge, etc. Cryogenic liquids, ordinary gases, and liquid fuel and oxidizers are included in the discussion, both for purity analysis and particulate analysis. Recommendations are made for the best techniques to be used for the various fluids.

 "Atlas 'E' Overhead Doors Design Validation and Product Improvement Study." Contract AF04(647)-863. Bechtel Corporation, Vernon, California, January 1962. AD 828734.

Extremely heavy contamination was discovered in overhead door hydraulic systems. Boors became inoperable or tended to settle down when left in open position. Pumps were found to be clogged and valves were sticking and leaking. The hydraulic systems had never undergone any contamination control whatsoever. Initial contamination had evidently been high and when water base fluid had been replaced by petroleum base fluid, water became an additional serious contaminant. The suggested remedy was to flush out contaminated fluid, add filtering processes, and replace malfunctioning components. Estimated cost of repairing damage to doors caused by malfunctioning hydraulic system and repairing the hydraulic system itself totaled \$596,000.

 Bose, R. E.: "The Effect of Cavitation on Particulate Contamination Generation." Oklahoma State University, Doctorate Thesis, 1966.

This paper describes an experimental program conducted to determine the effectiveness of the cavitation phenomenon in producing particulate contamination. The fluid used was distilled water, and several different materials were investigated to determine which offered the best resistance to the process... Materials were 1100-T'8 aluminum, 2024-T351 aluminum, freecutting brass, Monel, 304 stainless steel, and Electrolytic Tough-pitch copper.

It was found that large quantities of particulate could be generated by this process, with sizes ranging to 280 microns. The largest particles were generated from the softer aluminum and copper materials. The largest size generated from the Monel and stainless specimens was approximately 40 microns; however, these harder materials generated much larger quantities of the smaller-sized particles. A correlation was established between particle cutoff size and Brinell hardness number. Empirical relations are promulgated for particle size distribution versus strain energy of various materials.

 Brittain, R. C.: "Titan II: Retractable Work Platform Hydraulic Systems (HS-2) Test Program." Parsons Company, Los Angeles, California, 6 February 1963. AD 828725.

This report gives a detailed description of tests run on a Titan II retractable work platform hydraulic system. Contamination specifications are outlined. The procedures used to ensure that the hydraulic system met specifications are detailed. Data used to determine contamination levels before and after flushing is presented...After approximately ninety cycles, the contamination level of the system stabilized. The system contamination limit as specified is as shown for 100 ml at any sampling point:

| Particle Size | 26 thru 50 | 51 thru 100 | 101 thru 200 | 201 thru 500 | 500 thru 1000 | >1000 |
|------------------|---------------|----------------|-----------------|-----------------|------------------|-------|
| Maximum Ccunt | 1050 | 2.50 | 70 | 20 | 3 | 0 |
| | | | | | | |

| Fiber | 100 thru | 1001 thru | >2000 |
|------------------|----------|-----------|-------|
| Length | 1000 | 2000 | |
| Maximum Count | 25 | 5 | 0 |

6. Connelly, R. F. and Gatzek, L. E.: "Deteriorative Effects of Both Usage and Long Term Storage on Aircraft and Missile Hydraulic Fiuids." Journal of Engineering for Industry, May 1963; <u>ASME</u> <u>Transactions</u>, Paper 62-AV-13.

This paper presents a comparison of MIL-H-5606 and MIL-H-6083 hydraulic fluids with respect to particle agglomeration, chemical precipitation, crystal growth, and extraction of elastometer components. In 5606 fluid, particles tend to agglomerate, then decompose when disturbed, and reprecipitate during inactive periods. The corrosion additive in 6083 fluid is very effective in breaking up and preventing further particle growth. Vibration, either mechanical or sonic, increases the rate of particle growth. The Silting Index is used to measure this phenomenon; the following test results are presented:

| Storage Period | Silting Index |
|----------------|---------------|
| MIL-H-5606 | |
| 2 days | 0.004 |
| 9 days | 0.010 |
| 2 months | 0.016 |
| 5 months | 0.160 |
| 10 months | 2,960 |
| 12 months | 4.000 |
| 24 months | œ |
| MIL-H-6083 | |
| 2 hours | 0.002 |
| 42 months | 0.035 |
| 64 months | 0.098 |

Also, 5606 fluid tends to react chemically with storage containers, particularly in the presence of significant amounts of moisture.

Crystal growth as large as 5 x 150 microns has been observed in 5606 fluid; these melt at about 350 °F. Constituents of elastomers can be extracted by hydraulic fluids; these are mostly in the 25-micron range. C~5

7. Connelly, R. F.: "Relationships between Contamination and System Failure." <u>American Association for Contamination Control</u>, Fifth Annual Meeting, March 1966. AFRPL=TR-67-290.

This author maintains that so-called contamination failures in the vast majority of cases result in loss of performance rather than catastrophy. The long-term effect is wear resulting from silting. Effects of metallic particle silting is more severe than nonmetallic; fibers are particularly troublesome because they tend to "nest" and thus increase silting tendencies, and because they do not settle out as readily as metallic particles. MIL-H-5606 fluid with acrylic viscosity improvers appears quite prone to silting over a long term of activity. Homogenizing improves this tendency, but is tran-sient in nature. Fluids not containing these improvers have endured more than five years with no change in silting index. -

The major recommendation is made that contamination levels not be selected solely on the basis of blueprint clearances, because this results in the imposition of unrealistically low limits. Experimental evidence relative to the system effects ... should be obtained, including consideration of fluid composition, particle size, and contamination concentration... The statical nature of the contamination sample must be remembered when setting size limits.

8. Deane, T. N.: "Hydraulic Fluid Particle Growth Halted." <u>SAE</u> <u>Journal</u>, Volume 69, No. 3, March 1961.

> The subject of particle growth in MIL-H-5606 hydraulic oil is discussed in this paper. The cause is pinpointed as agglomeration of very small particles (less than 5 micron), the adhesion being provided by the additive viscosity improver, methacrylate. The following conclusions are stated:

- The mechanism is one of large particles being formed from small ones;
- Vibration accelerates the rate of growth by increasing the force with which the particles strike each other and therefore the probability of their sticking together;
- 3) The precipitate has been redispersed by agitation, the oil refiltered and repackaged, then after further storage the precipitate has reformed;

 Precipitate does not form in oils that contain rust preventative agents, or in oils that do not contain methacrylate viscosity improvers (such as MIL-H-6083).

It is also stated that the rate of growth is proportional to the square of the concentration of particles... Thus, if by filtering, the particle count is reduced by a factor of 10, then the growth rate will drop by a factor of 100.

Deane, T. N.: "The Effect of Contamination on Fluids and the Effect of the Ingredients of the Fluids on Contamination." <u>SAE Conference Proceedings: Aerospace Fluid Power Systems and Equipment Conference</u>, Los Angeles, California, May 18-20, 1965. 650352.

This paper discusses contaminant effects on hydraulic fluid functions. Contaminants lower temperature at which fluid oxidizes. Submicronic contaminants agglomerate to form 25 to 200 micron particles. The rust preventative in MIL-H-6083 prevents agglomeration.by neutralizing electrolytic properties of fluid. Moisture causes oxidation and thus speeds wear. Moisture combines with anti-wear agent to plug filters. Water creates acid in some fluids which causes chemical reactions. It is considered worthwhile to permanently remove all contaminants from hydraulic fluid regardless of size or substance.

 "Decontamination of Hydraulic Fluids and Dynamic Hose Study." Oklahoma State University Technical Report SEG-TR-64-74, January 1965. AD 612907.

> This report discusses a new means of upgrading the decontamination capabilities in USAF ground support equipment, a device known as the hydroclone. This is a centrifugal separating device which is used in place of a conventional filter. To evaluate the performance of the device in hydraulic systems, a field test program was undertaken. Field studies were conducted at Edwards AFB, California, and Tinker AFB, Oklahoma. Particle counts were obtained by a HIAC automatic particle counter; microscopic examinations were made to determine the types of contaminant present. Five hundred-milliliter samples were used. The following results were obtained:

Gravimetric Analysis (mg/1) -

| Sample No. | Upstream of Hydroclone | Downstream |
|-------------|------------------------|------------|
| l (Edwards) | 31.6 | 10.6 |
| 2 (Edwards) | 33.9 | 10.9 |

| Sample No. | Upstream of Hydroclone | Downstream |
|--------------|------------------------|------------|
| 3 (Edwards) | 15.2 | 12.5 |
| 4 (Edwards) | 11.7 | 11.2 |
| 5 (Edwards) | 8.6 | 8.6 |
| 6 (Edwards) | 12.3 | 11.2 |
| 7 (Edwards) | 79 | 11.0 |
| 8 (Edwards) | 10.2 | 10.2 |
| 9 (Tinker) | 32.8 | 24.5 |
| 10 (Tinker) | 33.0 | 20.5 |
| 11 (Tinker) | 12.5 | 13.1 |
| 12 (Tinker). | 12.1 | 13.5 |
| 13 (Tinker) | 11.8 | 10.0 |
| 14 (Tinker) | 10.6 | 7.7 |
| 15 (Tinker) | 10.7 | 14.0 |

Particle Counts -

| Micron Size | <u>Quantity</u> |
|--------------|-----------------|
| 6 (Tinker) | 3523 |
| ll (Tinker) | 1117 |
| 15 (Tinker) | 103 |
| 20 (Tinker) | 47 |
| 6 (Edwards) | 1591 |
| ll (Edwards) | 194 |
| 15 (Edwards) | 52 |
| 20 (Edwards) | 16 |

The particulate was analyzed as iron, bronze, paper, plastic, cotton, carbon, and aluminum. Maximum size encountered was 600 microns. The report concludes that the hydroclone is as efficient as normal filtration techniques, with the added advantage that it does not load up and require changeout.

In addition, cleaning of high pressure rubber and teflon-lined hoses was evaluated by dynamic pressure pulsation. It was found that, compared to normal flushing techniques, the dynamically cleaned hose would generate far fewer and smaller particles during operational service...

11. Dwyer, J. L.: <u>Contamination Analysis and Control</u>. Reinhold Publishing Corporation, New York, 1966.

> This book discusses the analysis and control of contamination in aerosols, gases, and liquids. The main points are aerosol sampling and inspection; particle sampling of cylinder gases; errors in probe sampling; liquid dispersions, suspensions, and

emulsions; particle counters; methods of quantitative and qualitative sample analysis; contaminants on surfaces; clean rooms; and component cleaning. It is a general survey and state of the art for theoretical as well as practical means of contamination analysis and control.

12. "Effect of Contamination on Fluid System Components: Bulletin A50." Aircraft Porous Media, Inc., Glen Cove, Long Island, New York. Pall Corporation, 1966.

> This paper abstracts and discusses ten articles that were selected after a thorough search of available information concerning contamination, wear, life, and performance of fluid systems. Filtration below five microns absolute appears to improve most hydraulic systems. In no instance observed did finer filtration degrade component performance. Finer filtration improves valve wear, component life, system operation, and hydraulic fluid performance and stability. Silting of submicronic particles can be reduced significantly by filtration with three-micron absolute filters.

13. "Effect of Contamination on Fluid System Components: Supplement 1 to Bulletin A50." Aircraft Porous Media, Inc., Glen Cove, Long Island, New York. Pall Corporation, 1967.

> This paper abstracts and discusses six articles which are intended to supplement those covered in Bulletin A50. Further evidence is presented to favor the use of submicronic filtration. Wear is reduced in piston rings and valve lifters when oil is filtered to eliminate submicronic contaminants. Tests show that contaminants severely increase damage in cavitational zones. Elimination of particulates of the five- to tenmicron range increase pump and servo valve life and reduce the frequency of hydraulic system cleaning.

14. Farri, John A.: "The Meaning of Fluid Filter Ratings." FSR #25, Aircraft Porous Media, Inc., April 1, 1965.

> This company bulletin is a comprehensive, readable discussion of nearly every aspect of filters that should be considered by any design engineer having a need to specify filtration equipment. The importance of adequate filtration to prevent wear and subsequent leakage of valves is pointed out with reference to work performed by General Electric. Wear versus contamination of aircraft piston pumps is discussed with reference to Grumman work. Experience of ultrafine filtration

MCR=69=484

in commercial aircraft hydraulic systems is tabulated. A review of existing military filter specifications is given; interestingly enough, no such specification exists for pneumatic (lications. All aspects of filter design are discussed in detail, including nomenclature, efficiency, and rating measurement techniques, bubble point tests, pore size versus ratings, limitations and interpretations of ratings, fiber removal, dirt capacity, cleaning techniques, collapse pressure, media migration, and flow fatigue.

15. Farris, John A.: "New Approach to Selecting Fluid System Filtration." Bulletin FSR-39, Pall Corporation, Glen Cove, Long Island, New York.

> This report discusses the various considerations that should be given to selecting proper filters for hydraulic systems. Descriptions are given of typical contamination failures. Types of filtration media are discussed for various applications. Recommendations of filter types are made, considering fluid life, additive removal, filter location, bypass valves, flow, pressure, and service interval with respect to area and dirt capacity. Dual element, 3-micron absolute filtration is advised. The optimum filter arrangement is to use relatively coarse (25 micron) filters in the pressure line ahead of each critical component to prevent catastrophic failures, and an ultrafine filter in the return line to minimize wear by preventing recirculation or buildup of ultrafine particles generated by components.

16. Fitch, E. C.:. "Fluid Contamination Project: Study in the Field of Fluid Contamination." Report No. 6. Oklahoma State University, Stillwater, Oklahoma. August 1963. AD 422550.

> This report describes the use of the HIAC automatic particle counter in determining contamination levels in fluids. Despite the expense, the author was pleased with the results and simplicity of the data obtained using the HIAC counter. Test filters were cleaned ten times with one of two solvents. After three or four cleanings the contamination level no longer showed a steady decrease but, instead, became erratic. After ten cleanings with one fluid, an additional cleaning with the other solvent repeatedly showed that one solvent was better at removing some type of contaminant in the filters than was the other solvent.

Distillation of the solvents proved a satisfactory method of reclaiming the solvents. It was indicated that care is required in the distillation process because under certain contamination conditions localized heating caused contaminants to be carried with distillate.

17. "Fluid Filters: Media and Contamination." Bendix Filter Division, Publication No. BFD 168, not dated.

> This informative booklet describes—sll conceivable aspects of the use of filters in hydraulic systems. No data are presented, but extensive discussions are given on types of filters, filter characteristics, filter cleaning and drying techniques, analysis procedures, clean room facilities, packaging techniques and materials, and considerations for writing filter specifications. All of this general information would be quite instructional to any person working hydraulic system cleanliness problems.

18. Gayle, J. B. and Romine, J. O.: "Studies on the Reliability of Particulate Contamination Analyses." George C. Marshall Space Flight Center. MPT-P&VE-M-62-5. March 6, 1962.

> There are many factors that can_influence the reliability of the results of a contamination analysis of a specific system. Examples are given where wide variations in particulate contamination count are experienced due to the operation or nonoperation of a valve. Generally, if a valve is opened and closed during contamination sampling, the particle count is greatly increased over that obtained when the valve is not operated.

> The reproducibility of a particle count is affected by the operator. Different operators will vary in their determination of the particle count for the same sample to a greater degree than the same operator will vary in several determinations with the same sample. Reproducibility improves with a greater number of particles in a sample. The primary conclusion is that variations in the sampling method have a much greater effect on reproducibility than variations associated with particle_count determination.

19. Hocutt, M. G.: "Establishing Hydraulic System Operational Contamination Limits." <u>SAE Conference Proceedings: Aerospace Fluid</u> <u>Power Systems and Equipment Conference</u>, Los Angeles, California, May 18-20, 1965. 650333.

Hydraulic system contamination limits must be established such that they prevent significant degradation of system performance and yet are cractical enough to command system eleanup when exceeded. The case history of the YJ93-GE-3 is presented as an example of how contamination levels are generated for a hydraulic system.

Through extensive testing it was determined that the system 'would continue to operate with some degradation of performance but without failure at contamination levels in excess of class 12.. The hydraulic function that degraded was the control servo valves; therefore, the system contamination levels would have to be limited so that the servo valves could function satisfactorily. It was determined that a class 12 level of contamination produced a 4.3 pound spool silting force to move the valve from null. The physical characteristics of the valve were a 0.375-inch spool diameter with a hardness equivalent to R_c 70 or greater and a 0.0006-inch diametrical clearance

between spool and sleeve. A valve silting force greater than 3.5 pounds caused unsatisfactory control performance; therefore a contamination level of class 8 which would maintain the valve silting force below 3.5 pounds was selected for the system.

In order to eliminate high Levels of particle counts emperienced during the first few hours of testing due to built-in contamination, all subsystems were cleaned by flushing to a class 6 level of contamination, and auxiliary 3-micron absolute filtration was added during initial system running hours.

Contamination Classes per NAS 1638

| Class | 5 to 15 | 15-to 25 | 25 to 50 | 50 to 100 | 100. |
|-------|-----------|----------|----------|-----------|-------|
| 6 | 16,000 | 2,850 | 506 | 90 | 16 |
| 8 | 64,000 | 11,400 | 2,025 | 360 | 64 |
| 12 | 1,024,000 | 182,400 | | 5,760 | 1,024 |

antma 1

All filters used were stainless steel wire mesh with high temperature and high pressure drop capability. The auxiliary filter had a 3-micron absolute element backed up by a 15-micron absolute element. The main dirt generators of the system were the 12 actuators and 14-piston hydraulic pump. These dirt generators, however, contributed very little of the metallic wear contaminants.

The operating contamination level sustained by the J93 hydraulic system is equivalent to or possibly one class lower than that of aircraft hydraulic systems according to SAE report 749D.

Important conclusions were:

- "The use of 3-micron absolute auxiliary filtration in addition to the normal system filtration lowers-the contamination level approximately 3 classes.
- 2) "The use of subsystem flushing prior to system assembly plus ultrafine auxiliary filtration of part of the system flow during initial hours of engine running have proven very successful in eliminating high initial operating contamination levels and the wide variation in contamination levels during the life of the system.
- 3) "Servo value spool silting forces, with all other parameters remaining constant, vary in direct proportion to the level of contamination."
- 20. Hollinger, R. H. and Donis, J. N.: "Contamination Tolerance of Aircraft Hydraulic Pumps." Eranklin Institute Research Laboratories, Philadelphia, Pennsylvania, March 1967. AD 814826.

This report presents a very comprehensive analysis of the effects of particulate density, size, and hardness on wear in hydraulic pumps. Three methods of measuring contamination level were used to supplement one another; they were silting index, HIAC counter and gravimetric analysis. Cotton linters, jeweler's rouge, iron filings, and AC fine test dust were generally used as the contaminants in controlled proportions. Careful dimensional analysis was run on the contaminants and pump components after each 50-hour and 1000-hour test. The conclusion reached was that some contaminants are more harmful than others and those proven to be harmful should be removed.

 Hollinger, R. H., et al.: "Evaluation of Wear and Contamination Generation of Hydraulic Components." Franklin Institute Research Laboratories. <u>Report F-B2116</u>. <u>NASA Accession No.</u> X66-14859, February 1965.

> This report covers investigations into the capability of same... pling values to give representative hydraulic samples; contamination generation and malfunction susceptibility of H-1. engine hydraulic system pumps; and an evaluation of the S-IV._ hydraulic system under known conditions of fluid contamination.

> FRC and Maledeo were compared, using AG coarse test dust and collecting 100 ml samples. A great amount of tabular data is presented; it was concluded that the Maledeo valve gave slightly better agreement between line and sample. However, the FRC valve had advantages in size, weight, and ease of installation. The Wyle wedge is not recommended for use in hydraulic sampling.

Vickers and Kellogg hydraulic pumps were compared for contaminate generation. Again, great amounts of tabular data are presented. The Kellogg pump appeared to show more variance, but no significant difference in amounts was found. For particles over 100 micron in size, case drain analysis indicated quantities as high as 178% of the input fluid level. After an initial wear-in period of about 8 hours, there was no significant change in leakage flow rates. Bronze cylinder blocks contributed more particulate than did ductile iron.

Systems were cleaned initially to SAE/ASTM Level 1 or better; contamination in the form of AC coarse test dust was then added______ in controlled amounts to achieve higher ASTM levels. Samples were counted per ARP-598. For the pumps, a maximum safe level ______ of ASTM Level 2 is recommended if leakage is not to become excessive in reasonable operating times. Levels 3-4 caused noticeable degradation in system performance and Levels 5-6 caused unacceptable performance. ______

22. Howell, G. W.: "A Bibliography of Aerospace Valve and Fluid Component Technology." TRW_Systems, Redondo Beach, California, December_1965. AD 435305.

> This document contains a list of 3502 articles that are pertinent to fluid component technology. Included is an introduction, alphabetical source list, numerical source list, and a descriptive cross-reference list. Several references are pertinent to contamination control.

G=14 .

23, Howell, G. W. and Weathers, T. M.: "Aerospace Fluid Component Designer's Handbook." TRW Systems, Redondo Beach, California, March 1967. AD 809183.

> Filtration and contamination are two sections in this rather extensive design handbook. Pneumatic and hydraulic filters of several types are rated and compared for a number of operational environments. Types of contamination are discussed and classified, such as internally generated metallic contaminants and external dust contaminants. Effects of hydraulic system contaminants are outlined. Industrial cleanliness requirements are presented for components and fluids as well as a guide for selection of cleaning agents. It is recommended that materials, uncontrollable contamination, fluids, and tolerances be given particular consideration when designing fluid systems.

24. Huggett, H. L.: "Servo Valve Internal Leakage as Affected by Contamination." <u>SAE Conference Proceedings: Aerospace Fluid Power</u> <u>Systems and Equipment Conference</u>, Los Angeles, California, May 18-20, 1965. 650334.

> Servo values were extensively tested using field launcher fluid and new fluid. Records were kept of viscosity and leakage rates of the fluids during the testing periods. After about four hours the fluid viscosities were similar but the leakage rate increase of the more highly contaminated fluids stabilized at 2.8 times that of the less highly contaminated fluids. The conclusion was that controlled fluid contamination level inereased the useful life of servo value assemblies by 277%.

25. Kinney, W. L., Schumann, E. P., and Weiss, P. A.: "Hydraulic Servo Control Valves, Part VI - Research on Electrohydraulic Servo Valves Dealing with Oil Contamination, Life and Reliability, Nuclear Radiation and Valve Testing." Cook Research-Laboratories, Skokie, Illinois, November 1958....AD. 211733.

> This report discusses problems encountered by aircraft companies in the field of hydraulic components. A comparative chart of maximum allowable contamination levels is shown for five companies. These contamination levels were established by each company on the ground that they worked consistently and could be maintained at not too great an expense. The maximum particle size allowed by any of the five companies is 300 microns.....

Failures due to contamination at temperatures above $160^{\circ}F$ are much more prevalent than those for systems whose operating temperature is below $160^{\circ}F$. Paper filters tend to disintegrate at temperatures above $200^{\circ}F$. General design considerations are discussed which if employed result in a less contaminationsensitive system.

A test procedure is presented and the acceleration of wear or contamination generation due to the addition of particle contaminants is discussed. Testers must be careful that they are actually testing components rather than filters; many component failures were due to filter clogging rather than general system contamination level.

26. Kinney, W. L., Schumann, E. P., and Weiss, P. A.: "Hydraulie Servo Control Valves, Part 7 - Design for Improved Reliability, Tolerable Oil Contamination Level Standards, and Nuclear Reactor Irradiation Test Results." Cook Research Laboratories, Skokie, Illinois, November 1958. AD 231657, WADC TR 55-29 Part-7.

> This report is a continuation of Part 6, which has been previously abstracted. Only the chapter on oil contamination is pertinent to this program. An experimental analysis of various hydraulic oils was obtained from selected aircraft at Wright-Patterson and Bergstrom AEB. Using this data along with the results of servo valve tests reported in Part 6, an upper limit for the contamination allowable in aircraft hydraulic system samples is presented.

The results of the field survey were as follows:

| <u>Source</u> | ≤ 10 μ | <u>10 to 20 µ</u> | 20 to 40 µ | <u>> 40 µ</u> |
|------------------|-----------------|-------------------|------------|------------------|
| F-100 | 434,921 | 21,352 | 20,058 | 1,391 |
| F-101 | Not Countable | 3,103 | 489 | 139 |
| F-102 | Not Countable | 6,850 | 1,500 | 435 |
| F-104 | Not_Countable | 107,565 | 1,950 | 505 |
| F-105 | Nor Countable | 3,333 | 789 | 179 |
| F-101 | 12,292,950 | 100,114 | 13,200 | 2,050 |
| F-1 01 | 822,819 | 86,052 | 33,865 | 6,050 |
| F-101 | 1,628,385 | 7,300 | 5,950 | 505 |
| F-101 | 728,490 | 84,348 | 29,842 | 4,500 |
| F-101 | 1,483,358 | 61,344 | 11,100 | 3,300 |
| F-101 | 1,427,717 | 231,318 | 120,984 | 13,550 |
| Cook Stand #1 | Not Countable | 49,927 | 1,175 | 77 |
| Cook Stand #2 | Not Countable | 60,279 | 700 | 70 |

The following is the recommended maximum contamination level for aircraft servo valve applications, based on a 100 ml sample;

| <u>± 10 µ</u> | <u>10 to 20 11</u> | <u>20 to 40 µ</u> | <u>> 40 µ</u> |
|---------------|--------------------|-------------------|------------------|
| Unlimited | 15,000 | 3000 | 80 |

In arriving at this specification, criteria of other valve users in the field were also considered but found to be much more conservative than the results of this analysis justify. They feel that the majority of the contamination is either airborne dust, or is generated by the system pump.

Several general recommendations pertaining to contamination test techniques are also presented. Reference is made to Part 6 for a more complete description.

<u>Note</u>: The above recommended level is revised in a further section of this report, Part 8.

27. Kinney, W. L.; Schumann, E. P., and Weiss, P. A.; "Hydraulic Servo Control Valves, Part 8 - Investigations of Oil Contamination Effects and Nuclear Radiation Testing," Cook Research Laboratories, Skokie, Illinois, October 1962, AD 464061, WADC TR 55-29, Part 8.

> This report contains a wealth of information from various users of hydraulic servo valves concerning the cleanliness of oil from actual installations, the cleanliness are fications from various companies, and test results of new valves tested with actual field fluid. As a result of these investigations, the criteria recommended by the authors in Part 7 of this report is revised herein to considerably looser limits. The revised recommendation is as follows, based on a 100 ml sample:

| <u><5µ</u> | <u>5-15µ</u> | <u>15-25µ</u> | 2 5-50µ | 50-100µ | >100µ |
|---------------|--------------|---------------|----------------|---------|-------|
| Unlimited | 25,000 | 3,000 | 1,000 | 200 | 1.50 |

As part of the above investigation, a questionaire was sent to more than 20 servo valve users, and many of those who responded included their own company cleanliness specifications for fluid used in servo systems. The information thus obtained is shown in the following Table I. Note: All dimensions refer to the largest particle dimension except for North American which uses the smallest particle dimension.

Also as part of the investigation, field samples of hydraulic oil were taken from 31 different aircraft, missiles, and test stands, all of which were in a fully operational condition. The results of this sampling program are shown in Table II.

The third effort reported on herein involved testing four new, different servo values with oil that was obtained from operational field sites. Test duration ranged as high as 40 hours. None of the four values demonstrated any aspect of failure during these tests. The contamination count is shown in Table III.

| | | 14 1 21001 | | | + TOTA CONFORMING TON DECEMPTONS | | |
|-----------------------------|----------------------------------|--------------------------------|---------------------------------|----------------------------------|----------------------------------|--|--|
| Organization | S | Systems | Maxiu | um Number | of Partic | Maximum Number of Particles/100 ml | Other Controls |
| Baeing | Test Stands Missiles in Fie | s n Field | | N N | No Limit No Limit | | Weight, 0.3 mg/100 ml Weight, 0.5 mg/100 ml |
| Hughes | New Oil | | Average of None >150µ | of four 50µ | largest p | Average of four largest particles, 50µ None >150µ | A "Time to Filter" specification |
| North American | AII | | <u>10+20н</u> 2,875 | 20+40µ 1,375 | <u>40-80µ</u> 80 350 1 | 80-100µ >100µ 100 0 | None |
| Martin Marietta | Vanguard Mace | | <u>10+25н</u> 2,150 4,500 | <u>25+40µ</u> 400 700 | <u>>40н</u> 270 450 | | 13 Fibers 20 Fibers |
| ABMA | A11 | | <u>10-25н</u> 2,150 | <u>25+50н</u> 530 | <u>50-100н</u> 60 | <u>>100µ</u> 0 | 10 Fibers |
| SAE Panel Recommendation | General Hydrauli Systems | drạul ícs | <u>5-15μ</u> 50 ,000 | <u>15-25и</u> 20 , 000 | <u>25+50н</u> 5,000 | <u>50+100н</u> 500 250 |) None |
| Lockheed | Ground Support Flight Control | port Equipment trol Systems | 3,500 10 ,00 0 | 1,250 2,500 | 250 500 | 25 3 50 10 | 3 None None |
| Westirghouse | A11 | | 5,000 | | | | Поле |
| BuWeps | Missile Fluid Sp cations | uid Specifi- | 10,000 | 4,000 | 1,000 | 100 53 | 8 None |
| Air Force | Rev. MIL-H-5606B | -5606B | 20,000 | 6 ,000 | 2,500 | 150 | <pre>1 A "Time to Filter" specification</pre> |
| | | | | | | | |

Table I Fluid Contamination Specifications

•

. .

.

į

MCR-69-484

C=19

| Table | Table II Contamination of Field Hydraulic Systems | Hydraulic | Systems | | |
|---------------|---|-----------|------------------------|----------------------|------|
| | | | Particle | Particles/100 ml Flu | n Li |
| Weapon System | Hydraulic Circuit | 5+15µ | 5-15µ 15-25µ 25-50µ 50 | 25-50u | S |
| TM-76 Mace | Power Pack 24 into Missile 33,800 | 33,800 | 1,640 | 788 | = |

| | | | | | ŀ | | |
|------------|------------------|----------------------------|---------|---------|------------------|-------------------|-------|
| | | | | Particl | Particles/100 ml | Fluid | |
| Fluid | Weapon System | Hydraulic Circuit | 5+15µ | 15-25μ | 25-50µ | 50-100µ | >100µ |
| MIL-H-5606 | TM-76 Mace | Power Pack 24 into Missile | 33,800 | 1.640 | 788 | 108 | 124 |
| | | 24 from Missile | 3,930 | 726 | 112 | 22 | 6 |
| | - V | Power Fack 13 Recycled | 2,520 | 740 | 524 | - C7 | 28 |
| | | | 2,756 | 3,160 | 1,104 | 204 | 254 |
| | | 26 | 3,200 | 1,560 | 434 | 132 | 34 |
| | | 27 | 9,980 | 3,520 | 708 | 134 | 124 |
| | | 29 | 13,200 | 1,980 | 854 | 62 | 108 |
| | | 39 | 4,360 | 866 | 244 | 58 | 80 |
| | GAM-77 Hound Dog | Power Pack S2-3A | 11,400 | 732 | 518 | 132 | 116 |
| | IM-99 Bomarc | -2733 | 32,500 | 4,590 | 3.600 | 312 | 152 |
| | | Hydraulic Bench No. 4 | 1,190 | 272 | 182 | 82 | 52 |
| | F-100D | Flight Control System | 8,800 | 2,170 | 392 | 80 | 46 |
| | F+101 | A/C 541 506 Primary System | 39.800 | 2.570 | 184 | 82 | 36 |
| | | Dr 11 1 ty | 203,000 | 25,700 | 2,886 | \$ 1 4 | 168 |
| | | 541 499 Utility | 3,800 | 1,526 | 824 | 162 | 152 |
| | | A/C 56 329 Utility System | 1,700 | 606 | . 306 | Q. | 23 |
| | F-102 | Hydraulic Cart | 5,660 | 1,260 | 2 9 54 | 3.2 | 160 |
| | | A/C 7795 | 31,600 | 9,220 | 2,520 | 142 | 466 |
| | F-104 | | 182,000 | 5,520 | 188 | 35 | 22 |
| | | | 69,500 | 3,700 | 604 | 7 8 0 | 28 |
| | | | 33,800 | | 1 96 | 32 | 14 |
| | | System | 3,080 | 1,280 | 430 | 106 1 | 38 |
| | | A/C 850 System 2 | į,800 | 408 | 216 | 58 | 9 |
| | New Oil | | 2,590 | 682 | 314 | 25 | 99 |
| | | Standard of California | 9,290 | 2,540 | 474 | 951 | 76 |
| | | Shell | 7,620 | 2,280 | 154 | 18 | 46 |
| MIL-H-8446 | B-58 | Hydraulic Cart | 76,100 | 632 | 80 | 20 | 64 |
| | | A/C 81014 | 65,800 | 1,560 | 236 | 28 | 80 |
| | New Oil | | 26,900 | 2,380 | 1,060 | 097 | 190 |
| | | Gallon Can | 2,570 | 700 | 334 | 60 | 72 |
| Rughes | GAR, Falcon | | 2,530 | 1,040 | 306 | 160 | 170 |
| 20-1124 | | No. 2 | 2,090 | 338 | 228 | 162 | 172 |
| | | | | | | | |

ť f

MCR-69-484

C-20

È

| | | | Test | | P | urticles/1 | Particles/100 ml Fluid | Id |
|------------|----------------|---------------------|----------------|----------------|--------|------------|------------------------|------------|
| Fluid | Source | Conditions of Test | Time | 5+15µ | 15-25μ | 25+50µ | Ξ0-100μ | >100µ |
| MIL-H-5606 | Ĩ | Moog 942 | | 17,600 | 2,160 | 180 | 140 | 166 |
| | POWET PACK | 150 psi | | 9,450 | 3,850 | 704 | 222 | 84 |
| | | 3- CTT | 24 hr 40 hr | 7,690 5,250 | 4,370 | 728 | 342 | 146 180 |
| MIL-H-5606 | IM-99 Bomarc | Cadillae FC-10 | 5 mín | 112,000 | 21,600 | 246 | 42 | 46 |
| | Test Stand | 3000 psi | | 28,000 | 2,200 | + | ŀ | ł |
| | | 150 °F | 24 hr | 20,200 | 8,760 | 4,580 | ; | ; |
| | | | 40 hr | 148,000 | 99,800 | 78,800 | 3,650 | 166 |
| MIL-H-5606 | ь Н | Atchley | 5 mín | 32,200 | 4,300 | 306 | 164 | 36 |
| | Hydraulic Cart | 3000 psi | | 14,200 | 2,220 | 86 | | } |
| | | 150 °F | 24 hr | 22,500 | 3,700 | ŀ | 1 | ! |
| | | | 40 hr | 6,570 | 1,550 | 460 | 72 | 64 |
| MIL-H-8446 | B-58 | Hydraulic Reservoir | 5 min | 8,180 | 2,760 | 580 | 210 | 140 |
| | Hydraulic Cart | 2000 psi | 12 hr | 5,650 | 1,930 | 806 | 246 | 280 |
| | | 160 °F | 24 hr | 4,150 | 1,140 | 424 | 114 | 204 |
| | | | 40 hr | 2,410 | 1,400 | 234 | 96 | 110 |
| | | | | | | | | |

Table III Contamination Levels puring Laboratory Tests

.

. . . .

.

,

MCR-69-484

é

C**-2**1.

28. Kirnbauer, Erwin A.: "A Method of Determining the Degree of Contamination of Sampling Valves." Aircraft Porous Media, Inc. APM-FSR-9B

This paper was written as a proposed ARP for the SAE. It presents detailed test procedures for determining the amount of contamination that is contributed to a fluid sample by the sampling valve itself, under low pressure conditions. Contaminants generated while mounting the valve into the system, that which is built into the valve itself during manufacture, and that generated by valve operation are the major sources considered.

Two appendixes are included thich present the results of tests conducted by APM on two different types of sampling valves: 1) ABMA Drawing No. 8941098 (Dr #198-59)(Benton Needle Valve P/N 2000); and 2) Fluid Regulator Corporation Bleeder Valve P/N. FRC7665-01. The results of both tests indicate that very little contaminate was generated by mounting the valves. The "built-in" contamination of the Fluid Regulator Corporation valves was negligible. However, the Benton did generate during opening and closing; the contaminate was 60 to 65% metallic and was of the following levels:

| <u>Size</u> | Particle Count | | | | |
|---------------------|----------------|--|--|--|--|
| 525µ | 50,000 | | | | |
| 25-5 0 µ | 750 | | | | |
| 50-100µ | 100 | | | | |
| 100µ plus fibers | 40 | | | | |

29. Longyear, D. M., Jr., Blatter, A., and Porter, D.: "Concepts to Extend Servosystem Life and Minimize Performance Degradation." <u>SAE Conference Proceedings: Aerospace Systems and Equipment Con-</u> ference, Los Angeles, California, May 18-20, 1965. 650316.

> This paper discusses design considerations that may reduce requirements for filtration to control contamination in hydraulic systems. Principal wear in servo values is due to cavitation and erosion. A means of reducing wear and contaminant generation is the use of better materials. A comparison study was run on materials selected for characteristics of machineability, stability, strength, and hardness. Wear can be considerably reduced by the use of tungsten-carbide servo values that are virtually insensitive to normal hydraulic system contamination.

30. McKenzie, G. W.: "Operation and Maintenance Requirements for SST Hydraulic Systems." <u>SAE Conference Proceedings</u>: <u>Aerospace Fluid</u> <u>Power Systems and Equipment Conference</u>, Los Angeles, California, May 18-20. 650343.

> This paper discusses the minimum filter requirements recommended for the SST hydraulic systems. For this system it was recommended that all return fluid should be filtered through dual filter assemblies comprising a 3-micron absolute primary element with bypass to a 15-micron absolute secondary filter______ with no bypass. All other system filters should be at least 15-micron absolute with no bypass. This paper also discusses desirable properties of a hydraulic fluid to be developed for SST with primary consideration placed on fire resistance properties.

31. MIL-STD-1246A. 18 August 1967. Department of Defense, Washington, D. C. 20301.

This specification describes DOD contamination control levels. This revision varies from the revision dated 27 May 1966 by allowing a greater number of particles above a given size for the same cleanliness level. Small particles for any level are controlled by listing a maximum weight of nonvolatile residue for each 100 milliliters of fluid. Examples of cleanliness levels with particles greater than a given size are listed below:

| Cleanli- ness Level | Particle Size (Microns) | Allowable Quantity of <u>Particles</u> | Nonvolatile Residue Ranges |
|---------------------------|-------------------------------|--|----------------------------------|
| 10 | 5 | 3 | A. Less than 1.0 mg |
| 100 | 15 | 280 | B. 1.0 to 2.0 mg |
| | 25 | 75 | C. 2.0 to 3.0 mg |
| | 50 | 11 | D. 3.0 to 4.0 mg |
| | 100 | 1 | E. 4.0 to 5.0 mg |
| 500 | 50 | 11,000 | F. 5.0 to 7.0 mg |
| | 100 | 950 | G. 7.0 to 10.0 mg |
| | 250 | 25 | H10.0 to 15.0 mg |
| | 500 | 1 | J. 15.0 to 25.0 mg |
| 1,000 | 250 | 1,000 | |
| | 500 | 45 | |
| | 750 | 7 | |
| | 1000 | 1 | |

32. Neiland, V. R.: "Contamination Effects and Controls in Saturn Launch Vehicle Hydraulic Systems." <u>AEC/NASA Symposium on Contemination Control: Current and Advanced Concepts in Instrumentation and Automation</u>. Albuquerque, New Mexico, September 12-14, 1967.

> Contamination in hydraulic systems can be much more effectively dealt-with when its sources and effects are understood. The contamination level of a closed system can be considerably reduced by the operation of some of its components prior to assembly since the contaminant generation level is reduced after a relatively short break=in period.

Plots are given of experimental data on critical elearances in some hydraulic system components, and the time requiredfor component malfunction due to silting versus contamination level. Examples are given of system filter failures due to resonance; excessive resonance may be prevented by proper support of filter elements. Vibration_and contamination_levels for Saturn hydraulic components are given as well as contamination specification limits.

33. Parker, James W.: "Hydraulic System Contamination." <u>Ground Sup-</u> port Equipment, Volume 4, No. 6 January 1963. AD 485305.

> This article was extracted from Air Force Report ASN TN 61-143. Fifteen operational aircraft and two ground-servicing units at Wright Patterson Air Force Base, Ohio, were surveyed for contamination in hydraulic systems. Large quantities of contanination were found; in the over-100-micron range, as many as 5100 particles were counted in the sample. The major problem source is identified as transfer of fluid-from shipping containers and poor treatment of ground test equipment. The complete results of contamination levels found during this survey are presented in the tabulation.

Contaminants in Operational Aircraft Hydraulic Systems

| A/C Type | 5-10 <u>Micron</u> | 10-25 Micron | 25-50 Micron | 50-100 Micros | 100 | . . | Weight |
|--------------|-----------------------|-----------------|-----------------|------------------|---------|----------------------|---|
| F-105 | 53,840 | | | Micron | Meron | Remarks | (mg/100 m1) |
| | | 28,160 | 13,480 | 5,410 | 1,730 | After Flush | 01717 MAN 2019 Mark 21-2, 16, 20, 400 al. ana ana - |
| F-105 | 12,140 | 5,170 | 3,070- | 520 | 370 | After Flush | |
| MJ-2A | 79,970 | 36,720 | 20,150 | 9,380 | 4,240 | After Flush. | |
| | | 12,261 | 5-,860 | 1,870 | 1,260 | Bafara Operation | |
| F=105 | 39,220 | 19,620. | 12,870- | 6,060 | 1.,820- | Before Operation | |
| MJ-2A | 101,330 | 47,150 | 24,380 | 8,340 | 3,590- | Beforg Operation. | |
| KC-135 | 2,750 | 1,050 | 1,440 | 1,430 | 2,620 | l og fluid | |
| KC+135 | 13,460 | 920 | 720 | 720 | 340 | | |
| KC-135 | 10,510 | 1,530 | 630 | 180 | 160 | | |
| B-58 | 0 | ••• | ** | •• | | | |
| B-58 | | | | | •• | ** | 0.2 |
| TB-58 | 48,900 | | •• | | •• | * - | 1.8 |
| TB58 | • | 3,200- | 1,600 | 800 | 18 | | 8.2 - |
| | | * * | | •• | 200 | 50 | 2.8 |
| B-52G | | | | | - | | 6.8 |
| B-52G | | | | | 5,100 | | 8.3 |
| F-105 | | 33,050 | 15,840 | -2.290 | 1,160 | Accident. | |
| B- 58 | 87,000 | 34,200 | 6,800 | 300 | 10 | | A/C |
| | | | -,500 | 200 | 10 | 3 | 5.2 |

34. Piccone, M.: "Control of Gontamination in Rocket Booster Hydraulic Systems." <u>SAE Conference Proceedings: Aerospace Fluid Power Sys-</u> tems and Equipment Conference, Los Angeles, California, May 18-20, 1965. 650345.

> This paper provides a comprehensive discussion on the importance of contamination control in hydraulic systems, types of contaminants, means of system contamination, sizes of particle eontaminants, specifications for hydraulic fluid eleanliness, effects of vibration and flushing on eleaning systems and components, methods of contamination control, comparison of automatic to light microscope contaminant counting methods, and a comparison of some automatic particle counters. General coverage is given to many aspects of contamination control in hydraulic systems and is liberally sprinkled with experience on actual systems.

35. Pino, M. A. and Furby, N. W.: "New Considerations-in Hydraulic Fluid Testing." <u>SAE Conference Proceedings: Aerospace Fluid Power</u> <u>Systems and Equipment Conference</u>, Los Angeles, California, May 18-20, 1965. 650329.

> This paper discusses the requirements imposed by specifications on aviation hydraulic fluids as being unjustified in view of . actual conditions to be met in application.

> In principle, the author agrees that revisions to MIL-H-5606 hydraulic fluid were beneficial but disagrees with the criteria of (essentially) a zero particle count in excess of 100 microns. This paper presents the problems inherent in transferring fluid from containers to the using system without introducing contamination and recommends that all fluid be passed through a filtration cart prior to filling the hydraulic system. White room conditions are required to package hydraulic oil to this specification with a high rejection rate and attendant costs.

The author further points out that MIL-H-5606 specifications are in excess of major_airframe manufacturers specifications whose limits have been shown to be perfectly adequate for broad use. The table compares the specifications (A, B, and C) used by major airframe manufacturers in_relation to MIL-H-5606._____

| Applica | tion A* | Applic | ation B |
|---|--|--|--|
| Particle Size Range | Number. (Mäximum) | Particle Size Range | Number (Maximum) |
| 5-10 10-20 20-40 40-80 80-160 >160 | 16,000 4,800 1,200 240 16 4 | 5-14 15-24 25-49 50-99 100-299 >300 | 10,000 4,000 1,000 100 50 3 |

· • •

Examples of Particulate Contamination Requirements

C#26

ł

| | Application C | MIL=H=5606A Exhibit A | : MII⊷H~5606B |
|--|--|---|-----------------------------------|
| Particle Size Range | Number- (Maximum) | Number (Maximum) | Number [‡] (Maximum)- |
| 5-15 15-25 25-50 51-100 >100 | 2,500 1,500 150 20 5 | 20,000 9,000 2,500 150 0 ⁺ | 2,500 1,000 250 25 0† |
| [‡] Filter r | a than number-of ate and total w ments also. | - | |

Examples of Particulate Contamination Requirements (concluded)

ŧ

The author also points out that superclean fluids are not superior to normal specification fluids (such as example C in the tabulation) in terms of oxidation stability and recommends a requirement of 3 or 4 particles in the largest size counted instead of a zero particle count criteria. The results would be (1) lower fluid costs, (2) increased sources of supply, (3) better fluid availability, (4) fluid quality functionally equal to present fluids. Nitrogen blanketing that has become accepted practice is also discussed.

36. "Precision Cleaning Methods and Cleanliness Requirements for Parts and Assemblies of Apollo Eluid Systems." North American Aviation, Inc., Downey, California, 19 July 1965. MAG610-017.

This specification details cleaning and contamination control requirements-used for the Apollo program. Filters as fine as 0.45-micron are required for analysis of a fluid contamination level. The cleanliness requirements used are shown in the tabulation on page C-28.

MCR=69=484

ŧ

| Level | Particle Size (microna) | Allowable Quantity (per 100 ml) | Maximum Nonvolatile Residue (mg) (per 100 ml fluid) |
|-------|--|---------------------------------------|---|
| 1 - | 50-75 75-100- Above 100 | 100 10 - 0 | 1 mg |
| 2 | 50-1 <u>00</u> 100-175 Above 175 | 100- 10 0 | 1 mg |
| 3. | 160-200 200-250 Above 250 | 5. 1 0 | No requirement |
| 4 | 175-700 (particles and fibers) Above 700 (particles) 700-1500 (fibers) Above 1500 (fibers) | 6- 0 1 0 | 2 mg; |

37. Reid, Stanley F.: "How Lockheed Keeps Gontaminates Out of Hydraulic Systems During the Manufacture of Large Cargo Aircraft." <u>Contamination Control</u>, Volume V., No. 8, August 1966....

> This article presents a comprehensive description of the program_that Lockheed/Georgia has instituted to ensure cleanliness of hydraulic systems on the C-5. Cargo aircraft. In-plant fabrication of tubing and hose assemblies is conducted by normal processes, but all subsequent operations are conducted under controlled cleanliness conditions. Special cleaning and capping equipment has been designed. Control of the fluid itself is considered vital. All test equipment is certified. Cleanliness clauses are a part of all vendor procurement. Educational and training programs have been instituted for the personnel involved. Sampling is accomplished by the "bomb" and_visual counting method, but. "in-place" techniques and automatic sampling equipment are being evaluated.

C=28

38, Rohinson, N. F.: "Fluid Contamination Survey of 143 Naval Aircraft Hydraulic Systems." Douglas Aircraft Company, Inc., Long Beach, California, 13 March 1968. AD 402711.

> This report describes the fluid sampling and analysis of 143 naval aircraft. Emphasis is placed on contamination lovel and type and number of filters employed in each system. The conclusion reached is that it is not unreasonable to expect the existing fluid system to be able to sustain a maximum contamination level of class 5 with minor modifications, and that newly designed systems should be able to maintain a maximum contamination level of class 4. The means of attaining these higher cleanliness levels are proper filtration and the use of components that have been broken in (passed initial high contaminant generating stage). The contamination classes recommended are the tentative SAE, ASTM, and AIA hydraulic-fluid standard contamination levels as shown:

| Size Range <u>(microns)</u> | Maximum Partiele <u>Count Class 4</u> | Maximum Particle <u>Count Class 5</u> |
|--------------------------------|--|--|
| 5-10 | 32,000 | 87,000 |
| 10-25 | 10,700 | 21,400 |
| 25-50 | 1,510- | 3,130 |
| 50-100 | 2.5 | 430 |
| >100 | 21 | 41 |

39. "SSFL Sampling Instructions." Rocketdyne Division, North American Rockwell Corporation. FL 11-5-1072. 1 May 1965.

1

This specification establishes sampling methods and practices for use in testing fluids for contamination at Santa Susana. Field Laboratories. The sampling methods for dynamic and static sampling are given in an explicit step by step manner to ensure that there is as little deviation in analysis due to sampling variation as is possible.

8

40. Stechmeyer, J. P.: "Construction of a Controlled Environmental Area Utilizing Commercial Construction Materials." <u>SAE Conference</u> <u>Proceedings: Aerospace Fluid Power Systems and Equiprent Conference</u>, Los Angeles, California, May 18-20, 1965, 650344.

> This paper discusses constructing and maintaining a clean room for assembly, test, and inspection of critical components. Considerations are made for cost, upkeep, and assembly time. Floor, wall, and ceiling materials are considered for appearance and function. Air conditioning and housekeeping must be checked and maintained uniformly throughout the operation of the clean room. Personnel clothing must be kept clean and in good repair. Equipment must be selected for cleanliness of operation and ease of maintenance. Every element must be considered to reduce expense and obtain required cleanliness level.

41. Tollier, G. F., Lewellen, J. W., and Standke, H.: <u>Survey of Con-tamination in Rocket Propulsion Fluid Systems</u>. Rocketdyne Division, North American Rockwell Corporation, Conoga Park, California. AFRPL-TR-67-290. AD 829701.

> This paper discusses fluid contamination. The primary interest is to demonstrate the many diverse aspects of contamination with which industry is now faced. Physical characteristics of particulate and chemical contaminants are described as well as their potential detremental effect in fluid systems. A general survey of contamination level control exercised by various corporations indicates a need for a much clearer definition of contamination problems and solutions. A bibliography of articles and assorted specifications outlines present knowledge and concern for contamination analysis. .. An extensive number of graphs and tables give an indication of data available for consideration in the design and maintenance of fluid systems.

٠

42. Van Loon, J. K.: "Silting Index - What It Is, How to Find It, What It Tells." <u>Hydraulics and Pneumatics</u>, Vol. 17, No. 3, March 1964.

> This article presents a derivation of the mathematics involved in the Silting Index and describes the test technique involved. Basically, the index is a measure of the time required to pass a specific volume of hydraulic fluid, under a specific pressure, through a 0.8 micron filter. The higher the index, the greater the tendency of the fluid to silt. It can predict failure rates of high tolerance servo valves. The detailed test procedure is given in ARP-788 of the SAE.

43. Van Loon, J. K.: "Value Engineering of Contamination Control." <u>SAE Conference Proceedings: Acrospace Fluid Power Systems and</u> <u>Equipment Conference</u>, May 18-20, 1965. 650331.

> Contamination control is mandatory for good component reliability. In order to keep reliability high and cost low, the customer and supplier should review their contamination controls and specifications to ensure that they are adequate but net too severe. Care must be taken that the component is not contaminated due to reliability testing at system installation. The 1-111 flight control servo actuator development is used to domonstrate the successful application of Value Engineering to Contamination Control. This is a case of a "contamination-control program designed for a specific component or system.... to eliminate the COLD PLATE from the product." It mentions that either MIL-H-5606B or MIL-H-6083 hydraulic fluid is used in testing, with a final flush of MIL-H-6083. The particle specification used for the F-111 components is presented below.

| Micron <u>Range</u> | Over 1000 | Fibers 500-1000 | <u>100-500</u> | <u>50-100</u> | <u>25-50</u> | <u>15-25</u> | <u>5-15</u> |
|-------------------------------------|---------------------|--------------------|----------------|---------------|--------------|--------------|-------------|
| <u>Component</u> | | | | | | | |
| Number of Particles Allowable | 0 | 5 | 11 | 55 | 1,000 | 4,000 | 20,000 |

. . . .

...

MCR=69-484

44. Wheeler, H. L., Jr.: <u>Fluid Filters: Media and Contamination</u>. Bendix Filter Division, Bendix Aviation Corporation. Publication No. BFD 168. 1960

> To control the level of contamination in hydraulic systems, a variety of filter types or combinations of types may be selected. Each hydraulic component generates its own type of contamination and is also sensitive to a certain range of contaminant sizes. The two primary filter types are surface filter (single-membrane element) and depth filter; each has advantages and disadvantages that should be considered when selecting filters for a specific system. The surface filter is more easily adaptable to "absolute" particle size filtration while the depth filter has a greater contaminant holding capacity. Clean room facilities are necessary in filter production to reduce migration effectively.

Particle counting in the range smaller than 10 microns is extremely unreliable with optical techniques because the particle sizes are approaching the wavelength of light.

45. Wiley, John W.: "Hydraulic Fluid Contamination." <u>Aerospace Main-</u> tenance Safety, Vol. 19(2), February 1964.

> This author maintains that the keys to maintaining clean aircraft hydraulic systems are (1) strict filter maintenance both in the aircraft and in ground servicing units, (2) prefiltering fluid added to reservoirs, and (3) knowledgeable servicing and maintenance techniques. Certain system functions deserve particular attention; for example, plugged filters may have gone into the bypass mode and passed contamination on down into the system. Special attention should also be given to maintaining cleanliness of air reservoirs on test stands, since contamination here can be passed on into the hydraulic fluid. Paper elements should not be used in high-velocity systems because the impact of a larger particle may perforate the fiber. Pressure surges can put a filter into momentary bypass. When a system is flushed and sampled, the sampling operation should be repeated after an engine run or test flight since engine vibration and system operation will often loosen particles that will show up in the filters.

ŧ

Convair Cleanliness Specification 13.07H and 13.17C are presented; the requirements are as follows:

Maximum Particle Size, p: 0-10 10-25 25-50 50-100 100-200 Maximum Quantity Allowable: None 9000 900 90 9

> One fiber allowed, 40µ maximum diameter Sample volume is 100 ml

Also in this paper, recommended particle counts are presented which are believed adequate to prevent silting of servo valves:

| Maximum Particle Size, it: | 5-14 | 15-24 | 25-50 | 50 100 | h 1 0 0 |
|-----------------------------|---------|--------|-------|--------|---------|
| Maximum Quantity Allowable; | 150.000 | 17.000 | 7 000 | 1.000 | |
| • | | .,,000 | 1,000 | 1,000 | 100 |

Sample volume is 100 ml

C=33