

KITTSON COUNTY HIGHWAY DEPARTMENT**S.A.P. 035-606-024**

Bids Close April 5, 2021, 1:00 P.M.

Hallock, Minnesota 56728

NOTICE TO CONTRACTORS

Sealed bids will be received by the Board of Commissioners, Kittson County at the office of the County Administrator, Hallock, Minnesota until 1:00 P.M. on April 5, 2021 for the purpose of letting the contract for the following projects:

S.A.P. 035-606-024: Bridge replacement (BR. 35540), Approach Grading and Bituminous Surfacing

Location: 1,080 Ft. south of the NW corner of Section 13, T162N, R48W to 730 Ft. south of the NW corner of Section 13, T162N, R48W

Approximate Major Quantities of Work for Approach Grading are:

Quantity	Unit	Item
656.	S.Y.	REMOVE BITUMINOUS PAVEMENT
242.	C.Y.	AGGREGATE BASE (CV) CLASS 5 (MODIFIED)
20.	C.Y.	SHOULDER BASE AGGREGATE (CV) CLASS 1
46.	GALLON	BITUMINOUS MATERIAL FOR TACK COAT
228.	TON	TYPE SP 12.5 WEARING COURSE MIX (2;C)
1.	L.S.	APPROACH GRADING
880.	L.F.	SILT FENCE; TYPE MS
200.	L.F.	FLOTATION SILT CURTAIN TYPE MOVING WATER
1.	L.S.	TURF ESTABLISHMENT
1880.	S.Y.	EROSION CONTROL BLANKETS CATEGORY 3N
18.	GALLON	RAPID STABILIZATION METHOD 3
350.	L.F.	4" DOUBLE SOLID LINE PAINT
700.	L.F.	6" SOLID LINE PAINT

Approximate Major Quantities of Work for Bridge Construction are:

Quantity	Unit	Item
1.	L.S.	MOBILIZATION
290.	C.Y.	SELECT GRANULAR BORROW MOD 10% (CV) (P)
256.	L.F.	TYPE S (TL-4) BARRIER CONC (3S52) (P)
96.	C.Y.	STRUCTURAL CONCRETE (3B52) (P)
93350.	LBS.	REINFORCEMENT BARS (EPOXY COATED) (P)
840.	LBS.	REINFORCEMENT BARS (STAINLESS-75KSI) (P)
1.	L.S.	STRUCTURE EXCAVATION
1.	L.S.	SLOPE PREPARATION
4934.	S.F.	BRIDGE SLAB CONCRETE (3YHPC-M) (P)
14.	EACH	FLOOR DRAIN TYPE B702 MODIFIED
167.	S.Y.	BRIDGE APPROACH PANELS
1.	L.S.	REMOVE EXISTING BRIDGE
2.	EACH	STEEL H-TEST PILE 90 FT LONG 12"
2.	EACH	STEEL H-TEST PILE 100 FT LONG 12"
22.	EACH	PILE TIP PROTECTION 12"
1540.	L.F.	STEEL H-PILING 12"
324.	L.F.	20" STEEL PILE SHELLS
1220.	S.Y.	GEOTEXTILE FILTER TYPE 7
550.	C.Y.	RANDOM RIPRAP CLASS III
4.	EACH	END TREATMENT-TANGENT TERMINAL
100.	L.F.	TRAFFIC BARRIER DESIGN TRANS TYPE 31
137.	L.F.	TRAFFIC BARRIER DESIGN TYPE 31
1.	L.S.	TRAFFIC CONTROL

Item	Counter Price	Delivered Price
11" x 17" Plan & Proposal	\$35.00	\$45.00

Price includes tax. Plans & Proposals not sold separately and no refunds will be made.

Proposal forms with specifications may be obtained at the office of the County Engineer, 401 2nd Street SW, Hallock, MN 56728, (218)843-2686. Each bid must be accompanied by a certified check or bidder's bond made payable to the County Administrator, Kittson County, Minnesota in the sum of not less than five (5%) percent of the amount bid.

The County Board reserves the right to reject any or all bids and to waive any informality therein and to accept the bid deemed most advantageous to the County.

Dated this 2nd day of March, 2021, Hallock, MN

Dillon Hayes, Kittson County Administrator

(March 10, 17, 24, 2021)